

UNCLASSIFIED

AD NUMBER
AD404228
NEW LIMITATION CHANGE
TO Approved for public release, distribution unlimited
FROM Distribution authorized to U.S. Gov't. agencies and their contractors; Administrative/Operational Use; MAY 1963. Other requests shall be referred to Naval Civil Engineering Laboratory, Port Hueneme, CA.
AUTHORITY
USNCBC ltr, 24 Oct 1974

THIS PAGE IS UNCLASSIFIED

UNCLASSIFIED

AD 404 228

*Reproduced
by the*

DEFENSE DOCUMENTATION CENTER

FOR

SCIENTIFIC AND TECHNICAL INFORMATION

CAMERON STATION, ALEXANDRIA, VIRGINIA



UNCLASSIFIED

NOTICE: When government or other drawings, specifications or other data are used for any purpose other than in connection with a definitely related government procurement operation, the U. S. Government thereby incurs no responsibility, nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

63-3-4

404228

CATALOGED BY ASTIA
AS AD NO.

Technical Report

R 120 SUPPLEMENT

BEHAVIOR OF INSTRUMENTED PRESTRESSED
CONCRETE PAVEMENT AT NAS LEMOORE,
CALIFORNIA

7 May 1963



U. S. NAVAL CIVIL ENGINEERING LABORATORY
Port Hueneme, California

MAY 21 1963

**SUPPLEMENT TO TR-120, BEHAVIOR OF INSTRUMENTED PRESTRESSED CONCRETE
PAVEMENT AT NAS LEMOORE, CALIFORNIA**

Y-R011-01-013

Type C

by

J. A. Bishop

ABSTRACT

The observations reported in TR-120 are supplemented by further observations of the behavior with age and use of an instrumented prestressed concrete taxiway at NAS Lemoore. Data will continue to be taken annually.

Qualified requesters may obtain copies of this report from ASTIA.
The Laboratory invites comment on this report, particularly on the
results obtained by those who have applied the information.

PURPOSE

As indicated in TR-120, observations of coupler and strain meter data from the prestressed concrete taxiway at NAS Lemoore were to be made bimonthly during the first year of the pavement life and then semiannually for a period of two years. This supplement updates the data presented in TR-120 and describes the condition of the instrumentation and the pavement after two years of life and after the pavement has been in operational use for one year. It is planned to continue observation of the coupler loads and concrete strains on an annual basis.

SCOPE

Data taken since the publication of TR-120, and reported herein, include two sets of measurements: (1) the distribution of prestressing forces along longitudinal and transverse tendons as indicated by the instrumented couplers, and (2) longitudinal and transverse strains in the concrete as defined by the Carlson strain meters placed adjacent to the couplers. No load tests have been conducted on the pavement since the completion of those reported in TR-120. The latest observation of data consisted of an around-the-clock set of readings to determine the variation of coupler loads and concrete strains over a period of 24 hours.

RESULTS

Coupler loads and strains in the concrete during the periodic observations since July 1960 are presented as extensions of Tables I and II of TR-120. The last entry in each table represents the final readings of data taken during the 24-hour observations mentioned above. The manner in which the distribution of tendon forces in longitudinal tendon 16 has changed during the first two years of pavement life is indicated in Figure S-1. Figure S-2 shows the changes in transverse tendons during the same period. Figure S-3 shows the manner in which concrete strains as reflected by the Carlson strain meters adjacent to the couplers in tendon 16 have changed also. (No "design" strains can be plotted as these were not known prior to prestressing.) The variation of transverse strains is shown in Figure S-4. The variation of coupler load and concrete strains (at position B-16) with slab temperature, air temperature, and humidity over a 24-hour period is shown in Figure S-5.

DISCUSSION

Examination of Table I will indicate that over half of the couplers installed in the longitudinal tendons have become inoperative since the data taken in June 1961. Until that time all of the couplers were providing reasonably reliable information regarding tendon forces. For example, in June 1961 all five couplers in tendon 15 were performing satisfactorily, but by February 1962 none of the five was able to provide any data on the force in tendon 15. Similarly, three of the five couplers in tendon 17 have been incapacitated. The reason for the destruction of the data-providing capability of these instrumented couplers is not known, but it may be significant that the taxiway was put into operational use within a very short time after the June 1961 readings. Neither the couplers installed in the transverse tendons nor the Carlson strain meters embedded in the concrete appeared to have been damaged. The variation in longitudinal tendon forces with time as indicated by Figure S-1 appears to be typical of the change taking place in all three longitudinal tendons which were instrumented (compare with Figure 12 of TR-120). There has apparently been a substantial reduction in the tendon force at each end of the slab, whereas the force at the center of the slab has not decreased appreciably. As a matter of fact, the force indicated at the center is greater than at either end. The reason for this anomalous situation is not readily apparent, but it is probably related to friction between the tendons and their ducts, caused by the sagging and misalignment of the flexible ducts as mentioned in TR-120. It is not possible to predict the minimum value to which the force in tendon 16 will reduce, but it would appear conceivable that, if the trend continues, eventually a point would be reached at which the concrete in the area of tendon 16 would no longer be considered "prestressed." Whether or not this situation exists in the other 30 longitudinal tendons of the taxiway is, of course, not known, and it may be that the rather odd distribution of tendon forces over the length of the cable may be due to the binding of an instrumented coupler in its enclosing sheath. If this is the case, then the other tendons would not be so affected since they are continuous.

The 24-hour observations plotted in Figure S-5 reveal the effects, at one instrumentation position, of slab temperature and humidity changes on concrete strains and on coupler loads. It is seen that during the last half of the 24-hour period the slab temperature increased a maximum of 10 degrees (temperature was sensed by the strain meters embedded in the concrete). During the same period of time the relative humidity dropped a total of 32 percent. The air temperature more or less paralleled the slab temperature and will not be considered further. During the last half of the 24-hour period the compressive strain in the concrete sensed by the Carlson meters increased 44 microinches, and the coupler load decreased a total of 320 pounds.

If the modulus of elasticity of the concrete is assumed to be the same as at the time of construction, the 44-microinch change in strain represents a 176-psi increase in compressive stress. If the coefficient of expansion is assumed to be the same as the initial value, an increase of 10 degrees should result in an increase of 228 psi. The difference between these figures, 52 psi, must then be due to the drop in relative humidity, which would tend to shrink or shorten the slab.

Similarly, if the coefficient of expansion and the modulus of elasticity of the steel are assumed to be at their initial values, a 10-degree increase in temperature is the equivalent of a relaxation of 75 pounds in the tendon. The coupler, however, indicated a drop in coupler load of 320 pounds. The difference in these values, 245 pounds, must be the result of the shortening of the slab caused by the decrease in relative humidity.

It would appear, therefore, that the net effect of a decrease in relative humidity is a reduction in the amount of compressive stress that would be developed because of increased temperature, and a larger relaxation of the tendon force than would be developed by the same temperature rise.

In June 1962 it was observed that two spalled areas were present in the center lane of the taxiway and that some of the instrumentation was exposed. The spalling occurred immediately over the trumpets surrounding two of the couplers in the longitudinal tendons. One spall was about 14 inches in diameter at the surface and the other about 12 inches; each was approximately 2 inches deep. There was no way of determining specifically what had caused the spalling, nor was there any indication of whether the spalls occurred suddenly or gradually. It was apparent, however, that the trumpets were disrupted and the instrumented couplers within were clearly visible. Figure S-6 shows the spalled areas and the damage to the trumpets. The pavement was carefully inspected and no other evidence of distress was observed over any of the trumpets or instrumentation. The damaged areas were immediately patched since they were considered hazards to aircraft operation.

CONCLUSIONS

The conclusion expressed in TR-120 that the instrumented couplers and Carlson strain meters were satisfactory means of extracting data from the pavement is reiterated. It would appear that after two years of life, however, and after many of the couplers are no longer providing data, that in future prestressed pavement work the trumpets or sheaths surrounding the instrumented couplers should be much longer than were used at NAS Lemoore to obviate the possibility of the coupler binding on a trumpet end when the prestressing tendons are stretched.




Figure S-1. Longitudinal coupler loads (coupler in tendon 16).




Figure S-2. Transverse coupler loads (averaged).




Figure S-3. Longitudinal strains in concrete (meters adjacent to tendon 16).




Figure S-4. Transverse strains in concrete (averaged).






Figure S-5. Around-the-clock observations (position B-16, north 1/4 point).



A



B

Figure S-6. Spalls over instrumentation in center lane of taxiway.

TABLE I.

DATE	LONGITUDINAL												
	A-15	A-16	A-17	B-15	B-16	B-17	F-15	F-16	F-17	G-15	G-16	G-17	H-15
2-2-60			73.6			67.2			59.8			69.7	
			70.4			67.2			60.2			69.8	
*		30.9	69.8		35.1	66.7		39.5	61.9		35.4	68.9	
		39.5	69.8		35.4	66.6		39.4	61.9		36.0	68.8	
		49.8	69.7		44.4	66.5		39.9	61.9		44.3	68.8	
		59.4	69.7		52.6	66.5		47.6	61.9		53.3	68.8	
		68.7	69.6		61.2	66.4		55.1	61.8		61.4	68.8	
		73.8	69.6		65.6	66.3		59.4	61.8		65.9	68.7	
**		50.0	69.3		57.3	66.0		59.0	61.4		65.3	68.5	
*	30.8	50.0	69.1	37.2	57.1	65.6	36.5	44.2	61.1	32.8	64.9	68.2	31.0
	39.3	49.9	69.0	37.3	57.1	65.6	36.5	44.1	61.1	38.2	64.9	68.2	40.6
	49.9	49.9	69.0	41.9	57.1	65.5	43.2	44.1	61.1	47.8	64.9	68.1	50.6
	59.9	49.9	69.0	50.1	57.0	65.5	51.4	44.1	61.0	57.7	64.8	68.1	61.3
2-2-60	69.5	49.9	69.0	58.0	57.0	65.4	60.4	44.1	61.0	66.7	64.7	68.0	70.9
2-2-60	74.6	49.9	68.9	62.1	57.0	65.4	60.3	44.1	61.0	66.5	64.7	68.0	70.3
2-2-60	71.6	49.9	68.9	62.0	57.0	65.4	60.2	44.1	60.1	66.4	64.7	68.0	68.8
2-2-60	70.4	49.6	68.1	61.7	57.0	65.2	59.8	58.4	60.7	65.6	64.3	67.6	67.9
2-3-60	70.4	50.4	68.2	62.5	57.6	65.8	60.8	59.7	62.1	66.0	64.8	67.9	67.8
2-3-60	70.1	50.4	67.7	62.3	57.5	65.5	60.7	59.7	62.0	65.7	64.6	67.7	67.8
2-4-60	70.0	50.4	67.7	62.7	57.6	65.7	61.1	60.0	62.5	65.7	64.6	67.7	67.8
2-5-60	69.8	50.3	67.4	62.5	57.2	65.4	60.8	59.7	61.9	65.4	64.5	67.5	67.7
2-5-60	69.6	50.1	67.2	62.3	57.0	65.2	60.7	59.5	61.6	65.3	64.1	67.3	67.3
2-8-60	69.2	49.8	66.7	62.0	56.7	64.7	60.3	59.2	61.2	64.9	64.0	66.8	67.4
2-8-60	69.1	49.8	66.4	61.9	56.7	64.6	60.3	59.2	61.2	65.2	64.1	66.8	66.9
2-9-60	69.0	49.6	66.4	62.1	56.7	64.7	60.4	59.2	61.1	64.9	64.0	66.8	66.8
2-9-60	69.0	49.6	66.4	62.1	56.6	64.6	60.3	59.2	61.0	64.9	64.0	66.8	66.7
2-9-60	68.9	49.5	66.4	62.1	56.6	64.6	60.3	59.2	61.1	64.9	63.9	66.7	66.8
2-9-60	68.9	49.5	66.3	62.1	56.7	64.6	60.3	59.2	61.1	64.8	63.9	66.7	66.8
2-9-60	69.3	50.0	66.6	62.1	56.8	64.6	60.3	59.2	61.1	64.8	63.8	66.7	67.1
2-9-60	69.4	50.0	66.6	62.2	56.8	64.6	60.4	59.2	61.2	64.8	63.9	66.7	67.3
2-11-60	69.0	67.6	66.3	60.7	65.4	63.1	59.0	60.4	59.5	63.5	64.5	65.4	66.9
2-13-60	68.6	66.0	65.9	60.7	64.6	62.6	58.6	60.2	59.4	63.0	63.9	65.1	67.9
2-17-60	68.5	65.4	65.8	60.5	63.8	62.3	58.5	59.7	60.0	63.0	63.5	64.9	66.3
3-2-60	68.1	67.3	65.2	60.0	61.8	61.2	58.0	59.2	59.7	62.3	62.6	64.1	65.5
3-31-60	65.0	59.8	63.3	58.4	58.6	58.9	56.7	58.1	57.1	58.9	59.7	62.3	65.4
5-2-60	61.9	56.0	61.9	56.7	56.7	57.1	55.9	57.4	55.6	58.2	56.7	60.3	58.3
5-3-60	62.7	56.2	62.4	57.5	57.6	58.0	56.8	58.5	56.7	59.0	57.6	61.2	55.9
6-6-60	57.9	49.8	59.1	53.0	53.5	54.0	54.0	55.5	52.9	53.1	50.0	55.6	57.3
7-11-60	55.4	46.0	55.9	49.3	51.4	51.2	52.1	53.3	51.1	47.0	44.7	51.2	51.0
9-13-60	53.1	43.0	51.7	46.7	49.4	48.4	49.4	51.0	47.1	42.1	40.5	47.2	37.5
11-16-60	53.7	43.0	52.2	47.6	50.5	49.7	50.2	52.3	48.4	39.8	41.8	48.2	38.7
1-18-61	54.2	43.2	52.5	47.9	51.3	50.4	48.1	53.2	49.3	41.4	42.7	47.3	40.8
6-20-61	46.9	37.1	39.1	40.8	46.5	44.5	45.0	47.8	43.1	35.2	35.9	42.5	33.1
2-8-62	***	34.6	***	***	45.7	38.2	***	45.7	***	***	31.9	***	***

* Note that loads on interior couplers are higher than on end couplers. Interior cc

** Difficulty with tendon locking device caused drop in load. Full load was not agai

*** Coupler inoperative.

TABLE I. INSTRUMENTED TENDON LOAD (kips)

	H-15	H-16	H-17	C-81	C-82	C-83	TRANSVERSE			E-81	E-82	E-83	AVERAGE TEMP °F	OPERATION
							D-81	D-82	D-83					
.7			74.1									46.1	Full jacking load	
.8			71.1										Jack released	
.9		31.2	70.2										Tendon 16 jacked to	
.8		40.6	70.2										Tendon 16 jacked to	
.8		50.2	70.2										Tendon 16 jacked to	
.8		60.8	70.1										Tendon 16 jacked to	
.8		71.0	70.1										Tendon 16 jacked to	
.7		76.2	70.1										Full jacking load	
.5		63.7	69.9										Jack released	
.2	31.0	63.4	69.8										Tendon 15 jacked to	
.2	40.6	63.4	69.8										Tendon 15 jacked to	
.1	50.6	63.4	69.7										Tendon 15 jacked to	
.1	61.3	63.3	69.7										Tendon 15 jacked to	
.0	70.9	63.3	69.7										Tendon 15 jacked to	
.0	70.3	63.3	69.7										Full jacking load	
.0	68.8	63.3	69.7										Jack released	
.6	67.9	62.9	69.2									58.2	End of work day	
.9	67.8	63.2	69.1	51.8	50.9		51.7	50.2		50.8		47.7	Tendons 81, 82, 83	
.7	67.8	63.0	68.8									48.8	(Jacking load 52k)	
.7	67.8	62.9	69.0									46.0	Stressing of transverse tendons	
.5	67.7	62.8	68.7									49.6		
.3	67.3	62.7	68.5	49.9	50.1		48.9	49.1		49.6		49.5		
.8	67.4	62.7	68.1	49.5	50.0		48.7	48.8		49.4		54.0		
.8	66.9	62.9	68.0									55.1		
.8	66.8	62.4	67.9									51.8		
.8	66.7	62.4	67.9											
.7	66.8	62.3	67.9											
.7	66.8	62.3	67.9											
.7	67.1	63.0	67.8											
.4	66.9	69.6	67.4	49.2	49.8		48.4	48.6		48.8		57.5	Stressing of longitudinal tendons	
.1	67.9	68.7	67.1									60.4		
.9	66.3	64.5	66.8									60.7		
.1	65.5	67.8	66.4	48.7	48.9		47.7	48.0		48.5		61.7		
.3	65.4	66.0	64.9	47.3	48.2		46.0	47.0		45.9		76.1		
.3	58.3	64.7	64.2	46.3	47.6			46.1				85.5		
.2	55.9	65.2	64.5									68.0		
.6	57.3	61.9	62.1	44.2	45.9			48.4				103.8		
.2	51.0	58.3	59.9	41.6	44.1			40.6				105.5		
.2	37.5	54.6	57.4	38.5	41.9		27.9	38.3		31.3		103.4		
.2	38.7	55.2	57.6	38.3	42.8		29.0	40.7		31.6		61.1		
.3	40.8	55.6	57.8	39.6	45.2		29.4	39.8		31.7		46.0		
.5	33.1	48.3	51.6	34.2	39.3		26.2	34.9		25.8		113.4		
* **	***	41.2	***	26.5	38.8		23.5	34.4		21.6		55.01		



terior couplers did not reflect complete releasing of full prestressing load applied during jack verification. Load was not again applied until end of prestressing (2-11-60).

LOAD (kips)

C-82	C-83	TRANSVERSE			E-81	E-82	E-83	AVERAGE TEMP °F	OPERATION		
		D-81	D-82	D-83							
							46.1	Full jacking load on tendon 17 Jack released Tendon 16 jacked to 30k Tendon 16 jacked to 40k Tendon 16 jacked to 50k Tendon 16 jacked to 60k Tendon 16 jacked to 70k Full jacking load on tendon 16 75.5k Jack released Tendon 15 jacked to 30k Tendon 15 jacked to 40k Tendon 15 jacked to 50k Tendon 15 jacked to 60k Tendon 15 jacked to 70k Full jacking load on tendon 15 75.5k Jack released			
50.9		51.7		50.2		50.8	58.2	End of work day			
	coupler damaged		coupler damaged		coupler damaged		47.7	Tendons 81, 82, 83 fully stressed (Jacking load 52k)			
50.1		48.9		49.1		49.6	49.5	49.6	48.8	Stressing of transverse tendons	
50.0		48.7		48.8		49.4	54.0	55.1	46.0		
							51.8				
49.8	48.4	48.6	48.8	57.5							
							60.4	Grouting of tendon ducts			
48.9	47.7	48.0	48.5	61.7			60.7				
48.2	46.0	47.0	45.9	76.1			68.0				
47.6		46.1		85.5			103.8				
45.9		48.4		105.5			103.4				
44.1		40.6		61.1			46.0				
41.9	27.9	38.3	31.3	113.4			55.01				
42.8	29.0	40.7	31.6								
45.2	29.4	39.8	31.7								
39.3	26.2	34.9	25.8								
38.8	23.5	34.4	21.6								

ct complete releasing of full prestressing load applied during jack verification.
of prestressing (2-11-60).



TRANSVERSE					AVERAGE	OPERATION
D-82	D-83	E-81	E-82	E-83	TEMP °F	
					46.1	Full jacking load on tendon 17 Jack released Tendon 16 jacked to 30k Tendon 16 jacked to 40k Tendon 16 jacked to 50k Tendon 16 jacked to 60k Tendon 16 jacked to 70k Full jacking load on tendon 16 75.5k Jack released Tendon 15 jacked to 30k Tendon 15 jacked to 40k Tendon 15 jacked to 50k Tendon 15 jacked to 60k Tendon 15 jacked to 70k Full jacking load on tendon 15 75.5k Jack released
-22	-11	-3	-71	-77	58.2	End of work day
-13	-1		-66	-74	47.7	<div style="border: 1px solid black; padding: 5px;"> Tendons 81, 82, 83 fully stressed (Jacking load 52k) Stressing of transverse tendons Stressing of longitudinal tendons </div>
-18	-7	-73	-72	-80	48.8	
-71	-52	-76	-71	-81	46.0	
-71	-52	-81	-76	-84	49.6	
-75	-56	-82	-80	-88	49.5	
-73	-47	-86	-80	-88	54.0	
-88	-65	-94	-92	-100	55.1	
					51.8	
					51.8	
					51.8	
-82	-64	-92	-87	-99	51.8	<div style="border: 1px solid black; padding: 5px;"> Grouting of tendon ducts </div>
-76	-50	-82	-79	-92	57.5	
-68	-45	-85	-82	-91	60.4	
81	-53	-86	-82	-100	60.7	
100	-67	-97	-94	-108	61.7	
133	-157	-116		-132	76.1	
140	-183	-134		-138	85.5	
124	-170	-134		-128	68.0	
203	-242	-175		-171	103.8	
302	-295	-211		-210	105.5	
411	-371	-265		-255	103.4	
282	-298	-336		-255	61.1	
233	-237	-242		-228	46.0	
322	-332	-246		-249	113.4	
229	-256	-177		-222	55.01	

meter
damaged



DISTRIBUTION LIST

SNDL Code	
	Chief, Bureau of Yards and Docks (Code 70)
23A	Naval Forces Commanders (Taiwan Only)
39B	Construction Battalions
39D	Mobile Construction Battalions
39E	Amphibious Construction Battalions
39F	Construction Battalion Base Units
A2A	Chief of Naval Research - Only
A3	Chief of Naval Operation (OP-07, OP-04)
A5	Bureaus
B3	Colleges
E4	Laboratory ONR (Washington, D. C. only)
E5	Research Office ONR (Pasadena only)
E16	Training Device Center
F9	Station - CNO (Boston; Key West; San Juan; Long Beach; San Diego; Treasure Island; and Rodman, C. Z. only)
F17	Communication Station (San Juan; San Francisco; Pearl Harbor; Adak, Alaska; and Guam only)
F41	Security Station
F42	Radio Station (Oso and Cheltenham only)
F48	Security Group Activities (Winter Harbor only)
H3	Hospital (Chelsea; St. Albans, Portsmouth, Va; Beaufort; Great Lakes; San Diego; Oakland; and Camp Pendleton only)
H6	Medical Center
J1	Administration Command and Unit - BuPers (Great Lakes and San Diego only)
J3	U. S. Fleet Anti-Air Warfare Training Center (Virginia Beach only)
J4	Amphibious Bases
J19	Receiving Station (Brooklyn only)
J34	Station - BuPers (Washington, D. C. only)
J37	Training Center (Bainbridge only)
J46	Personnel Center
J48	Construction Training Unit
J60	School Academy
J65	School CEC Officers
J84	School Postgraduate
J90	School Supply Corps
J95	School War College
J99	Communication Training Center
L1	Shipyards

Distribution List (Cont'd)

SNDL Code	
L7	Laboratory - BuShips (New London; Panama City; Carderock; and Annapolis only)
L26	Naval Facilities - BuShips (Antigua; Turks Island; Barbados; San Salvador; and Eleuthera only)
L30	Submarine Base (Groton, Conn. only)
L32	Naval Support Activities (London & Naples only)
L42	Fleet Activities - BuShips
M27	Supply Center
M28	Supply Depot (Except Guantanamo Bay; Subic Bay; and Yokosuka)
M61	Aviation Supply Office
N1	BuDocks Director, Overseas Division
N2	Public Works Offices
N5	Construction Battalion Center
N6	Construction Officer-in-Charge
N7	Construction Resident-Officer-in-Charge
N9	Public Works Center
N14	Housing Activity
R9	Recruit Depots
R10	Supply Installations (Albany and Barstow only)
R20	Marine Corps Schools, Quantico
R64	Marine Corps Base
R66	Marine Corps Camp Detachment (Tongan only)
W1A1	Air Station
W1A2	Air Station
W1B	Air Station Auxiliary
W1C	Air Facility (Phoenix; Monterey; Oppama; Naha; and Naples only)
W1E	Marine Corps Air Station (Except Quantico)
W1H	Station - BuWeps (Except Rota)

Deputy Chief of Staff, Research and Development, Headquarters, U. S. Marine Corps, Washington, D. C.
 President, Marine Corps Equipment Board, Marine Corps School, Quantico, Va.
 Chief of Staff, U. S. Army, Chief of Research and Development, Department of the Army,
 Washington, D. C.
 Office of the Chief of Engineers, Assistant Chief of Engineering for Civil Works, Department of
 the Army, Washington, D. C.
 Chief of Engineers, Department of the Army, Attn: Engineering R & D Division, Washington, D. C.
 Chief of Engineers, Department of the Army, Attn: ENG CW-OE, Washington, D. C.
 Library of Congress, Washington, D. C.
 Director, Office of Technical Services, Department of Commerce, Washington, D. C.

Distribution List (Cont'd)

Director, U. S. Army Engineer Research and Development Laboratories, Attn: Information Resources Branch, Fort Belvoir, Va.

Headquarters, Wright Air Development Division, (WWAD-Library), Wright-Patterson Air Force Base, Ohio

Headquarters, U. S. Air Force, Directorate of Civil Engineering, Attn: AFOCE-ES, Washington, D. C.

Commanding Officer, U. S. Naval Construction Battalion Center, Port Hueneme, Calif., Attn: Materiel Dept., Code 140

Deputy Chief of Staff, Development, Director of Research and Development, Department of the Air Force, Washington, D. C.

Director, National Bureau of Standards, Department of Commerce, Connecticut Avenue, Washington, D. C.

Office of the Director, U. S. Coast and Geodetic Survey, Washington, D. C.

Armed Services Technical Information Agency, Arlington Hall Station, Arlington, Va.

Director of Defense Research and Engineering, Department of Defense, Washington, D. C.

Director, Division of Plans and Policies, Headquarters, U. S. Marine Corps, Washington, D. C.

Director, Bureau of Reclamation, Washington, D. C.

Commanding Officer, U. S. Navy Yards and Docks Supply Office, U. S. Naval Construction Battalion Center, Port Hueneme, Calif.

Facilities Officer (Code 108), Office of Naval Research, Washington, D. C.

Federal Aviation Agency, Office of Management Services, Administrative Services Division, Washington, D. C., Attn: Library Branch

Officer in Charge, U. S. Navy Unit, Rensselaer Polytechnic Institute, Troy, N. Y.

Chief, Bureau of Naval Weapons, Navy Department, Washington, D. C., Attn: Research Division

U. S. Army, Washington, D. C., Attn: Director of Research and Development Group

Chief, Concrete Division, Waterways Experiment Station, P. O. Box 2131, Jackson, Miss.

Chief, Physical Research Branch, Research Division, U. S. Department of Commerce, Bureau of Public Roads, Washington, D. C.

Director, Engineering Research Institute, University of Michigan, Ann Arbor, Mich.

Director, The Technological Institution, Northwestern University, Evanston, Ill.

Library, Engineering Department, University of California, 405 Hilgard Ave., Los Angeles

Library, University of Southern California, University Park, Los Angeles

Library, Institute of Technology, University of Minnesota, Minneapolis, Minn.

Library, California Institute of Technology, Pasadena, Calif.

Materials and Research Laboratory, California Division of Highway, Sacramento

Joseph H. Moore, Head, Department of Civil Engineering, Clemson University, Clemson, S. C.