

UNCLASSIFIED

AD NUMBER

AD843345

NEW LIMITATION CHANGE

TO

**Approved for public release, distribution
unlimited**

FROM


**Distribution authorized to U.S. Gov't.
agencies and their contractors; Critical
Technology; MAY 1961. Other requests shall
be referred to Space and Missile Systems
Organization, Attn: SMSD, Los Angeles, CA
90045.**

AUTHORITY

**Air Force Space and Missile Systems
Organization ltr dtd 28 Feb 1972**

THIS PAGE IS UNCLASSIFIED

AD 843345



D
This document is subject
to special export controls and
each transmittal to foreign
governments or foreign
nationals may be made only
with prior approval of:
Hq.SAMSO, LA., Ca. 90045
Attn: SMSD

Limited number of copies containing color
material will be available until
such time as the color material will be
available in black and white only.



CONVAIR (ASTRONAUTICS) DIVISION
GENERAL DYNAMICS CORPORATION

D D C
F NOV 20 1968
L G E - A -

**Best
Available
Copy**

REPORT NO. 7A2236
DATE 5/23/61
NO. OF PAGES 132

CONVAIR ASTRONAUTICS

CONVAIR DIVISION OF GENERAL DYNAMICS CORPORATION

REPORT NO. 7A2236

EVALUATION TEST REPORT

FOR

SWITCH ASSEMBLY AC-DC, MAIN POWER

CHANGEOVER, MISSILEBORNE

DWG. NO. 27A-06186
27A-06177



PREPARED BY

R. J. Murphy
R. J. Murphy
Test Engineer

CHECKED BY

G. F. Sheets, Jr.
G. F. Sheets, Jr.
Ass't. Test Lab Grp. Engr.

APPROVED BY

J. M. Johnson
J. M. Johnson
For H. G. Campbell, Jr.
Test Lab Group Engr.

APPROVED BY

H. G. Campbell
H. G. Campbell
Chief of Test Labs

NOV 20 1961

REVISIONS

This document is subject
to special export controls and
each transmittal to foreign
governments or foreign
nationals may be made only
with prior approval of:
Hq. SAMSO, LA., Ca. 90045
Attn: SMSD

NO.	DATE	BY	CHANGE	PAGES AFFECTED
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				
101				
102				
103				
104				
105				
106				
107				
108				
109				
110				
111				
112				
113				
114				
115				
116				
117				
118				
119				
120				
121				
122				
123				
124				
125				
126				
127				
128				
129				
130				
131				
132				

Printed number of copies containing color

S U M M A R Y

The data presented in this report represents the results of Engineering Evaluation Tests performed on the Main Missile Power Changeover Switch, Part Number 27-00100, according to CVA test procedure 7-A-2236, and Test Laboratory Test Request 7-A-2236.

Two specimens, serial numbers 001 and 002, manufactured by the Kinetics Corporation, Seal Beach, California; and two specimens, serial numbers 121 and 124 manufactured by United Control Corporation, Seattle, Washington, were tested concurrently. The individual tests performed on each specimen are listed on Figure 3 with asterisks indicating failures.

Figures 5 and 6 are schematic diagrams of the test setup.

This test was performed on a semi-formal basis, in that an approved procedure, and standard data sheets were used; however, the tests were not witnessed by inspection.

While this evaluation test was being conducted a noise problem developed in CVA Receiving Inspection involving the production units being manufactured by United Control Corporation. CVA Components Test Laboratory was assigned the job of resolving the problems as an additional task to this test. The detailed testing data and results of the noise survey are included in this report as Addendum I.

Not including the noise problem, 18 failures and/or out-of-tolerance readings occurred during the test. Five of these failures and/or out-of-tolerance conditions occurred on the Kinetics Corporation specimens, and 13 failures and/or out-of-tolerance conditions occurred on the United Control Corporation specimens. A comprehensive discussion of these failures, and the test in general is included in a separate portion of the test report labeled "Discussion of the Data".

Original data, not included on the data sheets, is recorded in Engineering Work Book No. 7482 on permanent file in CVA Components Test Laboratory (Dept. 564-5).

DISCUSSION OF THE DATA:

The general test format and results, and more specifically, the failures, will be discussed by specimen, which is not necessarily the chronological sequence of the tests. Dates and more detailed information can be obtained by referring to the individual data sheets.

KINETICS S/N 001

This specimen was received first and was used to setup and calibrate the test set and instrumentation used for the remainder of the test.

While calibrating the vibration setup, a discrepancy in the test set wiring caused a wire in the specimen to overheat and char excessively. The specimen wire was from J 705L to J 705N. The test set was repaired and the specimen sent to the vendor for repair.

Before sending this specimen for repair, nonoperating vibration per design criterion specifications, was conducted to search for mechanical weaknesses. The results were completely satisfactory.

After being repaired and returned to CVA, testing was resumed according to Figure 3 schedule. During the cold test at ambient pressure, one cut-of-tolerance reading occurred. On an external to internal assembly cycle, AC switch circuit P40 required 16.5 milliseconds to make the transfer. The specification requires that the time be no greater than 15 milliseconds. This test was repeated several times the next day and all circuits were within tolerance than on all subsequent tests.

During the remainder of the tests performed no failures and/or cut-of-tolerance data occurred.

A Life Test was conducted on this specimen and on United Control S/N 121, but not on Kinetics S/N 002 or United Controls S/N 124. Voltage drop measurements were first made using the test setup and making measurements at sensing leads in the specimen mating electrical connectors according to Figure 3 (schematic of test setup). The specimens were then opened and voltage drop measurements were taken directly across the switching mechanisms according to the test procedure, Paragraph 4.3. The latter readings were subtracted from the former readings and are included as additional data sheets. These data should be subtracted from the voltage drop data taken during all other portions of the test, to obtain voltage drop across the switching mechanism.

DISCUSSION OF THE DATA: (CONTINUED)KINETICS S/N 002:

Before any testing was accomplished, this specimen was first used in a CVA demonstration in Washington, D.C. After being returned to San Diego it was lost. The test requestor's representative subsequently found it in the CVA salvage yard. From the quantity and severity of scratches and dents the specimen could very well have been subjected to severe mechanical shocks.

During the ambient conditions proof cycle the 200 ampere D.C. circuit indicated an out-of-tolerance dielectric resistance. The specification requires a minimum of 10 megohms dielectric resistance and this circuit measured .04 megohms to case, with 100 VDC applied. The specimen was sent to the vendor for repair. When it was returned to CVA the testing sequence was completely redone.

During the cold test (Paragraph 4.3.1.1(c)), the specimen failed to perform an assembly cycle from internal to external at 25 VDC. The specimen was again sent to the vendor for repair. When the specimen was returned to CVA testing was resumed from where the failure had occurred.

While sitting dormant in the CVA Components Test Laboratories (ambient San Diego climate conditions), corrosion was noted to be forming on the specimen hardware. The specimen was subsequently subjected to a Salt Atmosphere Test, according to CVA specification 7-00210. At the conclusion of the test a visual inspection showed considerable corrosion on the specimen ground plate studs and hardware. Figure 4 is a photograph of this condition, taken during the visual inspection. During the Post Salt Atmosphere Test proof cycle, a dielectric strength (HIPOT) failure occurred on J 701 A to J 701 D. The specification requires that this circuit withstand a minimum of 500 V RMS. The circuit broke down at 50 V RMS. The specimen was sent to the vendor for repair, and when returned to CVA, no further testing was accomplished.

CONVAIR ASTRONAUTICS

DISCUSSION OF THE DATA: (CONTINUED)UNITED CONTROL SPECIMEN S/N 121:

During the Initial Satisfactory Performance Test, and on all subsequent tests where measured, dielectric strength failures occurred. CVA specification 27-06166, Paragraph 3.6.3.6, requires that the specimen, between adjacent power circuits and between each power circuit and case, be capable of withstanding 1500 V RMS. Only one circuit was cut-of-tolerance on the Initial Satisfactory Performance Test. J 706 Z to case broke down at 950 V RMS. The number of breakdown increased as testing progressed, until 6 breakdowns occurred during the Hot Test. A more detailed description of the dielectric strength failures is included on the individual data sheets.

During the Operating Vibration Tests, a considerable amount of "noise" and "chatter" was noted on the D.C. switch circuits. Due to the vagueness of CVA specification 27-06166 requirements and tolerances on "chatter" this was not resolved as a failure at this time. When United Control S/N 124 was tested the same condition occurred and is discussed in this section, "Discussion of the Data" under United Control S/N 124.

UNITED CONTROL SPECIMEN S/N 124:

During the Initial Satisfactory Performance Test, two complete failures occurred on this specimen. The first of these failures was below tolerance readings for dielectric strength on several switch circuits. After the proof cycle was completed the specimen was opened for failure analysis, with design group and vendor representatives present. It was determined that the wrong type of relay was used for the AC switch. The dielectric strength specification for the relays used in this specimen was 1000 V RMS, and the CVA component specification (27-06166) is 1500 V RMS. The vendor's representative stated that this type of relay had gotten in by mistake and were probably in several production items. A check of the production items on hand at CVA showed this to be the case.

The second failure during the Initial Satisfactory Performance Test, occurred during the third assembly cycle attempted. On performing an internal to external assembly cycle the specimen s

DISCUSSION OF THE DATA: (CONTINUED)UNITED CONTROL SPECIMEN S/N 124: (CONTINUED)

D.C. switch assembly failed to transfer completely. When the specimen was opened, under circumstances stated in the preceding paragraph, the following situation was found; In the D.C. switch motor circuit, the motor limiting microswitch was contaminated by a glyptal like substance and was hanging up in the open position. This appeared to be more of a workmanship problem than a design problem.

The specimen, and all production units that were determined to have the improper type of relays, were sent to the vendor for repair. Upon return of the reworked specimen, testing was resumed according to Figure 3 schedule. During the Operating Vibration Tests, in all three axes, several of the D.C. switch circuits exhibited a considerable amount of noise and chatter. At this point the CVA specification was very vague about contact "noise" or "chatter". It simply stated that it should not exist but did not define the term. A concensus of opinion between CVA Electrical Design Group and CVA Components Test Lab personnel was, that the "chatter" was unacceptable, and that the CVA specification 27-06166 requirements section include a description and tolerance for contact "chatter". The specimen was again sent to the vendor for rework.

While this Evaluation Test was being conducted, the Receiving Inspection Dept. (280-2) was experiencing a "noise" problem on the AC switch circuits of the United Control production units. When United Control specimen S/N 124 was received back from rework, it was used solely for resolving this noise problem.

The report on testing done and results found in resolution of the "noise" problem are included in this report as Addendum I.

EVOLVING TIME SERIES

FREQUENCY vs TIME

FIGURE 1

1000

900

800

700

600

500


400

300

200

100

0



DESIGN VIBRATION CONDITIONS
PAGE 2 BANK SECTION

MAXIMUM DESIGN CONDITION

NOT REPRODUCIBLE

K-E 2000 359.91

SOIL-LAYER UNIT AT 17.5' (2)

		TEST SPECIMENS		UNITED CONTROL	
KINETICS S/N 001	KINETICS S/N 002	S/N 121	S/N 124		
1. Nonoperating Vibration Search for mechanical weaknesses	1. Initial Satisfactory Performance Test.	(*) 1. Initial Satisfactory Performance Test.	(*) 1. Initial Satisfactory Performance Test.		
2. Initial Satisfactory Performance Test.	2. Ambient Conditions	(*) 2. Operating Vibration, all 3 axes.	2. Second Initial Satisfactory Performance Test.		
	3. Operating Vibration all 3 axes.	3. Second Initial Satisfactory Performance Test.	(*) 3. Post Vibration		
	4. Post Vibration	4. Post Vibration	(*) 4. -30° at ambient pressure.		
	(*) 5. -30°F @ ambient pressure.	Vibration all 3 axes.	(*) 5. -30° @ 1 mm R.H.		
	6. -65°F @ 1mm Hg.	5. Post Vibration	(*) 6. +150° @ 95% R.H.		
	7. 160°F @ 95% RH	6. -30°F @ ambient pressure.	(*) 7. +160° @ 1mm Hg.		
	8. 160°F @ 1mm Hg.	(*) 7. -30°F @ 1mm Hg.	(*) 8. +40° @ 95% R.H.		
	9. 40°F @ 95% RH	(*) 8. Operating Acceleration.	(*) 9. Post Environmental.		
	10. Re-run of Environmental Tests No. 7 and 9,	9. Salt Atmosphere	10. Operating Acceleration.		
	11. Operating Acceleration	(*) 11. Re-run of all 3 axes of Operating Vibration.			
	12. Life Test	12. Life Test			


(*) Indicated Failure of this test.

FIGURE 3

CONVAIR ASTRONAUTICS


REPORT TA 2236

PAGE 9






Main Missile Power Changeover Switch P/N 27-06166-1 S/N 002
Results of Salt Atmosphere Test,



FIGURE 1



A








D

REVISIONS							EXHIBIT ONE						
REVIS.	INCHES	MM	DESCRIPTION	REV.	DATE	REV. BY	10" CM	IN. MM	IN. MM	EXHIBIT ONE	REV.	DATE	AMENDMENT



GP3100
56-193

GP3100E
56-193

SCHEMATIC FOR 632-1
TEST PROGRAM ONLY.

Revised by:	CHIEF DESIGNER:	Serial No.:	Revised by:	W.A.C. ID:	Date:	Final Rev.:	Final Rev.:	Revised by:	W.A.C. ID:	Date:	Gen. Spec:	Rev.:
Editor:	CORRECTED NO:	APPLICATION:	REVIS. ASST:	W.A.C. ID:	DATE:	ASST	ASST	REVIS.	W.A.C. ID:	DATE:	GEN. SPEC:	REV.




Figure 5
DIAGRAM -
MAIN POWER CHG -
OVER SWITCH
TEST SETUP NO. 2
SCHEMATIC.

CONTINENTAL-ASTRONAUTICS
COMPOSITE DIVISION OF
GENERAL DYNAMICS CORPORATION
SAN DIEGO, CALIFORNIA

005
7A-2286-2

005
005
005



CABLE NO. (1)



Notes:

1. USE #10 GA WIRE WITH HEAVY INSULATION.
EA CPT. 1500 VRMS.
2. MAKE CABLES 15 FT LONG +/-
3. CABLE 1 & 2 COMPRIZE "D" SERIES
HYPOT HARNESS.
4. CABLE 3 & 7 COMPRIZE "E" SERIES
HYPOT HARNESS.
5. IN CABLE 1 WIRE ON PIN 8 OF J706
HAS TO BE CHANGED TO PIN N J706
FOR "E" SERIES.


A



CABLE NO (3)

MAIN PWR C/O SW.
 HYPOT HARNESS

B




P10 GP3106E-32-73
 P10 GP3106E-30-43
 P3 GP3106E-24-233
 P4 GP3106E-28-125
 P5 GP3106E-24-10P
 P6 GP3106E-28-21P
 P7 GP3106E-28-213

P701 GP3106E-30-65 or GP3106E-30-65
 P702 GP3106E-10-103
 P703 PT06E-20-16P
 P704 GP3106E-22-14P
 P705 GP3106E-20-11P
 P706 GP3106E-32-73
 P707 PT06E-10-6P

Notes:

1. TAKE HARNESS 13 FT (+/- 5%) LOV.
2. USE STD AN WIRE (TYPE 304E - 10/13)
3. DIRECT ANY QUESTIONS TO BCT - 10/13

C



NO CLASS OTHERWISE NOTED
 NO 100% TEST 744

D




Figure 6

MAIN PWR C/O SW TEST SET NO. 2
'E' SERIES HARNESS

H.T. MOBLEY 10-10-59

PAGE 11
E

SHEET 2 OF 2

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Required: Rotating Date: Tuesday, 5/2
Specimen Preparation: Cop. Test Engg: R.L. Metcalf
Specimens by 50% Engg Inst: N.D.
Inst. Inst: BL

Parameter / Specification Requirements		Results
<u>4.1.8 Initial Starting</u>		
Start	10.2 hrs.	
Stop	10.7 hrs.	
Axial Thrust Cycles	14	
Start	hrs.	
Stop	hrs.	

Notes: 1. CEC recording Int. to Ext. to Int. recording 200

Best Available Copy

Part. 4113
 Per part. 4118 Revision 3/M 1001 Kinetor Corp. Date: Tuly 14, 59
 Engineer: E. T. Mackay
 CIVAC Lmp: 44
 USAF Lmp: 74

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control Part 4118	Step	Time (seconds)	Tolerance (seconds)	Time of assembly cycle
411	1	0.85	1 MAX	In to Ex Ex to In
412	2	0.204	1 MAX	
413	3	0.12	1 MAX	
414	4	0.30	1 MAX	
415	5	0.37	1 MAX	
416	6	0.57	2 MAX	

REFLECTIVE SWITCH:

All circuits satisfactory ----- YES. NO

ISOLATION RESISTANCE:

All circuits measured greater than 10 megohms --- YES NO

SOURCE CONTROLLER AND COMMUNICATOR

All switches satisfactory

Part 4118	Step	100	Switch position
			Internal to External
			External to Internal

CIRCUIT SWING TIME (20 millisecond minimum)

Internal to Internal 55 milliseconds

Internal to External 12 milliseconds

POSITION TRANSFER TIME (15 milliseconds maximum)

C.R.C.	In to Ex	Ex to In	C.R.C.	In to Ex	Ex to In
Circuit Num. No.	Time	Time	Circuit Num. No.	Time	Time
P11	1	0.5	6.5	5	2
P12	9	8	9	5.5	18
P13	8	9	5.5	5	2
P14	7	4	4	3.5	2
P15	11	10	10	6	2.5
P16	5	6.5	6	4.5	2
P17	1	2	2	1.5	1
P18	5	6.5	7	4.5	10.5
P19	2	3	3	2.5	6
P20	8	7.5	7		

VOLTAGE PROP:		Maximum Control Voltage (30 V.)		Switch in Internal Position		VOLTA
SW. NR.	CIRCUIT	DATA	SW. NR.	CIRCUIT	DATA	
A	J701G - J7012	.020	A	J701A - J701D	.150	A
B	J706P - J705L	.117	B	J701A - J705L	.151	B
C	J706T - J701I	.121	C	J701A - J705K	.155	C
D	J706 - J705I	.119	D	J701A - J705J	.154	D
E	J701 - J7052	.113	E	J701A - J705L	.151	E
F	J706A - J701A	.084	F	J702A - J704H	.051	F
G	J706A - J703D	.110	G	J702B - J703D	.070	G
H	J706Y - J705F	.072	H	J702B - J704F	.033	H
I	J706A - J703G	.107	I	J702C - J703G	.076	I
J	J706G - J703K	.084	J	J702C - J703K	.032	J
K	J706G - J703L	.110	K	J702A - J703L	.062	K
L	J706A - J703K	.110	L	J702A - J703M	.064	L
M	J706A - J703P	.115	M	J702A - J703P	.064	M
N	J706K - J703P	.130	N	J702C - J703P	.093	N
O	J706A - J704A	.112	O	J702A - J704A	.079	O
P	J706A - J704G	.100	P	J702B - J704G	.054	P
Q	J706A - J704J	.074	Q	J702C - J704J	.059	Q
R	J706F - J704N	.110	R	J702A - J704N	.080	R
S	J706X - J704R	.110	S	J702B - J704E	.058	S
T	J706G - J704T	.090	T	J702C - J704T	.058	T

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See Notes

4.1.8 Initial Satisfactory

A

Date: July 14, 1959Page 14Test Eng'r: R.T. Mobley

Report 7A2236

CVAC Insp: NAUSAF Insp: NA

VOLTAGE (KOHM)

Minimum Control Voltage (25 V.)

S/N. NO.	Switch in External Position		Switch in Internal Position		
	CIRCUIT	DATA	CIRCUIT	DATA	
A	J701C - J701D	.093	A	J701A - J701B	.125
C	J702F - J705L	.117	I	J701A - J705L	.152
G	J702E - J705K	.120	G	J701A - J705K	.154
L	J702C - J705J	.119	H	J701A - J705J	.153
B	J706F - J705G	.114	S	J701A - J705G	.150
Y	J706E - J701A	.081	T	J702A - J703A	.075
O	J706C - J703D	.110	S	J702B - J703D	.063
H	J700T - J702F	.071	E	J702B - J703E	.073
Z	J706a - J703C	.105	I	J702C - J703C	.074
J	J706f - J702K	.076	J	J703L - J703K	.031
X	J706G - J702L	.110	B	J702A - J703L	.060
L	J706H - J702M	.116	L	J702A - J703M	.062
M	J702H - J703P	.115	H	J702B - J703P	.072
N	J702C - J703R	.130	M	J702B - J703R	.071
O	J706S - J702A	.110	O	J702A - J702A	.076
P	J706U - J702C	.162	P	J702A - J702C	.073
Z	J706 - J702J	.092	S	J702A - J702J	.037
R	J706F - J702N	.110	R	J702A - J702N	.077
S	J706I - J702P	.160	S	J702B - J702P	.056
T	J702U - J702T	.090	T	J702C - J702T	.041

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N 001 Kinetics Corp.
SpecimenDate: July 17, 1959
Test Engr: R. T. Mobley
CTAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. "Y" Axis	
4.4	Operating Time: Start <u>1084</u> hrs. Stop <u>1092</u> hrs. Assembly Cycles 6 Start _____ hrs. Stop _____ hrs.	

- Notes:
1. Shaker overload kicked out at about 37 CPS but was reset immediately.
 2. Shut down at 85 CPS to change recorder mag. 5-85 CPS Midwest Mag. SN 137
 3. Made switch transfer Int. Ext. Int @ 210 CPS
 4. 85-2000 CPS Mag. # 159 No sw. transfer on this roll, at end of run.
 5. made switch transfer Int. Ext. Int on mag. sp 137
 6. Data reduced and run looked clean.

Part. 4.3 "Y" Axis
 For part. 4.3 Specimen S/N 001
Kinetics Corp. Spec.

* Indicates out of tolerance

Date: July 17 '59
 Engineer: E.L. Mobley
 CVAC Insp: NA
 USAF Insp: NA

ASSEMBLY CYCLE OPERATION:

Control voltage	Part 4.1.8 step	Time (seconds)	Tolerance (seconds)	Time of assembly cycle
				Int. to Ext. Ext. to Int.
16V	A		1 max	
16V	D	X	1 max	X
16V	F	X	2 max	X
30V	I	X	2 max	
25V	I		2 max	
25V	I		2 max	

Dielectric Strength:

All circuits satisfactory ----- NA YES NO

Insulation Resistance:

All circuits measured greater than 10 megohms NA YES NO

SWITCH COMMUTATION AND HOLD-COMMUTATION:

All switches satisfactory

Part 4.1.8 step	IIS	NC see note	Switch position
			Internal Internal
			X
			X

CIRCUIT SEQUENCE TIME: (20 milliseconds minimum)

External to Internal 50 milliseconds

Internal to External 52 milliseconds

POSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit Chan. No.	C.E.C.	Ex to Rx	Rx to Im
P11	P	NA	8
P32	Q	1	8
P30	R	1	6.5
P36	S	1	6.5
P42	T		10
P18	U		7
P20	V	1	7
P26	W	V	12

Circuit Chan. No.	C.E.C.	Ex to Rx	Rx to Im
P42	W		NA
P22	U		?
P34	P		6.5
P11	Q		7.5
P16	R		7.5
P28	S		7.5
P38	T		?
			V

CONVAIR ASTRONAUTICS

REF ID: 7A2236
PML 17

4.1 TEST CONDITIONS AND PROCEDURES: (Continued)

General Test Results: Satisfactory Date: 7-23-59
 Specimen S/N 001 Kinetics Test Engr: R. T. Mobley
 Corp. Specimen CVAC Insp: NA
 USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. "X" Axis	Accelerometer recorder #1 Drive #2 "X" Axis #3 "Y" Axis #5 "Z" Axis #6 Pipper Mag. # 26135
1.4	Operating Time: Start 111.4 hrs. Stop 111.9 hrs. Assembly Cycles 2 Start _____ hrs. Stop _____ hrs.	

Notes: 1.5-5A Mag. # 137

500-2000 Mag. # 159

switch I-E-P @ 750 CPS

Data reduced 7-24-59 - Entire run looks
clean.

Part. 4.3 "X" axis
 Per part. 4.3 Specimen S/N 001
Kinetics Corp.

- Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control voltage	Part 4.1.8 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle	
				Int. to Ext. Int. to Int.	Ext. to Int. Ext. to Ext.
15V	0		1 max		
15V	1	NA	1 max		
30V	2	NA	2 max		
30V	1	NA	2 max		
25V	1		2 max		
25V	1		2 max		

Dielectric Strength

All circuits satisfactory - - - - - NA YES NO

Insulation Resistance

All circuits measured greater than 10 megohms - NA YES NO

Switch continuity and non-continuity

All switches satisfactory

Part 4.1.8 step	YES	NO see note	Switch position	
			Internal	External
0		NA NA		
1		NA NA		
2		NA NA		

Cycle Sequence Time (20 milliseconds minimum)

External to Internal 50 milliseconds

Internal to External 46 milliseconds

Switch made
during vib. @ 750 CPS

Position Change Time (15 milliseconds maximum)

Circuit	C.R.C.	On Power	On to Off	Off to On
P14	P	5	7	
P12	Q	5	7	
P30	R	2	3	
P36	S	3	7	
P40	T	9	10	
P18		7	8	
P20		7	3	
P26		4	5	

Circuit	C.R.C.	On to Off	Off to On
P12	P	4	6
P22	Q	8	7
P36	R	7	8
P14	S	7	8
P16	T	7	8
P28	S	10	12
P38	T	9	4

CONVAIR ASTRONAUTICS

REPORT 7A2236
Page 18

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory
 Specimen S/N 001 Kinetics Corp.
 Specimen

Date: 7-23-'59
 Test Engr: R. T. Mobley
 CVAC Insp: NA
 USAP Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. "X" AXIS "Z"	
1.4	Operating Time: Start <u>111.9</u> hrs. Stop <u>112.4</u> hrs. Assembly Cycles 4 Start _____ hrs. Stop _____ hrs.	

Notes: 1. 5 - 225 MAG # 154
 SWITCH I-E-I (a) 185CPS
 225 - 6000 MAG # 157

Data reduced Run Looks Good on "Z" Axis

Part. 4.3 "Z" axis
 For para. 4.3 Specimen S/N 001
 Kinetics Corp.

Date: 7-23-59
 Engineer: R.L. Hobler
 CVAC Insp: _____
 USAF Insp: NA

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para b.1.6 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle Int. to Ext. Ext. to Int.
15V	A	NA	1 max	NA
15V	A	NA	1 max	NA
30V	F	NA	2 max	NA
30V	I	NA	2 max	NA
45V	I	NA	2 max	NA
25V	I	NA	2 max	NA

Dielectric Strength:

All circuits satisfactory ----- YES NO

Insulation Resistance:

All circuits measured greater than 10 megohms --- YES NO

Switch Conductivity and Non-Continuity

All switches satisfactory

NA

Para b.1.6 step	YES	NO see note	Switch position Internal External
1			
1			
1			
1			

Circuit Transition Time: (20 milliseconds minimum)

External to Internal 50 milliseconds

Internal to External 4.5 milliseconds

POSITION STABILIZATION TIME: (15 milliseconds maximum)

Circuit	Para. No.	Max. Rate to In	Max. Rate to Out
P1A	F	5.3	7.5
P1B	G	2	8
P20	H	3.3	6
P24	I	3	6
P40	J	10	10
P18	K	6	7.5
P20	L	6	6
P26	M	5	7.5

Circuit	Para. No.	In to Ext	Ext to In
P12	N	3	4
P22	O	8	8
P34	P	7.5	9.5
P44	Q	8	8
P16	R	5	6
P28	S	9	9
P38	T	3.5	3

CONVAIR ASTRONAUTICS

REPORT 7A2236
PAGE 21

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N 001 Kinetics Corp.
SpecimenDate: 7-29-58
Test Engr: R.F. Mobley
CVAC Instr: NA
USAF Instr: NA

Paragraph	Specification Requirement	Remarks
4.3	Frost Vibration Front Cycle	
1.4	Operating Time: Start <u>112.4</u> hrs. Stop _____ hrs. Assembly Cycles 8 Start _____ hrs. Stop _____ hrs.	

Notes: 1. CEC Mag. # 508, Record #39 Int.-Ext. Int.

CONVAIR ASTRONAUTICS

REPORT 7A2216
PAGE 22

Para. 4.1.7 Post Vibration
 For para. 4.1.3 Specimen S/N 201
 Kinetics Corp.

- Indicates out of tolerance

Date: 7-5-61
 Engineer: S. T. Mobley
 CVAC Insp: NH
 USAF Insp: NH

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle	
				Intr. to Extr.	Extr. to Intr.
10V	8	.215	3 MAX		
10V	4	.241	3 MAX		
30V	7	.118	2 MAX		
10V	1	.129	2 MAX		
25V	1	.144	2 MAX		
25V	1	.156	2 MAX		

DETERMINIC ATTENUATION:

All circuits satisfactory - - - - - YES NO

INSULATION RESISTANCE:

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NON-CONTINUITY:

All switches satisfactory

Para 4.1.8 step	YES	NO see note	Switch position	
			Internal	External
-				
-				
-				
-				
-				

CIRCUIT SWEEPBACK TIME: (20 milliseconds minimum)

External to Internal 27 milliseconds

Internal to External 27 milliseconds

POSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit	C.P.C.	In to Ex	Ex to In
P11	P	7	7
P12	Q	7	8
P30	R	2.3	6
P36	S	4.5	5
P41	T	10	10.5
P18	U	7	7.5
P20	V	2	8
P26	W	4	5

Circuit	C.P.C.	In to Ex	Ex to In
P12	P	2.75	3.5
P22	Q	7.5	7
P41	R	7.5	7
P11	S	7	8
P16	T	7.5	6
P28	U	10	10
P18	V	3	4

CONVAIR
SAN DIEGO

FORM 11

VOLTAGE DROP: Maximum Control Voltage (30 V.)

SW. NR.		CIRCUIT		SW. NR.		CIRCUIT	
		written in External Position				written in Internal Position	
		DATA				DATA	
A	J701G - J701L	.081	A	J701A - J701D	.112		
B	J701P - J705L	.129	B	J701A - J705L	.139		
C	J701T - J701F	.114	C	J701A - J705L	.141		
D	J701S - J705T	.108	D	J701A - J705S	.139		
E	J701V - J703C	.166	E	J702A - J702L	.136		
F	J702A - J702A	.088	F	J702A - J702L	.052		
G	J702E - J702B	.110	G	J702B - J702D	.068		
H	J702A - J702F	.096	H	J702A - J702S	.034		
I	J702A - J702G	.105	I	J702C - J702X	.069		
J	J702F - J702K	.087	J	J702K - J702X	.032		
K	J702G - J702L	.105	K	J702A - J702L	.059		
L	J702H - J702M	.112	L	J702A - J702M	.065		
M	J702W - J702P	.120	M	J702B - J702P	.070		
N	J702S - J702K	.115	N	J702C - J702S	.075		
O	J702I - J704A	.115	O	J702A - J704A	.086		
P	J702I - J704C	.100	P	J702A - J704C	.049		
Q	J702I - J704Y	.084	Q	J702C - J704Y	.055		
R	J702F - J704N	.120	R	J702A - J704N	.083		
S	J702X - J704R	.100	S	J702C - J704R	.099		
T	J702G - J704T	.090	T	J702C - J704T	.037		

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See Notes

4.3 Post Vib. Proof Cycle

A

Date: 7-24-'59

Page 23

Test Eng: E. T. Mobley

Report 7A2276

Test Input: NATest Output: NA

VOLTAGE INPUT

Minimum Control Voltage (25 V.)

S/N.	Model	Switch in External Position		Switch in Internal Position		Data
		Min	Max	Min	Max	
A	7701A - 7701B	.083		7701A - 7701B	.114	
C	7701F - 7701L	.109		7701A - 7701L	.141	
E	7702A - 7702E	.115		7701A - 7702E	.144	
F	7702A - 7702F	.110		7701A - 7702F	.142	
G	7702 - 7705C	.108		7701A - 7705C	.137	
H	7702 - 7705A	.089		7701A - 7705A	.052	
J	7702 - 7705B	.110		7701A - 7705B	.067	
K	7702 - 7705F	.098		7701A - 7705F	.035	
L	7702 - 7706	.104		7701A - 7706	.067	
M	7702 - 7708	.087		7701A - 7708	.030	
N	7702 - 7709	.105		7701A - 7709	.060	
O	7702 - 7709M	.110		7701A - 7709M	.065	
P	7702 - 7709P	.160		7701A - 7709P	.070	
Q	7702 - 7709R	.115		7701A - 7709R	.075	
R	7702 - 770A	.125		7701A - 770A	.086	
S	7702 - 770C	.100		7701A - 770C	.048	
T	7702 - 770E	.095		7701A - 770E	.056	
U	7702 - 770F	.120		7701A - 770F	.088	
V	7702 - 770G	.100		7701A - 770G	.049	
W	7702 - 770H	.091		7701A - 770H	.037	

B

CONVAIR
SAN DIEGO

VOLTAGE DROP:			Maximum Control Voltage (30 V.)			VOLT
	Switch in External Position			Switch in Internal Position		
SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA	SW.
A	J701G - J701D	0.110	A	J701A - J701D	0.114	A
B	J701P - J701L	0.114	B	J701A - J701L	0.127	Z
C	J706T - J705K	0.111	C	J701A - J705K	0.133	Z
D	J706T - J705I	0.112	D	J701A - J705I	0.132	Z
E	J702T - J703C	0.119	E	J702A - J703C	0.129	Z
F	J706A - J704I	0.115	F	J702A - J704I	0.042	P
G	J706C - J702D	0.100	G	J702B - J703B	0.062	O
H	J706Y - J703S	0.071	H	J702B - J703S	0.024	R
I	J706A - J703C	0.100	I	J702C - J703C	0.044	I
J	J700F - J703X	0.074	J	J702C - J703X	0.023	J
K	J706G - J703L	0.105	K	J702A - J703L	0.056	X
L	J706H - J703M	0.130	L	J702A - J703M	0.056	L
M	J702W - J702P	0.175	M	J702B - J703P	0.066	M
N	J706K - J703Y	0.100	N	J702C - J703Y	0.068	M
O	J706I - J704A	0.100	O	J702A - J704A	0.074	O
P	J706G - J704C	0.090	P	J702B - J704C	0.043	P
Q	J706K - J704J	0.075	Q	J702C - J704J	0.042	Z
R	J700F - J704N	0.120	R	J702A - J704N	0.084	R
S	J706X - J704R	0.087	S	J702B - J704R	0.043	S
T	J706B - J704T	0.078	T	J702C - J704T	0.034	I

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See notes

4.2.1.1c - 65°F. COLD TEST.

0043 Midwest Record # (137 1st run)

CURRGE: INT. - EXT. - INT.

A

Date 7-29-59Page 27Test Engg: Holley/Hanson/Levander

Report 7A2236

EVAC Insp: NHISAF Insp: NH

VOLTAGE Lkups:

Minimum Control Voltage (25 V.)

		Switch in External Position			Switch in Internal Position	
No.	SL	CIRCUIT	DATA	No.	CIRCUIT	DATA
A		J701C - J701D	0.130	1	J701A - J701B	0.126
B		J701F - J703I	0.106	2	J701A - J705L	0.108
C		J701T - J711K	0.106	3	J701A - J705X	0.134
D		J702S - J705J	0.102	4	J701A - J705J	0.134
E		J706F - J705C	0.114	5	J702A - J703A	0.128
F		J706Z - J703A	0.068	6	J702A - J703A	0.039
G		J706C - J703D	0.078	7	J702A - J703D	0.060
H		J726I - J727F	0.065	8	J702A - J703E	0.021
I		J726A - J72X	0.040	9	J702C - J703C	0.063
J		J726F - J727K	0.058	10	J703L - J72K	0.020
K		J726C - J727L	0.098	11	J702A - J703L	0.058
L		J726H - J727M	0.170	12	J702A - J703M	0.055
M		J726K - J727P	0.140	13	J702A - J703P	0.015
N		J726T - J727R	0.098	14	J702A - J72R	0.068
O		J726W - J727A	0.098	15	J702A - J72A	0.078
P		J726L - J724C	0.080	16	J702A - J72C	0.044
Q		J726L - J724L	0.072	17	J702A - J724L	0.042
R		J726F - J724C	0.115	18	J702A - J724N	0.084
S		J726Y - J727Z	0.080	19	J702A - J727L	0.042
T		J726I - J727T	0.074	20	J702C - J727I	0.033

B

CONVAIR ASTRONAUTICS

REPORT 7A2236

PAGE 24

4.1 TEST CONDITIONS AND PROGRESS (Continued)

General Test Results: Satisfactory

Specimen S/N 001. Kinetics
Corp. SpecimenDate: 7-28-59
Test Engn: R. T. Mobley
CVAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.2.1.1	Radiant Heat	Max. non-operating temp. of specimen is 154°F
1.4	Operating Time: Start NA hrs. Stop _____ hrs. Assembly Cycles: Start NA hrs. Stop _____ hrs.	

Note: 1. This test was attempted 7-27-59 but Bemco box malfunctioned and temperature went to 250°F in about 15 minutes time before it was caught. The box was repaired and the test was run this date.

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Unsatisfactory Date: 7/29/59
 Specimen S/N 001 Kinetics Corp. Test Engr: MORLEY-HANSON-LAUENDER
 CRAC Insp: N/A
 USAP Insp: N/A

* Indicates out-of-tolerance data

Paragraph	Specification Requirement	Remarks
4.2.1.1 c	c - 65° F. 3.44 Hg + Hz Proof @ AMBIENT PRESSURE - 30° F.	The environmental conditions were performed, w/specimen in Bemco Box #2, per applicable spec, paragraph noted in 1st column.
1.4	Operating Time: 113.3 Start <u>113.3</u> hrs. Stop <u>112.4</u> hrs. Assembly Cycles 8 Start _____ hrs. Stop _____ hrs.	

* Notes: 1. AC switch circuit p40 required 16.3 millsec.
to transfer from Ext. to Int. This test was
re-run several times, the next day, at the
same environment with this circuit in
tolerance on all runs.

Para. 4.1.9 for Para. 4.2.1.1.c.

For para. 4.1.9 Specimen SN 001 KINETICS

Date: 7/29/59

Engineer: MOBLEY-HANSON-LAWRENCE

CVAC Insp: N/A

SAF Insp: N/A

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Time of assembly cycle
15V	1	.780	1 MAX	This is Ext. Ext. is int.
15V	1	.270	1 MAX	
15V	1	.124	2 MAX	
30V	1	.134	2 MAX	
25V	1	.157	2 MAX	
25V	1	.151	2 MAX	

DISSIPATION STRAINERS:

All circuits satisfactory - Could not perform

NO

DISSIPATION RESISTANCE:

Could not perform

All circuits measured greater than 10 megohms --- T.S.

NO

SWITCH COHERENCY AND NON-COHERENCY:

All switches satisfactory

Para 4.1.8 step	YES	NO note	Switch position
			Internal External
1	X		X
1	X		X
1	X		X
1	X		X

CLOSE SQUENCH TIME: (20 milliseconds minimum)External to Internal 62 millisecondsInternal to External 58 millisecondsPOSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit Chan. No.	In to Rx	Rx to In
P11	7	2
P12	3	7.5
P10	2	7
P14	5	3
P12	13	10.5
P18	1	2.5
P20	11	10.5
P24	4	2.5

Circuit Chan. No.	In to Rx	Rx to In
P12	4	3.5
P22	0	7.5
P14	3	2.5
P11	3	2.5
P16	7	2.5
P28	11	11
P38	5	3.5

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory Date: 7-29-59

Specimen S/N 001, KINETIC

Test Engrs: BALOGH-HANSON-Lavender
CVAC Insp: N/A
USAF Insp: N/A

Paragraph	Specification Requirement	Remarks
4.2.1.1C	Operate Specimen while Reducing Pressure to 1 mm Hg Temp. -65°F	"
1.4	Operating Time: Start 113.9 hrs. Stop 114.8 hrs. .9 hrs. Assembly Cycles 8 Start _____ hrs. Stop _____ hrs.	

Notes:

1. During the first attempt to reach 1 mm the pressure indicated 1.3 mm Hg at the end of 10 minutes. Continuity lights OK.
2. A second attempt was made & reached 1 mm in 10 min. At the end of 10 min the best A.C. (now zero) was 1.7 MM. The proof cycle was run at 1.2 MM. The specimen temp increased to +17°F.
3. Ran out of time before getting Ext. to Int. 18 v assembly cycle.
4. AC switch, register time and cycle sequence were not accomplished on this proof cycle. See re-run of 1st 7-31-'59

Para. 4.19

For para. 4.20 b. Specimen S/N Q01 KINETICS Date: 7/29/57

Engineer: BELKLEY-HALSON-LAWRENCE

CVAC Imp: N/A

USAF Imp: N/A

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle
				Init. to Ext. Ext. to Init.
15V	8	.228	1 MAX	X
15V	4 could not get	3 MAX see note	1 MAX see note	X
30V	?	.130	2 MAX	X
30V	1	.113	2 MAX	X
30V	1	.149	2 MAX	X
25V	1	.140	2 MAX	X

Dielectric StrengthAll circuits satisfactory - Could not accomplish YES NO Insulation ResistanceAll circuits measured greater than 10 megohms - Could not accomplish YES NO Switch Conductivity and Non-Continuity

All switches satisfactory

Para 4.1.8 step	IIS	IV	Switch position
			Internal External
6	X	X	X
1	X	X	X
1	X	X	X
1	X	X	X

Cell Sequence Time (20 milliseconds minimum)

External to Internal _____ milliseconds See 10-12A of this

Internal to External _____ milliseconds first on 7-31-57

POSITION TRANSFER TIME (15 milliseconds minimum)

Circuit	C.S.C.	In to Ex	Ex to In
Circuit Num. No.			
P14	7		
P12	7		
P30	7		
P16	7		
P40	7		
P18	7		
P20	7		
P26	7		

Circuit	C.P.C.	In to Ex	Ex to In
P12	7		
P22	0		
P14	7		
P16	3		
P18	7		
P28	3		
P38	7		

VOLTAGE DROP:		Maximum Control Voltage (30 V.)		VOLTS	
Switch In External Position				Switch In Internal Position	
SW. #	CIRCUIT	DATA	SW. #	CIRCUIT	DATA
A	J701C - J701D	0.100	A	J701A - J701D	0.119
B	J706P - J705L	0.103	B	J701A - J701L	0.134
C	J706T - J705K	0.106	C	J701A - J705K	0.138
D	J706 - J705I	0.104	D	J701A - J705I	0.136
E	J704 - J705C	0.103	E	J701A - J705C	0.134
F	J706A - J702A	0.046 ⁰	F	J702A - J706A	0.041
G	J704C - J702D	0.100	G	J702B - J704D	0.062
H	J702Y - J703F	0.071	H	J704B - J706B	0.065
I	J706G - J704C	0.270	I	J702C - J705K	0.266
J	J704F - J702K	0.351	J	J703C - J702K	0.214
K	J706G - J702I	0.288	K	J702A - J703I	0.054
L	J706H - J7X	0.124	L	J702A - J703M	0.051
M	J704A - J704P	0.105	M	J704B - J703P	0.056
N	J706A - J702K	0.298	N	J702C - J703K	0.210
O	J706C - J704A	0.100	O	J702A - J704A	0.052
P	J706D - J704C	0.079	P	J702B - J704C	0.046
Q	J706R - J704J	0.071	Q	J703C - J704J	0.044
R	J706F - J704N	0.124	R	J702A - J704N	0.092
S	J706X - J704R	0.219	S	J702B - J704R	0.043
T	J706G - J704T	0.072	T	J703C - J704T	0.054

CONTINUITY CHECKS:All circuits indicated continuity . . . Yes No See NotesMidwest Record # ~~0044~~ 1001-1 of 1MM 1/4

FAILED TO RESET COUNTER ON 130

CHADAE OVER, FROM EXT TO INT.

SO MADE KERUP, but this did not get
counter running

A

Date: 7-29-'59Page 30Test Unit: Brieley/Power/Manson

Report 7A2236

VAC Insp: N/ASAP Insp: N/A

VOLTAGE DROPS:

MINIMUM Control Voltage (25 V.)

Part No.	CIRCUIT	Switch in External Position		Switch in Internal Position		
		No.	CIRCUIT	No.	CIRCUIT	
A	J701C - J701D	1	0.091	1	J701A - J701D	0.119
B	J704F - J705L	2	0.106	2	J701A - J705L	0.135
C	J705F - J705L	3	0.109	3	J701A - J705L	0.138
D	J700E - J700J	4	0.104	4	J701A - J705J	0.137
E	J706F - J705C	5	0.112	5	J701A - J705C	0.134
F	J706A - J701A	6	0.077	6	J701A - J701A	0.044
G	J700C - J7012	7	0.090	7	J701A - J7012	0.063
H	J721A - J721E	8	0.070	8	J701A - J703B	0.046
I	J706A - J703C	9	0.093	9	J700A - J703C	0.066
J	J700F - J702K	10	0.058	10	J701A - J702K	0.047
K	J700C - J703L	11	0.090	11	J701A - J703L	0.054
L	J700H - J703M	12	0.108	12	J701A - J703M	0.058
M	J700A - J703P	13	0.121	13	J701A - J703P	0.062
N	J700C - J703R	14	0.100	14	J701A - J703R	0.071
O	J700A - J704X	15	0.102	15	J701A - J704X	0.095
P	J700A - J704C	16	0.080	16	J701A - J704C	0.044
Q	J700A - J704I	17	0.074	17	J701A - J704I	0.044
R	J700F - J704A	18	0.118	18	J701A - J704A	0.081
S	J700A - J704B	19	0.082	19	J701A - J704B	0.044
T	J701A - J704Z	20	0.075	20	J701A - J704Z	0.044

B

6.1 TEST CONDITIONS AND PROCEDURES (continued)

General Test Results: Satisfactory

Specimen S1B 021 Kinetics obj.

Note: Lb 7-30-52

Test Engg: L. L. Mobley

CVAC Ingr: N/A

WAP Ingr: N/A

Paragraph	Specification Requirement	Remarks
4.2.1.1d	+160°F w/ 4.5 hr. L.H. Test - 1 foot cycle @ ambient pressure	
1.4	Operating Time: Start 11:45 hrs. Stop 11:45 hrs. Assembly Cycles: 5 Start _____ hrs. Stop _____ hrs.	

Note: 1. Dielectric strength and insulation resistance
 cannot be tested at $+160^{\circ}\text{F}$. Necessary
 ohm test, N/A will be entered in the
 file box when this procedure is
 performed.

Para. 2.1.7
 Per para. 2.1.1d Specimen S/N 001 kinetics
 Corp. Spec. Date: 7-30-54
 Engineer: R T Mobley
 CVAC Insp: -----
 USAF Insp: NA

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control voltage	Para 2.1.6 step	Time (seconds)	Tolerance (seconds)	Time of assembly cycle Int. to Int. Ext. to Int.
18V	A	2.62	1 max	
18V	B	2.48	1 max	
30V	C	1.12	2 max	
30V	D	1.33	2 max	
25V	E	1.40	2 max	
25V	F	1.63	2 max	

Dielectric Strength

All circuits satisfactory - - - See Note 2 - YES NO

Insulation Resistance

All circuits measured greater than 10 megohms - - - See Note 2 - YES NO

Switch Continuity and Non-Continuity

All switches satisfactory

Para 2.1.6 step	IES	NO see note	Switch position	Internal resistance

WIRE SWING TIME (20 milliseconds min. max)

External to Internal 3.6 milliseconds

Internal to External 4.62 milliseconds

POSITION TRANSFER TIME (15 milliseconds maximum)

Circuit num. No.	C.P.C.	In to Rx	Rx to In
P14	I	4.60	5.63
P32	O	6.74	8.15
P30	H	3.81	9.11
P16	J	5.22	3.6
P40	K	9.32	9.42
P18	L	6.02	6.62
P10	M	6.02	7.2
P26	N	2.54	4.7

Circuit num. No.	C.P.C.	In to Rx	Rx to In
P21	I	2.06	3.1
P22	O	3.23	9.0
P34	P	2.99	11.1
P14	J	7.32	9.1
P16	H	4.73	5.1
P18	K	9.37	11.6
P28	L	2.66	3.0

VOLTAGE DROP:

Maximum Control Voltage (30 V.)

Switch in External Position			Switch in Internal Position		
SW. NR.	CIRCUIT	DATA	SW. NR.	CIRCUIT	DATA
A	J701G - J701D	0.112	A	J701A - J701D	0.158
B	J706P - J705L	0.129	B	J701A - J705L	0.165
C	J706T - J725K	0.133	C	J7K1A - J705K	0.170
D	J706 - J705T	0.129	D	J701A - J705	0.167
E	J706X - J705C	0.128	E	J701A - J705C	0.161
F	J706X - J705A	0.100	F	J702A - J704A	.057
G	J706C - J701D	0.122	G	J702B - J704B	.074
H	J706Y - J704F	0.112	H	J702A - J704A	.036
I	J706A - J704C	0.120	I	J702C - J702K	.079
J	J706S - J702K	0.084	J	J702K - J703K	.028
K	J706G - J701H	0.122	K	J702A - J703L	.065
L	J702L - J703M	0.130	L	J702A - J703M	.069
M	J704U - J701P	0.138	M	J702A - J703P	.082
N	J706S - J702K	0.128	N	J702M - J703E	.085
O	J706I - J704A	0.118	O	J702L - J704A	.088
P	J706D - J704C	0.110	P	J702B - J704C	.054
Q	J706R - J704J	0.101	Q	J702C - J704J	.059
R	J706F - J704K	0.124	R	J702A - J704K	.091
S	J702X - J704R	0.112	S	J702B - J704R	.056
T	J706C - J704T	0.100	T	J702C - J704T	.043

CONTINUITY CHECK:All circuits indicated continuity . . . Yes No See Notes

4.2.1.1d +160°F w/ 95% RH
 Proof Cycle @ ambient pressure

B

Date: 7-30-59Page: 33Test Env: Rita Mobley

Report 7A2236

VAC Insp: NAISAY Insp: NA

VOLTAGE (KV)

Minimum Control Voltage (25 V.)

		Switch in External Position		Switch in Internal Position			
No.	Switch	Date	Switch	Circuit	Date	Switch	
A	J7010 - J7010	.113	A	J7011 - J7010	.159		
B	J701F - J705L	.129	I	J7011 - J705L	.166		
C	J702F - J705L	.135	G	J7011 - J705X	.174		
D	J703G - J705J	.127	H	J7011 - J705J	.172		
E	J706F - J705C	.126	S	J7011 - J7010	.163		
F	J706E - J705A	.094	T	J7011 - J705A	.056		
G	J706C - J705B	.094	P	J7011 - J705B	.074		
H	J707 - J708	.095	R	J7011 - J708	.036		
I	J706A - J705X	.120	N	J7011 - J705X	.073		
J	J706S - J705K	.083	J	J7011 - J705K	.028		
K	J705C - J705I	.120	L	J7011 - J705I	.065		
L	J706H - J705M	.145	M	J7011 - J705P	.061		
M	J705 - J705P	.140	N	J7011 - J705R	.081		
N	J706C - J705R	.130	O	J7011 - J705R	.085		
O	J706 - J705A	.122	P	J7011 - J705A	.088		
P	J706 - J705C	.110	Q	J7011 - J705C	.054		
Q	J706 - J705I	.166	R	J7011 - J705I	.059		
R	J706 - J705S	.124	S	J7011 - J705S	.092		
S	J706 - J705P	.112	T	J7011 - J705P	.056		
T	J706 - J705	.100	U	J7011 - J705	.042		

B

4.2 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Undetermined - See date: 7/30/59Specimen S/N 001 IGEUTICS Re-test Test Engr: MCGEE-LAVENDER-LAWSON
CVAC Ingr: DA
KDP Ingr: NH

Paragraph	Specification Requirement	Remarks
4.2.1.1 d)	+160°F Hot test Proof cycle @ 1 mm Hg.	
1.4	Operating Time: Start <u>1154</u> hrs. Stop <u>1159</u> hrs. Assembly Cycles <u>10</u> Start _____ hrs. Stop _____ hrs.	

Notes:

1. (1.4 mm) Hg AT THE END OF (10 MIN.)
2. AC switch transfer time and cycle sequence not recorded during this run because of test-set-up problems. See re-run of test made on 8-3-'59.

Para. 4.49
 For para. 4.2.11.d Specimen S/N 001 Kinetics Date: 7-30-59
 Engineer: Harrison Lawrence
 CVAC Insp: N/A
 USAF Insp: N/A

- Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control voltage	Para b.1.c step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle Int. to Ext. Ext. to Int.
10V	3	.254	3 max	X X X X
15V	4	.243	3 max	X X X X
30V	5	.132	2 max	X X X X
30V	1	.15	2 max	X X X X
25V	1	.13	2 max	X X X X
25V	1	.171	2 max	X X X X

CIRCUITRY ATTEMPT

All circuits satisfactory - - - - - NA YES NO

INSULATION RESISTANCE

All circuits measured greater than 10 megohms - - - YES NO

SWITCH COORDINATION AND HOMOCYCLEDENCY

All switches satisfactory

Para b.1.c step	YES	NO see note	Switch position Internal External
1	X X X X		X X X X
1	X X X X		X X X X
1	X X X X		X X X X

CYCLE STEPWISE TIMES (20 : seconds minimum)

External to Internal - - - milliseconds See 1E-12A of
 Internal to External - - - milliseconds this test E-3-'59

POSITION TRANSFER TIMES (15 milliseconds maximum)

Circuit Chan. No.	C.E.C.	In to Rx	Rx to In
P11	I		
P32	G		
P30	H		
P36	I		
P10	J		
P18	K		
P20	L		
P25	M		

Circuit Chan. No.	C.P.C.	In to Rx	Rx to In
P12	N		
P22	O		
P34	P		
P14	Q		
P16	R		
P28	S		
P38	T		

COMINAR
SAN DIEGO

4.2.1.7 d. +160° C

FORM 18

VOL

VOLTAGE DROP:		Maximum Control Voltage (30 V.)		VOL	
Switch in External Position		Switch in Internal Position			
SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA
A	J710 - J7212	0.115	A	J701A - J701B	0.159
B	J701P - J7051	0.132	B	J701A - J7051	0.169
C	J705T - J705X	0.134	C	J701A - J705X	0.170
D	J706 - J7053	0.124	D	J701A - J7053	0.175
E	J707 - J7050	0.168	E	J701A - J7050	0.166
F	J708A - J7081A	0.044	F	J702A - J7024	0.056
G	J708 - J7081	0.125	G	J702B - J702D	0.074
H	J708P - J708P	0.130	H	J702B - J7024	0.236
I	J709 - J709C	0.162	I	J703C - J703A	0.080
J	J709 - J709X	0.088	J	J703C - J703A	0.028
K	J709 - J7091	0.142	K	J703A - J703C	0.369
L	J710 - J710M	0.130	L	J704A - J704X	XH + 300°C 0.69
M	J710P - J710P	0.175	M	J704A - J704X	0.082
N	J710E - J710F	0.134	N	J704B - J704X	0.281
O	J710 - J7104	0.120	O	J704B - J704A	0.388
P	J710 - J710C	0.113	P	J704B - J704C	0.054
Q	J710 - J710I	0.122	Q	J704B - J704C	0.060
R	J710P - J710A	0.126	R	J704A - J704C	0.092
S	J710A - J710B	0.112	S	J704B - J704A	0.056
T	J710 - J710T	0.102	T	J704C - J704A	0.044

CONTINUITY CHECK

All circuits indicated continuity . . . See A See Notes

i80 CHANGE OVER WIRE ATTENTED BUT
POWER SUPPLY OUTPUT WAS OFF.

115.6 SPECIMEN TEMP. +200°F

PRESSURE IN 43 1.4 MM Hg AND LOADS WERE
REMOVED TO ALLOW SPECIMEN TO COO - OFF

COOLED FOR (10 MIN) TEMP. CONT. TO CLIMB TO 210°F
HEATING RODS IN TEMP. CHAMBER WERE LEFT
ON AND COULD HAVE POSSIBLY CAUSED RADIENT
HEAT ON THE SPECIMEN

A

Date 7-30-59Page 36Test Engr: Mobley, Leenderd/Hanson Report 7A2236

60° @ 1 mil Hg.

VAC Insp: NASAP Insp: NA

VOLTAGE DROPS

Minimum Control Voltage (25 V.)

Spec. No.	Switch in External Position		Switch in Internal Position		Action
	Series	Parallel	Series	Parallel	
A	J701C - J701D	0.113	J701A - J701D	0.153	
B	J701F - J705L	0.131	J701A - J705L	0.171	
C	J702G - J705L	0.157	J701A - J705X	0.124	
D	J702E - J705L	0.130	J701A - J705Y	0.170	
E	J704F - J705C	0.130	J701A - J705Z	0.166	
F	J702A - J705A	0.045	J701A - J705A	0.058	
G	J701C - J705B	0.148	J701A - J705B	0.076	
H	J701Y - J705L	0.102	J701A - J705L	0.038	
I	J702G - J705C	0.143	J701A - J705C	0.082	
J	J702C - J705L	0.033	J701A - J705L	0.027	
K	J702G - J705L	0.126	J701A - J705L	0.067	
L	J702F - J705Y	0.132	J701A - J705Y	0.078	
M	J702E - J705P	0.147	J701A - J705P	0.085	
N	J701C - J705B	0.156	J701A - J705B	0.089	
O	J701A - J705A	0.120	J701A - J705A	0.070	
P	J702A - J705C	0.112	J701A - J705C	0.056	
Q	J702A - J705L	0.108	J701A - J705L	0.063	
R	J701A - J705S	0.121	J701A - J705S	0.094	
S	J702G - J705L	0.116	J701A - J705L	0.058	
T	J701A - J705L	0.105	J701A - J705L	0.045	

M.M. SPECIMEN TEMP BEFORE HOLE WERE DRILLED OFF
 224°F.

°F

T

ADJUST

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N 001 Kinetics
Corp. SpecimenDate: 7-31-59
Test Engr: R. T. Hobley
CVAC Insp: N/A
USAF Insp: N/A

Paragraph	Specification Requirement	Remarks
4.2.1.1e	+40° w/ 95% RH	Specimen temp. at beginning of proof cycle +45°F
1.4	Operating Time: Start 115.4 hrs. Stop 14 hrs. Assembly Cycles 8 Start _____ hrs. Stop _____ hrs.	

Notes:

Para. 4.1.9
 Per para. 4.1.1(e) Specimen S/N 001
 Kinetics Corp.

Date: 7-31-'59
 Engineer: E.T. Nohley
 CVAC Insp: -----
 USAF Insp: NA

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Central voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle
				Int. to Ext. Ext. to Int.
15V	1	.205	1 max	
15V	4	.223	1 max	X X
30V	5	.113	2 max	X X
30V	1	.112	2 max	X X
25V	1	.155	1 max	X X
25V	1	.053	2 max	X X

Dielectric Strength:

All circuits satisfactory - - - Could not accomplish NO

Insulation Resistance:

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NON-CONTINUITY:

All switches satisfactory

Para 4.1.8 step	IES	RO see note	Switch position
			Internal External
1			X X
1			X X
1			X X
1			X X

CYCLE SEQUENCE TIME (20 milliseconds minimum)

External to Internal 48 milliseconds

Internal to External 40 milliseconds

POSITION TRANSFER TIME (15 milliseconds maximum)

Circuit Chan. No.	In to Rx	Rx to Tx
P14	1	6
P32	0	6
P30	0	7.5
P34	1	3.5
P40	1	11.5
P18	1	6
P20	0	6
P26	0	2.5

Circuit Chan. No.	In to Rx	Rx to Tx
P12	1	2.5
P22	0	0
P34	0	6
P44	0	7
P16	1	5
P28	1	9
P38	1	2.5

CORVVAIR
SAN DIEGO

FORM 11

VOLTAGE DROP:

Maximum Control Voltage (30 V.)

VOLT

SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA
A	J701C - J701D	0.093	A	J701A - J701D	149
B	J706P - J705L	0.119	B	J701A - J705L	153
C	J706T - J705K	0.136	C	J701A - J705K	0.177
D	J706 - J705J	0.112	D	J701A - J705J	0.159
E	J706P - J705G	0.112	E	J702A - J703C	0.153
F	J706A - J703A	0.066	F	J702A - J703A	0.072
G	J706C - J703D	0.100	G	J702B - J703B	0.166
H	J706Y - J703F	0.073	H	J702B - J703F	0.016
I	J706A - J703G	0.100	I	J702C - J703C	0.070
J	J706F - J703K	0.060	J	J702C - J703K	0.021
K	J706G - J703L	0.100	K	J702A - J703L	0.052
L	J706H - J703M	0.110	L	J702A - J703M	0.052
M	J706W - J703P	0.110	M	J702B - J703P	0.011
N	J706E - J703F	0.108	N	J702C - J703B	0.076
O	J706J - J704A	0.108	O	J702A - J704A	0.078
P	J706d - J704C	0.090	P	J702B - J704C	0.045
Q	J706R - J704J	0.082	Q	J702C - J704J	0.049
R	J706F - J704N	0.155	R	J702A - J704N	0.281
S	J706X - J704R	0.097	S	J702B - J704R	0.046
T	J706b - J704T	0.081	T	J702C - J704T	0.036

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See Notes

4.2.1.1e +40°F @ 95% R.H.

A

Date: 7-31-'59Page 39Test Enter: R.T. Mobley

Report 7A2236

EVAC Insp: NAIB&P Insp: NA

VOLTAGE DROF:

Minimum Control Voltage (25 V.)

S/N. NO.	Switch in External Position		Switch in Internal Position		
	CIRCUIT	DATA	S/N. NO.	CIRCUIT	DATA
A	J701C = J701D	0.091	1	J701A = J701D	0.143
B	J702P = J703L	0.119	2	J701A = J705L	0.151
C	J703P = J705K	0.190	3	J701A = J705K	0.174
L	J700S = J705J	0.144 0.114	4	J701A = J705J	0.154
E	J706R = J702C	2.111	5	J701A = J705C	0.150
F	J706E = J703A	0.067	6	J702A = J703A	0.140 now 0.041
O	J700C = J703D	0.105	7	J702B = J703D	0.065 now 0.064
H	J702Y = J702T	0.076	8	J702A = J703E	0.065 now 0.025
I	J706A = J703C	0.100	9	J702E = J703C	0.082 now 0.068
J	J706F = J703K	0.061	10	J702E = J703K	0.082 now 0.020
K	J702C = J703L	0.104	11	J702A = J703L	0.140 now 0.056
L	J706H = J702M	0.110	12	J702A = J703M	0.140 now 0.059
M	J704P = J703P	0.114	13	J702B = J703P	0.065 now 0.069
N	J706P = J703P	0.110	14	J702B = J703R	0.082 now 0.073
U	J706L = J704A	0.102	15	J702A = J704A	0.076
P	J706U = J704C	0.091	16	J702B = J704C	0.044
X	J706 = J704I	0.085	17	J702C = J704I	0.048
R	J704T = J704S	0.113	18	J702A = J704R	0.080
S	J700T = J704B	0.095	19	J702B = J704B	0.045
T	J702I = J704T	0.084	20	J702C = J704I	0.035

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Sat. Re-Test Date: 7-31-59

Specimen S/N 001. KINETICS

Test Engn: HARLEY-HANSON-LAUENPERZ
CVAC Instr: _____
ISAP Instr: NA

Paragraph	Specification Requirement	Remarks
4.2.1.1C	- 30°F @ 1mm Hg. Re-run of 001.	
1.4	Operating Time: Start 116.9 hrs. Stop 116.8 hrs. Assembly Cycles 8 Start _____ hrs. Stop _____ hrs.	

- Notes:**
1. Reached 1.7mm Hg. in 10 min. Specimen at -29°F
 2. SPECIMEN TEMP. AT END OF First Cycle +13°F

CONVAIR ASTRONAUTICS

REPORT 7A2296

PAGE 41

Para. 9469 Re-Test

For para. 92116 Specimen S/N 001 Kinetics

Date: 5/1/59

Engineer: P.T. Mobley

Corp. Spec. CVAC Insp: -----

USAF Insp: N/A

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 9469 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle	Int. to Ext.	Ext. to Int.
15V	3	.395	1 MAX			
18V	6	.204	1 MAX			
30V	?	.180	2 MAX			
30V	1	.149	2 MAX			
25V	1	.163	2 MAX			
25V	1	.164	2 MAX			

DIELECTRIC STRENGTH:All circuits satisfactory - Could not do YES NO INSULATION RESISTANCE:All circuits measured greater than 10 megohms - Could not do YES NO SWITCH CONTINUITY AND NON-CONTINUITY

All switches satisfactory

Para 9469 step	I.R.S.	NO see note	Switch position	Internal External
1				
1				
1				

CYCLE SEQUENCE TIME: (20 milliseconds minimum)

External to Internal 50 milliseconds

Internal to External 45 milliseconds

POSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit Chan. No.	C.E.C.	In to Ex	Ex to In
P14	F	8	7
P32	G	6	6.5
X30	H	5	5.0
P36	I	4.5	4.5
P12	J	12	10.5
P18	K	8.5	9.5
P20	L	11	7
P26	M	5	3.5

Circuit Chan. No.	C.E.C.	In to Ex	Ex to In
P12	N	3	3.5
P22	O	10	8.0
P34	P	2.5	6.5
P46	Q	11	9.0
P16	R	7	6.0
P28	S	13	11.0
P31	T	11	2.2

CONVAIR
SAN DIEGO

VOLTAGE DROPS:		Maximum Control Voltage (30 V.)		VOL.	
Switch in External Position		Switch in Internal Position			
SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA
A	J701C - J701D	0.082	A	J701A - J701D	0.147 0.132
B	J701F - J705L	0.119	B	J701A - J705L	0.122 0.149
C	J720T - J722K	0.112	C	J701A - J705K	0.147
D	J726 - J705I	0.109	D	J701A - J725I	0.149
E	J725F - J725G	0.104	E	J701A - J725G	0.139
F	J702A - J702B	0.058	F	J702A - J702B	0.036
G	J702C - J702D	0.098	G	J702A - J702D	0.060
H	J702A - J702F	0.064	H	J702A - J702G	0.020
I	J702H - J702G	0.044	I	J702C - J720C	0.063
J	J702F - J722K	0.053	J	J702C - J702E	0.017
K	J702G - J722L	0.045	K	J702A - J722L	0.050
L	J702H - J703M	0.100	L	J702A - J703M	0.053
M	J702W - J701P	0.120	M	J702A - J723P	0.064
N	J702X - J720X	0.100	N	J702C - J720X	0.064
O	J702Y - J704A	0.495	O	J702A - J704A	0.072
P	J702Z - J704C	0.090	P	J702F - J704C	0.039
Q	J704A - J704J	0.073	Q	J702C - J704J	0.042
R	J704F - J704S	0.045	R	J702A - J724N	0.074
S	J704I - J704P	0.086	S	J702B - J724S	0.040
T	J704T - J704T	0.074	T	J702C - J704T	0.030

CONTINUITY TEST

All circuits indicated continuity . . . Yes No See Notes

9.2.1.10) Re-Test -30°F @ 1mm Hg.

A

Date: 7-31-'59Page 42Test Engr: Rita Nobley

Report 7A2236

IVAC Insp: NAISAF Insp: NA

VOLTAGE TEST

Minimum Control Voltage (25 V.)

No. No.	Switch in External Position		Switch in Internal Position	
	DATA	Series	DATA	Series
A	J701A - J701B	0.085	J701A - J701D	0.129
B	J701F - J701L	0.118	J701A - J705L	0.153
C	J701E - J705E	0.113	J701A - J705X	0.154
D	J701A - J705I	0.108	J701A - J705I	0.119
E	J701E - J705C	0.106	J701A - J705G	0.142
F	J701A - J705A	0.054	J701A - J705A	0.050
G	J701A - J705B	0.042	J701A - J705B	0.043
H	J701A - J705F	0.066	J701A - J705F	0.020
I	J701A - J705C	0.014	J701A - J705C	0.065
J	J701E - J705X	0.054	J701A - J705L	0.017
K	J701C - J705I	0.075	J702A - J705L	0.051
L	J701F - J705K	0.040	J702A - J705M	0.055
M	J701A - J705P	0.100	J702A - J705P	0.065
N	J701A - J705B	0.077	J702A - J705B	0.070
O	J701A - J705A	0.095	J702A - J705A	0.071
P	J701A - J705C	0.040	J702A - J705C	0.040
Q	J701A - J705H	0.014	J702A - J705H	0.047
R	J701A - J705N	0.049	J702A - J705X	0.077
S	J701A - J705J	0.027	J702A - J705Y	0.044
T	J701A - J705	0.015	J702A - J705I	0.051

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

Re-test
 General Test Results: Satisfactory Date: 8-3-'51
 Specimen S/N 001. Kinetics Corp. Test Engr: Kelli Mobley
 Specimen CVAC Insp: _____ USAP Insp: NA

Paragraph	Specification Requirement	Remarks
4.2.1.1 d	+160°F Hot test @ 1mm Hg. Re-run of this test on SN 001	
1.4	Operating Time: Start <u>116.8</u> hrs. Stop _____ hrs. Assembly Cycles: 10 Start _____ hrs. Stop _____ hrs.	

Notes: 1. Achieved 1mm Hg. in 4½ minutes
 2. CEC run I to E to I Aug #. 151
 3. The specimen was inspected prior to performing this test. It was noted that the potting had expanded and was expanded out of the potting molds. A Hypot test was run at the end of the first cycle to determine if any damage had been done to the dielectric strength within potting cement.

Para. 4.1.9 Re-Test

For para. 2.1.1d Specimen S/N 001 Kinetics Date: 8-3-59
 Corp. Specimen Engineer: R. T. Mobley
 CVAC Insp: ----- USAF Insp: NA

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para b.1.c stop	Time (seconds)	tolerance (seconds)	Type of assembly cycle	
				Int. to Ext	Ext. to Int
18V	4	2.87	1 max		
18V	4	2.42	1 max		
30V	1	1.18	2 max		
30V	1	1.41	2 max		
25V	1	1.52	2 max		
25V	1	1.52	2 max		

DIELECTRIC STRENGTH

All circuits satisfactory - Performed at end of ^{TEST} Proof Cycle NO

INSULATION RESISTANCE

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NON-CONTINUITY

All switches satisfactory

Para b.1.c stop	IES	See note	Switch position	
			Internal	External
4				
1				
1				
1				

CYCLE SEQUENCE TIME (20 milliseconds minimum)

External to Internal 5.81 milliseconds

Internal to External 6.16 milliseconds

POSITION TRANSFER TIME (15 milliseconds maximum)

C.S.C.	In to Ex	In to In
P14	9.81	8.03
P32	12.15	8.92
P30	11.05	8.92
P36	6.30	3.29
P12	12.40	10.0
P11	8.60	10.15
P20	9.30	8.82
P26	5.10	4.26

Circuit Item No.	C.F.C.	In to Ex	Ex to In
P42	N	1.61	1.31
P22	O	11.82	12.42
P34	P	12.10	14.02
P44	Q	12.12	12.12
P16	R	1.88	1.48
P18	S	6.08	11.18
P18	T	1.90	1.11

CORVAN
SAFII OREGO

VOLTAGE DROP:

Maximum Control Voltage (30 V.)

VOLT.

SN. NO.	CIRCUIT	Switch in External Position		Switch in Internal Position		No.
		DATA	SN. NO.	CIRCUIT	DATA	
A	J701G - J701D	0.108	A	J701A - J701D	0.147	A
B	J706E - J705L	0.127	B	J702A - J705L	0.122	B
C	J706T - J705K	0.132	C	J701A - J705K	0.173	C
D	J706 - J705J	0.127	D	J701A - J705J	0.120	D
E	J706F - J705C	0.122	E	J702A - J705C	0.160, 167	E
F	J706B - J702A	0.100	F	J702A - J704A	0.051	F
G	J706C - J702D	0.123	G	J702B - J704D	0.027	G
H	J706Y - J702F	0.106	H	J702B - J704F	0.034	H
I	J706a - J703C	0.122	I	J702C - J703C	0.083	I
J	J706f - J703X	0.090	J	J702E - J703K	0.023	J
K	J706G - J702I	0.122	K	J702A - J703L	0.020	K
L	J706H - J703M	0.130	L	J702A - J703M	0.026	L
M	J706W - J701P	0.141	M	J702B - J703P	0.084	M
N	J706Z - J702F	0.133	N	J702C - J703B	0.088	N
O	J706J - J704A	0.130	O	J702A - J704A	0.088	O
P	J706d - J704C	0.114	P	J702B - J704C	0.058	P
Q	J706R - J704J	0.105	S	J702C - J704J	0.061	Q
R	J706P - J704N	0.131	R	J702A - J704N	0.089	R
S	J706X - J704R	0.115	S	J702B - J704R	0.060	S
T	J706b - J704T	0.102	T	J702C - J704T	0.046	T

CONTINUITY CHECK:

All circuits indicated continuity . . . Test No See notes

4.2.1.1(d) +160°F Hot test @ 1mm Hg.

Re-run of this test on SN 001

A

Date: 8-3-'59Page 45Test Engnr: R.T. Mobley

Report 7A2236

CVAC Insp: NAIBAF Insp: NA

VOLTAGE DROPS:

Minimum Control Voltage (25 V.)

Bn. No.	Switch in External Position		Switch in Internal Position		
	CIRCUIT	DATA	CIRCUIT	DATA	
A	J701C - J701D	0.102	A	J701A - J701D	0.143
B	J701F - J705L	0.130	B	J701A - J705L	0.169
C	J705I - J705K	0.134	C	J701A - J705K	0.172
D	J706S - J705J	0.129	D	J701A - J705J	0.169
E	J706R - J705C	0.124	E	J701A - J705C	0.165
F	J702E - J703A	0.098	F	J702A - J703A	0.051
G	J702C - J703D	0.120	G	J702A - J703D	0.076
H	J721Y - J721E	0.102	H	J702A - J703E	0.035
I	J726A - J723C	0.118	I	J702C - J703C	0.081
J	J726F - J723K	0.087	J	J702C - J723K	0.023
K	J726C - J703L	0.120	K	J702A - J703L	0.069
L	J726H - J703M	0.124	L	J702A - J703M	0.075
M	J724 - J703P	0.135	M	J702A - J703P	0.062
N	J724 - J703R	0.130	N	J702A - J703R	0.087
O	J724 - J704A	0.124	O	J702A - J704A	0.086
P	J725E - J724G	0.110	P	J702A - J704C	0.057
Q	J726 - J704I	0.101	Q	J702A - J704J	0.060
R	J726F - J704J	0.126	R	J702A - J704A	0.087
S	J706T - J706R	0.110	S	J702A - J704I	0.060
T	J721 - J707	0.100	T	J702A - J704I	0.045

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N ~~001~~. Kinetics Corp.
SpecimenDate: 10-16-67
Test Engr: John Moody
CVAC Insp: NH
USAP Insp: NH

Paragraph	Specification Requirement	Remarks
4.4	Post Acceleration Flight test	Midwest Recording, I-E-I Mag. # 137 record # 876
1.4	Operating Time: Start <u>10:01</u> hrs. Stop <u>10:25</u> hrs. Assembly Cycles 24 Start _____ hrs. Stop _____ hrs.	

Notes: 1. Results of Operating Acceleration
were completely satisfactory.

Para. 4.4

For para. 4.4 Specimen S/N C-1

Date: 10-10-57
Engineer: K. L. Mobley
CVAC Insp: _____
USA: Insp: _____

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control Para 4.1.6 voltage	Para 4.1.6 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle Int. to Ext. Ext. to Int.
15V	A	.130	1 max	
15V	A	.137	1 max	
30V	B	.072	2 max	
30V	C	.072	2 max	
25V	D	.095	2 max	
25V	E	.103	2 max	

DIELECTRIC STRENGTH

All circuits satisfactory - - - - - YES 

INSULATION RESISTANCE

All circuits measured greater than 10 megohms - - - YES 

SWITCH CONTINUITY AND NON-CONTINUITY

All switches satisfactory

Para 4.1.6 step	YES	NO see note	Switch position External to Internal

SWITCH SEQUENCE TIME (20 milliseconds minimum)

External to Internal 5.2 milliseconds

Internal to External 5.0 milliseconds

POSITION TRANSFER TIME (15 milliseconds maximum)

C.R.C. Circuit No.	In to Ex	Ex to In
P1	1.4	4.2
P3	1.4	2.2
P5	1.4	2.3
P24	1.4	1.4
P21	2.2	4
P18	2.1	6.4
Z10	2.2	4.5
P36	2.5	3.5

C.R.C. Circuit No.	In to Ex	Ex to In
P12	1.6	3.5
P12	1.8	2.5
P14	1.5	1.6
P12	1.7	8.5
P15	1.7	8.5
P12	1.7	7.2
P18	1.7	7.2

CONNAM
SAN DIEGO

FORM 11

VOLTAGE DROP:

Maximum Control Voltage (30 V.)

VOLT

Switch in External Position		Switch in Internal Position				
SM. NR.	CIRCUIT	DATA	SM. NR.	CIRCUIT	DATA	SM. NR.
A	J701G - J702R	0.108	A	J701A - J701D	0.141	A
B	J706R - J705L	0.068.126	B	J701A - J705L	0.159	B
C	J706T - J705K	2.055.141	C	J701A - J705K	0.174	C
D	J706 - J705J	2.064.152	D	J701A - J705J	0.164	D
E	J704 - J705C	NA SEE NOTE 5	E	J701A - J705C	2. NA SEE NOTE 5	E
F	J706B - J702A	0.290	F	J702A - J704	0.053	F
G	J706C - J702D	0.112	G	J702B - J704	0.066	G
H	J706Y - J702F	0.186	H	J702A - J704F	0.031	H
I	J706H - J702G	0.105	I	J702C - J703K	0.012	I
J	J706I - J702K	0.036	J	J702C - J703K	0.028	J
K	J706G - J702L	0.112	K	J702A - J703L	0.063	K
L	J706H - J702M	2.111	L	J702A - J703M	0.066	L
M	J706W - J702P	0.104	M	J702B - J703P	0.062	M
N	J706S - J702P	1.110	N	J702C - J703P	0.275	N
O	J706C - J704A	0.115	O	J702A - J704A	0.074	O
P	J706C - J704C	0.041	P	J702B - J704C	0.052	P
Q	J706R - J704J	0.045	Q	J702C - J704J	0.051	Q
R	J706P - J704N	0.118	R	J702A - J704N	0.080	R
S	J704X - J704R	0.039	S	J702B - J704R	0.032	S
T	J706B - J704T	0.061	T	J702C - J704T	0.039	T

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See Notes

except 1 D.C. ckt. SEE AS
THE

4. 4 Post 4 Post

De-681 IC-16-52 Page 46
 Test Eng'g: C. T. Mobley Report 7A2236
 CVAC Insp: NA USAP Insp: NA

VOLTAGE DROPS:

Minimum Control Voltage (25 V.)

No. & R.	Switch in Internal Position		No. & R.	Switch in Internal Position	
	CIRCUIT	DATA		CIRCUIT	DATA
A	J701C - J701D	0.111	A	J701A - J701D	0.146
B	J702P - J703L	0.129	B	J702A - J703L	0.164
C	J704S - J705K	0.142	C	J703X - J705X	0.179
D	J705G - J705J	0.133	D	J703A - J705J	0.167
E	J706P - J705C	NA	E	J701A - J705C	NA *
F	J706Z - J703A	0.073	F	J702A - J703A	0.055
G	J706C - J703D	0.111	G	J702P - J703D	0.267
H	J706Y - J703F	0.103	H	J702A - J703F	0.040
I	J703A - J703G	0.108	I	J702Z - J703G	0.073
J	J706S - J703K	0.093	J	J703G - J703K	0.029
K	J706C - J702L	0.110	K	J702A - J703L	0.054
L	J706H - J703M	0.111	L	J702A - J703M	0.063
M	J706I - J702P	0.105	M	J702B - J703P	0.062
N	J706T - J703R	0.118	N	J702C - J703R	0.016
O	J706J - J704L	0.115	O	J702A - J704A	0.080
P	J706L - J704C	0.099	P	J702A - J704C	0.054
Q	J706N - J704L	0.110	Q	J702C - J704L	0.060
R	J706E - J704S	0.118	R	J702A - J704S	0.030
S	J706X - J704B	0.130	S	J702B - J704B	0.057
T	J706V - J704T	0.091	T	J702C - J704T	0.040

See Note on 1st of
these 3 sheets

B:

CONVAIR ASTRONAUTICS

REPORT 7A2236

PAGE 89

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory Date: 10-19-59
 Specimen S/N 001. Kinetics Test Engr: R.T. Melby
 CVAC Insp: NA
 USAP Insp: NA

Paragraph	Specification Requirement	Remarks
4.5	Life Test	
1.4	Operating Time: Start _____ hrs. Stop _____ hrs.	
	Assembly Cycles Start _____ hrs. Stop _____ hrs.	

Note: 1. The following two data sheets contain voltage drop data measured at 350 assembly cycles and at 500 assembly cycles.

COORSAN
SAN DIEGO

Room 71

VOLTAGE DROP:		Maximum Control Voltage (29.5)		WOL	
Switch In External Position		Switch In Internal Position			
SN. NO.	CIRCUIT	DATA	SN. NO.	CIRCUIT	DATA
A	J701C - J701D	.103	A	J701A - J701D	.124
B	J706B - J705L	.120	B	J701A - J705L	.141
C	J706T - J705K	.139	C	J701A - J705K	.154
D	J706S - J705J	.122	D	J701A - J705L	.143
E	J706B - J705G	N/A	E	J702A - J705G	N/A
F	J706A - J703A	.088	F	J702A - J704H	.052
G	J706C - J703D	.108	G	J702B - J704D	.064
H	J706Y - J703Y	.096	H	J702B - J704F	.049
I	J706A - J703C	.105	I	J702C - J703C	.071
J	J706E - J703K	.080	J	J702C - J703K	.022
K	J706C - J703L	.108	K	J702A - J703L	.064
L	J706B - J703M	.29	L	J702A - J703M	.062
M	J706W - J702P	.104	M	J702A - J703P	.261
N	J706S - J703R	.114	N	J702C - J703R	.073
O	J706T - J704L	.115	O	J702A - J704L	.082
P	J706A - J704C	.095	P	J702B - J704C	.052
Q	J706R - J704J	.097	Q	J702C - J704J	.058
R	J706F - J704H	.115	R	J702A - J704N	.081
S	J706A - J704R	.096	S	J702B - J704E	.055
T	J706B - J704T	.089	T	J702C - J704T	.040

CONTINUITY CHECK:

All circuits indicated continuity. N/A No See Notes

Life Test: Voltage drop: at 350 assembly cycles, control voltage at 29.5 volts first reading in the 1st position, made one assembly cycle to int. position.

Cont. life cycling of specimen

1. Voltage drop measurements made the normal way, using test set.

A

Date: 19 Oct 1959Page 50Test Engt: E. T. Mackay

Report 7A2236

CVAC Insp: NAISAP Insp: NA

VOLTAGE DROPS:

Minimum Control Voltage (25 V.)

SL. NO.	Switch in External Position			Switch in Internal Position		
	CIRCUIT	DATA	SL. NO.	CIRCUIT	DATA	
A	J701C = J701D	NA	1	J701A = J701D	NA	
B	J704E = J705L		2	J701E = J705L		
C	J706T = J705K		3	J701L = J705K		
D	J706S = J705J		4	J701A = J705J		
E	J706F = J705G		5	J701A = J705G		
F	J706E = J703A		6	J702A = J703A		
G	J706G = J703D		7	J702B = J703D		
H	J706Y = J702F		8	J702B = J703E		
I	J706a = J703G		9	J702C = J703G		
J	J706f = J703K		10	J702C = J703K		
K	J706C = J703L		11	J702A = J703L		
L	J706H = J703M		12	J702A = J703M		
M	J706W = J703P		13	J702D = J703L		
N	J706g = J703R		14	J702D = J703R		
O	J706i = J704A		15	J702A = J704A		
P	J706j = J704G		16	J702A = J704G		
Q	J706Z = J704J		17	J702B = J704J		
R	J706Z = J704N		18	J702A = J704N		
S	J706X = J704R		19	J702B = J704R		
T	J702I = J704I	V	20	J702C = J704I	V	

B

COMPAK
SAN DIEGO

Directly across contacts at 500 cycles

VOLTAGE DROP:

Normal Control Voltage (30 v.)

VOLTA

SW. NR.	CIRCUIT	DATA	Switch in External Position		Switch in Internal Position		SW. NR.
			SW. NR.	CIRCUIT	DATA	VOLTA	
A	J7010 - J701D	.033	A	J701A - J701D	.053	A	
B	J706P - J705L	.011	B	J701A - J705L	.055	B	
C	J706T - J705K	.039	C	J701A - J705K	.055	C	
D	J706S - J705J	.046	D	J701A - J705J	.056	D	
E	J706R - J705C	This circuit NG	E	J701A - J705C	This circuit NG	E	
F	J706M - J703A	.007	F	J702A - J703A	.011	F	
G	J706N - J703D	.007	G	J702B - J703D	.009	G	
H	J706Y - J703F	.007	H	J702B - J703F	.010	H	
I	J706G - J703C	.007	I	J702C - J703C	.011	I	
J	J706F - J703K	.013	J	J702C - J703K	.009	J	
K	J706G - J703L	.007	K	J702A - J703L	.014	K	
L	J706H - J703M	.007	L	J702A - J703M	.010	L	
M	J706W - J703P	.025	M	J702B - J703P	.012	M	
N	J706Z - J703R	.006	N	J702C - J703R	.011	N	
O	J706J - J704A	.007	O	J702A - J704A	.010	O	
P	J706D - J704C	.010	P	J702B - J704C	.011	P	
Q	J706A, J704J	.006	Q	J702C - J704J	.010	Q	
R	J706P - J704H	.010	R	J702A - J704H	.011	R	
S	J706X - J704R	.008	S	J702B - J704R	.012	S	
T	J706B - J704I	.006	T	J702C - J704I	.010	T	

CONTINUITY CHECK:

All circuits indicated continuity. NA Yes No See Notes

Voltage drop readings made at end of life test directly across contacts (1st & 2nd columns) using id. test set 3.1% & 10 ohms.

A

Date: 11-6-59Page 51Test Ingr: R. T. Mobley

Report 7A2236

CVAC Ingr: NAISAF Ingr: NA

VOLTAGE DROP:

Minimum Control Voltage (25%) - Made using test set up at 300 Cycles

Switch in External Position			Switch in Internal Position		
SN. NO.	CIRCUIT	DATA	SN. NO.	CIRCUIT	DATA
A	J701C - J701D	0.105	A	J701A - J701D	0.121
B	J706P - J705L	0.104 0.123	B	J701A - J705L	0.141
C	J706T - J705X	0.423 0.136	C	J701A - J705X	0.141
D	J706S - J705J	0.134	D	J701A - J705J	0.144
E	J706R - J705G	NA	E	J701A - J705G	NA
F	J706Z - J703A	0.090	F	J702A - J703A	0.027
G	J706e - J703D	0.093	G	J702B - J703D	0.227
H	J706Y - J703F	0.100	H	J702B - J703F	0.211
I	J706n - J703G	0.053	I	J702C - J703G	0.267
J	J706r - J703K	0.070 110	J	J7032 - J703K	0.232
K	J6C - J703L	0.110	K	J702A - J703L	0.063
L	J706H - J703M	0.110	L	J702A - J703M	0.260
M	J706W - J703P	0.150	M	J702B - J703P	0.211
N	J706f - J703R	0.110	N	J702B - J703R	0.201
O	J706J - J704A	0.110	O	J702A - J704A	0.231
P	J706d - J704C	0.100	P	J702B - J704C	0.223
Q	J706B - J704J	0.014	Q	J702A - J704J	0.230
R	J706K - J704N	0.125	R	J702A - J704N	0.267
S	J706x - J704P	0.130	S	J702B - J704P	0.235
T	J706p - J704T	0.313	T	J702C - J704T	0.273

at Cad

1053

1000

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N Kinetics Corp. 002

Date: 19 July 1954
Test Engn: R. T. Mobley
CVAC Instr: NA
USAF Instr: NA

Paragraph	Specification Requirement	Remarks
4.1.8	Initial Satisfactory Performance Test	
1.4	Operating Time: Start <u>101.8</u> hrs. Stop <u>108.3</u> hrs. Assembly Cycles 16 Start <u>NA</u> hrs. Stop <u>NA</u> hrs.	

Note: 1. An Initial Satisfactory performance test and Ambient Conditions frost cycle were run on this specimen 4-14-54, and the specimen failed on the latter test. The specimen was then sent to the plant for repair. Unit 2 was received in Engineering, Stock No. 7482 and test sheet not used.

CONVAIR ASTRONAUTICS

REPORT 7A2236
PAGE 53

Para. 4.1.8
 Per para. 4.4.8 Specimen S/N All Kinetics Corp. Specimen Date: 14 July 1959
Engineering 24944/RT Assembly
CVAC Insp: N/A

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle	Int. to Ext.	Ext. to Int.
18V	A	.195	1 max			
18V	I	.102	1 max	X		
30V	F	.122	2 max	X		
30V	I	.144	2 max	X		
25V	I	.142	2 max	X		
25V	I	.201	2 max	X		

DIELECTRIC STRENGTH:

All circuits satisfactory - - - - - YES NO

INSULATION RESISTANCE:

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NON-CONTINUITY

All switches satisfactory

Para 4.1.8 step	YES	NO see note	Switch position	
			Internal	External
A	X			X
I	X			X
F				
J	X			X

CIRCLE SEQUENCE TIME: (20 milliseconds minimum)

External to Internal 0.1 milliseconds.

Internal to External 0.1 milliseconds

POSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit Chan. No.	C.F.C.	In to Rx	Rx to In
P14	E	All Satisfactory	
P32	G		
P30	H		
P36	I		
P40	J		
P18	K		
P20	L		
P26	M		

Circuit Chan. No.	C.F.C.	In to Rx	Rx to In
P12	N	Satisf.	
P22	O		
P24	P		
P14	Q		
P16	R		
P28	S		
P38	T		

CONVARD
SAN DIEGO

VOLTAGE DROP:

Maximum Control Voltage (30 V.)

VOL.

Switch in External Position		Switch in Internal Position				
SW. NR.	CIRCUIT	DATA	SW. NR.	CIRCUIT	DATA	NR.
A	J701G - J701D	.106	A	J701A - J701D	.204	
B	J706P - J705L	.126	B	J701A - J705L	.170	
C	J706T - J705K	.123	C	J701A - J705K	.161	
D	J706T - J705T	.140	D	J701A - J705T	.163	
E	J702A - J705C	.129	E	J702A - J705C	.157	
F	J702A - J702A	.024	F	J702A - J702A	.043	
G	J702C - J702B	.110	G	J702B - J702B	.067	
H	J702X - J702F	.094	H	J702B - J702F	.035	
I	J702N - J702C	.115	I	J702C - J702G	.073	
J	J702E - J702K	.102	J	J702C - J703K	.022	
K	J702G - J702L	.101	K	J702A - J703L	.058	
L	J706H - J702M	.108	L	J702A - J703M	.037	
M	J702W - J702P	.115	M	J702B - J703P	.069	
N	J702S - J702F	.113	N	J702C - J703F	.075	
O	J702J - J702A	.110	O	J702A - J702A	.080	
P	J706J - J702C	.108	P	J702B - J704C	.056	
Q	J702R - J704J	.108	Q	J702C - J704J	.065	
R	J702F - J702A	.118	R	J702A - J702N	.080	
S	J702X - J704R	.108	S	J702B - J702R	.067	
T	J702b - J704T	.102	T	J702C - J704T	.047	

CONTINUITY CHECK:

All circuits indicated continuity Yes No See Notes

4.1.8 Initial Satisfactory Kinetics Corp. Specimen S/N 002

A

Date: 14 July 1956Page 54Test Eng'g: J.H.Wetz/R.J.Sombley

Report 7A2236

CVAC Insp: NoISAF Insp: No

VOLTAGE (DC):

Minimum Control Voltage (25 V.)

SW. #K.	Switch in External Position		Switch in Internal Position		
	CIRCUIT	DATA	SW. #K.	CIRCUIT	DATA
A	J701C - J701N	.101	1	J701A - J701B	.156
B	J706P - J705L	.130	1	J701A - J705L	.169
C	J706T - J705X	.126	6	J701A - J705X	.162
D	J706S - J705J	.144	9	J701A - J705J	.163
E	J706P - J705C	.129	8	J701A - J705G	.156
F	J706E - J703A	.075	1	J702A - J703A	.044
G	J706C - J703D	.110	6	J702B - J703D	.1068
H	J706Y - J703F	.097	8	J702A - J703F	.036
I	J706 - J703C	.113	1	J702C - J703C	.076
J	J706F - J703K	.083	3	J702E - J703K	.1023
K	J706C - J703L	.102	8	J702A - J703L	.1059
L	J706H - J703M	.108	6	J702A - J703M	.1067
M	J706W - J703P	.115	4	J702B - J703P	.1020
N	J706F - J703R	.118	5	J702C - J703R	.077
O	J706J - J704A	.112	0	J702A - J704A	.029
P	J706E - J704C	.110	8	J702B - J704C	.056
Q	J706I - J704J	.108	6	J702C - J704J	.1065
R	J706F - J704N	.114	1	J702A - J704N	.050
S	J706X - J704R	.106	6	J702B - J704R	.1062
T	J706I - J704T	.1102	5	J702C - J704T	.1045

002

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N 002 Kinetics Corp.
SpecimenDate: July 17, 1959
Test Engr: R. T. Mobley
CVAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vibration "Y" Axis	Accelerometers # 1 Drive # 2 X 3 Y 4 Z 5 Pinner
1.4	Operating Time: Start <u>109.1</u> hrs. Stop <u>109.8</u> hrs. Assembly Cycles 6. Start _____ hrs. Stop _____ hrs.	

- Notes: 1. made switch transfer @ ^{INT. EXT. INT.} 215 CPS. on mag. sh 159
 2. made switch transfer Int. Ext. Int. at end of run
 3. When the data reduced, the run looked good.

CONVAIR ASTRONAUTICS

REPORT 7A2236

DATE 56

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results:

Specimen S/N 002 Kinetics Corp. Specimen

Date: 7-20-59

Test Engnr: R. T. Madley

CVAC Instr: NA

USAF Instr: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. "Z" Axis	#1 - Drive 2 - "Y" Axis 3 - "X" Axis 4 - "Z" Axis 5 - Pumper
4.4	Operating Time: Start 110.0 hrs. Stop 110.5 hrs. Assembly Cycles Start _____ hrs. Stop _____ hrs.	

- Notes: 1. Made switch tests @ 120 CPS Int.-Ext.-Int.
 5 - 125 CPS Midwest mag. # 137
2. It was determined at about 200 CPS that CEC-mtr. switch was in wrong position which meant no record 5-200 CPS. This axis will be re-run at end of u.s. testing.
3. No results obtained on this run -

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N 002 Kinetics Corp.
Specimen #4

Date: 7-20-59

Test Engr: R.T. Hobday/L. Haskin
CVAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vibration "X" Axis	Accelerometers #1 - Drive #2 - "Y" Axis #3 - "X" Axis #4 - Z Axis
1.4	Operating Time: Start 110.5 hrs. Stop _____ hrs. Assembly Cycles 4 Start _____ hrs. Stop _____ hrs.	

Notes:

1. MADE SWITCH TRANS (D 140 CPS INT-EXT-INT
5-250 CPS MIDWEST MAG 2-137
2. 250-500 CPS. ERRATIC MOVEMENT OF
PAPER WAS NOTICED DURING THIS PERIOD.
AT 500 CPS PAPER MOVEMENT COMPLETELY
STOPPED AND TEST WAS STOPPED.

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N 202 Kinetics

Corp. Switch

Date: Z=Z4-'59
 Test Engn: R.T. Mobley
 CVAC Insp: NA
 USAP Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Post Vibration Proof Cycle	
4.4	Operating Time: Start <u>113.0</u> hrs. Stop <u>113.3</u> hrs. Assembly Cycles <u>8</u> Start _____ hrs. Stop _____ hrs.	

Notes: 1. Recording is sequential record on May. # 208
 Int. Ext. Int.

Para. 4.1.7
 For para. 4.3 Specimen S/N 002
Lin tics corp.
 * Indicates out of tolerance

Date: 7-24-59
 Engineer: P.L. Mabley
 CVAC Insp: NA
 USAF Insp: NA

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.8 step	Time (seconds)	tolerance (seconds)	Type of assembly cycle	
				Int. to Ext	Ext. to Int
18V	A	.206	3 max		
10V	A	.173	3 max		
30V	F	.115	2 max		
30V	I	.123	2 max		
25V	I	.141	2 max		
25V	I	.143	2 max		

DUCTILE STRENGTH

All circuits satisfactory - - - - - YES NO

INSULATION RESISTANCE

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NON-CONTINUITY

All switches satisfactory

Para 4.1.8 step	YES	NO see note	Switch position	
			Internal	External
A				
B				
C				
D				
E				
F				
G				
H				
I				
J				

CLOSE SWING TIME (20 ± 3 seconds minimum)

External to Internal 6.1 milliseconds

Internal to External 6.1 milliseconds

POSITION TRANSFER TIME (15 milliseconds maximum)

C.R.C. In to Ex	Ex to In	Position transfer time	
		Specified	Actual
P1A		All	Transfer
P1B			
P1C			
P1D			
P1E			
P1F			
P1G			
P1H			
P1I			
P1J			
P2A			
P2B			

Circuit from In to	In to Ex	Ex to In	
		Specified	Actual
P1A		All	Transfer
P1B			
P1C			
P1D			
P1E			
P1F			
P1G			
P1H			
P1I			
P1J			

CONVAIR
SAN DIEGO

FORM 11

2 VOLTAGE DROP:

Maximum Control Voltage (30 v.)

VOLT

Switch in External Position		Switch in Internal Position				
SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA	SW.
A	J701G - J702D	.112	A	J701A - J702D	.183	A
B	J706P - J705L	.116	B	J701A - J705L	.169	B
C	J706T - J705K	.114	C	J701A - J705K	.146	C
D	J706 - J705J	.119	D	J701A - J705J	.148	D
E	J706 - J705C	.127	E	J701A - J705C	.145	E
F	J701A - J702A	.074	F	J701A - J704A	.044	F
G	J701C - J702D	.108	G	J702B - J704B	.065	G
H	J706Y - J704F	.094	H	J702B - J704F	.034	H
I	J706A - J703C	.125	I	J703C - J703C	.073	I
J	J704F - J704K	.097	J	J703K - J703K	.022	J
K	J706G - J702I	.100	K	J702A - J702I	.055	K
L	J706H - J703M	.102	L	J702A - J702M	.097	L
M	J706W - J704P	.126	M	J702A - J703P	.066	M
N	J706S - J703F	.118	N	J703K - J703K	.069	N
O	J704C - J704A	.111	O	J702A - J704A	.088	O
P	J706G - J704C	.111	P	J702B - J704C	.051	P
Q	J706R - J704J	.104	Q	J703K - J704J	.059	Q
R	J706F - J704N	.155	R	J702A - J704N	.084	R
S	J706X - J704R	.100	S	J702B - J704R	.054	S
T	J706B - J704T	.100	T	J703K - J704T	.040	T

CONTINUITY CHECK:

All circuits indicated continuity . . . No See notes

4.3 Post Vibration Proof Cycle
Kinetics SN 902

A

Date: 7-24-'59Page 60Test Engnr: R. T. Mobley

Report 7A2236

CVAC Insp: NAEAP Insp: NA

VOLTAGE DRAFT:

Minimum Control Voltage (25 V.)

SN. NO.	CIRCUIT	Switch in Original Position		Switch in Internal Position	
		DATA	SN. NO.	CIRCUIT	DATA
A	J701C - J701D	.097	I	J701A - J701B	.156
H	J701P - J703L	.120	J	J701A - J705L	.155
C	J706G - J705L	.115	K	J701A - J705L	.149
D	J706S - J705J	.183	L	J701A - J705J	.149
B	J706P - J709C	.121	M	J701A - J705G	.144
F	J706Z - J703A	.074	N	J702A - J703A	.046
O	J700C - J703D	.108	P	J702A - J703D	.066
H	J701I - J703F	.096	Q	J702A - J703E	.035
I	J706A - J703X	.110	R	J702A - J703X	.070
J	J706F - J702L	.079	S	J702A - J703L	.023
K	J706C - J702L	.100	T	J702A - J703L	.055
L	J706R - J703M	.104	U	J702A - J703M	.065
M	J706W - J703P	.112	V	J702A - J703P	.067
N	J706T - J703P	.115	W	J702A - J703S	.070
O	J706S - J704U	.114	X	J702A - J704A	.088
P	J706C - J704C	.103	Y	J702A - J704C	.052
Z	J706A - J704Z	.100	Z	J702A - J704S	.060
X	J706F - J704S	.168	AA	J702A - J704S	.090
S	J706Y - J704Z	.180	AB	J702A - J704A	.055
T	J706I - J704Z	.100	AC	J702A - J704I	.040

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: See Notes 1 & 2 Date: 7-28-'59
 Specimen S/N 002 Kinetics Corp. Test Length: R.T. Mod. 4
 Specimen CVAC Insp: NA USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.2.1.1	Radiant Heat	Max. itca-operating temp. was 152°F
1.4	Operating Time: <u>NA</u> Start _____ hrs. Stop _____ hrs. Assembly Cycles: <u>NA</u> Start _____ hrs. Stop _____ hrs.	

- Notes:
1. This test was attempted 7-27-59 in Bimco Box #8. The unit was subjected to the test per 4.2.1.1 on circuit 30 specimen - it failed. The Bimco Box did function and the temperature rose from 125°F to 250° in 20 minutes time.
 2. The Box was repaired and the test cont. on 7-28-59.

CONVAIR ASTRONAUTICS

Report 7A2236

Page 62

4.1 TEST CONDITIONS AND RESULTS (Continued)

General Test Results: Satisfactory
 Specimen S/N 002 Kinetics Corp.
 Specimen

Date: 8/4/59
 Test Engg.: Rita Mobley
 CVAC Engg.: _____
 DAP Engg.: N/A

Paragraph	Specification Requirement	Remarks
4.2.1.1(c)	-65°F Cold test 3.44" Hg. 1hr. Proof cycle @ 30" Hg. -30°F	
1.4	Operating Time: Start <u>117.1</u> hrs. Stop <u>117.6</u> hrs. Assembly Cycles <u>12</u> Start _____ hrs. Stop _____ hrs.	

Notes: 1. Specimen temp. at beginning of proof cycle
 -34°F

Part. 461
 For part. 461 Specimen S/N 001 Kinetics Date: E-4-39
COP. SPECIMEN CVAC Insp: _____
 USAF Insp: NA

- * Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.6 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle
				Intr. to Ext. Ext. to Int.
10V	A	.232	1 max	X
10V	A	.264	1 max	X
30V	F	.778	2 max	X
30V	I	.623	2 max	X
25V	J	.142	2 max	X
25V	J	.171	2 max	X

Dielectric Strength:

All circuits satisfactory - - - - - YES NO

Insulation Resistance:

All circuits measured greater than 10 megohms - - - YES NO

Switch Continuity and Non-Continuity

All switches satisfactory

Para 4.1.6 step	YES	NO see note	Switch position
			Internal External
1	X		X
2	X		X
3	X		X
4	X		X

Cycle Sequence Time (20 milliseconds minimum)

External to Internal 11 milliseconds

Internal to External 11 milliseconds

Position Transfer Time (15 milliseconds maximum)

Circuit Chan. No.	C.R.C.	In to Ex	Ex to In
P14	I	All	all
P32	O		
P30	H		
P34	I		
P42	J		
P18	X		
P20	I	V	V
P26	H		

Circuit Chan. No.	C.R.C.	In to Ex	Ex to In
P12	N	All	all
P22	C		
P34	S		
P42	S		
P16	R		
P18	S		
P38	I	V	V

CONVAIR
SAN DIEGO

VOLTAGE DROP: Maximum Control Voltage (30 V.)

Switch in External Position		Switch in Internal Position			
SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA
A	J701G - J701D	.108	A	J701A - J701D	.200
B	J706P - J705L	P2M .2-2.116	B	J701A - J706L	.199
C	J706T - J705K	P2M .043.107	C	J701A - J705K	.141
D	J706 - J705I	P2M .035.116	L	J701A - J705L	.148
E	J706X - J705C	P2M .014.136	E	J701A - J705C	.146
F	J706B - J702A	.070	F	J702A - J702B	.032
G	J706C - J701D	.076	G	J702B - J703B	.063
H	J706Y - J703F	.072	H	J702B - J703F	.022
I	J706A - J703C	.165	I	J702C - J703C	.028
J	J706I - J703K	.138	J	J702E - J703K	.016
K	J706G - J703L	.091	K	J702A - J703L	.055
L	J706H - J703M	.102	L	J702A - J703M	.170
M	J706W - J703P	.120	M	J702B - J703P	.064
N	J706X - J703Y	.140	N	J702C - J703B	.010
O	J706J - J704A	.100	O	J702A - J704A	.078
P	J706B - J704C	.091	P	J702B - J704C	.041
Q	J706R - J704J	.084	Q	J702C - J704J	.099
R	J706F - J704N	.171	R	J702A - J704N	.022
S	J706X - J704R	.093	S	J702B - J704B	.050
T	J706B - J704T	.112	T	J702C - J704T	.042

CONTINUITY CHECK:All circuits indicated continuity . . . No See Notes

4.2.1.1(0) - 65°F Cold Test

Root cycle is - 30°F - 30°Hg.

A

Date: 8-4-59Page 64Test Engg: P.T. Mobley

Report TA2236

IVAC Insp: NAISAF Insp: NA

VOLTAGE DROP:

Minimum Control Voltage (25 V.)

No. No.	Switched In External Position		Switched In Internal Position		DATA
	CIRCUIT	DATA	CIRCUIT	DATA	
A	J701C - J701D	0.121	A	J701A - J701D	.217
B	J701P - J705L	0.114	I	J701A - J705L	.163
C	J705L - J705K	0.104	G	J701A - J705K	.140
D	J705C - J705J	0.115	H	J701A - J705J	.151
E	J706R - J705C	0.118	K	J701A - J705G	.153
F	J706E - J703A	0.059	L	J702A - J703A	.033
G	J706C - J703D	0.095	M	J702B - J703D	.064
H	J706I - J702F	0.070	N	J702A - J703E	.024
I	J706A - J703G	0.195	O	J702C - J703G	.072
J	J706F - J703L	0.066	P	J703C - J703L	.017
K	J706C - J703L	0.088	R	J702A - J705L	.055
L	J706F - J703K	0.105	S	J702A - J703N	.133
M	J706W - J703P	0.102	T	J701B - J703P	.066
N	J706F - J703R	0.100	U	J702A - J703R	.070
O	J706J - J704L	0.100	V	J702A - J704L	.078
P	J706I - J704C	0.090	W	J702B - J704C	.048
Q	J706E - J704L	0.083	X	J702C - J704L	.054
R	J706F - J704C	0.112	Y	J702A - J704A	.077
S	J705X - J702P	0.090	Z	J702A - J704	.050
T	J705A - J702C	0.087	AA	J702A - J704	.090

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Unsatisfactory

Date: 8-4-59

Specimen S/N 001 Kinetics Corp.
SpecimenTest Eng: Edwards/LaFender/West
CVAC Instr: _____
USAF Instr: TIA

Paragraph	Specification Requirement	Remarks
4.2.1.(c)	-65°F Cold Test Proof Cycle at -30°F, 1mm Hg.	Specimen temp. -290°F beginning at 1mm rug Specimen temp. -5°F at failure Perkins DC power supply current noted to be 10 amperes during "interrupted assembly cycle
1.4	Operating Time: Start <u>117.6</u> hrs. Stop <u>118.6</u> hrs. Assembly Cycles Start _____ hrs. Stop _____ hrs.	6

Note: 1. 1mm @ 60 mins.

- * 2. @ 26.50. When making transfer from INT. to EXT. switch
didn't transfer. The command switch on the test
setup was thrown to Ext. position but the
Int. light just dimmed instead of going out.
A buzzing noise was noted until the command
switch was thrown back to Int.

Para. 4.1.9
 For para. 2.2.1.16 Specimen S/N 601 Kinet. Date: 8-4-'54
 Corp. Specimen CVAC Insp: _____
 USAF Insp: _____

- Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Time of assembly cycle Int. to Ex. Ext. to Int.
18V	A	.338	1 max	X X
18V	A		1 max	X X
30V	C	.037	2 max	X X
30V	I	.192	2 max	X X
25V	I	.171	2 max	X X
* 25V	I	*	2 max	X X

Dielectric Strength:

All circuits satisfactory - - - - - YES NO

Insulation Resistance:

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NONCONTINUITY:

All switches satisfactory

Para 4.1.8 step	IES	No see note	Switch position Internal External
A	X X		X X
C	X X		X X
I	X X		X X

Cycle Sequence Time (20 milliseconds minimum) These data not

External to Internal _____ milliseconds Measured because of
 Internal to External _____ milliseconds failure on previous step.

POSITION TRANSFER TIME (15 milliseconds maximum):

Circuit Chan. No.	On to Ex	Ex to In
P12	P	
P12	Q	
P30	H	
P36	J	
P42	J	
P18	K	
P20	L	
P26	M	

Circuit Chan. No.	On to Ex	Ex to In
P12	N	
P22	C	
P36	P	
P42	Q	
P15	R	
P28	S	
P38	T	

CCXVAR
SAN DIEGO

FORM 11

VOLTAGE DROP:		Maximum Control Voltage (30 V.)		VOLT	
SH. NO.	CIRCUIT	DATA	SH. NO.	CIRCUIT	DATA
A	J701C - J701D	.095	A	J701A - J701D	.183
B	J706P - J705L	.111	B	J701A - J705L	.145
C	J706T - J705K	.104	C	J701A - J705K	.137
D	J706I - J705J	.112	D	J701A - J705J	.139
E	J704Z - J705C	.115	E	J701A - J705C	.133
F	J706B - J705A	.058	F	J701A - J705A	.029
G	J706C - J702D	.093	G	J701B - J704D	.060
H	J706Y - J705Y	.070	H	J701B - J704Y	.019
I	J706W - J705C	.132	I	J701C - J703G	.066
J	J706F - J705K	.098	J	J701C - J703K	.014
K	J706G - J702I	.082	K	J702A - J703L	.050
L	J706H - J703H	.095	L	J702A - J703M	.023
M	J706V - J704P	.102	M	J701B - J703P	.062
N	J706X - J704P	.103	N	J702C - J703K	.066
O	J706J - J704A	.180	O	J702A - J703A	.023
P	J706I - J705C	.088	P	J701B - J704C	.044
Q	J706R - J705Z	.081	Q	J701C - J704J	.046
R	J706F - J704N	.112	R	J702A - J704N	.023
S	J706X - J704P	.090	S	J702B - J704B	.046
T	J706B - J705Z	.092	T	J701C - J704T	.035

CONTINUITY CHECK:

All terminals indicated continuity . . . Yes No See Notes

4.2.1.13) Total test @ 1000 ohms.

A

Date: 8-4-59Page 67Test Engg: Matley/West

Report 7A2236

EVAC Insp: NASAP Insp: NA

VOLTAGE (VAC):

Minimum Control Voltage (25 V.)

SW. NO.	Switch in External Position		Switch in Internal Position	
	CIRCUIT	DATA	CIRCUIT	DATA
A	J701C - J701D	Because of	J701A - J701D	.124
B	J702F - J703L		J701A - J703L	.149
C	J702G - J703K	Failure Could	J701A - J705K	.140
D	J706S - J705J		J701A - J705J	.142
E	J706R - J705C	Not get these	J701A - J705G	.132
F	J706T - J702A	data.	J702A - J703A	.030
G	J705C - J703D		J702A - J703D	.061
H	J729I - J702F		J702A - J703E	.021
I	J726a - J703C		J702C - J703C	.062
J	J726f - J702Y		J702C - J703K	.015
K	J706G - J702L		J702A - J705L	.051
L	J706H - J702M		J702A - J703M	.069
M	J706N - J702P		J702B - J703P	.063
N	J706P - J702R		J702C - J703R	.067
O	J706Q - J702A		J702A - J704A	.044
P	J726i - J702C		J702B - J704C	.045
Q	J726j - J702I		J702C - J704J	.048
R	J726p - J702A		J702A - J704N	.024
S	J706T - J702R		J702B - J704S	.048
T	J726t - J702Z		J702C - J704I	.035

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory
 Specimen S/N 002 Kinetics Corp. Date: 6-30-'54
 Test Eng: R.E. Makley
 CVAC Insp: N/A
 USAF Insp: N/A

Paragraph	Specification Requirement	Remarks
4.4	Operating Altitude	The specimen cores mounted on CEMAT and IBM for appl. to core rod, and once rotated in each axis
1.4	Operating Time: <u>1 hr.</u> Start _____ hrs. Stop _____ hrs. Assembly Cycles <u>14</u> Start _____ hrs. Stop _____ hrs.	

- Notes:
1. OEG recordings made during 30 sec. runs in each axis, 10000 rpm for all 6 runs.
 2. H3 switch transfer time and cycle seq. backwards at the end of each 30-second run. Late for those on the next 3 runs.

+ "—" Axis * - "Z" Axis

Para. 4.1.5 k 41
For para. 4.1.5 Specimen S/N 666
L140T1S 2017.

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control voltage	Para 4.1.5 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle	Int. to Ext.	Ext. to Int.
15V	1		3 max			
15V	4		3 max			
30V	1		2 max			
30V	1		2 max			
25V	1		2 max			
25V	1		2 max			

DISSIPATIVE STRENGTH

All circuits satisfactory - - - - - YES NO

INSULATION RESISTANCE

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NON-CONTINUITY

All switches satisfactory

Para 4.1.8 step	YES	NO see note	Switch position Internal External
-	-	-	-
-	-	-	-
-	-	-	-

SETTLE TIME (20 milliseconds minimum)

External to Internal 74 milliseconds + - " Axis E 1.152

Internal to External 54 milliseconds + - " Axis E 1.152

SETTLE TRANSFER TIME (15 milliseconds maximum)

Circuit Chassis No.	C.F. In to Rx	C.F. Rx to In
P14	1	3 0.8
P12	2	3 0.8
P10	3	3 0.8
P18	4	3 0.8
P36	1	3 0.8
P11	1	3 0.8
P18	1	3 0.8
P20	2	3 0.8
P26	1	3 0.8

Circuit Chassis No.	C.F. In to Rx	C.F. Rx to In
P12	1	3 0.8 6 2 6 2
P22	2	3 0.8 1 3 6 2
P14	3	3 0.8 1 1 2 0 2
P11	4	3 0.8 0 1 2 2
P12	1	3 0.8 1 2 0 2
P12	2	3 0.8 1 2 0 2
P12	3	3 0.8 1 2 0 2
P22	4	3 0.8 1 2 0 2

+ "X" A 102 + - X A 102

Para. 4.1.814M

For para. 4.1.4 Specimen S/N 001

KINDRED, Calif.

Date: _____
Engineer: M. J. Mosby
CVAC Inspec: _____
USAF Inspec: _____

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control voltage	Para U.I.C. step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle
10V	A		1 max	
10V	A		1 max	
30V	B	4.4	2 max	X A
30V	C		2 max	
25V	D		1 max	
25V	E		2 max	

DISSIPATIVE DISCHARGEAll circuits satisfactory - - - - - YES NO INSULATION RESISTANCEAll circuits measured greater than 10 megohms - - - YES NO SWITCH CONTINUITY AND NON-CONTINUITY

All switches satisfactory

Para U.I.C. step	YES	NO see note	Switch position internal, external

SWITCH SWING TIME 70 milliseconds min

External to Internal 78.4 milliseconds + - X A 102 B 1

Internal to External 51 milliseconds + - X A 102 B 1 C 1

TRANSISTOR TURN-ON 15 milliseconds max

Circuit No.	C.E.C. No	In to Ex	Ex to In
P14	8	7.0 .75	.8 .9
P32	9	7.2 .75	.1 .11
P30	8	6.2 .8	.10 .10
P38	7	8 .2 .2	.4 .5
P42	7	6.8 .7	.2 .2
P18	1	12 .8 .1	.8 .8
P20	8	7.0 .75	.1 .2
P26	8	10 .1 .2	.10 .11

Circuit No.	C.E.C. No	In to Ex	Ex to In
P12	7	7.8 .5 .2	.2 .5
P22	9	6.8 .2 .1	.1 .10
P34	7	7.2 .7 .3	.4 .9
P44	3	6.4 .2 .2	.2 .2
P16	7	11.3 .1 .2	.1 .2
P24	7	6.4 .2 .2	.2 .2
P18	6	6.8 .2 .1	.1 .1

+ "Y" Axis + "Y" Axis

Para. 4.1.5.1, 19

For para. 4.1.5 Specimen S/N 66

* Indicates out of tolerance

Date: _____
Engineer: S. L. Mckay
CVAC Insp: _____
USAF Insp: 147

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.5 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle
10V	1		3 max	Int. to Ext. Ext. to Int.
10V	4		3 max	
10V	5	14.4	2 max	14.4
10V	1		2 max	
25V	1		2 max	
25V	1		2 max	

DIELECTRIC STRENGTH:

All circuits satisfactory - - - - - YES NO

INSULATION RESISTANCE:

All circuits measured greater than 10 megohms - - - YES NO

SWITCH COORDINATE AND LINEAR CONCILIABILITY:

All switches satisfactory

Para 4.1.5 step	YES	NO see note	Switch position
			Internal External
1			
2			
3			
4			
5			

CIRCUIT SEQUENCE TIME (20 milliseconds minimum)

External to Internal 30 milliseconds + "Y" Axis E to I + 4

Internal to External 22 milliseconds + "Y" Axis I to E - 6

TRANSITION TRANSFER TIME (15 milliseconds maximum)

Circuit	C.P.C.	In to Ex	Ex to In
P1A	1	6.5 8	8 3.5
P1B	2	8 7.7	7.5 1.5
P1C	3	8.5 8	11 1.5
P2A	1	9 9	10.5 2.5
P2B	2	6.5 6	7.5 2.5
P2C	3	11 10.5	9 2.5
P2D	4	2.5 2	3 2.5
P2E	5	2.5 10	11 2.5

Circuit	C.P.C.	In to Ex	Ex to In
P1A	N	5 2	8 8
P1B	2	9.5 8	10 1
P1C	3	8 7	11.5 1.5
P2A	1	5.5 2	8 8.5
P2B	2	8 7	8 3
P2C	3	7.5 5	8 3
P2D	4	2.5 2	2.5 3

4.1 TEST CONDITIONS AND PROCESSES (Continued)

General Test Results: Failed

Specimen S/N 414473 Corp.Date: 10-9-57
Test Engn: Rita Mabrey
CVAC Insp: N/A
USAF Insp: N/A

Paragraph	Specification Requirement	Remarks
1.4	<p>Notes:</p> <p>Suit Atmosphere</p>	
	<p>Operating Time:</p> <p>Start <u>NA</u> hrs. Stop <u>NA</u> hrs.</p> <p>Assembly Cycles</p> <p>Start <u>NA</u> hrs. Stop <u>NA</u> hrs.</p>	

- Notes:
1. While sitting in storage in the vib. loc., the gal. stud hardware was noted to be rusting. A 100 hr. Salt Atmosphere test (per Spec. 27-06166 IV 4.4.8) was performed.
 2. After the test, considerable corrosion of the subject hardware was noted.
 3. After 4.4.8 test was performed a hipot test was run. T701A to T711C broke down @ ~50 VEMs.
 4. IL # 414473 was written and specimen returned to Vlador

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Unsatisfactory

Specimen A/B 121 United Control
Specimen

Date: 6-10-'59

Test Engn: R. T. Hobley

CTAC Insp: N/A

USAF Insp: N/A

Paragraph	Specification Requirement	Remarks
4.1.8	Initial Satisfactory	
1.4	Operating Time: .6 hrs. Start _____ hrs. Stop _____ hrs. Assembly Cycles 13 Start _____ hrs. Stop _____ hrs.	

Notes: 1. While performing Para. 4.1.8 (Hypot test),
 J706 E to case indicated excessive
 leakage current and breakdown at 1500V.
 Breakdown occurred at approx. 950 VAC.

Para. 4.1.8
Per para. 4.1.8 Specimen S/N 121
United Control

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Time of assembly cycle Int. to Ext. Ext. to Int.
15V	1	1.39	1 max	X
15V	2	1.31	1 max	X
30V	1	0.87	2 max	X
30V	2	0.81	2 max	X
PSV	1	0.97	2 max	X
25V	1	0.97	2 max	X

Dielectric Strength:

All circuits satisfactory - - - - - YES NO

Insulation Resistance:

All circuits measured greater than 20 megohms - - - YES NO

SWITCH CONDITION AND LOGIC CONSISTENCY:

All switches satisfactory

Para 4.1.8 step	YES	NO See note	Switch position Internal External
1	X		X
2	X		X
3	X		X
4	X		X

Cycle Sequence Time: (20 milliseconds minimum)

External to Internal 220 milliseconds

Internal to External 202 milliseconds

POSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit Chan. No.	C.B.C.	In to Ext	Ext to In	
P14	1	5	6.3	
P32	0	1	1	
P30	1	1	1	
P16	1	1	1	
P40	1	1	1	
P18	1	1	1	
P20	1	1	1	
P26	1	5	6.3	

Circuit Chan. No.	C.P.C.	In to Ext	Ext to In	
P42	1	5	6.3	
P22	0	1	1	
P34	1	1	1	
P44	0	1	1	
P76	1	1	1	
P28	0	1	1	
P38	1	5	6.3	

VOLTAGE DROP:

Maximum Control Voltage (30 V.)

VOLTA

SW. NO.	Switch In External Position			Switch In Internal Position			SW. NO.
	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA	SW. NO.	
A	J701G - J701H	0.263	A	J701A - J701B	0.065	A	
B	J706P - J705L	0.015	B	J701A - J705L	0.152	B	
C	J706T - J705K	0.045	C	J701A - J705K	0.116	C	
D	J704G - J704H	0.039	D	J701A - J705L	0.165	D	
E	J706R - J702S	0.002	E	J702A - J705C	0.177	E	
F	J706M - J703U	0.192	F	J702A - J703U	0.064	F	
G	J706N - J703W	0.130	G	J702B - J703W	0.105	G	
H	J706Y - J703X	0.110	H	J702B - J703X	0.024	H	
I	J706S - J703G	0.125	I	J702C - J703G	0.100	I	
J	J706F - J703K	0.080	J	J702C - J703K	0.040	J	
K	J706Q - J702L	0.128	K	J702A - J703L	0.082	K	
L	J706H - J703W	0.142	L	J702A - J703W	0.095	L	
M	J706W - J703P	0.144	M	J702A - J703P	0.108	M	
N	J706X - J703R	0.131	N	J702C - J703R	0.112	N	
O	J706J - J704A	0.138	O	J702A - J704A	0.110	O	
P	J706G - J704C	0.094	P	J702B - J704C	0.059	P	
Q	J706R - J704J	0.089	Q	J702C - J704J	0.070	Q	
R	J706P - J704H	0.142	R	J702A - J704H	0.110	R	
S	J706I - J704K	0.115	S	J702B - J704K	0.067	S	
T	J706B - J704T	0.097	T	J702C - J704T	0.036	T	

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See Notes

Initial Satisfactory

A

Date: 6-10-'59Page 75Test Engr: R. T. Moseley

Report 7A2236

CVAC Insp: NASAT Insp: NA

VOLTAGE DROP:

Minimum Control Voltage (25 V.)

Switch in External Position			Switch in Internal Position		
SW. NR.	CIRCUIT	DATA	SW. NR.	CIRCUIT	DATA
A	J701C - J701D	0.253	J701A - J701D	J701A	0.070
B	J706P - J705L	0.004	J701A - J705L	J705L	0.113
C	J706T - J705K	0.043	J701A - J705K	J705K	0.116
D	J706S - J705J	0.031	J701A - J705J	J705J	0.162
E	J706R - J705C	0.014	J702A - J705C	J705C	0.214
F	J706Z - J703A	0.088	J702A - J703A	J703A	0.020
G	J706O - J703D	0.125	J702B - J703D	J703D	0.034
H	J706I - J703V	0.101	J702B - J703E	J703E	0.023
I	J706N - J703K	0.120	J702C - J703C	J703C	0.083
J	J706R - J703K	0.077	J702C - J703K	J703K	0.042
K	J706G - J703L	0.115	J702A - J703L	J703L	0.070
L	J706M - J703M	0.138	J702A - J703M	J703M	0.079
M	J706W - J703P	0.142	J702B - J703P	J703P	0.081
N	J706Y - J703R	0.130	J702C - J703R	J703R	0.086
O	J706J - J704A	0.134	J702A - J704A	J704A	0.082
P	J706A - J704C	0.142	J702B - J704C	J704C	0.058
Q	J706B - J704J	0.096	J702C - J704J	J704J	0.061
R	J706F - J704M	0.140	J702A - J704N	J704N	0.082
S	J706X - J704R	0.111	J702B - J704R	J704R	0.062
T	J706D - J704T	0.094	J702C - J704T	J704T	0.037

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

Desert Test Results: Satisfactory

Specimen S/N United Control
Corp. 121Date: 6-10-'59
Test Engr: R.L. Mobley
CVAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. "Y" Axis	Only one resonance occurred - 30G @ 110 cps
4.4	Operating Time: 1.2 hrs. Start _____ hrs. Stop _____ hrs. Assembly Cycles 8 Start _____ hrs. Stop _____ hrs.	

- Notes: 1. First portion of sweep 5-125-5 cps -
 Second portion of sweep 125-2000 cps
 2. Made Switch Int-Ext-Int at 300 cps
 3. Made Switch Int-Ext-Int at 1200 cps
 4. CEC Mag # - 5-250 cps #137, - 250-2000 #506
 5. Accelerometer outputs recorded CEC Mag. #
 26118 - 50g/inch - #1 drive ~~1~~ next, #2 2
 #3 Y, #4 X' next to piper, piper

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Marginal

Specimen S/N 121.

United Control Corp. Specimen

Date: 6-11-'59
 Test Engn: R. T. Mobley
 CVAC Insp: NA
 USAP Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. Z Axis	No resonance occurred
4.4	Operating Time: Start <u>90.5 hrs.</u> Stop <u>91.5 hrs.</u> Assembly Cycles <u>8</u> Start _____ hrs. Stop _____ hrs.	

- Notes:
1. Made switch Int. to Ext. to Int. at 260 cps.
 2. 400w pur. supply okt. bkr. popped out about 270 cps
 3. A considerable amount of hash was noted between 6 - 20 CPS. The hash and changes in voltage step were great enough that a 12-12-12-12-12-125 was decided upon for all 3 Axes.

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory
 Specimen 3/8 121.
 United Cont. Corp. Specimen

Date: 6-11-59
 Test Engg: R.T. Mabley
 CVAC Insp: NA
 USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. "X" Axis	No resonance occurred 5-250 Mag. #187
4.4	Operating Time: Start <u>91.2</u> hrs. Stop <u>91.9</u> hrs. Assembly Cycles <u>8</u> Start _____ hrs. Stop _____ hrs.	

Notes: Made switch from Int. to Ext. to Int. at 350 cps
 Made switch at 1000 cps Int. to Ext. to Int.
 Cycle sequence was well within tolerance
 at 1000 cps switch add at end of run,
 H/C switch transfer 3.4 ms at end of
 1000 switch.

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Unsatisfactory Date: 6-15-'59
 Specimen S/N 121 Test Engr: P. T. Mabley
 United Control Specimen CVAC Insp: NA
 USAF Insp: NA

Paragraph	Specification Requirement	Remarks
	Post Vib. Proof Cycle & Ambient Conditions Proof Cycle Combined	
4.4	Operating Time: Start 91.9 hrs. Stop 92.6 hrs. Assembly Cycles 10 Start _____ hrs. Stop _____ hrs.	

Notes: * During Proof Cycle 4.1.9 (para. 6), JT08
 A showed excessive current leakage and voltage breakdown. Breakdown began at about 950 AC.
 JT08B was marginal at 1550 V - Hyper
 fire took right cylinder on intermittently.

Para. 4.1.9
For para. 4.3 Specimen S/N 121
United Cent.

* Indicates out of tolerance

Date: 6-15-54
Engineer: W.T. Mobley
CVAC Insp: AIA
USAF Insp: NA

ASSEMBLY CYCLE OPERATIONS

Control Para 4.1.8 voltage	stop	Time (seconds)	Tolerance (seconds)	Time of assembly cycle Int. to Ext. Ext. to Int.
3V	1	11.57ms	2 max	
10V	4	14.26ms	2 max	
30V	5	8.49ms	2 max	
30V	1	7.15ms	2 max	
25V	1	10.10ms	2 max	
25V	1	8.59ms	2 max	

Dielectric Strength:

All circuits satisfactory - - - - - YES NO

See Note: *

Insulation Resistance:

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTACTIVITY AND NON-CONTACTIVITY

All switches satisfactory

Para 4.1.8 stop	YES	NO see note	Switch position Internal External
1			
2			
3			
4			

CLOCK SEQUENCE TIMES (20 milliseconds minimum)

External to Internal 255 milliseconds

Internal to External 278 milliseconds

POSITION TRANSFER TIMES (15 milliseconds maximum)

Circuit	Chan. No.	From	To	Time ms
P14	2	3.3	3.1	
P12	1	3.3	3.1	
P30	1	3.2	3.1	
P34	1	3.2	3.1	
P10	1	3.2	3.1	
P18	1	3.2	3.1	
P20	1	3.2	3.1	
P26	1	3.2	3.1	

Circuit	Chan. No.	From	To	Time ms
P12	1	3.2	3.1	
P22	1	3.2	3.1	
P34	1	3.2	3.1	
P14	1	3.2	3.1	
P16	1	3.2	3.1	
P28	1	3.2	3.1	
P36	1	3.2	3.1	

VOLTAGE DROP:

Maximum Control Voltage (30 V.)

VOLTS

Switch in External Position		Switch in Internal Position				
SL. NO.	CIRCUIT	DATA	SL. NO.	CIRCUIT	DATA	SL. NO.
A	J701A - J701B	.231	A	J701A - J701D	.061	A
B	J706P - J705L	.133	B	J701A - J705L	.111	B
C	J706T - J705K	.144	C	J701A - J705K	.112	C
D	J706S - J705J	.161	D	J701A - J705U	.113-.144	D
E	J706R - J705N	.177	E	J702A - J703C	.215	E
F	J706M - J703A	.091	F	J702A - J702B	.073	F
G	J706A - J703D	.13	G	J702B - J703B	.10	G
H	J706Y - J703F	.10	H	J702B - J703Z	.030	H
I	J706G - J703G	.12	I	J702C - J703G	.095	I
J	J705X - J703I	.070	J	J702C - J703K	.042	J
K	J706Q - J703L	.115	K	J702A - J703L	.032	K
L	J706H - J703M	.14	L	J702A - J703K	.094	L
M	J706W - J703P	.18	M	J702A - J703P	.096	M
N	J706K - J703R	.13	N	J702C - J703R	.105	N
O	J706J - J704A	.125	O	J702A - J704A	.11	O
P	J706I - J704C	.09	P	J702B - J704C	.057	P
Q	J706R - J704J	.019	Q	J702C - J704J	.068	Q
R	J706P - J704H	.13	R	J702A - J704H	.11	R
S	J706Z - J704R	.11	S	J702B - J704R	.065	S
T	J706B - J704T	.091	T	J702C - J704T	.053	T

CONTINUITY CHECK

All circuits indicated continuity . . . Yes No See Notes

Pest Vibration Root Cycle
 & Ambient Condition Root Cycle Combined

A

Date: 6-15-59Page 81Test Engr: E. T. Mobley

Report 7A2236

CVAC Insp: NADIFAF Insp: NA

VOLTAGE DROP:

Minimum Control Voltage (25 V.)

Switch in External Position			Switch in Internal Position		
SM. NO.	CIRCUIT	DATA	SM. NO.	CIRCUIT	DATA
A	J701C - J701D	.025	A	J701A - J701D	.057
B	J706P - J703L	.164	B	J701A - J703L	.119
C	J706T - J705K	.139	C	J701A - J705K	.127
D	J706B - J705J	.145	D	J701A - J705J	.153
E	J706R - J705G	.181	E	J701A - J705G	.212
F	J706R - J703A	.087	F	J702A - J703A	.074
G	J706G - J703D	.13	G	J702B - J703D	.10
H	J706Y - J703P	.10	H	J702B - J703P	.029
I	J706A - J703G	.125	I	J702C - J703G	.096
J	J706Z - J703K	.073	J	J702C - J703K	.045
K	J706O - J703L	.11	K	J702A - J703L	.079
L	J706H - J703M	.14	L	J702A - J703M	.092
M	J706U - J703P	.14	M	J702B - J703P	.094
N	J706g - J703R	.13	N	J702C - J703R	.105
O	J706J - J706L	.128	O	J702A - J706L	.115
P	J706M - J704C	.091	P	J702B - J704C	.056
Q	J706R - J704J	.091	Q	J702C - J704J	.070
R	J706P - J704N	.185	R	J702A - J704N	.115
S	J706X - J704R	.112	S	J702B - J704R	.063
T	J706B - J704T	.093	T	J702C - J704T	.033

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Specimen S/N 621

2/Unitized Control

Date: 6-16-59
 Test Engr: P. T. McElroy
 CVAC Insp: NA
 USAP Insp: NA

Paragraph	Specification Requirement	Remarks
4.3.11 b)	Radial heat	Time Spec. Temp 1830 78°F 1915 124°F Radial heat C1 2020 125 2100 144 2130 144 2155 144 2210 144 2315 144
1.6	Operating Time: Start <u>NN</u> hrs. Stop <u>NN</u> hrs.	
	Assembly Cycles Start <u>NN</u> hrs. Stop <u>NN</u> hrs.	

Notes:

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Unsatisfactory

Specimen S/N 121.

United Control Spec.

Date: 6-17-'59
 Test Engr: P. T. Mobley
 CVAC Insp: NA
 USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.2.1.1	-65°F 1mm Hg. + alt. @ 30" Hg.	
1.4	Operating Time: <u>92.6</u> Start <u>6:26</u> hrs. Stop <u>9:33</u> hrs. Assembly Cycles <u>12</u> Start _____ hrs. Stop _____ hrs.	

- Notes:
1. Dielectric strength test made at the end of -65°F @ 1mm Hg. test, after box pressure brought back to atmospheric.
 2. The -65° failure auto after during Hg pot occurs en test. See next test & Hgpot & failure details

Para. 4.1.9
 For para. 4.2.1.1 C) Specimen S/N 121
 United Control

* Indicates out of tolerance

Date: 6-17-'59
 Engineer: R.I. Mobley
 CVAC Disp: ALW
 USAF Disp: NA

ASSEMBLY CYCLE OPERATION:

Control Para. No. ^a	Step	Time (seconds)	Variance (seconds)	Type of assembly cycle Int. to Ext. Ext. to Int.
15	1	1.63	1 max	
16	1	1.83	1 max	
17	1	1.63	1 max	
18	1	1.99	2 max	
21	1	1.24	1 max	
29	1	1.21	2 max	

Dielectric Strength:

All circuits satisfactory ----- YES NO

Insulation Resistance:

All circuits measured greater than 10 megohms --- YES NO

Switch Commutator and Non-Controllability:

All switches satisfactory

Para. 4.1.8 step	YES	No note	Switch position Internal External
1			
1			
1			

Cycle Sequence Time: (20 milliseconds minimum)

Internal to Internal 3.5 milliseconds

Internal to External 3.36 milliseconds

POSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit Para. No.	C.E.C. In to Int.	In to Ext.	Ext to In
P14	1	3	3
P32	1	4	4
P30	1	4	4
P26	1	4	4
P40	1	4	4
P18	1	4	4
P20	1	4	4
P31	1	3	9

Circuit Para. No.	C.E.C. In to Int.	In to Ext.	Ext to In
P12	1	9	5
P23	1	8	5
P14	1	8	5
P16	1	8	5
P22	1	8	5
P32	1	8	5

CORSAIR
SAN DIEGO

POLM 71

VOLTAGE TEST:

Maximum Central Voltage (30 V.)

VOLTA

S/N. NO.	Switch In External Position		Switch In Internal Position		S/N.
	CIRCUIT	DATA	CIRCUIT	DATA	
A	J701A - J701D	0.100	A	J701A - J701D	0.060
B	J706P - J705L	0.156	B	J701A - J705L	0.125
C	J706T - J703K	0.120	C	J701A - J703K	0.172
D	J706S - J702J	0.129	D	J701U - J703X	0.162
E	J706R - J702H	0.155	E	J702A - J703E	0.341
F	J706N - J703I	0.059	F	J702B - J703N	0.042
G	J706M - J703M	0.105	G	J702C - J703P	0.090
H	J706Y - J703Z	0.088	H	J702D - " J703P	0.021
I	J706X - J703O	0.091	I	J702E - J703X	0.088
J	J706C - J703K	0.060 seen	J	J702F - J703X	0.030
K	J706G - J703L	0.740.071	K	J702A - J703L	0.068
L	J706H - J703M	0.110	L	J702A - J703M	0.073
M	J706Y - J703P	0.115	M	J702A - J703P	0.089
N	J706Z - J703R	0.110	N	J702B - J703R	0.093
O	J706J - J704A	0.108	O	J702A - J704A	0.079
P	J706G - J704C	0.074	P	J702B - J704C	0.055
Q	J706A - J704J	0.069	Q	J702C - J704J	0.052
R	J706P - J704E	0.110	R	J702A - J704E	0.082
S	J706X - J704R	0.088	S	J702B - J704R	0.071
T	J706B - J704T	0.075	T	J702C - J704T	0.034

CONFIDENCY CHECK

All contacts indicated continuity . . . Yes No See Notes

Cold Test @ 30" Hg.

A

Date: 6-11-59Page 85Test Engg: R. T. Mobley

Report 7A2236

CVAC Loop: NAEMAF Loop: NA

VOLTAGE DROP:

Minimum Control Voltage (25 V.)

Swtch in External Position			Swtch in Internal Position		
REL. NO.	CIRCUIT	DATA	REL. NO.	CIRCUIT	DATA
A	J701G - J701D	0.293	J701A - J701D	E.059	
B	J706P - J705L	0.148	J701A - J705L	E.115	
C	J705T - J705K	E.117	J701A - J705K	E.133	
D	J705S - J705J	E.128	J701A - J705J	E.156	
E	J706R - J705G	E.157	J701A - J705G	E.305	
F	J706R - J703A	0.056	J702A - J703A	0.044	
G	J706G - J703D	E.105	J702B - J703D	E.092	
H	J706I - J703F	E.089	J702B - J703F	E.122	
I	J706A - J703E	E.098	J702C - J703A	E.388	
J	J706C - J703K	E.061	J702C - J703K	E.130	
K	J706D - J703L	E.068	J702A - J703L	E.671	
L	J706H - J703M	E.110	J702A - J703M	E.079	
M	J706W - J703P	0.1615 P.D.	J702A - J703P	E.920	
N	J706Z - J703N	E.120	J702C - J703N	E.694	
O	J706J - J704A	0.160	J702A - J704A	0.080	
P	J706I - J704C	0.076	J702B - J704C	0.056	
Q	J706B - J704I	E.070	J702B - J704I	E.052	
R	J706P - J704M	E.160	J702A - J704M	E.023	
S	J706X - J704K	E.090	J702B - J704K	E.062	
T	J706B - MK1	0.077	J702A - MK1	E.035	

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results:

Specimen S/N 121

United Control Corp.

Date: 6-17-59
 Test Engrs: E. T. Mobley
 CVAC Insp: NA
 USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.2.1.1 C)	Cold test @ 1MM Hg. test	CEC Recording 1st run @ 19.5V E to I. 2nd " @ 29.5V I to E. 3rd " @ 29.5V E to I.
1.4	Operating Time: Start <u>8:55</u> hrs. Stop <u>9:55</u> hrs. Assembly Cycles Start <u>12</u> hrs. Stop <u> </u> hrs.	

Notes:

1. Reached 1.3MM Hg. in 10 min. — 1MM Hg.
13 min.
2. During Hypot test J706E showed breakdown from 1250 VAC and up. Switch was in External position.
3. Hypot test was performed @ -30°F and approx. 30" Hg.

Report 7A2236

Rev 87

Para. 4.1.9 IMM⁴
 Per para. 4.1.11 Specimen S/N 131
Unit 1 cont.

Date: 6-17-57
 Engineer: P. J. Mobley
 CVAC Disp: A.H.
 USAF Disp: N.H.

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control Para 4.1.8 voltage	Step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle Int. to Ext. Ext. to Int.
131	1	1.87	1 MAX	
131	4	1.84	1 MAX	
131	5	1.23	1 MAX	
131	1	1.62	2 MAX	
131	1	1.22	2 MAX	
231	1	1.20	2 MAX	

DIELECTRIC STRENGTH

All circuits satisfactory - - - - - YES NO

See Note X

INSULATION RESISTANCE

All circuits measured greater than 10 megohms - - - YES NO

SWITCH COORDINATION AND INTEGRITY

All switches satisfactory

Para 4.1.8 step	YES	NO	Switch position Dashed = Reference Solid = Actual
1			
2			
3			
4			
5			
6			

CYCLE SEQUENCE TIME (20 milliseconds minimum)

Internal to Internal 2.70 milliseconds

Internal to External 3.00 milliseconds

POSITION TRANSITION TIME (15 milliseconds maximum)

C.I.C. Circuit No.	Step	Time Secs	Step No.
P14	1	2.8	2.1
P12	2	4	4
P20	3		
P24	4		
P40	5		
P18	6		
P22	7		
P24	8		
P24	9		
P24	10		
P24	11		
P24	12		
P24	13		
P24	14		
P24	15		
P24	16		
P24	17		
P24	18		
P24	19		
P24	20		
P24	21		
P24	22		
P24	23		
P24	24		
P24	25		
P24	26		
P24	27		

C.I.C. Circuit No.	Step	Time Secs	Step No.
P22	1	2.8	2.7
P22	2		1
P24	3		
P24	4		
P24	5		
P24	6		
P24	7		
P24	8		
P24	9		
P24	10		
P24	11		
P24	12		
P24	13		
P24	14		
P24	15		
P24	16		
P24	17		
P24	18		
P24	19		
P24	20		
P24	21		
P24	22		
P24	23		
P24	24		
P24	25		
P24	26		
P24	27		

MURRAY COUNTRY VILLAGE (30 F.)

W. #.	STATION	DATE	TIME	ACTIV.	Initial Internal Condition	
					DATE	TIME
A	J7016 - J7010	C. 6/29	A	J701A - J701D	E.C.76	
I	J706P - J705L	C. 14/6	B	J701A - J703L	C. 11.	
G	J706I - J705K	C. 12/6	C	J701A - J703K	C. 134	
H	J706S - J705R	C. 11/9	D	J701A - J703R	C. 156	
I	J706R - J705A	C. 15/5	E	J701A - J703A	C. 314	
J	J706A - J703M	C. 9/56	F	J701A - J703M	E. 146.	
K	J706M - J703N	E. 14C	G	J701A - J703N	E. 290	
L	J706X - J703P	C. 26/9	H	J701A - J703P	E. 622	
I	J706A - J703G	C. 17/5	I	J701A - J703G	E. 070.	
J	J706I - J703H	C. 6/63	J	J701A - J703H	C. 930	
K	J706Q - J703L	C. 5/25	K	J701A - J703L	C. 073	
L	J706E - J703M	C. 11C	L	J701A - J703M	C. 083	
M	J706W - J703P	C. 12/6	M	J701A - J703P	C. 692.	
N	J706S - J703R	C. 17/5	N	J701A - J703R	E. 695	
O	J706J - J704A	C. 11C	O	J701A - J704A	E. 082	
P	J706A - J704C	C. 5/20	P	J701A - J704C	C. 655	
Q	J706B - J704J	C. 12	Q	J701A - J704J	C. 654	
R	J706P - J704Y	C. 1/3	R	J701A - J704Y	C. 656	
S	J706X - J704B	C. 2/90	S	J701A - J704B	C. 667	
T	J706B - J704T	C. 6/39	T	J701A - J704T	C. 638	

CONFIRMED

All stations indicate a scatlonality . . . Yes No See Notes

A. L. I. of 3610 feet is fine.

A

Date: 6-17-59Page 88Test Engg: Rita Mayley

Report 7A2236

Circuit Temp: 874JMAP Temp: N/A

RELEASED DROP:

Maximum Central Voltage (25 V.)

S/N.	CIRCUIT	DATA	Series in Interval Position		
			S/N.	CIRCUIT	DATA
A	J7012 - J7018	0.120	1	J7014 - J7018	0.072
B	J7062 - J7064	0.164	2	J7014 - J7021	0.110
C	J7067 - J7068	0.128	3	J7014 - J7038	0.145
D	J7068 - J7073	0.122	4	J7014 - J7033	0.145
E	J7068 - J7036	0.159	5	J7014 - J7036	0.310
F	J7068 - J7031	0.128	6	J7021 - J7034	0.051
G	J7068 - J7030	0.110	7	J7023 - J7030	0.045
H	J7061 - J7032	0.093	8	J7021 - J7038	0.224
I	J7061 - J7031	0.163	9	J7021 - J7038	0.090
J	J7061 - J7038	0.166	10	J7021 - J7038	0.032
K	J7061 - J7031	0.166	11	J7021 - J7031	0.123
L	J7061 - J7031	0.115	12	J7021 - J7031	0.050
M	J7064 - J7027	0.120	13	J7023 - J7027	0.020
N	J7065 - J7038	0.120	14	J7023 - J7038	0.144
O	J7051 - J7061	0.112	15	J7021 - J7061	0.038
P	J7061 - J7045	0.079	16	J7021 - J7045	0.054
Q	J7061 - J7042	0.074	17	J7021 - J7042	0.056
R	J7062 - J7041	0.115	18	J7021 - J7041	0.086
S	J7061 - J7048	0.972	19	J7021 - J7048	0.046
T	J7061 - J7031	0.050	20	J7021 - J7031	0.036

B

CONVAIR ASTRONAUTICS

REF ID: 7A236

PAGE 89

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results:

Specimen S/N 121. United Control
Corp. SpecimenDate: 6-18-59
Test Engg: R. T. Mobley
CVAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.2.1.1 d)	Hot test 3160° and 3174°	CEC Recording Ext. to Int. Int. to Ext. Int. to Ext.
1.4	Operating Times: Start <u>73.8 hrs.</u> Stop <u>94.5 hrs.</u> Assembly Cycles <u>8</u> Start _____ hrs. Stop _____ hrs.	

Notes:

Part. 4.1.9
For part. 4.2.11 Specimen 2/1 121
United Control

Date: 6-18-57
Engineer: R. T. Mobley
CVAC Insp: NA
USAF Insp: NA

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control voltage	Part 4.1.8 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle Int. to Ext. Ext. to Int.
12	2	1.36	1 max	
12	4	1.16	1 max	
12	5	.67	2 max	
12	6	.72	2 max	
12	7	.93	2 max	
12	8	.82	2 max	

DISSIPATIVE STABILITY

All circuits satisfactory ----- YES NO

INSULATION RESISTANCE

All circuits measured greater than 10 megohms --- YES NO

SWITCHES CONDUCTIVITY AND NO CONDUCTIVITY

All switches satisfactory

Part 4.1.8 step	YES	NO See note	Switch position Internal External
1	X		
2	X		
3	X		

CYCLE SEQUENCE TIMES (20 milliseconds minimum)

External to Internal 230 milliseconds

Internal to External 256 milliseconds

POSITION TRANSFER TIMES (15 milliseconds maximum)

Circuit	C.E.C. Chan. No.	In to Ext Sec	In to Ext Sec
P14	P	3.12	2.1
P32	Q		
P30	R		
P16	S		
P40	T		
P18	U		
P20	V		
P26	W	3.9	2.1

Circuit	C.E.C. Chan. No.	In to Ext Sec	In to Ext Sec
P42	H	3.9	2.1
P22	O	A	
P34	P		
P44	Q		
P16	R		
P28	S		
P38	T	3.9	2.1

2. WIRELESS TEST:

Maximum Current Voltage (30 V.)

SL. NO.	CIRCUIT	Soldered in External Position		Soldered in Internal Position		SL. NO.
		DATA	CIRCUIT NO.	CIRCUIT	DATA	
A	J7010 - J7010	0.240	A	J701A - J701D	0.059	A
B	J706P - J706L	0.179	B	J701A - J705L	0.130	B
C	J706T - J705L	0.142	C	J701A - J705R	0.150	C
D	J706S - J705T	0.155	D	J701A - J705T	0.190	D
E	J706R - J705R	0.198	E	J702A - J705S	0.329	E
F	J706B - J705U	0.115	F	J702B - J705U	0.075	F
G	J706A - J705B	0.132	G	J702A - J705B	0.108	G
H	J706Y - J705T	0.123	H	J702A - J705T	0.027	H
I	J706G - J703G	0.125	I	J702G - J703G	0.167	I
J	J706F - J703K	0.090	J	J702C - J703K	0.142	J
K	J706G - J703L	0.135	K	J702A - J703L	0.080	K
L	J706H - J703M	0.145	L	J702A - J703M	0.100	L
M	J706H - J703P	0.145	M	J702B - J703P	0.116	M
N	J706K - J703R	0.150	N	J702G - J703R	0.114	N
O	J706J - J704A	0.137	O	J702A - J704A	0.167	O
P	J706I - J704C	0.098	P	J702B - J704C	0.062	P
Q	J706B - J704J	0.094	Q	J702C - J704J	0.079	Q
R	J706P - J704N	0.140	R	J702A - J704N	0.169	R
S	J706X - J704R	0.120	S	J702B - J704R	0.072	S
T	J706B - J704T	0.130	T	J702C - J704T	0.537	T

CONTINUITY CHECK:All circuits indicated continuity . . . Yes No See Notes

4.2.11 Hot Test - 160°F @

30" Hg.

A

Date: 6-18-59Page 91Test Engg: R. T. Mobley

Report 7A2236

CVAC Insp: NASAP Insp: NA

VOLAGE DROP:

Minimum Central Voltage (25 V.)

SW. NO. & CIRCUIT POSITION			SW. NO. & CIRCUIT POSITION		
SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA
A	J701C - J701D	0.029	J701A - J701D	J701	0.061
B	J706P - J706L	0.183	J701A - J706L	J701	0.129
C	J706T - J706K	0.145	J701A - J706K	J701	0.148
D	J706S - J705J	0.152	J701A - J705J	J701	0.112
E	J706R - J705C	0.203	J702A - J703G	J702	0.226
F	J706R - J703A	0.100	J702A - J703A	J702	0.074
G	J706G - J703D	0.135	J702B - J703D	J702	0.140
H	J706Y - J703P	0.125	J702A - J703P	J702	0.026
I	J706 - J703G	0.130	J702C - J703G	J702	0.108
J	J706S - J703K	0.091	J702C - J703K	J702	0.043
K	J706O - J703L	0.155	J702A - J703L	J702	0.052
L	J706R - J703M	0.147	J702A - J703M	J702	0.100
M	J706W - J703P	0.150	J702B - J703P	J702	0.110
N	J706Z - J703R	0.131	J702C - J703R	J702	0.116
O	J706J - J704A	0.135	J702A - J706A	J702	0.103
P	J706A - J704C	0.102	J702B - J706C	J702	0.066
Q	J706B - J704J	0.096	J702C - J706J	J702	0.080
R	J706T - J704N	0.145	J702A - J706N	J702	0.105
S	J706I - J704R	0.122	J702B - J706R	J702	0.076
T	J706B - J706J	0.102	J702C - J706J	J702	0.039

B

CONVAIR ASTRONAUTICS

Report 7A2236
Page 92

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results:

Specimen S/N 121.

United Central Corp. Spec.

Date: 6-18-59
Test Eng: R. T. Mabrey
CVAC Insp: N/A
USAF Insp: N/A

Paragraph	Specification Requirement	Remarks
4.2.1.1 d)	Hot Test 160°F @ 1.7 mm Hg.	CEC Recordings Run #1 Ext. to Int. Int. to Ext.
1.4	Operating Time: Start 94.5 hrs. Stop 94.9 hrs. Assembly Cycles 10 Start _____ hrs. Stop _____ hrs.	

Notes: 1. Following discrepancies occurred on Hypot test
 * a. J706 E, switch Ext. - breakdown @ 175 VEMMS
 * b. J702 A, switch Ext. - breakdown @ 175 VEMMS
 * c. J702 B, switch Int. - breakdown @ 150 VEMMS
 Some intermittent breakdown @ 1375 VEMMS
 * d. J702 A, no case on dielectric strength test
 measured at 60 u.a.

Note: e. J701 A to case 4.5 u.i

Note: f. J701 C to case 2.5 u.i

Part. Sel. 9
For para. 2.2.1.1 Specimen 3/N 1621
United Control

- Indicates out of tolerance

ASSEMBLY CYCLE OPERATION

Control Para 4.0.8 voltage	Step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle Int. to Ext. IES. to Int.
10V	2	1.26	2 max	
10V	3	1.24	2 max	
10V	4	0.79	2 max	
10V	5	0.69	2 max	
10V	6	0.92	2 max	
20V	7	0.91	2 max	

Date: 6-18-'59
Engineer: R. T. Mobley
CVAC Disp: NA
USAF Disp: NA

* DIELECTRIC ATTENUATION

All circuits satisfactory - - - - - YES NO

* INSULATION RESISTANCE

All circuits measured greater than 10 megohms - - - YES NO

SWITCH COMPLETION AND HOLD CAPACITY

All switches satisfactory

Para 4.0.8 step	IES	No sec note	Switch position Internal, External
1			
2			
3			

CIRCUIT SEQUENCE TIME (20 milliseconds minimum)

External to Internal 20.8 milliseconds

Internal to External 2.37 milliseconds

POSITION TRANSFER TIME (15 milliseconds maximum)

Circuit Chan. No.	C.S.C. No	In to Ex	Ex to In
P14	2	4.8	3.2
P32	9	▲	▲
P10	1		
P16	1		
P40	1		
P18	1	Y	Y
P20	1	Y	Y
P26	8	4.8	3.2

Circuit Chan. No.	C.S.C. No	In to Ex	Ex to In
P12	1	4.8	3.2
P22	0		
P34	1		
P44	9		
P16	8		
P28	3	Y	Y
P38	7	4.8	3.2

VOLTAGE DROP:

Maximum Control Voltage (30 V.)

No. No.	CIRCUIT	DATA	TEST	No. No.	CIRCUIT	DATA
A	J701G - J701D	0.069	A	J701A - J701D	0.061	
B	J706P - J705L	0.176	B	J701A - J705L	0.133	
C	J705I - J705K	0.141	C	J701A - J705K	0.145	
D	J706B - J705I	0.166	D	J701A - J705I	0.265	
E	J705I - J702B	0.187	E	J702A - J705B	0.235	
F	J702A - J703B	0.118	F	J702A - J702B	0.071	
G	J706A - J703D	0.132	G	J702B - J702D	0.122	
H	J706Y - J703E	0.148	H	J702B - J703E	0.135	
I	J706A - J703D	0.130	I	J702C - J703D	0.112	
J	J706F - J703H	0.083	J	J702D - J703H	0.042	
K	J706G - J703L	0.126	K	J702A - J703L	0.081	
L	J706H - J703M	0.147	L	J702A - J703M	0.103	
M	J706H - J703P	0.150	M	J702B - J703P	0.113	
N	J706Z - J703R	0.185	N	J702C - J703R	0.132	
O	J706J - J704A	0.133	O	J702A - J704A	0.103	
P	J706G - J704C	0.100	P	J702B - J704C	0.065	
Q	J706R - J704J	0.094	Q	J702C - J704J	0.081	
R	J706P - J704N	0.172	R	J702A - J704N	0.106	
S	J706X - J704R	0.122	S	J702B - J704R	0.075	
T	J706B - J704T	0.102	T	J702C - J704T	0.061	

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See Notes

9.2.1.1 Hot test 160°F

C 1.7 mm Hg.

Date: 6-19-59Page 94Test Engg: R. T. Mobley

Report 1A2236

CVAC Ingr: N4MAP Loop: NA

VOLTAGE DROP:

Minimum Control Voltage (25 V.)

Switch In External Position		Switch In Internal Position			
SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA
A	J701C - J701D	6.299	J701L - J701D	6.162	
B	J706P - J706L	6.177	J701L - J706L	6.132	
C	J706T - J705K	0.149	J701L - J706K	0.139	
D	J706S - J705J	6.180	J701L - J705J	6.214	
E	J706R - J705G	0.202	J701L - J705H	0.236	
F	J706K - J703A	0.120	J702A - J703A	0.074	
G	J706G - J703D	0.136	J702B - J703D	0.114	
H	J706Y - J703W	6.120	J702A - J703W	0.075	
I	J706M - J703N	0.132	J702B - J703G	0.114	
J	J706E - J703K	6.085	J702B - J703K	6.044	
K	J706Q - J703L	0.129	J702A - J703L	0.131	
L	J706H - J703M	0.150	J702A - J703M	6.102	
M	J706H - J703P	6.151	J702B - J703P	0.115	
N	J706G - J703R	6.138	J702B - J703R	0.122	
O	J706J - J704A	0.135	J702A - J704A	0.105	
P	J706A - J704C	6.100	J702B - J704C	0.166	
Q	J706B - J704J	6.076	J702C - J704J	0.082	
R	J706Z - J704M	0.145	J702A - J704M	6.107	
S	J706Y - J704R	0.124	J702B - J704R	0.078	
T	J706D - J704T	6.102	J702A - J704T	0.041	

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results:

Specimen S/N 421

United Control Corp. Spec.

Date: 6-19-'59

Test Engn: E.L. Mobley

CVAC Insp: NA

USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.2.1.1 c)	+40°F @ 75%RH test	SEC Recording Run #1 Int. to Ext. #2 Ext. to Int. Mag. #
1.4	Operating Time: .6 hr. Start <u>04.9</u> hrs. Stop <u>05.5</u> hrs. Assembly Cycles 10 Start _____ hrs. Stop _____ hrs.	

Notes: Hypot Test

J702 A (switch Int.) broke down appx. 200VAC

J702 A to case \rightarrow 60 ua

J706 Y to case 13 ua

J706 f to case 12 ua

J702 A to J706 Y 15 ua

J706 Y to J706 f 11 ua

Part. 4.1.7
 Per part. 4.1.1 Specimen S/N 121 Date: 6-19-'59
 United Control Corp. CVAC Imp: NA
 * Indicates out of tolerance Specimen USAP Imp: NA

ASSEMBLY CYCLE OPERATION:

Control Part 4.1.7	Time	Tolerance	Time of assembly cycle	
voltage	step	(seconds)	(seconds)	In to Ext Ext to In
15V	A	1.37	1 max	
15V	C	1.44	1 max	
30V	B	.86	2 max	
30V	D	.58	2 max	
PSV	E	.90	2 max	
25V	F	1.24	3 max	

Dielectric Strength:

All circuits satisfactory ----- YES NO

See Note X

Insulation Resistance:

All circuits measured greater than 10 megohms --- YES NO

Switch Continuity and Non-Continuity:

All switches satisfactory

Part 4.1.7	NO	Switch position
step	see note	Internal External

SWITCH SWING TIME: (20 milliseconds minimum)

External to Internal 26.7 milliseconds

Internal to External 27.0 milliseconds

POSITION SWING TIME: (15 milliseconds maximum)

Circuit Chan. No.	C.P.C.	In to Ext	Ext to In
P14	I	9.2	3.3
P32	II	↑	↑
P30	III	↑	↑
P34	IV	↑	↑
P40	V	↑	↑
P18	VI	↓	↓
P20	VII	↓	↓
P26	VIII	9.2	3.3

Circuit Chan. No.	C.P.C.	In to Ext	Ext to In
P42	I	3.2	3.3
P22	II	4	4
P34	III	↑	↑
P44	IV	↑	↑
P16	V	↑	↑
P28	VI	↓	↓
P38	VII	3.2	3.3

WAVEFORM

Medium Control Voltage (30 V.)

External

SW. NO.	CIRCUIT	DATA	SW. NO.	CIRCUIT	DATA
A	J701A - J701D	0.066	A	J701A - J701D	0.200
B	J706P - J705L	0.156	B	J701A - J705L	0.161
C	J706T - J705K	0.135	C	J701A - J705K	0.130
D	J706N - J705P	0.202	D	J701A - J705P	0.152
E	J706R - J705Q	0.322	E	J701A - J705Q	0.180
F	J706S - J705U	0.066	F	J702A - J702D	0.072
G	J706N - J705N	0.091	G	J702A - J705N	0.110
H	J706Y - J705Y	0.025	H	J702A - J705Y	0.110
I	J706A - J705G	0.091	I	J702C - J703G	0.111
J	J706F - J703X	0.039	J	J702C - J703X	0.075
K	J706G - J703L	0.063	K	J702A - J703L	0.075
L	J706H - J703M	0.081	L	J702A - J703M	0.124
M	J706W - J703P	0.081	M	J702A - J703P	0.124
N	J706K - J703R	0.097	N	J702C - J703R	0.118
O	J705J - J704A	0.093	O	J702A - J704A	0.118
P	J706E - J704Q	0.060	P	J702B - J704C	0.083
Q	J706A - J704J	0.065	Q	J702C - J704J	0.080
R	J706P - J704V	0.092	R	J702A - J704V	0.123
S	J706X - J704R	0.071	S	J702B - J704R	0.116
T	J706B - J704T	0.035	T	J702C - J704T	0.098

CONTINUITY CHECKSAll circuits indicated continuity . . . Yes No See Notes

4.2.1.1e) + 40°F @ 95% R.H.

A

Date: 6-19-59Page 99Test Engg: R. T. Mobley

Report 712236

CVAC Insp: NATIAF Insp: NA

VOLTAGE DROP:

Minimum Control Voltage (25 V.)

Switch in External Position		Switch in Internal Position			
SL. NO.	CIRCUIT	DATA	SL. NO.	CIRCUIT	DATA
A	J701C - J701D	0.029	A	J701A - J701D	0.066
B	J701P - J705L	0.162	B	J701A - J705L	0.142
C	J706T - J705K	0.137	C	J701A - J705L	0.136
D	J706G - J705S	0.146	D	J701A - J705J	0.217
E	J706R - J705C	0.180	E	J701A - J705Q	0.301
F	J705F - J703A	0.073	F	J702A - J703A	0.069
G	J706G - J703D	0.111	G	J702B - J703D	0.092
H	J706I - J703P	0.111	H	J702B - J703P	0.026
I	J706 - J703Q	0.110	I	J702C - J703Q	0.292
J	J706C - J703K	0.072	J	J702C - J703K	0.040
K	J706G - J703L	0.074	K	J702A - J703L	0.065
L	J706H - J703M	0.122	L	J702A - J703M	0.192
M	J706W - J703P	0.174	M	J702B - J703P	0.092
N	J706G - J703R	0.120	N	J702C - J703R	0.100
O	J706J - J704A	0.120	O	J702A - J704A	0.092
P	J706I - J704C	0.083	P	J702B - J704C	0.052
Q	J706B - J704J	0.078	Q	J702B - J704J	0.066
R	J706Y - J704N	0.122	R	J702A - J704N	0.094
S	J706X - J704R	0.113	S	J702B - J704R	0.070
T	J706B - J704T	0.088	T	J702B - J704T	0.036

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Unsatisfactory

Specimen S/N 126, United Control
Corp. SpecimenDate: 6-19-57
Test Engr: R. T. Mobley
CVAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.4.1.1 +)	Post Env. & Ambient Cond. Protect Cycle	
1.4	Operating Time: .4 hr. Start <u>22.5</u> hrs. Stop <u>25.1</u> hrs. Assembly Cycles 10 Start _____ hrs. Stop _____ hrs.	

- Notes:
- X 1. During Hypot test (switch Ext.) had breakdown of 200VDC in T116 E
 - X 2. Dielectric strength test (Ext.) - T116 E
→ 1000vdc.
 - 3. JEC Record #1. Int. to Ext.; #2. Ext. to Int.

Para. 4.1.9
 For para. Exhibit Specimen S/N 1st
United Control Corp.
 * Indicates out of tolerance Specimen

Date: 14-59
 Engineer: Ring, Model 4
 CVAC Insp: NH
 USAF Insp: NH

ASSEMBLY CYCLE OPERATION:

Control Para 4.1.8 voltage	Step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle
				Int. to Ext. Ext. to Int.
18V	1	1.26	1 MAX	
18V	4	1.49	3 MAX	
30V	1	0.73	2 MAX	
30V	1	0.83	2 MAX	
25V	1	2.79	2 MAX	
25V	1	2.76	2 MAX	

DIELECTRIC STRENGTH:

All circuits satisfactory - - - - - NO

INSULATION RESISTANCE:

All circuits measured greater than 10 megohms - - - NO

SWITCH CONTINUITY AND NONCONTINUITY:

All switches satisfactory

Para 4.1.8 step	YES	NO see note	Switch position
			Internal External
1			
1			

CYCLE SEQUENCE TIME: (20 milliseconds minimum)

External to Internal 240 milliseconds

Internal to External 225 milliseconds

POSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit Chan. No.	In to Ex	Ex to In
P14	R	S, E
P32	O	A
P30	H	
P36	I	
P40	J	
P28	K	
P20	L	V
P26	M	S, D

Circuit Chan. No.	In to Ex	Ex to In
P42	N	S, D
P22	O	A
P34	P	
P16	Q	
P28	R	
P28	S	V
P28	T	S, D

CONVAIR
SAN DIEGO

VOLTAGE READ?

Maximum Central Voltage (30 V.)

VOLTA

		Switch In External Position		Switch In Internal Position		
SW. NR.	CIRCUIT	DATA	SW. NR.	CIRCUIT	DATA	SW.
A	J701A - J701D	0.079	A	J701A - J701D	0.059	A
B	J705F - J705L	0.159	B	J701A - J705L	0.133	B
C	J706T - J705E	0.136	C	J701A - J705K	0.138	C
D	J705S - J705J	0.146	D	J701A - J705T	0.226	D
E	J706B - J702B	0.125	E	J702A - J703C	0.213	E
F	J706A - J703A	0.082	F	J702A - J703A	0.080	F
G	J706A - J703D	0.120	G	J702B - J703D	0.095	G
H	J706Y - J703F	0.115	H	J702B - J703F	0.110	H
I	J706A - J703G	0.120	I	J702C - J703G	0.096	I
J	J706S - J703K	0.075	J	J702C - J703K	0.044	J
K	J706G - J703L	0.094	K	J702A - J703L	0.026	K
L	J706H - J703M	0.130	L	J702A - J703M	0.090	L
M	J706W - J703P	0.140	M	J702A - J703P	0.095	M
N	J706X - J703R	0.120	N	J702C - J703R	0.105	N
O	J706J - J704A	0.125	O	J702A - J704A	0.110	O
P	J706G - J704C	0.089	P	J702B - J704C	0.056	P
Q	J706R - J704J	0.084	Q	J702C - J704J	0.070	Q
R	J706F - J704N	0.135	R	J702A - J704N	0.115	R
S	J706Y - J704B	0.110	S	J702B - J704B	0.063	S
T	J706B - J704T	0.092	T	J702C - J704T	0.034	T

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See Notes

4.2.1.1 f. Post Environmental Ambient
Env. Proof Cycle

A

Date: 6-19-59Page 100Test Engr: R. T. Melley

Report 7A2236

CVAC Insp: NAIBAF Insp: NA

VOLPAGE DROP:

Minimum Control Voltage (25 V.)

Switch in External Position			Switch in Internal Position		
No. BR.	CIRCUIT	DATA	No. BR.	CIRCUIT	DATA
A	J701C - J701D	0.105		J701A - J701D	0.069
B	J706P - J708L	0.162		J701A - J703L	0.131
C	J706T - J705K	0.136		J701A - J705K	0.147
D	J706S - J705J	0.153		J701A - J705J	0.228
E	J706R - J705C	0.180		J701A - J705Q	0.259
F	J706B - J703A	0.094		J702A - J703A	0.084
G	J706O - J703D	0.135		J702B - J703D	0.102
H	J706I - J703P	0.120		J702B - J703P	0.037
I	J706M - J703N	0.120		J702C - J703N	0.098
J	J706X - J703K	0.028		J702G - J703K	0.045
K	J706Q - J703L	0.110		J702A - J703L	0.029
L	J706H - J703M	0.140		J702A - J703M	0.192
M	J706W - J703P	0.140		J702B - J703P	0.097
N	J706G - J703R	0.130		J702C - J703R	0.110
O	J706J - J704A	0.130		J702A - J704A	0.115
P	J706I - J704C	0.092		J702B - J704C	0.056
Q	J706R - J704J	0.088		J702C - J704J	0.072
R	J706Y - J704N	0.140		J702A - J704N	0.120
S	J706X - J704R	0.115		J702B - J704R	0.065
T	J706B - J704T	0.094		J702C - J704T	0.034

B

CONVAIR ASTRONAUTICS

REPORT 7A2236

Page 101

4.1 TEST CONDITIONS AND PROCEDURES: (Continued)

General Test Results: Satisfactory

Specimen S/N 121.

United Control Corp.

Date: 6-30-'59
Test Engr: Ruth Mobley
CVAC Insp:
USAF Insp:

Paragraph	Specification Requirement	Remarks
4.4	Operating Acc. Post Acc. Prod Cycle	CEC Recording Speed # 4 timing A Int. to Ext. to Int, Speed # 2, timing B Loads off Loads ON Int. to Ext. to Int. Loads off Recorder Mag. #
2.4	Operating Time: Start <u>961 hrs.</u> Stop <u>970 hrs.</u> Assembly Cycles Start _____ hrs. Stop _____ hrs.	14

- * Notes: 1. During operating Acceleration Acc. within one cycle no greater than 7.5 millile. and for 3M, 4G must
- * 2. cycle sequence will be less than 1.0 sec. and, * exact time in registering Not work

Part. 4.1.7

For part. 4.4 Specimen S/N 121

United Control Corp. Spec.

* Indicates out of tolerance

Date: 6-30-'59
 Engineer: P. T. Mobley
 CVAC Insp: NA
 USAF Insp: NA

ASSEMBLY CYCLE OPERATION:

Control voltage	Part 4.1.8 step	Time (seconds)	tolerance (seconds)	Type of assembly cycle	
				Int. to Ext	Ext. to Int
15V	A	1.48	1 max	X	X
15V	B	1.37	1 max	X	X
30V	C	0.84	2 max	X	X
30V	D	0.70	2 max	X	X
25V	E	0.48	2 max	X	X
25V	F	0.95	2 max	X	X

DIRECT ELECTRIC STRENGTH:

All circuits satisfactory - - - - - YES NO

INSULATION RESISTANCE:

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NON-CONTINUITY:

All switches satisfactory

Part 4.1.8 step	YES	NO see note	Switch position	
			Internal	External

CYCLE SEQUENCE TIMES (20 milliseconds minimum)

External to Internal $\frac{1}{2}$ cycle 1 second $\frac{1}{2}$ millisecond

Internal to External millisecond

POSITION TRANSFER TIME (0.5 milliseconds maximum)

Circuit Chan. No.	C.E.C. No	Position Transfer Time	
		To Ext	To Int
P1			
P12			
P31			
P36			
P41			
P42			
P43			
P44			
P16			
P28			
P38			
P26			

Circuit Chan. No.	C.E.C. No	Position Transfer Time	
		To Ext	To Int
P42			
P22			
P31			
P44			
P16			
P28			
P38			

CONVAIR,
SAN DIEGO ✓

FORM 71

WOL

WELCHER JUMP:

Minimum Control Voltage (30 V.)

SWITCH IN External Position		SWITCH IN Internal Position			
SW. NR.	CIRCUIT	DATA	SW. NR.	CIRCUIT	DATA
A	J701G - J702D	.458	A	J701A - J701D	.074
B	J706P - J705L	.120	B	J701A - J705L	.129
C	J706T - J705K	.163	C	J701A - J705K	.133
D	J704B - J702F	.180	D	J701A - J702F	.126
E	J706R - J702E	.216	E	J702A - J702E	.154
F	J706M - J703A	.092	F	J702A - J703A	.159
G	J706N - J703D	.192	G	J702A - J703D	.160
H	J706Y - J703F	.110	H	J702A - J703F	.030
I	J706a - J703O	.130	I	J702C - J703O	.170
J	J706S - J703K	.074	J	J702C - J703K	.082
K	J706G - J703L	.109	K	J702A - J703L	.150
L	J706H - J703M	.142	L	J702A - J703M	.168
M	J706W - J703P	.145	M	J702A - J703P	.160
N	J706Z - J703R	.132	N	J702C - J703R	.179
O	J706J - J704A	.122	O	J702A - J704A	.193
P	J706d - J704C	.092	P	J702B - J704C	.081
Q	J706R - J704J	.092	Q	J702C - J704J	.139
R	J706T - J704L	.186	R	J702A - J704L	.190
S	J706I - J704B	.117	S	J702A - J704B	.092
T	J706b - J704T	.094	T	J702C - J704T	.066

CONTINUITY CHECK:

All circuits indicated continuity Yes No see Notes

4.4 Post Acceleration
Proof Cycle

A

Date: 6-30-58Page 103Test Engr: P.I. Mobley

Report 7A2236

CVAC Insp: NADEAF Insp: NA

VOLTAGE DROP:

Minimum Control Voltage (25 V.)

Switch in External Position			Switch in Internal Position		
SN. NO.	CIRCUIT	DATA	SN. NO.	CIRCUIT	DATA
A	J701C - J701D	.497	A	J701A - J701D	.051
B	J706P - J703L	.163	B	J701A - J705L	.129
C	J706T - J703K	.149	C	J701A - J702Y	.130
D	J706S - J703J	.154	D	J701A - J703J	.119
E	J706R - J703G	.190	E	J702A - J703G	.159
F	J706X - J703A	.084	F	J702A - J703A	.160
G	J706O - J703D	.132	G	J702B - J703D	.162
H	J706Y - J703F	.110	H	J702A - J703F	.030
I	J706N - J703H	.130	I	J702C - J703H	.172
J	J706F - J703K	.079	J	J702C - J703K	.082
K	J706Q - J703L	.105	K	J702A - J703L	.156
L	J706H - J703M	.147	L	J702A - J703M	.171
M	J706W - J703P	.145	M	J702B - J703P	.160
N	J706Z - J703R	.133	N	J702C - J703R	.180
O	J706J - J704A	.124	O	J702A - J704A	.195
P	J706M - J704C	.094	P	J702A - J704C	.082
Q	J706B - J704J	.095	Q	J702C - J704J	.140
R	J706P - J704H	.132	R	J702A - J704H	.193
S	J706I - J704R	.127	S	J702B - J704R	.022
T	J706B - J704J	.100	T	J702C - J704J	.067

B

CONVAIR ASTRONAUTICS

REPORT 7A2236

PAGE 104

4.1 TEST CONDITIONS AND PROCEDURES₁ (Continued)

General Test Results: Marginal (Re-test) Date: 6-30-59

Specimen S/N 121. UNITED CONTROL
CORP SPECIMENTest Engrs: R.L. MOOLEY, J.C. GOURAUD
CVAC Insp: N/A
USAF Insp: N/A

Paragraph	Specification Requirement	Remarks
4.3	OPERATING VIBRATION 5 to 125 CPS. "X" AXIS	RECORDER MAG. NO. 159 SPEED #2, (16"/sec) RECORD NO. TIMING - "B" 0253 18 CHANNEL C.E.C RECORDING RESONANCES: #1 - DRIVE 2 - "X" AXIS 3 - "Y" AXIS 4 - "Z" AXIS 5 - APPEE MAG. NO. 199 CK 21 RECORD NO. 08233
4.4	Operating Time: Start <u>27.5</u> hrs. Stop <u>27.66</u> hrs. Assembly Cycles 2 Start _____ hrs. Stop _____ hrs.	APS EVERY CYCLE FROM 5-20, " 5 CYCLES 30-100, 110, 120, & 125. DOUBLE PIPS AT 5, 20, 125.

Notes:

CONVAIR II ASTRONAUTICS

6.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Marginal (Retsst) Date: 6-30-'59
 Specimen S/N 121. Test Engr: R. T. Mobley
 United Control Corp. CVAC Insp: NA
 USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	OPERATING VIBRATION 5-125 CPS "Y" Axis (re-run)	Recorder Mag. # 137 Speed # 2 (16 ^{Vi} /sec) Timing B 18 channel CEC recording resonances #1 Drive #2 "X" Axis #3 Y Axis #4 Z Axis #5 Pipper Pips every cycle 5-20 every 5! 20-100 110, 120, 125 double pips @ 20, 125, 5
1.4	Operating Time: Start <u>97.0</u> hrs. Stop <u>122.2</u> hrs. Assembly Cycles Start _____ hrs. Stop _____ hrs.	Mag. # <u>25073</u> 4

- Notes: 1. Made a switch transfer I to E to I @ 90 CPS
 2. There were NO large resonances during this sweep - the only one of note was in "Y" Axis @ 120 CPS

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Marginal (Retest) Date: 6-30-59Specimen S/N 121. United Control Corp. Specimen
Test Engr: R.T. McALEY / J. CURTRIGHT
CVAC Insp: NIA / JAC
USAF Insp: NIA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. 5 - 12.5 CPS "Z" AXIS (RERUN)	RECORDER MAG. NO. 159 SPEED #2, (16"/SEC.) TIMING "B" 18 CHANNEL C.E.C. RECORDINGS RESONANCES: #1 - DRIVE 2 - "X" AXIS MAG NO. 3 - "Y" AXIS 26073 4 - "Z" AXIS 5 - PIPER
4.4	Operating Time: Start <u>97.2</u> hrs. Stop <u>97.5</u> hrs. Assembly Cycles 2 Start _____ hrs. Stop _____ hrs.	PIPS EVERY CYCLE FROM 5-20, " " 5 CYCLES FROM 20-100 10, 120, 125 DOUBLE PIPS AT 5, 20, 125 See Note 1 BELOW.

- Notes:
1. IT APPEARS THAT THE 18 CHANNEL C.E.C. RECORDER ON THE ACCELEROMETER OUTPUTS WAS FUNCTIONING ABERRANTIALLY DURING THIS VIBRATION TEST. IN ORDER TO PREVENT OVERTESTING IN THE X AXIS IT WAS DECIDED TO END THE "X" AXIS RESONANT SEARCH BEFORE RE-RUNNING THE "Z" AXIS.
 2. The Accelerometer output recording was N.G. so it was destroyed.

4.1 TEST CONDITIONS AND PROCEDURES: (Continued)

General Test Results: Marginal (1st Re-test)Specimen S/N 121. UNITED CONTROL
CORP. SPECIMEN.

Date: 6-30-59

Test Engr: E.T. MOSELEY / J. COURTRIGHT
CVAC Insp: N/A
USAP Insp: N/A

Paragraph	Specification Requirement	Remarks
4.3	OPERATING VIBRATION 5 - 125 G.P.S. RERUN OF "Z" AXIS (SEE NOTE 1 BELOW).	RECORDED MAG. NO. 333 SPEED #2 (16"/sec) RECORD NO. 0256 18 CHANNEL CEC Readings RESONANCES: #1 - DRIVE 2 - "X" AXIS 3 - "Y" AXIS 4 - "Z" AXIS 5 - PAPER MAG. NO. 199 CLK. 21 RECORD NO. 08234
1.4	Operating Time: Start 97.66 hrs. Stop 97.85 hrs. Assembly Cycles 2 Start _____ hrs. Stop _____ hrs.	PIDS EVERY CYCLE FROM 5 TO 20, " 5 CYCLES " 20 TO 100 110, 120, & 125. DOUBLE PIDS AT 5, 20, 125

Notes: 1. THIS VIBRATION SWEEP IS A REPEAT OF THE ONE CONDUCTED FROM 97.2 TO 97.5 HOURS OPERATING TIME EARLIER THIS EVENING.

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results:

Specimen S/N 121. United Control
Corp. SpecimenDate: July 7, 1959
Test Engr: P.T. Mobley
CVAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.5	Life Test	
1.4	Operating Time: Start <u>97.2</u> hrs. Stop _____ hrs. Assembly Cycles Start _____ hrs. Stop _____ hrs.	

- Notes: 1. A total of 132 cycles (switching) had been put on specimen in testing prior to beginning of Life Test.
 2. 214 cycles required to obtain 331 cycles.

VOLTAGE CHECK:

Maximum Control Voltage (30 V.)

VOLTA

Switch in External Position		Switch in Internal Position				
SN. NO.	CIRCUIT	DATA	SN. NO.	CIRCUIT	DATA	SN.
A	J701A - J701D	0.013 + .030	A	J701A - J701D	0.024	A
B	J701P - J705L	0.005	B	J701A - J705L	0.012	B
C	J706T - J705K	0.013	C	J701A - J705K	0.028	C
D	J706S - J705W	0.009	D	J701A - J705W	0.024	D
E	J706B - J702R	0.021	E	J702A - J703C	0.007	E
F	J702B - J702H	0.032	F	J702B - J702H	0.025	F
G	J702A - J703M	0.032	G	J702B - J703P	0.115	G
H	J706Y - J703P	0.031	H	J702B - J703P	0.115 ON 3	H
I	J706A - J703O	0.028	I	J702C - J703O	0.137	I
J	J706F - J703S	0.030	J	J702C - J703K	0.105	J
K	J706G - J703L	0.025	K	J702A - J703L	0.038	K
L	J706H - J703M	0.030	L	J702A - J703M	0.025	L
M	J706W - J703P	0.032	M	J702A - J703P	0.115	M
N	J706R - J703R	0.030	N	J702C - J703R	0.028	N
O	J706J - J704A	0.029	O	J702A - J704A	0.025	O
P	J706S - J704C	0.027	P	J702B - J704G	0.084	P
Q	J706R - J704J	0.031	Q	J702C - J704J	0.027	Q
R	J706P - J704H	0.025	R	J702A - J704H	0.027	R
S	J706X - J704S	0.027	S	J702B - J704R	0.082	S
T	J706B - J704T	0.018	T	J702C - J704T	0.090	T

CONTINUITY CHECK:

All circuits indicated continuity . . . Yes No See Notes

4.5 Life Test United Control

Corp. Specimen SN-121

Made at 354 cycles

Switch w/ INT CIR

made at 500

A

Date: _____

Page 109

Test Engr: _____

Report 7A2236

CVAC Insp: _____

USAF Insp: _____

VOLTAGE DROP:

Maximum Control Voltage (25 V.)

SW. MK.	Switch in External Position		Switch in Internal Position			
	CIRCUIT	DATA	SW. MK.	CIRCUIT	DATA	
A	J7013 - J7010			J701A - J701D		
B	J706P - J705L			J701A - J705L		
C	J706E - J705X			J701A - J705X		
D	J706S - J705J			J701A - J703J		
E	J706R - J703G			J701A - J703G		
F	J706Z - J703A			J702A - J703A		
G	J706C - J703D			J702B - J703D	0.030	
H	J706Y - J703F			J702B - J703F	0.029	
I	J706 - J703O			J702C - J703O	0.028	
J	J706Y - J703K			J702C - J703K	0.026	
K	J706Q - J703L			J702A - J703L	0.028	
L	J706H - J703M			J702A - J703M		
M	J706W - J703P			J702B - J703P	0.028	
N	J706Z - J703R			J702C - J703R		
O	J706J - J704A			J702A - J704A		
P	J706d - J704C			J702B - J704C	0.028	
Q	J706R - J704J			J702C - J704J		
R	J706P - J704N			J702A - J704N		
S	J706X - J704R			J702B - J704R	0.025	
T	J706b - J704T			J702C - J704T	0.027	

in INTERNAL POSITION

at 500 cycles

B

CONVAIR ASTRONAUTICS

REPORT 7A2236

Page 110

Part. No. 4.1.9For Part. 4.5
United Control Corp.
Specimen SN 121Date: July 10, 1959Test Engg: R. T. MobleyCVAC Insp: NAUSAID Insp: NA~~VOLTAGE DROP MEASUREMENTS ON CONTROL~~ Using Test Set.
4P @ end of Life Test

SWITCH	CRT.	DATA	Internal	SWITCH	CRT.	External DATA
A	P2-P1	0.059		A	P2-P3	0.096
B	P6-P1	0.109		B	P6-P5	0.162
C	P12-P1	0.104		C	P12-P11	0.160
D	P10-P1	0.105		D	P10-P9	0.142
E	P8-P1	0.122		E	P8-P7	0.178
F	P14-P13	0.031		F	P14-P15	0.114
G	P32-P25	0.096		G	P32-P33	0.120
H	P30-P25	0.031		H	P30-P31	0.114
I	P26-P37	0.105		I	P36-P39	0.120
J	P10-P37	0.040		J	P10-P43	0.077
K	P18-P13	0.080		K	P18-P19	0.128
L	P20-P13	0.090		L	P20-P21	0.136
M	P26-P25	0.102		M	P26-P27	0.136
N	P42-P37	0.110		N	P42-P45	0.127
O	P22-P13	0.112		O	P22-P23	0.127
P	P34-P25	0.054		P	P34-P35	0.127
Q	P46-P37	0.074		Q	P46-P47	0.086
R	P16-P13	0.110		R	P16-P17	0.137
S	P28-P25	0.063		S	P28-P29	0.112
T	P38-P37	0.032		T	P38-P41	0.142

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Failed

Specimen S/N 123 United Control
Corp. SpecimenDate: July 14, 1967
Test Engr: E.T. Mobley
CVAC Insp: NA
USAP Insp: NA

Paragraph	Specification Requirement	Remarks
4.1.8	Initial satisfactory	- see note 1 below - The Hypot breakdown was determined to be caused by the vendor using an improper relays for the AC switch
1.4	Operating Time: Start 1C 9 hrs. Stop 102 hrs. Assembly Cycles 0 2 Start _____ hrs. Stop _____ hrs.	

Note 1. During Hypot test with 1500 V RMS applied, leakage & breakdown occurred between T706F-T706G; T706H-T706G; intermittent between G & H and between F & G and between F & H.

Note 2. D.C. switch failed on plunger on third cycle after 10 hours operation. Motor limiting micro-switch was found to be contaminated and hanging-up in the open position. Exercising the plunger a few times freed the switch and allowed the DC switch to operate. The switch was replaced and sent to the vendor.

CONVAIR ASTRONAUTICS

Report 7A2236

Page 113

Para. 4.1.8
 Per para. 4.1.8 Specimen S/N 124
 United Control Corp.

* Indicates out of tolerance

Date: July 14 '59
 Engineer: E. T. Mobley
 CVAC Insp: NH
 USAF Insp: NH

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle
				Int. to Ext. Ext. to Int.
10V	A	1.933	1 MAX	
15V	A	1.514	1 MIN	
30V	I		2 MAX	
30V	I		2 MAX	
25V	I		2 MAX	
25V	I		2 MAX	

Dielectric Strength:X All circuits satisfactory - - - - - YES NO Insulation Resistance:All circuits measured greater than 10 megohms - - - YES NO Switch Continuity and Non-Continuity:

All switches satisfactory

Failed before these steps ran

Para 4.1.8 step	YES	NO	Notes	switch position
1				Internal
2				External
3				External
4				External

CYCLE SEQUENCE TIME (20 milliseconds minimum)

External to Internal - - - milliseconds

Internal to External - - - milliseconds

POSITION TRANSFER TIME (15 milliseconds maximum)

Circuit	C.R.C.	In to Rx	Rx to Tx	Tx to In
P14	F			
P32	G			
P30	H			
I4	I			
P20	J			
P18	K			
P20	L			
P20	M			

Circuit	C.R.C.	In to Rx	Rx to Tx	Tx to In
P4R	N			
P2R	O			
P3R	P			
P1A	Q			
P1B	R			
P2R	S			
P1B	T			

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: Satisfactory

Date: Oct. 5

Specimen S/N 124, United Control

Test Instr: H. Edwards

CVAC Instr:

UAP Instr: NA

Paragraph	Specification Requirement	Remarks
4.1.8	Initial Satisfactory	Initial Sat. 104
	Operating Time:	
1.4	Start 158.6 hrs. Stop 159.4 hrs.	

Assembly Cycles 8

Start _____ hrs.
Stop _____ hrs.

The voltage drop across J701A - J701D was considerably too high. It was determined that the sensing lead on J701A was loose. This was repaired but the voltage drop was then meas. as 1.3 VDC. It was noted that plug in J701 was badly pitted and that the plug heated up. (One on test set pitted) This plug will be changed after Vib. and a new set of E'drop meas. made.

Para. 4.1.8 United Control
 Para para. 4.1.8 Specimen S/N 124
 * Indicates out of tolerance Initial Sat.

Date: Oct. 5
 Engineer: H. Edwards
 CVAC Insp: ---
 USAF Insp: TVA

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.8 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle	Int. to Ext.	Ext. to Int.
16V	A	1.449	1 max	X		
16V	d	1.525	1 max	X	X	
20V	f	0.673	2 max	X		
20V	i	0.661	2 max	X	X	
25V	j	0.781	2 max	X		
25V	j	0.914	2 max	X	X	

Dielectric Strength:

All circuits satisfactory ----- YES NO

Insulation Resistance:

All circuits measured greater than 10 megohms ---- YES NO

Switch Continuity and Non-Continuity

All switches satisfactory

Rec. No. 0849

Para 4.1.8 step	YES	NO	Switch position	Internal	External
1	X				
2	X				
3	X				

Cycle Sequence Times (20 milliseconds minimum)

External to Internal 142 milliseconds

Internal to External 140 milliseconds

Position Transfer Time (15 milliseconds minimum)

Circuit Num.	In to Rx	In to Tx	Rx to In	Tx to In
P14	X	1.0	1.0	
P32	0	A	A	
P30	B			
P34	I			
P42	J			
P18	I			
P20	K			
P26	M			

Circuit Num.	In to Rx	In to Tx	Rx to In	Tx to In
P42		1.0	1.0	
P22				A
P14				
P1				
P14				
P42				
P22				
P14				

CONVAIR
SAN DIEGO

110K DROP:

Maximum Control Voltage (30 V.)

Switch in External Position		Switch in Internal Position			
NO.	CIRCUIT	DATA	NO.	CIRCUIT	DATA
A	J701C - J701D	.048	A	J701A - J701D	.194
B	J706P - J705L	.142	B	J701A - J705L	.124
C	J705T - J705X	.162	C	J701A - J705X	.107
D	J706 - J705Y	.194	D	J701A - J705Y	.109
E	J702P - J705C	.119	E	J702A - J705C	.204
F	J706A - J702A	.110	F	J702A - J702U	.102
G	J701E - J702D	.105	G	J702B - J703B	.087
H	J702Y - J702W	.094	H	J702B - J703W	.031 .090
I	J706A - J705C	.105	I	J702C - J705C	.102
J	J702P - J703X	.082	J	J702C - J703X	.052
K	J706C - J701L	.140	K	J702A - J703L	.106
L	J706A - J703M	.135	L	J702A - J703M	.099
M	J706H - J701F	.102	M	J702A - J703P	.080
N	J706G - J702E	.113	N	J702E - J703B	.095
O	J701C - J701A	.146	O	J702A - J704A	.149
P	J706E - J701C	.099	P	J702B - J704C	.078
Q	J706R - J701J	.093	Q	J702C - J704J	.078
R	J706P - J704N	.138	R	J702A - J704N	.131
S	J706I - J704R	.118	S	J702B - J704B	.077
T	J702S - J704T	.93	T	J702C - J704T	.042

CONTINUITY CHECK

All circuits indicated continuity . . . See No See Notes

4.1.8. Initial Satisfactory Terminal Test

Date

Oct. 5

Page 115

Test Engr: H. Edwards

Report 7A2236

EVAC Loop: NA

IGAP Loop: NA

VOLTAGE DROPS:

Minimum Control Voltage (25 V.)

Ref. No.	Switched In External Position		Switched In Internal Position		
	CIRCUIT	DATA	CIRCUIT	DATA	
A	J701C - J701D	.064	A	J701A - J701D	.824 *
B	J701F - J701L	.133	B	J701A - J703L	.128
C	J706S - J705K	.168	C	J701L - J703X	.111
D	J706S - J705J	.177	D	J701L - J703J	.112
E	J706R - J705C	.193	E	J701A - J705C	.185
F	J706Z - J703A	.111	F	J702A - J703A	.099
G	J706C - J703D	.102	G	J702B - J703D	.087
H	J702I - J702T	.095	H	J702A - J703T	.030
I	J706M - J703G	.108	I	J702C - J703G	.100
J	J706P - J702K	.079	J	J703E - J702K	.050
K	J706C - J702L	.124	K	J702A - J703L	.0910
L	J706W - J703Y	.122	L	J702A - J703Y	.0910 .030
M	J706W - J702P	.098	M	J701B - J703P	.078
N	J706P - J703R	.111	N	J701Y - J703R	.028 .092
O	J706J - J702A	.143	O	J702A - J702A	.141
P	J706I - J702C	.098	P	J702B - J702C	.076
Q	J706E - J702J	.090	Q	J702C - J704J	.077
R	J702P - J702Y	.134	R	J702A - J704Y	.125
S	J706T - J702Z	.105	S	J701B - J704Z	.076
T	J701 - J702	.092	T	J702C - J704Z	.051

* NOTE: READING FLUCTUATED BETWEEN

0.324 AND 0.824 VOL.

It was determined that this discrepancy
was in the test set.

B

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results:

Specimen 124 United
Control SpecimenDate 10-6-59
Test Environs R.I. Mobley
CVAC Instr: NA
USAP Instr: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. Y Axis	#1 Z axis 2 acell. record #2 Y Axis 3 #3 X Axis 4 #1 drive 1 25G/II 2,3 & 4 50G/inch mag # 200cts/s record # 17994 5-80ps 17995 80-200ps
1.4	Operating Time: Start 159.4 hrs. Stop 160.0 hrs.	

Assembly Cycles 6

Start _____ hrs.
Stop _____ hrs.

- Notes: 1. Channel "A" (200A ckt.) was noted to have quite a bit of noise - an assembly cycle was made I to E at speed #1 @ 48 ps to see what ext. located here. Back to 2 at 36 ps.
2. Made assembly cycle I to E to I @ speed 4 timing A" at 200 ps
3. Assembly cycle at end of run made at speed 3

Para. 4.3 Open Vib. "V" Axis.
 Para para. 4.3 Specimen S/N 124

United Control

* Indicates out of tolerance

Date: 10-6-54
 Engineer: P.T. Mobley
 CVAC Insp: _____
 USAF Insp: NA

ASSEMBLY CYCLE OPERATION:

Control Para 4.1.6 voltage	step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle Int. to Ext. Ext. to Int.
15V	2	1.1	1 max	
15V	4	1.1	1 max	
30V	1	1.1	2 max	
30V	1		2 max	
25V	1		2 max	
25V	1		2 max	

Dielectric Strength:

All circuits satisfy - - - - - YES

Insulation Resistance:

All circuits measured greater than 10 megohms - - - YES

Switch Continuity and Non-Continuity:

All switches satisfactory

Para 4.1.6 step	YES	NO See note	Switch position Internal External
1			
2			
3			

Circuit Transfer Time: (20 milliseconds minimum)

External to Internal 260 milliseconds

Internal to External 225 milliseconds

End of run (hereby)

POSITION TRANSFER TIME: (15 milliseconds maximum)

Circuit Circuit Chan. No.	C.P.C. In to Ext. Ex to In	1.5	1.5
P11	1	1.5	1.5
P12	0	1.5	1.0
P10	1	2.0	2.0
P16	1	1.5	1.5
P13	1	1.5	2.2
P18	1	1.5	1.5
P20	1	1.5	1.2
P26	1	1.5	2.0

Circuit Circuit Chan. No.	C.P.C. In to Ext. Ex to In	1.5	1.5
P11	1	1.5	1.5
P12	0	1.5	1.5
P14	1	1.5	1.2
P15	1	1.5	2.5
P1A	1	1.5	1.5
P13	1	1.5	1.5
P18	1	1.5	1.5
P20	1	1.5	1.5
P26	1	1.5	1.5

4.1 TEST CONDITIONS AND TESTS (Continued)

General Test Results:

Specimen S/N 124 United Cont.

Date 10-6-'59
 Test Engg. R.J. Mobley
 CVAC Inspr.
 ADAP Inspr. N/A

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. "Z" axis	Calib. on front of "Z" axis scope - Textronix calib. input 12" run at 100 m.v.in 12" run at 600 m.v.in record mag. # 159
4.4	Operating Times: Start 160.0 hrs. Stop 162.5 hrs. Assembly cycles: Start 6 Stop 10	acell. record mag. # 2000 & 21 record # 18000 Calib. and pos. same as "Y" Axis

- ^{Notes:}
1. Made assembly cycle I to E at 45 cps - back to I at 65 cps - switch made considerable rattling noise during both 'Y' & 'Z' sweeps
 2. Made assembly cycle I-E-I @ speed 4, timing A, @ 140 cps

Opn. Vib. "Z" Axis

Para. 4.3
 Per para. 4.3 Specimen S/N 124
United Control

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para 4.1.6 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle
				Int. to Ext. Ext. to Int.
10V	A		3 max	
15V	A		1 max	
30V	?	N/A	2 max	N/A
30V	I		2 max	
25V	I		2 max	
25V	I		2 max	

DIELECTRIC STRENGTH:

All circuits satisfactory - - - - - YES NO

INSULATION RESISTANCE:

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND MAIN CONTINUITY:

All switches satisfactory

Para 4.1.6 step	YES	NO see note	Switch position
			Internal External
1		N/A	
1			
1			
1			

CYCLE SEQUENCE TIME: (20 milliseconds minimum)

External to Internal 530 milliseconds

Internal to External 225 milliseconds

POSITION TRANSFER TIME: (15 milliseconds maximum) end of run

C.R.C. Circuit Chan. No.	In to Ex	Ex to In	C.R.C. Circuit Chan. No.	In to Ex	Ex to In
P14	1.5	1.5	P12	1.5	1.5
P12	4.0	4.5	P22	2.0	1.5
P30	2.0	2.5	P34	1.8	1.0
P36	1.0	1.0	P44	2.8	1.5
P42	1.5	1.0	P16	2.5	1.5
P18	1.5	1.5	P18	2.3	2.0
P20	1.5	1.5	P38	1.0	1.5
P20	2.0	2.0			

CONVAIR ASTRONAUTICS

REPORT 7A2236

PAGE 120

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results:

Specimen S/N 114 United
Control Corp.Date: 10-6-'59
Test Engr: R. L. Mobley
CVAC Insp: _____
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
4.3	Operating Vib. "X" axis	
1.4	Operating Time: Start <u>160.5</u> hrs. Stop _____ hrs. Assembly Cycles Start _____ hrs. Stop _____ hrs.	

- Notes:
1. Made assembly cycle at 140 CPS @ speed #4
 2. 5-300 mag. # 137 20-2000 SN
 3. Assembly cycle → ROM Performed at 67.2 CPS.

Para. 1.3 Opn. Vib. "X" Axis.

For para. 1.3 Specimen S/N 124
United Control

* Indicates out of tolerance

Date: 10-6-'54
Engineer: Mobley - P.T.
CVAC Insp: ---
USAF Insp: NA

ASSEMBLY CYCLE OPERATION:

Control Para 1.1.6 voltage	Para 1.1.6 step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle Int. to Ext. Ext. to Int.
15V	A		1 max	
15V	B	NA	1 max	NA
30V	C	NA	2 max	
30V	D		2 max	
25V	E		2 max	
25V	F		2 max	

Dielectric Strength:

All circuits as satisfactory ----- NA NO

Insulation Resistance:

All circuits measured greater than 10 megohms - NA YES NO

Switch Continuity and Non-Continuity

All switches satisfactory

Para 1.1.6 step	YES	NO see note	Switch position Internal External
1			
2		NA	
3			
4			

Cycle Sequence Time (20 milliseconds minimum)

External to Internal _____ milliseconds

Internal to External _____ milliseconds

Position Transfer Time (15 milliseconds maximum)

Circuit Chan. No.	C.E.C. no	In to Rx msec	In to Im msec
P14	F		
P32	G		
P30	H		
P36	I		
P40	J		
P18	K		
P20	L		
P26	M		

Circuit Chan. No.	C.E.C. no	In to Rx msec	In to Im msec
P21	N		
P22	O		
P34	P		
P44	Q		
P14	R		
P28	S		
P28	T		

4.1 TEST CONDITIONS AND PROCEDURES (Continued)

General Test Results: See Note 2

Specimen S/N 124 United Cent.

Date: 10-9-'59
Test Engn: Ruth Mobley
CVAC Insp: NA
USAF Insp: NA

Paragraph	Specification Requirement	Remarks
	Post Vibration Proof cycle	
1.4	Operating Time: Start <u>1617</u> hrs. Stop <u> </u> hrs. Assembly Cycles Start <u> </u> hrs. Stop <u> </u> hrs.	

Notes:

1. CEC May. # I-E-I @ 1244/500.
2. Reducing Midwest data indicated that JTOLATE JTOL D was still intermittent - specimen was 1244 (ID # 414475) 10-12-'57 was sent back to Vendor for repair - per vendor specimen with ID# 51F. King, Etc. 1 Dec.

Post Vibration
Proof Cycle

Para. 4.3
For para. 4.3.1 Specimen S/N 124 U.C.

Date: 10-9-'59
Engineer: Bert Maldey
CVAC Insp: _____
USAF Insp: NA

* Indicates out of tolerance

ASSEMBLY CYCLE OPERATION:

Control voltage	Para L.I. # step	Time (seconds)	Tolerance (seconds)	Type of assembly cycle	Int. to Ext.	Ext. to Int.
15V	8	1.93	3 MAX			
15V	4	1.59	1 MAX			
30V	?	1.871	2 MAX			
30V	1	1.760	2 MAX			
25V	1	1.64	2 MAX			
25V	1	1.00	2 MAX			

CIRCUITRY INSPECTION

All circuits satisfactory - - - - - YES NO

INSULATION RESISTANCE

All circuits measured greater than 10 megohms - - - YES NO

SWITCH CONTINUITY AND NON-CONTINUITY

All switches satisfactory

Para L.I. # step	YES	NO see note	Switch position	Internal	External
1					
2					
3					
4					

WILLE SEQUENCE TIME (10 milliseconds minimum)

External to Internal 2.5 milliseconds

Internal to External 3.8 milliseconds

SEGMENT TRANSFER TIME (15 milliseconds maximum)

C.E.C. 1 to 2 or 2 to 1	1	2	3
P1.1	1	1	1
P1.2	2	2	2
P1.3	3	3	3
P1.6	2	2	2
P1.7	1	1	1
P1.8	1	2	3
P2.1	4	3	3
P2.6	3	1	1

C.E.C. 1 to 2 or 2 to 1	1	2	3
P1.1	1	1	1
P1.2	2	2	2
P1.3	3	3	3
P1.4	4	4	4
P1.5	5	5	5
P1.6	6	6	6
P1.7	7	7	7
P1.8	8	8	8
P2.1	9	9	9
P2.6	10	10	10

CONVAIR
SAN DIEGO

VOLTAGE (D.C.)

Maximum Control Voltage (30 V.)

		Switch in External Position			Switch in Internal Position	
SY. NR.	CIRCUIT	DATA	SY. NR.	CIRCUIT	DATA	
A	J7012 - J7010	.090	A	J701A - J701B	.356	
B	J704P - J705L	.138	B	J701A - J705L	.130	
C	J706T - J705K	.174	C	J701A - J705K	.180	
D	J706C - J705I	.167	D	J701A - J705W	.099	
E	J706R - J705C	.203	E	J702A - J705C	.191	
F	J706A - J702A	.105	F	J702A - J702B	.089	
G	J701C - J702B	.108	G	J702A - J702B	.074	
H	J706Y - J705F	.087	H	J702B - J703	.083	
I	J706e - J701G	.108	I	J702C - J701C	.104	
J	J706f - J703K	.071	J	J702C - J703K	.046	
K	J706G - J703L	.118	K	J702A - J703L	.088	
L	J706H - J702LM	.122	L	J702A - J702M	.091	
M	J701N - J701P	.100	M	J702A - J703P	.086	
N	J706L - J702F	.111	N	J702C - J703B	.074	
O	J706J - J701A	.141	O	J702A - J701A	.138	
P	J706D - J704C	.096	P	J702B - J704C	.075	
Q	J706R - J701J	.089	Q	J702C - J701J	.074	
R	J704F - J704N	.135	R	J702A - J704N	.121	
S	J706X - J704P	.102	S	J702B - J704P	.074	
T	J706S - J704T	.091	T	J702C - J704T	.077	

CONTINUITY CHECK:

All circuits indicated continuity Yes No See notes

Post V.I.B. Post Cycle

A

Date: 10-9-'59Page 124Test Engg: R.T. Mobley

Report 7A2276

EVAC Insp: NATSAP Insp: NA

VOLTAGE D.C.R.

Minimum Control Voltage (25 V.)

Rel. No.	Switch In Internal Position			Switch In Internal Position		
	CIRCUIT	DATA	REL. NO.	CIRCUIT	DATA	REL. NO.
A	J701C	.122		J701A	.510D	.440
B	J701E	.152		J701A	.510S	.121
C	J701F	.166		J701A	.510S	.104
D	J701G	.176		J701A	.510S	.107
E	J701H	.214		J701A	.510S	.214
F	J701I	.105		J702A	.510S	.092
G	J701C	.108		J702B	.510S	.095
H	J702I	.088		J702A	.510S	.233
I	J702C	.108		J702C	.510S	.102
J	J702F	.072		J702C	.510L	.046
K	J702G	.113		J702A	.510L	.083
L	J702H	.124		J702A	.510M	.092
M	J702I	.100		J702C	.510P	.086
N	J702J	.111		J702A	.510K	.095
O	J702L	.142		J702A	.510A	.044
P	J702M	.097		J702B	.510C	.076
Q	J702N	.090		J702A	.510L	.075
R	J702P	.136		J702A	.510N	.122
S	J702Q	.102		J702A	.510P	.074
T	J702R	.092		J702A	.510I	.044

B

ADDENDUM I

SUBJECT: Evaluation of the noise problem on the United Control Corp. 27-06166 and 27-06177 Main Power Changeover switches, which includes testing of the Leach Relays, P/N 9225.

A SUMMARY OF THE PROBLEM:

The United Control Corp. Main Missile Power Changeover switches, CV-A part No. 27-06166-1 and 27-06177-1 started failing in CV-A Receiving Inspection about 10 December 1959. The Engineering Operating Procedure (EOP) used by Receiving Inspection, required that contact "noise" be less than 10 millivolts, when vibrated on the TET-H10 Vibration machine. All of the United Control switches being received by CV-A at this time were failing to meet this requirement, with some units exhibiting as much as 300 millivolts of noise.

CV-A Components Test Laboratory (Dept. 564-5) was performing the Engineering Evaluation Test on the 27-06166-1 switch at this time. The job of investigating the "noise" phenomena, and determining what was generating it was assigned as an additional task to this test.

On reviewing the failures that had occurred, it was determined that all of the out-of-tolerance readings were occurring on the AC switch contacts. United Control Corp. was using Leach, Magnetic latch, 10 amp., 4 PDT relays (Leach P/N 9225), for the AC switch, in all of the units giving trouble at this time.

ADDENDUM I (CONTINUED)

TESTING PERFORMED ON THE 27-06166 SWITCH:

The first general approach, in pursuing this problem, was to determine how much effect the different variables had on the noise generated. This was done by holding all variables except one, constant, and changing it in a logical sequence of steps.

A test setup was built according to Figure 3 to duplicate Receiving Inspection's test set voltage and current characteristics. United Control switch, S/N 124 was connected to this test set and all AC circuits measured for noise. With R-1 load set at 10K (approximately 3 ma current), 4 circuits exhibited more than 100 MV of noise when the switch case was taped gently with a light metallic object. This specimen was next connected to the Evaluation Test Setup and all AC circuits, except 2 (2 of the 4 circuits that exhibited more than 100 MV noise on the prior test) were energized with full rated loads, 5A, 400 cps. When the specimen was taped gently with a light metallic object, the result of noise measured was the same as the results of the former test. Three assembly cycles were performed at rated loads, with the noise on some circuits increasing, some circuits decreasing and some staying the same.

These results were next rechecked by using a different switch. A production unit, S/N 125, had 8 circuits exhibit more than 20 millivolts of noise when checked by Receiving Inspection on the TET-810 Production Vibration machine. All 15 AC circuits were first energized with rated loads (5 amp. 400 cycles) and the contacts monitored for noise. Next, twenty-five assembly cycles were accomplished at rated loads. The overall result was the same as with S/N 124. The switch (S/N 125) was next rechecked with the Receiving Inspection test setup on the TET-810. Only one circuit exhibited more than 20 millivolts of noise. The unit was re-run on the Receiving Inspection setup the next day with the noise condition getting steadily worse.

United Control switch S/N 124 was next subjected to random vibration on the CV-A Components Test Laboratory facilities. The one circuit that had exhibited the most noise in prior tests was selected and monitored. Random vibration stimulus was a 2G RMS, 1 minute burst of energy (bandwidth as noted below). The following results were recorded on a Hughes Memoscope, Model No. 104.

ADDENDUM I (CONTINUED)

TESTING PERFORMED ON THE 27-06166 SWITCH: (CONTINUED)

<u>Bandwidth of Stimulus:</u>	<u>Avg. Noise Level:</u>	<u>Spike Noise Level:</u>
18 cps - 1 Kc	60 millivolts	170 MV
18 cps - 500 cps	60 MV	160 MV
18 cps - 100 cps	10 MV	16 MV
100 cps - 300 cps	60 MV	170 MV
100 cps - 300 cps	70 MV	180 MV
300 cps - 500 cps	40 - 60 MV	160 MV
300 cps - 1 Kc	40 - 80 MV	140 MV
1 Kc - 1.5 Kc	150 MV	300 MV
1 Kc - 1.2 Kc	125 MV	225 MV
The amplitude was changed to 1G RMS:		
1 Kc - 1.2 Kc	6 MV	28 MV
The amplitude was changed to 3G RMS.		
1 Kc - 1.2 Kc	175 MV	280 MV

Accelerometers were attached (using dental cement) to the relay enclosures of the 4, 5 amp. circuit relays in S/N 121. The switch was subjected to an 8G, slow sine sweep and resonances were recorded as follows:

<u>Vibration Frequency(cps):</u>	<u>Amplification Factor:</u>	<u>g. Level:</u>
220	4.5	36
280	5	40
460	6	48 (*)
590	4	32
1100	5	40
2200	8.5	68

(*) Perpendicular to the axis of vibration

The final check on the switch, as an integral component, was to subject it to a 5 minute random vibration test with characteristics according to Figure 1. All AC circuits of the specimen were energized with rated current, 5 amperes, and noise was determined as the voltage drop difference between static and vibration conditions. Results were as follows: All circuits exhibited some noise, 5 circuits more than 10 millivolts, with the worst condition being 74 millivolts.

In reviewing the test results and data taken thus far, the logical conclusion was that the Beach Relays, P/N 9225, being used as the AC switch, were the source of noise.

ADDENDUM I (CONTINUED)

TESTING OF LEACH RELAYS, P/N 9225:

Relay K-2 was removed from United Control specimen S/N 121. This relay contained circuit P-26 which exhibited the most noise during prior tests. The relay cover was very carefully removed and the internal mechanism given a thorough visual inspection. The circuit shown in Figure 3 was connected to a set of contacts and several forms of stimuli were applied in an attempt to reproduce noise. Negative results were encountered in all except the following situation. A normally closed set of contacts were gently pried open with a Nylon probe. Just as the contacts started to separate, it was noted visually that arcing was occurring between the normally closed and common contacts. This circuit was being monitored on a Hughes Memoscope, Model 104, and the pattern on the scope caused by this condition was essentially the same as the pattern that Receiving Inspection had been getting when a switch failed on the TET-810.

In view of the results to date, it was decided that the open relay should be vibrated and its physical and electrical action during vibration recorded and analyzed. A vibration jig was designed and built that would give a minimum of resonances. Figure 2 is a photograph of the jig with a relay mounted. An electrical test circuit was built to allow a stimulus signal to be applied to the relay contacts selectively and the contact, so energized, to be monitored on an oscilloscope or other instrumentation. Figure 4 is a schematic of the test set. Relay K-2 which had been removed from switch S/N 121 was subjected to a slow 10G sine sweep, and the amount of displacement of the contacts during resonances was noted. Many resonances occurred from 118 cps to 1670 cps with the average displacement during a resonance being about 0.03 inches and the maximum displacement (at 380 cps) being 0.08 inches. Electrical noise was not monitored during this run.

Relay K-2, which had been removed from S/124 was subjected to a slow, 8G sine sweep with essentially the same results as were obtained from the previous test. The maximum contact displacement on this relay was 0.02 inch at 1077 cps. Noise was monitored and occurred as follows: From 380 MV to 10G VM between 1050 and 1100 cps, peaking at 1068 cps.

APPENDIX I (CONTINUED)

TESTING OF LEACH RELAYS, P/N 9225: (CONTINUED)

Two Leach relays P/N 9225, directly off the Leach production line, were hand carried to CV-A by a Leach representative. One of these relays was vibrated under the same conditions as the test just completed on K-2 from S/N 124. The results were practically the same as those on the previous two tests, with the noise occurring, if anything, more often (more resonances of relay contacts) than on the previous test. Figures 5 and 6 are photographs of one of these P/N 9225 relays with the cover removed. Figure 5 shows the contacts open and Figure 6 shows the contacts closed.

Fastax movies (16mm) were made of two different opened relays being subjected to an 8G sine sweep vibration. The results of these movies confirm the data measured in other ways on the previous tests and give a graphic record of the vibration characteristics of the Leach 9225 relay.

Two Leach relays were hand carried from United Control Corp. by an engineering representative. These relays were from a lot that was currently being used in the production of the Main Power Changeover switch P/N 27-06166. The relays were not opened but were checked for noise. When subjected to an 8G sine sweep on the fixture shown in Figure 2 and monitored with the test circuit shown in Figure 4, 6 of the 8 contacts monitored, exhibited more than 10 millivolts of noise.

CONVAIR ASTRONAUTICS

ADDENDUM I (CONTINUED)

CRITIQUE ON CONFERENCE HELD TO DISCUSS AND RESOLVE THIS PROBLEM:

At this time a conference was called by CV-A, with United Control representatives, Leach Corp. representatives and cognizant CV-A department representatives attending. The purpose of the meeting was to discuss the switch failures and the results of the tests performed to date, and to try to adopt a program for resolving the overall problem.

The results of the testing that has been described thus far, were presented by CV-A Engineering, with the following conclusions:

- 1) The United Control switches, P/N 27-06177 and 27-06166, because of the noise, do not do the job that CV-A engineering requires.
- 2) The source of the noise is in the Leach 9225 relay.
- 3) Under a broad interpretation of CV-A specification 27-06166, revision "C", the United Control Switch does meet CV-A requirements; however the specification is grossly inadequate.
- 4) The characteristics of the TET-810 were not known well enough to continue using it, in any capacity, as a test instrument for power changeover switches.

United Control Corporation stated that they would effect the redesign necessary to make the AC switch of the Main Power Changeover switch, satisfy the CV-A requirements. Leach stated that they would modify the design of the 9225 relay to make it meet CV-A noise requirements. CV-A stated that specification 27-06166 would be revised to adequately reflect the CV-A requirements.

ADDENDUM I (CONTINUED)

TEST RESULTS OF MODIFIED SPECIMENS:

The Leach Corporation effected two modification programs for the 9225 relays to be purchased by United Control Corporation for the Main Missile Power Changeover switches. The first modification consisted of adding stiffeners to, and increasing the mass of the relay contact arms. The second modification consisted of changing the relay contact material to a high gold content alloy. Two of each type relay just described were hand carried to CV-A test laboratories. The two relays with gold contacts were redesignated as Leach P/N 9225-5811 and the two with stiffened contact arms as Leach P/N 9225-5373.

Both of the 9225-5811 relays were subjected to 3 axes of 3G sine sweep vibration and monitored for contact noise using the test circuit shown in Figure 4. (8.5 MA contact current) No noise was measured on the 8 contacts in either, "External Closed" or "Internal Closed" positions for the 6 sweeps. Figures 7, and 8 are photographs of one of the two 9225-5811 relays with the cover removed. It can be seen by comparing photographs of the 9225 and 9225-5811 relays that the contact shape and contact area were also changed in addition to changing contact material.

The two 5373 relays were next subjected to the same type test as just described. One relay exhibited no noise under all the conditions tested. The second of the two 5373 relays exhibited more than 300 millivolts of noise at 1625 cps (vibration frequency) on one of the 4 contacts. The specimen was allowed to dwell in the critical vibration frequency area. Other contacts developed noise greater than 10 MV, and the situation grew progressively worse. The test requestor's representative decided that this modification was unsatisfactory, so testing on the 5373 relays was discontinued.

As pointed out in a previous paragraph, amplification factors of up to 8.5 were encountered from the input to the switch mountings, to the input to the relay mountings. In view of this, United Control Corp. redesigned the relay mounting arrangement. A rework kit was shipped to CV-A and installed in switch S/N 121. Figure 9 is a photograph of S/N 121 with the rework accomplished and two of the relays instrumented for vibration. The reworked switch was vibrated, at 8G, 5-2000 cps and the accelerometers were monitored for resonances. The maximum resonances encountered were 12G, or an amplification factor of 1.5.

ADDENDUM I (CONTINUED)

TEST RESULTS OF MODIFIED SPECIMENS:

An investigation into the TFT-810 problem, revealed that the vibration fixtures used for mounting the 27-06166 and 27-06177 switches were amplifying the "G" level considerably. At some frequencies the amplification factor was as great as 5. Up to this time there was no record of a validation having been run on the fixtures. Another group at CV-A was given the task of re-designing, fabricating and validating new fixtures with a low amplification factor. To the writers knowledge this task was attempted but never completed. The final test on S/N 121, with the new 5811 relays and the rework kit installed, was to have been vibrated on the TFT-810 using the new vibration fixture. Since this new fixture never materialized this test was never performed.

Both the Leach relay P/N 9225 and P/N 9225-5811 were subjected to contact chemical analysis (spectrography technique) with the following results:

9225-5811 Relay:

Au	Pt	Zn	Cu	B	P	N ₁	Cd	Ag
10%	5%	10%	2%	0.5%	0.01%	5%	0.1%	Remainder

9225 Relay:

Au	Pt	Zn	Cu	B	P	N ₁	Cd	Al	Ag
-	-	1%	1%	1%	0.2%	-	15%	2%	Remainder

United Control Corporation has redesigned the 27-06166 and 27-06177 switches to use a rotary switching mechanism in lieu of relays for the AC circuits, however some components had been manufactured using relays, and are currently being used by CV-A

CONVAIR ASTRONAUTICS


REPORT 7 A 2236
PAGE 133

ADDENDUM I (CONTINUED)

TEST RESULTS OF MODIFIED SPECIMENS: (CONTINUED)


In summarizing the results of this test the writer concludes that the Leach relay, P/N 9225, is not suitable for use in the Missile Power Changeover switches and recommends that they be removed from all subject components. The Leach relay, P/N 9225-5811 is suitable for use and it should be substituted for the 9225 relay.

FIGURE 1 RANDOM VIBRATION SPECTRUM
NOSE AND TANK SECTIONS




CONVAIR ASTRONAUTICS

REPORT 7-10-64
PAGE 35



TYPICAL ELECTRICAL RECEPT.
ON SPECIMEN ~ PINS FOR REF. ONLY



HUGHES, MODEL 104,
MEMO - SCOPE

FIGURE 3
9225 RELAY TEST CIRCUIT
E.W. Mckay

CONVAIR ASTRONAUTICS

REPORT 7 A 2236
PAGE 137




FIGURE 4



MAIN POWER CHANGEOVER SWITCH TEST SET
TO TEST 9225 RELAY NOISE

R.D. Motley

CONVAIR ASTRONAUTICS

REPORT 7A 2225

PAGE 123



MARCH 16, 1961, 10:25
CONVAIR ASTRONAUTICS, SAN DIEGO, CALIFORNIA


SI 201-5

FORM NO. A702-1

Best Available Copy

CONVAIR ASTRONAUTICS

REPORT 7A-200
PAGE 239




MANUFACTURED, NO 7225
SPLICED WITH CONVENTIONAL WIRE, COTTON CORD, NO 515

RECEIVED

CONV AIR 7021

Best Available Copy



MONITOR, P/N 9205-4611 (3 IN. X 1.5 IN. X .5 IN.)
SILICON VITREOUS ENAMEL, C-1200-100

PAGE 7

Best Available Copy






FIGURE 8
MATERIAL, P/N 9225-5811 (30X 40 INCHES)
SH 10 MM WITH RUBBER BACKING, 100% VITON COATED

FIGURE 8



MAIN ENGINE POWER CONTROL SWITCH, P/N 27-36166-1
(WITH TOOL KIT, PART # KIT INSTALLED, PART # 27-36166-1 INCL'D)

FIGURE 9

Best Available
EIA 100-A-7021