

AD-A105 328

HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE  
NATIONAL DAM SAFETY PROGRAM, LAKE TIMBER RIDGE DAM (MO 30762); --ETC(U)  
JUN 79 R S DECKER, G JAMISON, G ULMER


F/8 13/13

DACW43-79-C-0046

NL

UNCLASSIFIED

101  
205-206



**LEVEL II**

**OSAGE-GASCONADE BASIN**

1  
8

LAKE TIMBER RIDGE DAM  
GASCONADE COUNTY, MISSOURI  
MO. 30762

AD A 1 0 5 3 2 8

**PHASE 1 INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**



**United States Army  
Corps of Engineers**  
... Serving the Army  
... Serving the Nation

**St. Louis District**

**DTIC  
ELECTE  
OCT 13 1981**

**A**

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

This document has been approved  
for public release and its  
distribution is unlimited.

JUNE, 1979

81 10 9 028

FILED

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER	
	AD-A105328		
4. TITLE (and Subtitle)		5. TYPE OF REPORT & PERIOD COVERED	
Phase I Dam Inspection Report National Dam Safety Program Lake Timber Ridge Dam (MO 30762) Gasconade County, Missouri	(9)	Final Report,	
7. AUTHOR(s)		6. PERFORMING ORG. REPORT NUMBER	
Hoskins-Western-Sonderegger, Inc.			
9. PERFORMING ORGANIZATION NAME AND ADDRESS	(15)	8. CONTRACT OR GRANT NUMBER(s)	
U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		DACW43-79-C-0046	
11. CONTROLLING OFFICE NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		(11)	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE	
(10) Rey S. /Decker Gordon /Jamison Garold /Ulmer Harold P. /Hoskins		June 1979	
16. DISTRIBUTION STATEMENT (of this Report)		13. NUMBER OF PAGES	
Approved for release; distribution unlimited.		Approximately 60	
(6) National Dam Safety Program. Lake Timber Ridge Dam (MO 30762), Osage - Gasconade Basin, Gasconade County, Missouri. Phase I Inspection Report.		15. SECURITY CLASS. (of this report)	
17. DISTRIBUTION STATEMENT		UNCLASSIFIED	
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
18. SUPPLEMENTARY NOTES			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)			
Dam Safety, Lake, Dam Inspection, Private Dams			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)			
This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.			

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE


394131

Gu

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

**SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)**



**SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)**

## INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

**RESPONSIBILITY.** The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

**CLASSIFICATION.** Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

### COMPLETION GUIDE

**General.** Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

**Block 1.** Report Number. Enter the unique alphanumeric report number shown on the cover.

**Block 2.** Government Accession No. Leave Blank. This space is for use by the Defense Documentation Center.

**Block 3.** Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

**Block 4.** Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

**Block 5.** Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

**Block 6.** Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

**Block 7.** Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

**Block 8.** Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

**Block 9.** Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

**Block 10.** Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

**Block 11.** Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

**Block 12.** Report Date. Enter here the day, month, and year or month and year as shown on the cover.

**Block 13.** Number of Pages. Enter the total number of pages.

**Block 14.** Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

**Blocks 15 & 15a.** Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

**Block 16.** Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 17.** Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 18.** Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with . . . Translation of (or by) . . . Presented at conference of . . . To be published in . . .

**Block 19.** Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

**Block 20.** Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.

LAKE TIMBER RIDGE DAM  
GASCONADE COUNTY, MISSOURI

MO. 30762

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

PREPARED BY  
HOSKINS-WESTERN-SONDEREGGER, INC.  
CONSULTING ENGINEERS  
LINCOLN, NEBRASKA

UNDER DIRECTION OF  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS

FOR  
GOVERNOR OF MISSOURI  
JUNE, 1979

Accession For	
DTIC CR&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
A	



DEPARTMENT OF THE ARMY  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS  
210 NORTH 12TH STREET  
ST. LOUIS, MISSOURI 63101

IN REPLY REFER TO

SUBJECT: Lake Timber Ridge Dam Phase I Inspection Report

This report presents the results of field inspection and evaluation of Lake Timber Ridge Dam.

It was prepared under the National Program of Inspection of Non-Federal Dams.

This dam has been classified as unsafe, non-emergency by the St. Louis District as a result of the application of the following criteria:

- 1) Spillway will not pass the Probable Maximum Flood.
- 2) Overtopping could result in dam failure.
- 3) Dam failure significantly increases the hazard to loss of life downstream.

SUBMITTED BY SIGNED 17 DEC 1979  
Chief, Engineering Division Date

APPROVED: SIGNED 17 DEC 1979  
Colonel, CE, District Engineer Date

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

TABLE OF CONTENTS

<u>PARAGRAPH NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
	Assessment Summary	
	Overview Photograph	
SECTION 1 - PROJECT INFORMATION		
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	2
SECTION 2 - ENGINEERING DATA		
2.1	Design	5
2.2	Construction	5
2.3	Operation	5
2.4	Evaluation	5
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	6
3.2	Evaluation	8
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	10
4.2	Maintenance of Dam	10
4.3	Maintenance of Operating Facilities	10
4.4	Description of Any Warning System in Effect	10
4.5	Evaluation	10
SECTION 5 - HYDRAULIC/HYDROLOGIC		
5.1	Evaluation of Features	11
SECTION 6 - STRUCTURAL STABILITY		
6.1	Evaluation of Structural Stability	13
SECTION 7 - ASSESSMENT/REMEDIAL MEASURES		
7.1	Dam Assessment	14
7.2	Remedial Measures	14

## APPENDIX - MAPS

Plate A-1 Vicinity Topography  
Plate A-2 Location Map

## APPENDIX B - PHOTOGRAPHS

Plate B-1	Photo Index	
Plate B-2	Photo No. 2	Upstream Face From Right Abutment
	Photo No. 3	Crest From Right End
Plate B-3	Photo No. 4	Downstream Slope From Right End
	Photo No. 5	Upstream From Sta. 4+00
Plate B-4	Photo No. 6	Downstream From Sta. 4+00. Spring In Left Center
	Photo No. 7	Downstream In Spillway On Left Side
Plate B-5	Photo No. 8	Limestone and Shale Formations In Left Abutment
	Photo No. 9	Upstream In Left Spillway
Plate B-6	Photo No. 10	Looking Downstream At Left Spillway Control Section
	Photo No. 11	Downstream From Left Spillway Control Section. 6 To 7 Foot Head-Cut To Bedrock
Plate B-7	Photo No. 12	Downstream Side Of Left Spillway Control Section
	Photo No. 13	Overview From High On Left Abutment
Plate B-8	Photo No. 14	Crest, Downstream Slope And Left Spillway From Left Abutment
	Photo No. 15	Spring Area Outcropping 20' ± Downstream From Toe
Plate B-9	Photo No. 16	Looking Upstream At Spring Area
	Photo No. 17	Seep Area In Right Abutment Trough
Plate B-10	Photo No. 18	Downstream In Right Spillway
	Photo No. 19	Looking Across Right Spillway At Crest Of Dam
Plate B-11	Photo No. 20	Looking Downstream In Right Spillway
	Photo No. 21	Seep In Old Channel Below Dam

## APPENDIX C - PROJECT PLATES

Plate C-1	Phase I - Plan and Centerline Profile of Dam
Plate C-2	Phase I - Section of Dam and Section of Emergency Spillway
Plate C-3	Phase I - Principal Spillway Section
Plate C-4	Phase I - Profiles of Principal and Emergency Spillways

APPENDIX D - HYDRAULIC AND HYDROLOGIC DATA

Plates D-1 and D-2	Hydrologic Computations
Plate D-3	Principal Spillway Rating Curve
Plate D-4	Total Spillway Rating Curve
Plate D-5	Ratio-Discharge Curve
Plate D-6 to D-18	Computer Input and Output for PMF

PHASE I REPORT  
NATIONAL DAM SAFETY PROGRAM  
ASSESSMENT SUMMARY

Name of Dam	Lake Timber Ridge Dam
State Located	Missouri
County Located	Gasconade County
Stream	Tributary Pinoak Creek
Date of Inspection	May 16, 1979

↓  
Lake Timber Ridge Dam was inspected by an interdisciplinary team of engineers, ~~from Hoskins-Western-Sonderregger, Inc.~~ The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.

The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers, and developed with the help of several Federal and State agencies, professional engineering organizations, and private engineers. Based on these guidelines, this dam is classified as an intermediate size dam with a high downstream hazard potential. Failure would threaten life and property. The estimated damage zone extends approximately three miles downstream of the dam. Within the damage zone are two or three dwellings, several outbuildings, U.S. Highway 50, Highway BB and two bridges.

Our inspection and evaluation indicates that the spillway does not meet the criteria set forth in the recommended guidelines for an intermediate dam having a high hazard potential. The probable Maximum Flood is the appropriate spillway design flood. The spillways will pass the 100-year flood (flood having a one percent chance of being exceeded in any year) without overtopping the dam. The spillways will pass 14% of the Probable Maximum Flood without overtopping the dam. The Probable Maximum Flood (PMF) is defined as the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region. Recommendations presented in Section 7 of this report relative to minimizing or eliminating the potential for overtopping of the dam should be pursued on a high priority basis.

↑  
This dam appears to be in good condition and structurally stable. However, seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams", including appropriate earthquake loadings should be obtained in the near future.

Action should be initiated as soon as possible on measures to evaluate and/or correct the following minor deficiencies observed during the inspection: tree growth on the upstream face of the dam and in the entrance to the left spillway; deterioration of concrete around the culverts in the left spillway (if this spillway is not modified by other corrective measures); and the quantity and clarity of seepage effluent just downstream from the dam.


Maintenance of this dam is generally satisfactory except as noted above.




Rey S. Decker  
E-3703



Gordon Jamison



Garold Ulmer  
E-4777



Harold P. Hoskins  
Chairman of Board  
Hoskins-Western-Sonderegger, Inc.  
E-8696



PHOTO NO. 1  
OVERVIEW

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
LAKE TIMBER RIDGE DAM - MO 30762  
GASCONADE COUNTY, MISSOURI

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, District Engineer directed that a safety inspection of Lake Timber Ridge Dam be made.
- b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.
- c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report of the Chief of Engineers on the National Program of Inspection of Dams", dated May, 1975, and published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

- a. Description of Dam and Appurtenances.
  - (1) The dam is an earthfill approximately 900 feet in length and about 43 feet in height. It is located in rolling hills with sharply incised valleys cut into limestone and shale formations.
  - (2) The principal spillway is uncontrolled and consists of a cut through limestone and shale bedrock on the left abutment.
  - (3) An uncontrolled vegetated earth emergency spillway is cut through the right abutment.
  - (4) Pertinent physical data are given in paragraph 1.3 below.

- b. Location. The dam is located in the west central portion of Gasconade County, Missouri, as shown on Plate A-2. The dam is shown on Plate A-1 in the S $\frac{1}{2}$  of Section 16, T43N, R6W. The lake formed behind the dam is shown in the S $\frac{1}{2}$  of Section 16, T43N, R6W, and the N $\frac{1}{2}$  of Section 21, T43N, R6W.
- c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. Based on these criteria, this dam and impoundment is in the intermediate size category.
- d. Hazard Classification. Guidelines for determining hazard classification are presented in the same guidelines as referenced in paragraph 1.1c above. Based on referenced guidelines, this dam is in the High Hazard Classification. The estimated damage zone extends approximately three miles downstream of the dam. Within the damage zone are two or three dwellings, several outbuildings, U.S. Highway 50, Highway BB and two bridges.
- e. Ownership. The dam is owned by Lake Timber Ridge Owners Association; James Patley, Trustee, 48 Park Charles Blvd. South, St. Peters, Mo. 63376.
- f. Purpose of Dam. The dam impounds a recreational lake of about 680 acre-feet  $\pm$ .
- g. Design and Construction History. No design or construction history were available.
- h. Normal Operating Procedure. There are no operating facilities for this dam.

### 1.3 PERTINENT DATA

- a. Drainage Area. 616 acres (0.96 square miles).
- b. Discharge at Damsite.
  - (1) All discharge at the damsite is through one or both earthen spillways which are located at each end of the dam. The left (west) spillway is restricted by 5-12" culverts capped by concrete.
  - (2) Estimated maximum flood at damsite -- unknown.

- (3) The principal spillway capacity varies from 0 cfs at elevation 655.3 feet to 125 cfs at the crest of the emergency spillway (elevation 657.2 feet).
- (4) The emergency spillway capacity varies from 0 cfs at its crest elevation 657.2 feet to 19 cfs at elevation 658.1 feet (minimum top of dam).
- (5) Total spillway capacity at the minimum top of dam is 431 cfs  $\pm$ .

c. Elevations (feet above M.S.L.).

- (1) Top of dam (min. elev.) - 658.1 ft.
- (2) Principal spillway crest - 655.3 ft.
- (3) Emergency spillway crest 657.2
- (4) Streambed at centerline - 615  $\pm$
- (5) Maximum tailwater - unknown

d. Reservoir. Length (feet) of maximum pool - 2,500  $\pm$ .

e. Storage (Acre-feet).

- (1) Top of dam - 810  $\pm$
- (2) Principal spillway crest - 680  $\pm$

f. Reservoir Surface (Acres).

- (1) Top of dam - 47  $\pm$
- (2) Principal spillway crest - 12  $\pm$

g. Dam.

- (1) Type - earthfill
- (2) Length - 900 ft.  $\pm$
- (3) Height - 43 ft.  $\pm$
- (4) Top width - 16 ft.
- (5) Side slopes
  - (a) Downstream - 2.3H on 1V (measured)
  - (b) Upstream - 2.3H on 1V (measured on exposure)
- (6) Zoning - unknown
- (7) Impervious core - unknown
- (8) Cutoff - unknown
- (9) Grout curtain - unknown
- (10) Wave protection - limestone riprap

h. Diversion Channel and Regulating Tunnel. None

i. Spillway.

(1) Principal

- (a) Type - Uncontrolled, excavated earth and rock through the left abutment.
- (b) Crest (channel) elevation - 655.3 ft.  $\pm$   
Culvert invert (U.S.) - 654.4 ft.  $\pm$
- (c) Length - 250 ft.  $\pm$

(2) Emergency

- (a) Type - Uncontrolled, vegetated earth cut through the right abutment.
- (b) Control section - parabolic shape, about 12 feet in length with top width of about 50 feet.
- (c) Crest elevation - 657.2 ft.  $\pm$
- (d) Upstream channel - well vegetated with some limestone riprap at inlet end, approximately 20 feet in length with slope of 10%.
- (e) Downstream channel - well vegetated. Outlets adjacent to right abutment trough. Exit channel on 6% slope.

j. Regulating Outlets. None

## SECTION 2 - ENGINEERING DATA

### 2.1 DESIGN

No design data were available for this dam.

### 2.2 CONSTRUCTION

No construction data were available.

### 2.3 OPERATION

No data were available on spillway operation.

### 2.4 EVALUATION

- a. Availability. No data were available.
- b. Adequacy. The field surveys and visual observation presented herein are considered adequate to support the conclusion of this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.
- c. Validity. Not applicable.

## SECTION 3 - VISUAL INSPECTION

### 3.1 FINDINGS

- a. General. A visual inspection of the Timber Ridge Lake Dam was made on June 27, 1979. Engineers from Hoskins-Western-Sonderegger, Inc., Lincoln, Nebraska making the inspection were: R. S. Decker, Geotechnical; Gordon Jamison, Hydrology; Garold Ulmer, Civil Engineer.
- b. Dam.
  - (1) Geology and Soils (abutment and embankment). Upland and valley slope soils consist of thin loess overlying residual cherty clays derived from limestone and shale. Stratified beds of limestone and silty clay shale are exposed on the left abutment (spillway cut, see photo 8). The limestone is fractured but no solution channels or vugs were observed. These limestones and shales are probably part of the Jefferson City-Cotter formation. Massive coherent limestone is exposed in the creek channel immediately downstream from the dam. This would indicate that foundation materials under the dam probably consist of a relatively thin deposit of plastic alluvium over bedrock. The damsite area is located between the Cuba fault, Kruegers Ford Anticline and the Pershing-Bay-Gerald Anticline. However, no surface indication of structural deformation was observed at the site. Many seep and spring outcrops were observed in the general area. Auger borings on the embankment showed plastic silty clay (CL or CH) materials to depths of 2 feet.
  - (2) Upstream slope. The upstream slope is well riprapped with good limestone having nominal size of 8 to 12 inches. The slope is well vegetated above the riprap. A few small trees and shrubs were observed growing along the upper edge of the riprap. No significant erosion, slides or deformations were noted on the slope.
  - (3) Crest. The crest serves as a gravel surfaced roadway for access to the west side of the reservoir. The crest is well vegetated with adapted grasses adjacent to the roadway. The crest profile is somewhat irregular but no slides, cracks or deformations were noted on the crest.

- (4) Downstream slope. The downstream slope is well vegetated with adapted grasses. No cracks, slides, rodent holes or deformations were observed. A spring area is located about 20 feet downstream from the toe of the dam downstream from Station 5+00 ±. The spring appears to emerge through coarse gravel material in the old stream channel bottom. (It was impossible to penetrate the bottom materials with a hand auger). Cobble and gravel are exposed along the toe of the dam in the area adjacent to the spring area. It appears that the outlet channel for the spring has been excavated and it is possible that the spring may be the discharge from a toe drain. (See photos 15 and 16) Discharge from the spring was estimated at 1 gal/min. It was clear and iron stained. Another seepy area was noted downstream from Station 7+65 to 8+15. This seep occurs in the old channel downstream from the toe. No water was flowing and it was clear. A seep area also occupies the upper end of the right abutment trough. Some standing water was observed in this area. Seep in the right abutment trough probably originates through the limestone abutment materials. Total seepage discharge in the old channel, some 100 to 150 feet downstream from the dam was estimated at 3 to 4 gal/min. (See photo 21)
- (5) Miscellaneous. The dense vegetation and the CL or CH materials observed in the dam indicate that this dam would withstand significant overtopping without serious damage.

c. Appurtenant Structures.

- (1) The principal spillway consists of a channel cut through limestone and shale on the left abutment. The approach channel and control section are open with limestone bedrock exposed in most of the bottom. The lower end of the control section is restricted by a roadway across the spillway consisting of a concrete slab over five concrete pipe culverts 12 inches in diameter. Some deterioration was noted in the concrete filleting around the upstream and downstream ends of the culverts. (Photos 10 and 12) The exit channel is eroded through CL-CH Soil and Shale and outlets over a near vertical drop of 8 feet  $\pm$  where the channel bottom has stabilized on limestone bedrock (photo 11). Discharges from this spillway would not encroach upon the dam. The reservoir level was slightly below the inlet elevation of the spillway when inspected.
- (2) The emergency spillway consists of a shallow earth channel excavated through the right abutment. The inlet section is riprapped with a few small trees growing at the water edge. The control section and outlet channel are densely vegetated with adapted grasses. The outlet channel drops off onto the stable abutment some 100 feet downstream from the control section. No erosion was noted in the spillway. The water level was approximately 2 feet below the control elevation when inspected. Trash in the inlet section indicated that the reservoir level had been up to within 8 to 12 inches of the control elevation.
- (3) Drawdown facilities. No drawdown facilities were observed for this dam.

d. Reservoir Area. No significant erosion was observed around the reservoir area.

e. Downstream channel. The stream channel is overgrown with trees and shrubs. The channel bottoms on massive, competent limestone bedrock.

3.2 EVALUATION

There does not appear to be any serious potential of failure of this structure. The embankment slopes are somewhat steeper than normally used for a dam of this height. Seepage at the downstream toe apparently moves through erosion resistant foundation bedrock

and cherty gravels and has no apparent adverse affect on the integrity of the dam. The roadway culverts and slab across the principal spillway would cause some impedance in maximum discharge. The slab is 2 feet below the top of dam and 1 foot below the emergency spillway crest elevation. The dam and appurtenances appear to be well maintained with exception of the few small trees and shrubs on the upstream face and deterioration of concrete around the culverts in the spillway.

## SECTION 4 - OPERATIONAL PROCEDURES

### 4.1 PROCEDURES

There are no controlled outlet works for this dam. The pool level is controlled by rainfall, evaporation, and the capacity of the uncontrolled spillways.

### 4.2 MAINTENANCE OF DAM

Maintenance is generally satisfactory. The small trees and shrubs on the upstream face should be removed and measures taken to prevent recurrence. Concrete deterioration in the spillway roadway culvert area could be repaired but does not appear to be significant.

### 4.3 MAINTENANCE OF OPERATING FACILITIES

No operating facilities exist at this dam.

### 4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no warning system in effect for this dam.

### 4.5 EVALUATION

There does not appear to be any serious potential of failure of this structure.

## SECTION 5 - HYDRAULIC/HYDROLOGIC

### 5.1 EVALUATION OF FEATURES

- a. Design Data. No design data were found for this dam.
- b. Experience Data. The drainage area, reservoir surface area, and elevation-storage data were developed from the USGS Bland, Missouri 15 minute topographic quadrangle map. The hydraulic computations for the spillway and dam overtopping discharge ratings were based on data collected in the field at the time of the field inspection.
- c. Visual Observations.
  - (1) An almost vertical headcut exists in the principal (left) spillway approximately 85 ft. below the culvert and weir control. It is eroded down to bedrock and is approximately 8 ft. deep. This should pose no threat to the dam.
  - (2) Some erosion has occurred to both the upstream and downstream ends of the concrete cap covering the culverts in the principal spillway channel.
  - (3) Emergency (right) spillway appears to be in satisfactory condition.
- d. Overtopping Potential. The spillways are too small to pass the probable maximum flood without overtopping. The spillways will pass the 100-year flood as well as 14% of the probable maximum flood without overtopping. The dam should withstand significant overtopping without serious damage. The results of the routings through the dam are tabulated in regards to the following conditions.

<u>Frequency</u>	<u>Inflow Discharge c.f.s.</u>	<u>Outflow Discharge c.f.s.</u>	<u>Maximum Pool Elevation</u>	<u>Freeboard Top of Dam Min. Elev. 658.1</u>	<u>Time Dam Overtopping Hr.</u>
100 Yr.	700	280	657.8	0.3	-
1/2 PMF	4900	4400	659.6	-1.5	5+
PMF	9900	9100	660.4	-2.3	7-
0.14 PMF	1400	450	658.1	0	-

According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, this dam is classified as having a high hazard rating and an intermediate size. Therefore, the PMF is the test for the adequacy of the dam and its spillway.

The estimated damage zone is described in Paragraph 1.2d in this report.

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observation. There are no visual indications of structural instability. In fact, the structure looks good. Additional studies would be required to determine the effects of foundation seepage, steeper than normal side slopes and of overtopping on the structural stability of the dam. It would appear that overtopping would not seriously impair the structural stability.
- b. Design and Construction Data. No design or construction data were available. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Operating Records. There are no controlled operating facilities for this dam.
- d. Post Construction Changes. The inspection team is not aware of any post construction changes for this structure.
- e. Seismic Stability. This dam is located near Seismic Zone 2, in an area of previous diastrophic activity. Additional studies would be required to determine the seismic activity in the area and the effect of such activity on the stability of this structure.

## SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

### 7.1 DAM ASSESSMENT

- a. Safety. There does not appear to be a serious potential of failure of this dam from the standpoint of structural stability. However, seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available which is considered a deficiency.

According to the approximate data used for analyses in Section 5, the dam will not be overtopped by the 100-year flood but will be overtopped to a depth of 2.3 feet for about 7 hours by the Probable Maximum Flood. The effects of much overtopping on the structural and erosional stability of the dam is not known, but it appears that it would not cause serious damage to the structure.

- b. Adequacy of Information. Due to the lack of engineering data, the conclusions in this report are based upon performance history and visual observations. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available which is considered a deficiency.
- c. Urgency. The item regarding spillway capacity recommended in paragraph 7.2.a should be pursued on a high priority basis.
- d. Necessity for Phase II. Phase II investigation is not considered necessary.
- e. Seismic Stability. This dam is located near Seismic Zone 2 in an area of recognized faults and geologic formational distortions. Additional studies would be required to determine the seismic stability of this structure.



### 7.2 REMEDIAL MEASURES

- a. Alternatives.
  - (1) Additional information should be obtained on the hydrologic characteristics of the watershed and on the topographic characteristics of the reservoir area to determine the increase in the height of the dam or the size of the spillways that is necessary

to pass the Probable Maximum Flood without overtopping the dam.


- (2) The quantity and clarity of the seepage effluent should be monitored at periodic intervals and the data made a part of the records of this dam.
  - (3) The services of an engineer experienced in the design of dams should be obtained to evaluate the present reservoir storage capacity, to provide seepage and stability analyses of the present dam including potential seismic forces, and to design protective measures, including the seepage monitoring system, as required.
- b. O & M Procedures. Present maintenance appears to be good. However, a program of periodic inspection should be initiated and implemented with measures to remove and control trees and shrubs on the upstream slope and to repair and maintain the concrete in the principal spillway.

APPENDIX A  
MAPS




**N**

**VICINITY TOPOGRAPHY**  
**LAKE TIMBER RIDGE DAM**  
**GASCONADE COUNTY, MO.**  
**MO. 30762**  
**PLATE A-1**



APPENDIX B  
PHOTOGRAPHS



**PHOTO INDEX**

LAKE TIMBER RIDGE DAM

GASCONADE COUNTY, MISSOURI

MO. 30762

PLATE B-1



PHOTO NO. 2 - UPSTREAM FACE FROM RIGHT ABUTMENT




PHOTO NO. 3 - CREST FROM RIGHT END



PHOTO NO. 4 - DOWNSTREAM SLOPE FROM RIGHT END



PHOTO NO. 5 - UPSTREAM FROM STA. 4 + 00



PHOTO NO. 6 - DOWNSTREAM FROM STA. 4 + 00. SPRING IN  
LEFT CENTER



PHOTO NO. 7 - DOWNSTREAM IN SPILLWAY ON LEFT SIDE



PHOTO NO. 8 - LIMESTONE AND SHALE FORMATIONS IN LEFT ABUTMENT



PHOTO NO. 9 - UPSTREAM IN LEFT SPILLWAY



PHOTO NO. 10 - LOOKING DOWNSTREAM AT LEFT SPILLWAY CONTROL SECTION



PHOTO NO. 11 - DOWNSTREAM FROM LEFT SPILLWAY CONTROL SECTION.  
6 TO 7 FOOT HEAD-CUT TO BEDROCK



PHOTO NO. 12 - DOWNSTREAM SIDE OF LEFT SPILLWAY CONTROL SECTION



PHOTO NO. 13 - OVERVIEW FROM HIGH ON LEFT ABUTMENT



PHOTO NO. 14 - CREST, DOWNSTREAM SLOPE AND LEFT SPILLWAY  
FROM LEFT ABUTMENT




PHOTO NO. 15 - SPRING AREA OUTCROPPING 20' ± DOWNSTREAM  
FROM TOE



PHOTO NO. 16 - LOOKING UPSTREAM AT SPRING AREA



PHOTO NO. 17 - SEEP AREA IN RIGHT ABUTMENT TROUGH



PHOTO NO. 18 - DOWNSTREAM IN RIGHT SPILLWAY



PHOTO NO. 19 - LOOKING ACROSS RIGHT SPILLWAY AT CREST OF DAM



PHOTO NO. 20 - LOOKING DOWNSTREAM IN RIGHT SPILLWAY






PHOTO NO. 21 - SEEP IN OLD CHANNEL BELOW DAM


APPENDIX C  
PROJECT PLATES






DAM SECTION (STA. 5+00)

Scale: 1" = 20'




EMERGENCY SPILLWAY SECTION

Scale: 1" = 20' H.  
1" = 5' V.




PRINCIPAL SPILLWAY SECTION

Scale : 1" = 10' H  
 1" = 5' V



PROFILE OF PRINCIPAL SPILLWAY

Scale: 1" = 50'H.  
 Scale: 1" = 5'V.



PROFILE OF EMERGENCY SPILLWAY

Scale: 1" = 20'H.  
 Scale: 1" = 5'V.

APPENDIX D  
HYDRAULIC AND HYDROLOGIC DATA

## HYDROLOGIC COMPUTATIONS


1. The SCS dimensionless unit hydrograph and the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Corps of Engineers, Davis, California, were used to develop the inflow hydrographs (See Appendix D).
  - a. Twenty-four hour, 100-year rainfall for the dam location was taken from the data for the rainfall station at Jefferson City, MO. as supplied by the St. Louis District, Corps of Engineers per their letter dated 6 March 1979. The twenty-four probable maximum precipitation was taken from the curves of Hydrometeorological Report No. 33 and current Corps of Engineers and St. Louis policy and guidance for hydraulics and hydrology.
  - b. Drainage area = 0.96 square miles (616 acres).
  - c. Time of concentration of runoff = 24 minutes (computed from "Kirpich" formula).
  - d. The antecedent storm conditions for the probable maximum precipitation were heavy rainfall and low temperatures which occurred on the previous 5 days (SCS AMC III). The antecedent storm conditions for the 100-year precipitation were an average of the conditions which have preceded the occurrence of the maximum annual flood on numerous watersheds (SCS AMC II). The initial pool elevation was assumed at the primary spillway crest.
  - e. The total twenty-four hour storm duration losses for the 100-year storm were 3.45 inches. The total losses for the PMF storm were 2.03 inches. These data are based on SCS runoff curve No. 85 and No. 70 for antecedent moisture conditions SCS AMC III and AMC II respectively. The watershed is composed of primarily SCS soil groups B, C, and D (Soil Association Union-Gass-Gasconade-Peridge) and consists entirely of wooded area.
  - f. Average soil loss rates = 0.10 inch per hour approximately.
2. The discharge ratings for the principal spillway were developed using equations for weir and culvert flow, and channel flow. They are as follows:
  - a. Weir flow equation ( $Q_w = CLH^{3/2}$ )

Where C = weir coefficient = Varies with H (2.7 - 3.0)  
L = length of weir, ft. = Varies with H.  
H = total head, ft.

- b. Culvert flows were taken from nomograph, "Headwater Depth for Concrete Pipe Culvert with Inlet Control", BPR, Jan. 1963.
- c. Channel spillway discharge ratings were developed using the HEC-2.

Channel conditions prevailed as the control from the principal spillway crest to 656 ft., and culvert plus weir control prevailed thereafter. The emergency spillway discharge rating was developed using the Corps of Engineers Surface Water Profile HEC-2 computer program and was added to the principal spillway discharge to give total spillway discharge. The flows over the dam crest were developed using the HEC-1 (Dam Safety Version) program with a discharge coefficient of 2.9 and a value of 1.5 for the exponent of head.

- 3. Floods were routed through the reservoir using the HEC-1 (Dam Safety Version) program to determine the capabilities of the spillway and dam embankment crest. The output and plotted hydrographs are attached in this Appendix.



Lake Timber Ridge Dam  
Missouri #30762

Overbank on Right Side

Weir (Road E. 516)

Left Spillway Rating  
(Culverts + Weir + Overbank)


Combined Principal Spillway


Total Spillway Discharge  
Principal Spillway (L. Abut.)  
plus Emergency Spillway  
(R. Abut.)

Elev.	Principal	Emergency	Total
655.3	0	0	0
655.4	15	0	15
655.5	35	0	35
655.7	10	0	10
655.8	15	0	15
656.0	24	0	24
656.4	39	0	39
657.0	99	0	99
657.2	125	0	125
657.5	186	0	186
658.0	333	19	347
659.0	1075	115	1190
660.0	2117	410	2527

\* C of E. Hec-2 Program

Discharge in CFS	600	700	800
100			
200			
300			
400			
500			
600			
700			
800			







\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 26 FEB 79  
 \*\*\*\*\*

RUN DATE= 79/07/18.  
 TIME= 17.50.47.

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF  
 HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF LAKE TIMBER RIDGE DAM 30762  
 RATIOS OF PMF REDDIED THROUGH THE RESERVOIR

JOB SPECIFICATION											
NQ	MHR	MHIN	TDAY	THR	IMIN	METRC	IPLT	IPRT	INSTAN		
288	0	5	0	0	0	0	0	3	0		
				JOPER	NMI	LROPT	TRACE				
				5	0	0	0				

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= .20 .35 .50 .65 .80 1.00  
 MPLAN= 1 NRTIO= 6 LRTIO= 1

\*\*\*\*\* SUB-AREA RUNOFF COMPUTATION \*\*\*\*\*

CALCULATION OF INFLOW HYDROGRAPH TO RES 30762

SUB-AREA RUNOFF COMPUTATION											
ESTAQ	ICOMP	TECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO			
000001	0	0	0	2	0	1	0	0			
HYDROGRAPH DATA											
IHYDC	IUGC	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISHOW	ISAME	LOCAL		
1	2	.96	0.00	.96	1.00	0.000	0	1			

PRECIP DATA  
 SPEE PMS R6 R12 R24 R58 RTZ R96  
 0.00 25.40 102.00 121.00 130.00 0.00 0.00 0.00

LOSS DATA											
LADPT	STRKR	DLTKR	RTIOL	ERAIN	STRS	RTIOK	STRCL	CNSTL	ALSMX	RTIMP	
0	0.00	0.00	1.00	0.00	0.00	1.00	-1.00	-85.00	3.00	0.00	

CURVE NO = -05.00 WETNESS = -1.00 EFFECT CH = 85.00

UNIT HYDROGRAPH DATA  
 IC= 0.00 LAG= .24

RECESSION DATA  
 SIRTO= 0.00 QRCN= -.01 RTICK= 1.00

UNIT HYDROGRAPH 16 END OF PERIOD ORDINATES, IC= 0.00 HOURS, LAG= .24 VOL= 1.00 98.  
 306. 1059. 1619. 1545. 1152. 670. 418. 258. 181.  
 61. 38. 23. 15. 9. 4.

END-OF-PERIOD FLOW

0

HYDROGRAPH AT STA00001 FOR PLAN 1, RTID 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1978.	521.	160.	160.	45948.
CMS	59.	15.	5.	5.	1301.
INCHES		5.05	6.18	6.18	
MM		128.33	157.07	157.07	
AC-FT		259.	316.	316.	
THOUS CU M		319.	390.	390.	

HYDROGRAPH AT STA00001 FOR PLAN 1, RTID 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3462.	912.	279.	279.	80410.
CMS	98.	26.	8.	8.	2277.
INCHES		8.84	10.82	10.82	
MM		224.59	274.87	274.87	
AC-FT		452.	554.	554.	
THOUS CU M		558.	683.	683.	

HYDROGRAPH AT STA00001 FOR PLAN 1, RTID 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4945.	1304.	399.	399.	114871.
CMS	140.	37.	11.	11.	3253.
INCHES		12.63	15.46	15.46	
MM		320.84	392.67	392.67	
AC-FT		666.	791.	791.	
THOUS CU M		797.	976.	976.	

HYDROGRAPH AT STA00001 FOR PLAN 1, RTID 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	6428.	1695.	519.	519.	169333.
CMS	182.	48.	15.	15.	5229.
INCHES		16.42	20.10	20.10	
MM		417.09	510.48	510.48	
AC-FT		840.	1028.	1028.	
THOUS CU M		1037.	1269.	1269.	

HYDROGRAPH AT STA00001 FOR PLAN 1, RTID 5

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	7912.	2086.	638.	638.	183794.
CMS	224.	59.	18.	18.	5204.
INCHES		20.21	24.74	24.74	
MM		513.34	628.28	628.28	
AC-FT		1034.	1266.	1266.	
THOUS CU M		1276.	1561.	1561.	



01VW\*

PMF

STATION 000002, PLAN 1, RATIO 6  
END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW										
0.	1.	2.	3.	4.	5.	6.	7.	8.	9.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
3.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
6.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
9.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
12.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
15.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
18.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
21.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
24.	3.	3.	3.	3.	3.	3.	3.	3.	3.	3.
27.	13.	15.	17.	19.	19.	22.	24.	24.	26.	26.
30.	27.	31.	33.	35.	37.	39.	41.	44.	49.	54.
33.	59.	64.	69.	74.	79.	84.	89.	94.	105.	115.
36.	111.	117.	123.	132.	141.	153.	159.	168.	176.	184.
39.	194.	206.	217.	227.	230.	247.	257.	266.	274.	283.
42.	291.	298.	306.	313.	319.	326.	332.	338.	344.	352.
45.	365.	377.	387.	396.	407.	428.	468.	531.	609.	717.
48.	846.	976.	1097.	1201.	1286.	1353.	1407.	1456.	1510.	1569.
51.	1633.	1686.	1733.	1771.	1801.	1824.	1841.	1854.	1866.	1891.
54.	1938.	2016.	2100.	2175.	2234.	2278.	2309.	2331.	2346.	2357.
57.	2355.	2331.	2302.	2328.	2473.	2851.	3765.	5541.	7722.	9085.
60.	9054.	8041.	6750.	5592.	4652.	3932.	3405.	3031.	2774.	2598.
63.	2570.	2394.	2237.	2298.	2269.	2233.	2174.	2098.	2018.	1949.
66.	1900.	1863.	1835.	1813.	1798.	1783.	1767.	1706.	1574.	1385.
69.	1183.	1001.	854.	740.	653.	589.	540.	495.	456.	418.
72.	386.	357.	341.	332.	323.	315.	307.	299.	292.	285.
75.	270.	272.	266.	260.	254.	247.	244.	239.	235.	231.
78.	226.	223.	219.	215.	212.	208.	205.	202.	200.	197.
81.	194.	192.	189.	188.	186.	183.	183.	182.	181.	180.
84.	178.	177.	176.	175.	174.	173.	172.	171.	170.	169.
87.	168.	168.	167.	166.	165.	164.	164.	163.	163.	163.

STORAGE										
0.	1.	2.	3.	4.	5.	6.	7.	8.	9.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
3.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
6.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
9.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
12.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
15.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
18.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
21.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
24.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
27.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
30.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
33.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
36.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
39.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
42.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
45.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
48.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
51.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
54.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
57.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
60.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
63.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
66.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
69.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
72.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
75.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
78.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
81.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
84.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
87.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

797. 796. 795. 794. 793. 792. 791. 790. 790. 790.  
 789. 788. 787. 786. 785. 784. 783. 782. 782. 782.  
 781. 781. 781. 780. 780. 780. 780. 780. 780. 779.  
 779. 779. 779. 778. 778. 778. 778. 778. 778. 778.

STAGE									
655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3
655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3
655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3
655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3
655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3	655.3
655.4	655.4	655.4	655.4	655.4	655.4	655.4	655.4	655.4	655.4
655.4	655.4	655.4	655.4	655.4	655.4	655.4	655.4	655.4	655.4
655.6	655.7	655.7	655.8	655.8	655.9	655.9	656.0	656.0	656.0
656.1	656.2	656.2	656.3	656.3	656.4	656.4	656.5	656.5	656.5
656.6	656.7	656.7	656.8	656.8	656.9	656.9	657.0	657.0	657.0
657.1	657.1	657.2	657.2	657.3	657.3	657.4	657.4	657.4	657.5
657.5	657.6	657.6	657.6	657.7	657.7	657.7	657.8	657.8	657.8
657.8	657.9	657.9	657.9	657.9	658.0	658.0	658.0	658.0	658.0
658.0	658.0	658.0	658.1	658.1	658.1	658.2	658.2	658.2	658.2
658.5	658.6	658.6	658.7	658.7	658.8	658.8	658.8	658.8	658.9
658.9	658.9	658.9	659.0	659.0	659.0	659.0	659.0	659.0	659.0
659.0	659.0	659.0	659.1	659.1	659.1	659.1	659.1	659.1	659.1
659.1	659.1	659.1	659.1	659.1	659.2	659.2	659.2	659.2	659.2
660.3	660.2	660.0	659.8	659.6	659.5	659.4	659.3	659.2	659.2
659.1	659.1	659.1	659.1	659.1	659.1	659.1	659.0	659.0	659.0
659.0	659.0	659.0	659.0	659.0	658.9	658.9	658.9	658.9	658.8
658.7	658.6	658.5	658.4	658.4	658.3	658.2	658.1	658.1	658.1
658.0	658.0	658.0	657.9	657.9	657.9	657.9	657.8	657.8	657.8
657.8	657.8	657.7	657.7	657.7	657.7	657.7	657.6	657.6	657.6
657.6	657.6	657.6	657.6	657.6	657.6	657.6	657.5	657.5	657.5
657.5	657.5	657.5	657.5	657.5	657.5	657.5	657.5	657.5	657.5
657.5	657.4	657.4	657.4	657.4	657.4	657.4	657.4	657.4	657.4
657.4	657.4	657.4	657.4	657.4	657.4	657.4	657.4	657.4	657.4

PEAK OUTFLOW IS 9385. AT TIME 15.83 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	9085.	2571.	749.	749.	215768.
CMS	257.	73.	21.	21.	6110.
INCHES		24.92	29.04	29.04	29.04
MM		632.85	737.58	737.58	737.58
AC-FT		1235.	1486.	1486.	1486.
THOUS CU W		1573.	1833.	1833.	1833.



4.45 571  
4.50 581  
4.55 591  
5.00 601  
5.05 611  
5.10 621  
5.15 631  
5.20 641  
5.25 651  
5.30 661  
5.35 671  
5.40 681  
5.45 691  
5.50 701  
5.55 711  
6.00 721  
6.05 731  
6.10 741  
6.15 7501  
6.20 7601  
6.25 7701  
6.30 7801  
6.35 7901  
6.40 8001  
6.45 8101  
6.50 8201  
6.55 8301  
7.00 8401  
7.05 8501  
7.10 8601  
7.15 8701  
7.20 8801  
7.25 8901  
7.30 9001  
7.35 9101  
7.40 9201  
7.45 9301  
7.50 9401  
7.55 9501  
8.00 9601  
8.05 9701  
8.10 9801  
8.15 9901  
8.201000  
8.251010  
8.301020  
8.351030  
8.401040  
8.451050  
8.501060  
8.551070  
9.001080  
9.051090  
9.101100  
9.151110  
9.201120  
9.251130  
9.301140  
9.351150  
9.401160  
9.451170  
9.501180

8-55119.01  
 10-00120.01  
 10-55121.01  
 12-10122.01  
 10-15123.01  
 10-20124.01  
 10-25125.01  
 10-30126.01  
 10-35127.01  
 12-40128.01  
 10-45129.01  
 10-50130.01  
 10-55131.01  
 11-00132.01  
 11-05133.01  
 11-10134.01  
 11-15135.01  
 11-20136.01  
 11-25137.01  
 11-30138.01  
 11-35139.01  
 11-40140.01  
 11-45141.01  
 11-50142.01  
 11-55143.01  
 12-00144.01  
 12-05145.01  
 12-10146.01  
 12-15147.01  
 12-20148.01  
 12-25149.01  
 12-30150.01  
 12-35151.01  
 12-40152.01  
 12-45153.01  
 12-50154.01  
 12-55155.01  
 13-00156.01  
 13-05157.01  
 13-10158.01  
 13-15159.01  
 13-20160.01  
 13-25161.01  
 13-30162.01  
 13-35163.01  
 13-40164.01  
 13-45165.01  
 13-50166.01  
 13-55167.01  
 14-00168.01  
 14-05169.01  
 14-10170.01  
 14-15171.01  
 14-20172.01  
 14-25173.01  
 14-30174.01  
 14-35175.01  
 14-40176.01  
 14-45177.01  
 14-50178.01  
 14-55179.01  
 15-00180.01



20.15293. |  
 20.20244. |  
 20.25245. |  
 21.30246. |  
 21.35247. |  
 20.40248. |  
 20.45249. |  
 20.50250. |  
 20.55251. |  
 21.00252. |  
 21.05253. |  
 21.10254. |  
 21.15255. |  
 21.20256. |  
 21.25257. |  
 21.30258. |  
 21.35259. |  
 21.40260. |  
 21.45261. |  
 21.50262. |  
 21.55263. |  
 22.00264. |  
 22.05265. |  
 22.10266. |  
 22.15267. |  
 22.20268. |  
 22.25269. |  
 22.30270. |  
 22.35271. |  
 22.40272. |  
 22.45273. |  
 22.50274. |  
 22.55275. |  
 23.00276. |  
 23.05277. |  
 23.10278. |  
 23.15279. |  
 23.20280. |  
 23.25281. |  
 23.30282. |  
 23.35283. |  
 23.40284. |  
 23.45285. |  
 23.50286. |  
 23.55287. |  
 24.00288. |

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS					
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6
				.20	.35	.50	.65	.80	1.0
HYDROGRAPH AT 000001									
	(	.96	1	1978.	3462.	4945.	6429.	7912.	9890.
	(	2.49)	(	56.01)	98.02)	140.03)	182.04)	224.05)	283.07)
ROUTED TO 000002									
	(	.96	1	1091.	2880.	4370.	5795.	7198.	9085.
	(	2.49)	(	30.90)	81.54)	123.76)	164.09)	203.82)	257.25)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 ..... ELEVATION 655.30 INITIAL VALUE 655.30 SPILLWAY CREST 650.10 TOP OF DAM  
 STORAGE 682. 682. 811.  
 OUTFLOW 0. 0. 431.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.20	658.64	.54	836.	1091.	2.17	16.08	0.00
.35	659.24	1.14	864.	2880.	4.25	15.92	0.00
.50	659.56	1.46	879.	4370.	5.42	15.92	0.00
.65	659.82	1.72	891.	5795.	6.17	15.92	0.00
.80	660.05	1.95	901.	7198.	6.50	15.92	0.00
1.00	660.35	2.25	915.	9085.	6.92	15.92	0.00

