

AD-A173 777


SPILLWAY MODIFICATION GRAPEVINE LAKE TEXAS (U) ARMY
ENGINEER DISTRICT FORT WORTH TX A J MARR JUN 86


1/2

UNCLASSIFIED

F/G 13/2

NL







**US Army Corps
of Engineers**
Fort Worth District

12

**FINAL
FOUNDATION
REPORT**

AD-A173 777

**SPILLWAY MODIFICATION
GRAPEVINE LAKE, TEXAS**

This document has been approved
for public release and sale; its
distribution is unlimited.

THIS IS A COPY

IC
CTE
OCT 29 1986
A

JUNE 1986

12 19 28 0 1

CORPS OF ENGINEERS
FORT WORTH DISTRICT, TEXAS

FINAL
FOUNDATION REPORT

GRAPEVINE LAKE
SPILLWAY MODIFICATION

BY

ALAN J. MARR
ENGINEERING GEOLOGY SECTION

Accession For	
RECORD GRA&I	<input checked="" type="checkbox"/>
RECORD TAB	<input type="checkbox"/>
Announced	<input type="checkbox"/>
Classification	
By	
Distribution/	
Availability Codes	
Avail and/or	
Special	
AT-1	



JUNE, 1986

PREFACE

This report was prepared by Fort Worth District Staff Geologist, Alan J. Marr, under the supervision of the Chief of the Engineering Geology Section, Robert C. Behm, and the Chief of the Geotechnical Branch, Melvin G. Green.

District Engineers for the Fort Worth District during construction of the Grapevine Spillway were Colonel Theodore Stroupe and Colonel A. J. Genetti, Jr. Mr. Shigeru Fujiwara was Chief of the Engineering Division and Mr. William Niese, Jr. served as Resident Engineer during construction.

TABLE OF CONTENTS

<u>Para. No.</u>	<u>Paragraph Title</u>	<u>Page No.</u>
<u>I INTRODUCTION</u>		
1	Project Location and Description	1
2	Construction Authority	1
3	Purpose of Report	2
4	Project History	2
5	Modification of the Spillway	6
6	The Contract	6
7	Quality Control	7
8	Contract Supervision	7
<u>II FOUNDATION EXPLORATIONS</u>		
1	Investigations Prior to Construction of the Existing Spillway	8
2	Investigations Prior to Modification of the Spillway	8
3	Investigations During Construction	8
<u>III GEOLOGY</u>		
1	Physiography and Regional Geology	9
2	Geology of the Spillway	9
	(a) Description of the Overburden	9
	(b) Bedrock Stratigraphy and Lithology	9
	(c) Bedrock Structure	10
	(d) Weathering	11
	(e) Ground Water	11
3	Engineering Characteristics of the Overburden Materials	12
4	Engineering Characteristics of the Primary Materials	13
5	Unusual or Unanticipated Conditions	14
<u>IV SPECIAL DESIGN CONSIDERATIONS</u>		15
<u>V EXCAVATION PROCEDURES</u>		
1	Excavation Grades	17
2	Dewatering Provisions	17
3	Overburden Excavation	19
4	Rock Excavation	19
5	Overexcavation	20
6	Foundation Preparation	23
	(a) Foundations Beneath the Structure	23
	(b) Foundations Adjacent to the Structure	24
	(c) Overburden	25
7	Safety	25

TABLE OF CONTENTS

<u>Para. No.</u>	<u>Paragraph Title</u>	<u>Page No.</u>
<u>VI FOUNDATION ANCHORS</u>		
1	General	27
2	Equipment	27
3	Grout Mix Design	27
4	Procedure	30
5	Modification	32
6	Pull-Out Tests	32

VII POSSIBLE FUTURE PROBLEMS

1	Observations	35
2	Future Considerations	35

PLATES

<u>Plate No.</u>	
1	Project Location
2	Site Plan
3	Areal Geology
4	Plan of Borings and Locations of Sections
5	Centerline Profile
6	Section B-B
7	Section C-C
8	Section D-D
9	Geologic Map of the Excavation (As-Built)
10	Structure Foundation Map (As-Built)
11	Centerline Profile (As-Built)
12	Section B-B (As-Built)
13	Record of Foundation Approval
14	Chute Slab Anchor Plan and Sections
15	Test Data Summary
16	Test Data Summary
17	Test Data Summary
18	Log of Boring 8A6C-602
19	Log of Boring 8A6C-603
20	Log of Boring 8A4C-606
21	Log of Boring 8X4C-607

ILLUSTRATIONS

<u>Figure No.</u>	<u>Titles</u>	
1	Flow through the Grapevine Spillway in November, 1981	3
2	Damage resulting from the November, 1981 flood	5

ILLUSTRATIONS (Continued)

<u>Figure No.</u>	<u>Title</u>	<u>Page No.</u>
3	Bulk excavation	21
4	Neat-line excavation	21
5	Parabolic-shaped slab at top of spillway slope	26
6	Slide area	26
7	Anchor holes being drilled	28
8	Anchor bars in place	28
9	Grout arrives at site	29
10	Grout being placed	29
11	Grout being vibrated	31
12	Anchor bars and steel in place ready for concrete	31
13	Pull-out test in progress	33
14	Exposed foundation surface - 25 April 1984	37
15	Exposed foundation surface - 9 May 1984	37
16	Exposed foundation surface - 9 May 1984	38
17	Exposed foundation surface - 25 June 1984	38
18	Exposed foundation surface - 10 July 1984	39
19	Exposed foundation surface - 10 July 1984	39
20	Exposed foundation surface - 18 July 1984	40
21	Exposed foundation surface - 25 July 1984	40
22	Excavation for cut-off wall - 28 August 1984	41
23	Exposed foundation surface - 10 September 1984	41
24	Exposed foundation surface - 10 September 1984	42
25	Exposed foundation surface - 17 September 1984	42
26	Exposed foundation surface - 9 October 1984	43
27	Exposed foundation surface - 9 October 1984	43
28	Exposed foundation surface - 20 November 1984	44
29	Exposed foundation surface - 6 March 1984	44
30	Exposed foundation surface - 6 March 1984	45
31	Exposed foundation surface - 7 March 1984	45
32	End sill excavation - 5 April 1984	46
33	Placement of non-expansive backfill	46

I - INTRODUCTION

1. Project Location and Description. Grapevine Dam is located in Tarrant County, Texas, about 20 miles northwest of Dallas, Texas, on Denton Creek about 11.7 river miles above its confluence with the Elm Fork of the Trinity River. The location of the project is shown on Plate 1.

The Grapevine Lake project consists of a compacted earth-fill embankment, an uncontrolled, off-channel, chute-type concrete spillway, and a cut-and-cover conduit outlet. The embankment is 12,850 feet long and has a maximum crest width of 28 feet. Top of dam elevation is 588 NGVD which is 137 feet above the streambed. The 500-foot wide spillway has a crest elevation of 560 NGVD and is located in a natural saddle near the right abutment of the dam. The 13-foot diameter outlet conduit, located near the left end of the dam, is controlled by two 6.5- by 13-foot electrically operated sluice gates. A site plan of the project is shown on Plate 2.

2. Construction Authority. Congressional authority for the construction of Grapevine Lake and subsequent spillway modification is contained in the River and Harbor Act approved March 2, 1945 (Public Law 14, 79th Congress 1st Session), in accordance with the recommendations of the Chief of Engineers contained in House Document No. 403 (77th Congress, 1st Session). Public Law 79-14 authorizes the U.S. Army Corps of Engineers to construct, repair, and preserve certain water resources projects in the Trinity River Basin, including Grapevine Dam and Lake.

3. Purpose of Report. This report has been prepared in accordance with requirements as set forth by the Office, Chief of Engineers, in ER 1110-1-1801. This report provides a complete record of foundation conditions encountered during construction of spillway modifications at Grapevine Lake. Information contained in this report will be valuable when evaluating: (1) necessary remedial action required to prevent or repair any failures resulting from foundation deficiencies; (2) Contractor claims related to foundation conditions or alleged change of conditions; and (3) planning and design of future comparable construction project.

A copy of this report will be included in the permanent records maintained at the project office.

4. Project History. Construction of Grapevine Dam began in January 1948 and was completed in June 1952. During heavy rains in May 1957 the reservoir level reached conservation pool, elevation 535, for the first time and eventually peaked at elevation 560.8 which was 0.8 feet above the spillway crest. Flow through the spillway washed out FM 2499 and caused minor erosion damage in the spillway channel, all of which was repaired.

Again during October and November 1981, the spillway went into service for 21 days. The reservoir elevation peaked at elevation 563.29, or 3.29 feet above the spillway crest. Discharge through the spillway, shown in Figure 1, peaked at 9100 cfs flowing at a velocity of 30-40 feet per second. The heavy discharge caused severe erosion



Fig. 1 - Flow through the Grapevine Spillway in November 1981

in the unprotected discharge channel, as seen in Figure 2. The erosion cut reached a maximum depth of about 30 feet below the original channel floor at a point about 600 feet downstream from the end of the existing concrete spillway apron slab.

The severity of the erosion damage created concern that another overflow event could undermine the concrete spillway chute and weir and ultimately endanger the integrity of the entire structure. As a result the Fort Worth District conducted a study of the project which resulted in the following recommendations:

(a) The spillway should be modified to include an elongated concrete chute that terminated into a stilling basin.

(b) The downstream face of the embankment which has been periodically subjected to erosion and sloughing, would be stabilized by constructing a berm using soils excavated for the spillway modification.

(c) FM 2499 would be relocated to cross the existing spillway apron.

The Southwestern Division Office and the Office of the Chief of Engineers approved the recommendations and requested that a design memorandum detailing the proposed work be prepared. Design Memorandum No. 3 - Modification of Embankment and Spillway was published in June 1983 followed by the project plans and specifications in August 1983. The contract was awarded and construction began in November 1983 with a scheduled completion date of June 1985.



Fig. 2 - Damage resulting from the November 1981 flood

5. Modification of the Spillway. The existing spillway was cut in a relatively narrow saddle about 1500 feet left (northwest) of the left abutment of the dam. It consists of a 500-foot wide by 400-foot long approach channel cut in natural ground to approximate elevation 550, a 500-foot wide concrete ogee weir with a crest elevation of 560.0 connected to a 200-foot long concrete apron sloping at a 5 percent grade, and a 500-foot wide discharge channel cut in natural ground and terminating in a natural ravine about 900 feet from the end of the apron. A plan of the existing spillway is shown on Plate 4.

The spillway modification consisted of constructing a reinforced concrete chute and stilling basin immediately downstream of the existing spillway apron. The chute is 500 feet wide by 301 feet long and provides a transition from elevation 540.0 to the new stilling basin elevation 462.0. The stilling basin is 130 feet long and bordered on each side by 33-foot high vertical concrete walls. For a distance of 265 feet from the end of the stilling basin the 510-foot wide downstream channel is graded to elevation 465 and protected by rip-rap. The channel then slopes upward on a 1 vertical on 10 horizontal grade to intersection with natural ground.

6. The Contract. Pertinent information related to the contract is listed below:

Modification of Embankment and Spillway - Grapevine Lake

Contractor: Granite Construction Company, Watsonville, CA

Contract No.: DACW63-83-C-0160

Bid: \$9,561,342.50

Contract Award Date: 30 Sep 83

Notice to Proceed: 26 Oct 83

Work Completed: November 1985

Contractor Superintendent at Site: Edouard (Skip) Izac

7. Quality Control. Quality control for all phases of the contract was furnished by the Contractor. Mr. John Moran performed all quality control functions from the beginning of the work until 3 Jan 85. During the remainder of the contract quality control functions were performed by Mr. Ron Milan.

8. Contract Supervision. Work under this contract was performed under the immediate supervision of the District Engineer, U.S. Army Engineer District, Fort Worth, Texas. The Contracting Officer's representative for administration of the contract was Mr. James D. Leslie, Area Engineer, North Texas Area Office. Mr. Bill Niese served as Resident Engineer during construction.

II FOUNDATION EXPLORATIONS

1. Investigations Prior to Construction of the Existing Spillway.

Geological investigations were conducted at the Grapevine Dam site as early as 1924. Much of the data collected during design and construction of the project, including original core boring logs and laboratory test results, are no longer available. A summary of some of this early data is found in the Definite Project Report, dated July 1947, which is available in SWFED-F.

2. Investigations Prior to Modification of the Spillway. Investigations for rehabilitation of the Grapevine Spillway began in December 1981, 2 months after the overtopping event. A total of 10 combination auger, fishtail, rock-bit and core borings were drilled to develop subsurface information. The borings included 302 linear feet of 4- and 6-inch core samples and 688 linear feet of auger, fish-tail and rock-bit borings. Electric logs were run in all but one of the borings to aid in stratigraphic correlation. Three bail-down/recovery tests were performed in selected borings in order to determine general ground-water conditions at the site. Locations of the borings and sections are shown on Plate 4. A centerline profile is shown on Plate 5, and Section B-B, C-C, and D-D are presented on Plates 6, 7, and 8 respectively. Results of all investigations were presented in Design Memorandum No. 3 - Modification of Embankment and Spillway - Grapevine Lake, published in June 1983.

3. Investigations During Construction. No unanticipated foundation conditions or problems were encountered during construction that required additional subsurface investigations.

III GEOLOGY

1. Physiography and Regional Geology. Grapevine Dam and spillway are located within the Eastern Cross Timbers Section of the West Gulf Coastal Plain physiographic province. The Eastern Cross Timbers Section occurs as a relatively narrow belt of moderately rugged topography which trends north-south through the area generally reflecting the outcrop of the basal member of the Woodbine Formation of Upper Cretaceous Age. Regional dip of the strata is toward the southeast at a steeper slope than that of the land surface resulting in older strata being encountered as one travels northwest upstream from the dam. In the project area the Woodbine Formation reaches an estimated thickness of 320 feet and consists of an alternating series of sands, clays, shales, and weakly indurated sandstones. The areal geology map is presented on Plate 3.

2. Geology of the Spillway.

(a) Description of the Overburden. Overburden in the vicinity of the Grapevine spillway consists of a thin mantle of residual soils resulting from the weathering of the sands and shales of the upper portion of the Woodbine Formation. Overburden exposed in the excavation slopes consists of fine-to-medium grained, loose to medium dense sand with varying amounts of silt, clay and gravel.

(b) Bedrock Stratigraphy and Lithology. The Grapevine Spillway is founded within strata of the Woodbine Formation. Borings within

the limits of the existing spillway encountered a 5-foot thick layer of reddish-brown, massive, fine-grained, weakly cemented sandstone which served as the spillway floor immediately downstream from the concrete apron. Underlying the sandstone layer was approximately 40 feet of soft, often carbonaceous, dark gray to brown, massive-bedded, sandy shale with occasional thin interbeds of glauconitic sandstone. Lignitic seams were noted along some of the bedding planes. Below the shale section is a sequence of alternating soft to moderately hard, fine-grained, weakly to moderately cemented, thin-bedded sandstones and soft, sandy shales which continue down to and below the base of the excavation. An increasing percentage of sandy material and the occasional occurrence of thin, moderately hard to very hard, very fine-grained sandstone and siltstone layers were observed as the excavation deepened.

Gradational changes in the lithologic composition of the Woodbine strata are typically pronounced, often changing from sandy shale to shaly sand or sandstone within a few feet. The lithology shown on the geologic map (Plate 9), generally classifies the materials according to their dominant composition. See Plates 5 through 8 for geologic profile and sections.

(c) Bedrock Structure. The Woodbine strata in the spillway area dip toward the southeast at a rate of about 100 feet per mile. No major faulting or folding was observed within the spillway excavation limits. Some minor jointing and fracturing was observed during the course of the excavation down to elevation 495; below this elevation

the strata was essentially free of structural discontinuities. Individual layers of competent material were sometimes separated by bedding planes of weaker material, often resulting in some minor overexcavation in areas where finished grade occurred within the more competent layers.

(d) Weathering. Weathering of strata within the Woodbine Formation is generally recognized by the change in color of the materials from gray when unweathered to light brown or yellow when weathered. This weathering reaction is caused by oxidation of the iron within the highly ferruginous formation. Shales are generally altered to the consistency of stiff clay, while sandstones tend to become indurated, as was the case with the 5-foot thick sandstone layer exposed on the spillway floor. Since the sandstone on the floor of the spillway had only been exposed to the weathering processes for the period since original construction in 1952, weathering was apparent only within 3 to 5 feet of the surface. In the slopes of the spillway excavation, the thickness of the weathered zone was generally from 10 to 15 feet. The spillway was founded entirely within unweathered strata.

(e) Ground Water. Ground water encountered during the course of the spillway excavation was minor and was adequately controlled using collector ditches and sump pumps. Minor amounts of ground water leaked out of the overburden on the upper slopes of the excavation. The amount of seepage and number of seepage areas varied according to the amount of rainfall. During dry periods there were only 3 seepage areas which continued to produce water. The 3 areas are shown on Plate 9.

Individual seepage points in the Woodbine Formation strata beneath the spillway structure were rarely detected during the course of the excavation because of the small amount of flow and the short time period that the surface was exposed. However, as the excavation progressed downward through the increasingly sandy Woodbine strata, reaching the base of the 1 vertical on 3.5 horizontal slope, water exiting from the sand filter blanket gave evidence of the collective seepage emitting from the foundation strata. The amount of seepage from any one area along the filter blanket generally amounted to only a few gallons per minute, only slightly hindering the cleaning of the freshly excavated surfaces downslope from the filter blanket.

After the excavation reached the stilling basin level the Contractor installed a collector well with collector ditches to care for both surface water and ground water entering the excavation. The location of the collector well is shown on Plate 9. Details of the collector well are described in Dewatering Provisions, Section V-2 of this report.

3. Engineering Characteristics of the Overburden Materials. All foundation investigation borings were located within the limits of the existing spillway where the overburden had been removed during original construction. As a result, no overburden samples were collected during the investigations for laboratory testing. Based on original project design values, the following design parameters were adopted by the Geotechnical Branch, Soils Design and Dam Safety Sections for the overburden materials:

Unit Weight

moist - 125 pcf

saturated - 130 pcf

Q - strength

c - 1.0 tsf

0 - 5 degrees

R - strength

c - 0.5 tsf

0 - 16 degrees

S - strength

c - 0.1 tsf

0 - 20 degrees

Overburden materials located outside the limits of the existing spillway, but within the limits of the new spillway excavation were used as select fill in constructing a berm on the downstream face of the main embankment under this contract.

4. Engineering Characteristics of the Primary Materials. Laboratory testing of primary materials was performed on core samples obtained from borings 8A6C-602 and 8A6C-603. A summary of the test results is presented on Plates 15 thru 17.

The results of laboratory testing indicate a slight variation in the strength and character of the Woodbine materials with depth. Therefore, the following design parameters were adopted for the primary materials:

Upper Primary Materials

Unit Weight

moist - 135 pcf

saturated - 140 pcf

Q - strength

c - 0.7 tsf

0 - 25 degrees

R - strength

c - 0.2 tsf

0 - 30 degrees

S - strength

c - 0 tsf

0 - 30 degrees

Lower Primary Materials

Unit Weight		R - strength
moist - 140 pcf		c - 0.2 tsf
saturated - 145 pcf		0 - 30 degrees
Q - strength		S - strength
c - 0.7 tsf		c - 0.2 tsf
0 - 25 degrees		0 - 30 degrees

5. Unusual or Unanticipated Conditions. There were no unusual or unanticipated conditions encountered that adversely affected the construction of the Grapevine Spillway.

The discovery of an isolated ± 1-foot thick limestone layer approximately 220 feet left of centerline station 14 + 20 was unexpected. (limestone was not observed in any of the samples retrieved during subsurface investigations). The presence of limestone is unusual, though not unprecedented within the Woodbine Formation. The occurrence of the limestone did not affect the excavation phase of the project, but it was the basis of a claim by the Contractor citing the extra time required to drill rock anchor holes.

IV SPECIAL DESIGN CONSIDERATIONS

1. During design of the spillway special consideration was given to the fact that the spillway is an active spillway for an existing reservoir with the possibility of engagement during the period of construction. Operation of the spillway during construction could have results ranging from lost construction time to catastrophic loss of the entire spillway. Although this fact did not alter the design of the spillway, special precautions were undertaken during construction to reduce the risk of spillway engagement and resulting damage. These precautions include the following:

(a) Sandbags were placed on the existing spillway weir raising the spillway crest from 560.0 to 562.5, thus increasing the computed spillway operation frequency from 100 years to approximately 270 years.

(b) A lower reservoir elevation was maintained during construction through the cooperation of local water supply users who responded to a letter request by CE to increase their water usage from Grapevine Lake when the reservoir elevation was above elevation 528 NGVD (about 75 percent of normal conservation pool).

(c) And finally, the amount of unprotected excavated surface was kept to a minimum by requiring the excavation and concrete placement to be staged into coordinated phases of work so that concrete placement would closely follow the deepening excavated surface.

2. Due to the proximity of the existing reservoir to the proposed spillway excavation, special consideration was given to ground water

during design of the project. There was early concern that the Woodbine Formation, which often has the capability of transporting and producing significant amounts of ground water, could transmit water to the excavation directly from the reservoir. However, the results of investigations in the spillway area indicated that the permeabilities of the Woodbine Formation sands were very low and that any ground water entering into the excavation could be controlled by a system of ditches and sump pumps.

V EXCAVATION PROCEDURES

1. Excavation Grades. Actual foundation conditions encountered during excavation for the rehabilitation of the Grapevine Spillway were essentially as described in the subsurface data presented in the contract plans and specifications. The design slopes in the overburden and primary materials were achieved and maintained generally without difficulty. Minor concerns which developed in the excavation slopes during construction were the low resistance of the material in the overburden slopes to erosion, and one minor slide which occurred in a vertically excavated shale face. Some minor variations (over-excavation) from the designed grade lines occurred. Final cross-sections on the excavation slopes were taken by the Contractor's survey team. The CE geologist, assisted by the Contractor's survey team, made all measurements of final excavation grade and recorded the foundation conditions below the new spillway structure. Final excavation grades below the spillway structure are shown on Plate 10. As-built centerline geologic profile and geologic section are presented on Plate 11 and Plate 12 respectively.

2. Dewatering Provisions. No serious ground-water problems were encountered in the spillway excavation. Perched water flow from the overburden slopes was the primary source of ground water within the excavation. Seepage from the exposed Woodbine strata in the excavation slopes was very minor, usually drying up before reaching the base of the slope. Ground water flowing from the excavation slopes was

controlled using collector ditches and sump pumps. The locations of ground water exit points are shown on the As-Built Geologic Maps on Plates 9 and 10.

For the most part the excavation of materials and the subsequent backfill of filter sand beneath the structure took place in the dry. Only an occasional small seep of water was observed in the Woodbine strata underlying the spillway structure during the brief periods between excavation and backfill that the surface was exposed. As the excavation approached the base of the 1V on 3.5H slope beneath the structure the accumulative water produced by the seeps became noticeable. Seepage water draining from the sand filter blanket trickled downslope and hindered the cleaning of the exposed sections of the foundation.

Surface water, i.e. run-off from rain, was a more difficult problem. The relatively large drainage area of the excavation combined with the highly erosive character of the excavation slopes caused heavy siltation in the work area even after moderate rains. Considerable construction time was lost while the work area, which normally was near the lower part of the excavation, was unwatered and cleaned of silt.

The Contractor installed a collector well in the base of the excavation as it neared final grade. A system of collector ditches intercepted the surface run-off and channeled it to the collector well for removal. The location of the collector well is shown on Plate 9. The well was equipped with a 6-inch 58 hp Flyght pump capable of pumping

800 gallons of water per minute from the well location to the edge of the excavation (approximately 60 ft head). However, it was estimated that, with the heavy silt load, the actual pumping rate was about 400 to 500 gallons per minute. During dry periods the pump was operated intermittently - once every two to three days - to handle "nuisance water" exiting from the sand blanket. A 6-inch diesel pump supplemented pumping after rain storms.

3. Overburden Excavation. Overburden materials in the spillway excavation consist of tan to reddish-brown fine-grained sand mixed with varying amounts of clay, silt, and gravel as previously described. Within the limits of the old spillway the overburden had been removed during construction leaving only primary strata exposed on the spillway floor. Excavation for the new spillway began in April 1984. Overburden materials, where present, were excavated using Caterpillar scrapers pushed by Caterpillar D6 and D8 bulldozers. Suitable overburden materials removed from the spillway excavation were used as fill in a berm being constructed on the downstream face of the main embankment as part of the same construction contract.

4. Rock Excavation. Primary material removed from the spillway excavation ranged from weathered sand and clay, to unweathered, sandy, soft shale, and soft to hard fine-grained sandstone. The methods used to excavated the primary material changed as the excavation neared final grade. The following methods were employed:

(a) Bulk excavation of the primary materials was accomplished in the same manner as the excavation of the overburden materials, i.e.,

Caterpillar scrapers pushed by D6 and D8 bulldozers (See Figure 3). Ripper equipped dozers plowed and loosened the material prior to removal. Most of this material was suitable for use as fill material in embankment berm. That material which was not suitable, either due to the presence of large pieces of sandstone or too much sand, was spoiled in on-site waste areas.

(b) Bulk excavations were halted a minimum of 2 feet above final grade. Final grade surfaces were required to be covered within 4 hours of excavation. Excavation of the final 2+ feet of primary material in the areas beneath the spillway structure was accomplished with a Warner Swassey Model G-1000 Gradall (track-mounted), and a Caterpillar Model 235 backhoe. As shown on Figure 4, the Gradall, with its wide, smooth-edged bucket was used to cut the flat surfaces to final grade, whereas the backhoe, with a deeper bucket equipped with 6-inch teeth, was more efficient at cutting ditches and at breaking through the moderately hard sandstone layers that were occasionally encountered. No blasting was required for any of the excavation or handling of materials during this project.

5. Overexcavation. A significant amount of overexcavation occurred during this project. The amount of overexcavation can be estimated by the amount of overrun in the sand required to construct the filter blanket between the excavated surface and the protective concrete slab beneath the structure. Using the designed thickness of the filter blanket, 6 inches, the estimated amount of sand required was 5465 cubic yards. Records show that 9134 cubic yards of sand were delivered to




Fig. 3 - Bulk excavation down to grade plus a minimum of 2 feet is accomplished with scrapers pushed by bulldozers



Fig. 4 - Neat-line excavation is accomplished with Gradall equipped with straight-edged bucket

the site. Although it is estimated that as much as 20 percent of the overrun was due to waste, there were also numerous occasions when the excavation surface was measured in excess of a foot below grade. The following factors resulted in overexcavation:

(a) One factor was the angle or slope of the excavation. Past experience has shown that excavating through horizontally layered strata at an angle is very difficult to master even with experienced equipment operators. The horizontal layers usually break unevenly, leaving a stair-step appearance, especially if their hardness is inconsistent, as was the case in this excavation.

(b) Another factor contributing to overexcavation was the tendency of the Contractor to attempt to excavate to grade and backfill very large areas each day. Contract specifications required that when excavating in primary material, the exposed surface was to be cleaned and covered with backfill (either filter sand or protective concrete) within 4 hours of achieving final grade. In order to excavate, clean and cover larger areas within the required time frame the accuracy of excavating was sometimes sacrificed, resulting in overexcavation.

(c) A minor amount of overexcavation was caused by the presence of bedrock weaknesses such as jointing, fracturing, or soft pockets. The locations of these areas are shown on the Structure Foundation Map, Plate 10. Excavation in these areas typically resulted in the material breaking out irregularly, leaving a depression or a vertical face. Another example was the rock breaking out along a softer,

weaker horizontal bedding plane which could be up to several inches below the desired grade.

In areas where overexcavation was the direct result of naturally occurring weaknesses in the foundation bedrock, the Contractor was paid for the extra amount of excavation and backfill. The quantities were measured and agreed upon by representatives of the Government and the Contractor immediately after excavation and before placement of backfill. Under this agreement the Government paid for a total of 354 cubic yards of extra sand, and 61 cubic yards of extra concrete.

6. Foundation Preparation. Preliminary test results indicated the need to minimize the exposure time of the primary material in order to retard change in moisture content and subsequent deterioration. A minimum of 2 feet of undisturbed primary protective cover was left on all rock foundation surfaces for subsequent removal immediately prior to backfill with filter sand or protective concrete.

(a) Foundations Beneath the Structure. Each day the final 2 + feet of primary material was excavated from an area using the Gradall or the backhoe. Upon achieving final grade, all loose, drummy, or otherwise unsatisfactory rock was removed and the surface was cleaned using compressed air. Figures 14 thru 32 show typical foundation surfaces. While the surface was being cleaned the Contractor's survey team assisted the CE geologist in taking final grade cross-sections and mapping any geologic features in the foundation. Immediately after the cleaning and mapping were completed, and the foundation was

approved by the inspecting geologist, Aerospray 70, a resin-type sealer manufactured by the American Cynamid Company, Wayne, New Jersey, was mechanically sprayed onto the foundation surface. The surface was then covered with either filter sand in the area beneath the spillway floor, or protective concrete in the area beneath the spillway training walls. A complete record of foundation approval is presented on Plate 13.

The use of Aerospray 70 was ineffective in areas of predominantly sand or sandy material. It was observed that in sandy material, the Aerospray mixture actually penetrated and softened or loosened the top ± 1-inch of material, making the surface soft and slippery. The Aerospray was effective in the shaly zones of the foundation. Therefore, the decision whether or not to use the Aerospray was made on a daily basis by the CE geologist, depending on the type of material exposed on the excavation surface.

(b) Foundations Adjacent to the Structure. Foundations adjacent to the structure include unweathered strata of the Woodbine Formation. The excavation slopes beyond the limits of the spillway structure foundation were essentially excavated to final grade during the initial spillway excavation. Primary material immediately adjacent to the outside toe of the training walls was excavated to a 1 vertical on 1 horizontal slope and allowed to stand during the period of construction. Adjacent to each wall the 1 vertical on 1 horizontal slope came up to a specified height, then changed to a 1 vertical on 3.5 horizontal slope to the top of the excavation. After the training walls were

completed, non-expansive material was placed between the training walls and the 1 vertical on 1 horizontal slope. Before placement of fill, the slope was hand-cleaned of loose, deteriorated, or otherwise unsatisfactory materials. Figure 33 shows an area of the 1 vertical on 1 horizontal slope being backfilled with non-expansive material.

(c) Overburden. Overburden materials exposed in the excavation slopes are shown on Plate 9. Horizontal and vertical limits of the overburden are shown on the cross-section on Plate 12. No backfill occurred adjacent to overburden materials. Overburden materials exposed in the slopes were covered with topsoil and turf to protect against erosion.

7. Safety. The slopes of the excavation were designed so that there would be no requirement for protection against slides and rock falls within the excavation. However, one minor slide did occur in a nearly vertical shale face about 300 feet left of centerline at station 14 + 50. (See Figure 6) After a significant weekend rain it was discovered that about 20 cubic yards of material had fallen down the slope, possibly the result of water entering an isolated zone of jointing behind the shale mass. Fortunately there were no workmen or equipment immediately below the slide area at the time of occurrence. To preclude future slope stability problems the Contractor was directed to lower the top of the slope as the excavation deepened, thereby maintaining a decreased standing height. The remainder of the excavation slopes remained stable throughout the construction period.



Fig.5 - Parabolic-shaped slab at top of spillway slope -
note collars placed at rock anchor locations



Fig.6 - Slide area shown in upper center portion
of photo - note nearly vertical slopes

VI FOUNDATION ANCHORS

1. General. Permanent foundation anchors were installed in the existing spillway apron at Grapevine Dam and in the newly constructed chute and stilling basin. A total of 3549 foundation anchors were installed to a minimum depth of 16 feet below the surface of the apron slab in the existing section and the protective concrete slab in the new section. A plan of rock-anchor installation is presented on Plate 14.

2. Equipment. The 6-inch diameter holes for the foundation anchors were drilled using a Gardner-Denver RDC-16B track-mounted pneumatic drill, shown on Figure 7. Two types of bits were used for drilling: The majority of drilling was done using a 5 $\frac{1}{2}$ -inch drag bit in the soft shales, clays and sandstones; and, a 6-inch Varel Tri-cone rock-bit was used to penetrate the moderately hard to hard sandstone layers which were encountered. The anchors consisted of No. 11 rebar bent in an L-shape. The grout mixture placed around the anchors was mixed at a commercial off-site batch plant and delivered in ready-mix trucks. (See Figure 9) The grout was dumped into a hopper attached to a side-winder pump and subsequently pumped into the holes through a 1 $\frac{1}{4}$ -inch ID flexible hose.

3. Grout Mix Design. One cubic yard of grout contained the following ingredients:



Fig. 7 - Anchor holes being drilled with track-mounted pneumatic drill



Fig. 8 - Anchor bars in place and ready for grouting



Fig.9 - Grout arrives at site and is dumped into hopper and pumped to hole locations



Fig.10 - Grout being placed in bottom of hole through 1½-inch ID flexible rubber hose

Cement (Normal Portland Type I)	2.630 cf (5.5 sacks)
Fine Aggregate (0 - #4 Trinity Newark Sand).	19.189 cf
Water	4.776 cf (35.75 gal.)
Admixture (MB-322N-Water Reducing Admixture)	<u>.405 cf</u>
	27.000 cf

4. Procedure. Work on the Grapevine Spillway was scheduled so that the drilling and installation of foundation anchors could be accomplished simultaneously with other phases of construction. All of the anchors were installed perpendicular to the spillway structural concrete slab. Holes for installing the anchors were drilled through 6-inch diameter collars installed through the protective concrete slab and filter blanket. The anchor holes were drilled 15 feet into the foundation bedrock. Upon reaching the required depth the holes were blown clean using compressed air and tightly plugged until the subsequent insertion of anchor bars and grout. The normal procedure was to drill and plug approximately 50 anchor holes, insert the anchor bars, and place grout, all within 2 to 3 consecutive days. After the anchor bars were fixed in the holes at the correct elevation the grout mixture was pumped through a 1 $\frac{1}{4}$ -inch ID flexible rubber hose extending to the bottom of the hole (Figure 10). Pumping continued until pure grout returned to the surface, indicating the hole was filled. The hose was then withdrawn from the hole while pumping continued. The grout in the hole was then vibrated from the bottom of the hole up (Figure 11). Finally, after vibrating was completed, the hole was topped off with more grout, completing the installation.



Fig.11 - Grout being vibrated in the hole




Fig.12 - Anchor bars and steel in place ready for concrete

5. Modification. In accordance with the Value Engineering Incentive Clause of the contract, the Contractor submitted two proposals to modify the rock anchor design and installation. The first proposal was to eliminate the 1/2-inch grout tube attached parallel to each anchor through which grout would be pumped causing the hole to be filled with grout from the bottom up. Instead, grout would be pumped to the bottom of the hole through a 1/2-inch steel pipe which would be retracted as the hole filled with grout. The second proposal was to reduce the number of spacers fixed to each anchor from four to two.

Both of the proposals were accepted by the SWF Value Engineering Officer, resulting in Modification No. P00005, DO-C0612 being issued on September 30, 1983. The net savings to the Government was \$7,296.

After installation of the rock anchors began, the Contractor requested and was granted approval to fill the grout holes through a flexible hose, as described above, rather than through a steel pipe.

6. Pull-Out Tests. Two rock anchors were installed on February 8, 1984, for the purpose of conducting pull-out tests. Both were installed at design grade near the centerline of the spillway at approximate station 12 + 80, about 50 feet downstream from the end of the existing spillway apron. The pull-out tests were performed by Southwestern Laboratories' personnel. The initial tests conducted on Feb 23-24, 1984, were unsuccessful because of problems with the jack and jack support. The same anchor bars were retested on March 8, 1984, with successful results. The anchors were stressed to 45 tons during which



Fig. 13 - Pull-out test in progress

the maximum deformation observed was 0.551 inch. Figure 13 shows the pull-out tests in progress.

As a result of this test it was concluded that the design for the spillway slab anchors was satisfactory, and the Contractor was given authorization to proceed with the fabrication and installation of the rock anchors based on the design given in the contract plans and specifications. A complete record of the pull-out test data is on file in the SWF Design Branch, Structural Section.

VII POSSIBLE FUTURE PROBLEMS

1. Observations. There were no unanticipated foundation conditions discovered during construction of the Grapevine Spillway Modification which would pose a threat to the stability of the structure. All foundation surfaces were stable and sufficiently competent as anticipated in the design, and remained so until covered by filter sand or protective concrete.

The materials exposed in the upper portion of the excavation are highly erodible in nature. The establishment and maintenance of a good turf zone will be required in this area in order to prevent severe erosional damage and subsequent heavy siltation over the spillway floor.

The channel downstream from the new spillway is founded in materials varying from loose clayey sand to soft to moderately hard, very fine-grained, weakly to moderately cemented sandstone. The channel will suffer severe erosional damage in the event of a major flow event. Measures to control erosion in the spillway discharge channel should be considered.

2. Future Considerations. The excavation of a 1 horizontal on 4 vertical slope, as required in the excavation for the spillway end sill, is very difficult to achieve. Normally, when excavating in soft materials where line drilling would not be required, a Contractor will use a backhoe, which will result in a rectangular-shaped ditch, as

was the case in this project (see Figure 32). Consideration should be given to designing a rectangular-shaped end sill excavation with a typical bottom width conforming to the width of a typical backhoe bucket.




Fig. 14 - Exposed foundation surface - 25 April 1984




Fig. 15 - Exposed foundation surface - 9 May 1984




Fig. 16 - Exposed foundation surface - 9 May 1984



Fig. 17 - Exposed foundation surface - 25 June 1984



Fig. 18 - Exposed foundation surface - 10 July 1984



Fig. 19 - Exposed foundation surface - 10 July 1984




Fig. 20 - Exposed foundation surface - 18 July 1984




Fig. 21 - Exposed foundation surface - 25 July 1984



Fig. 22 - Excavation for cut off wall -
28 June 1984




Fig. 23 - Exposed foundation surface - 10 September 1984



Fig. 24 - Exposed foundation surface - 10 September 1984



Fig. 25 - Exposed foundation surface - 17 September 1984



Fig. 26 - Exposed foundation surface - 9 October 1984




Fig. 27 - Exposed foundation surface - 9 October 1984



Fig. 28 - Exposed foundation surface - 20 November 1984



Fig. 29 - Exposed foundation surface - 6 March 1985



Fig. 30 - Exposed foundation surface - 6 March 1985



Fig. 31 - Exposed foundation surface - 7 March 1985



Fig. 32 - End sill excavation - 5 April 1985





Fig. 33 - Placement of nonexpansive backfill between training wall and excavation slope



NORTH SHORE PARK

ROANOKE PARK

NOB HILLS PARK

ROCKY

MARSHALL CREEK PARK

WALNUT GROVE PARK

MEADOWMERE PARK

OAK GROVE PA

TOP OF FLOOD CONTROL POOL
ELEV 560

TOP OF CONSERVATION POOL
ELEV 535'

STATE HWY NO 114
TO ANHOLE

DENTON COUNTY
TARRANT COUNTY

ROANOKE


TO KELLER
F.M. ROAD NO 1709

LEGEND

-  RESERVOIR DEPTH 0-15 FT
-  RESERVOIR DEPTH 15-25 FT
-  RESERVOIR DEPTH 25-84 FT
-  PAVED OR HARD SURFACED ROAD
-  GRAVELED OR IMPROVED ROAD
-  GRADED OR UNIMPROVED ROAD
-  PRIMITIVE ROAD OR TRAIL

SCALE OF MILES





VICINITY MAP
NOT TO SCALE

F

D

C

B

K
S AREA
RK

REV	NO.	ACTION	DATE	DESCRIPTION OF REVISION
				U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS
DESIGNED BY	GRAPEVINE LAKE			
K. MCCARTHY	DENTON CREEK, ELM FORK, TRINITY RIVER, TEXAS			
DRAWN BY	MODIFICATION OF			
STD. DWG	EMBANKMENT AND SPILLWAY			
REVIEWED BY	PROJECT LOCATION			
A. MARR	3			
SUBMITTED BY	INVITATION NO. DACW63-83-B-0052	DATE	AUG 1983	
MEL GREEN	CONTRACT NO. DACW63-83-C-0160	SHEET NO.	PLATE	
ENGINEER	DRAWING NUMBER	OF	1	

CONTRACT NO. DACW63-83-C-0160

6

7

8

9



APPROXIMATE LOCATION
WATER LINE IN THE
MOUND THE CONTRACTOR
TO THIS LINE TO PRO
GOVERNMENT FIELD

CONSERVATION POOL EL. 5350

STA 60+00

STA 49+34

DENTON CREEK

EMBANKMENT MODIFICATION
BETWEEN STA. 57+00 AND
STA. 65+00

OUTLET
WORKS

WASTE AREA II

LIMITS OF CONSTRUCTION
R.O.W. Δ

STOCKPILE AREA
FOR R DRAP

OUTLET CHANNEL

BRICKA-30 FAIRWAY DR

ROCKLESE PARK DR

645' W.S. DETOUR

ARMANDO

FAIRWAY DRIVE

WASTE AREA III

Δ	AM #0001	23 AUG 83	ADDED LIMITS OF
SYM NO.	ACTION	DATE	DESCR
			U.S. ARMY E
DESIGNED BY	GRAPEVINE I		
APPROVED BY	DENTON CREEK, ELM FORK, TR1		
DESIGNED BY	MODIFICATION OF EM		
APPROVED BY	AND SPILLW		
DESIGNED BY	SITE P		
APPROVED BY			
SUBMITTED BY	INVITATION NO. DRAWING		
MEL GREEN	CONTRACT NO. DRAWING		
ENGINEER	DRAWING NUMBER		



6

7

8

TO ACCOMPANY FINAL FOUNDATION REPORT

8


9

10



APPROXIMATE LOCATION OF EXISTING 24" WATER LINE IN THE CITY OF FLOWER MOUND. THE CONTRACTOR SHALL CONNECT TO THIS LINE TO PROVIDE WATER TO THE GOVERNMENT FIELD OFFICE

DEBRATON POOL EL 5350



DESIGNED BY <i>A. MARR</i>	AM #0001	23 AUG 83	ADDED LIMITS OF CONSTRUCTION R.O.W.
DRAWN BY <i>C. SMITH</i>	REVISED BY <i>A. MARR</i>	INVIATION NO. DACW63 83 B-0052	DATE AUG 1983
SUBMITTED BY MEL GREEN ENGINEER		CONTRACT NO. DACW63 83 C-0160	DRAWING NUMBER
U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS		PLATE	2
GRAPEVINE LAKE DENTON CREEK, ELM FORK, TRINITY RIVER, TEXAS		SHEET NO.	OF
MODIFICATION OF EMBANKMENT AND SPILLWAY		3	
SITE PLAN		2	



F
E
D
C
B

CONTRACT NO. DACW63-83-C-0160

F


E

D

C


B

A



GRAPEVINE
SPILLWAY

1
POLYMER 833



LEGEND

- RECENT [ (Qa) ALLUVIUM
- PLEISTOCENE [ (Ql) FLUVIALITE TERRACE DEPOSITS
- UPPER CRETACEOUS [ (Kef) EAGLE FORD GROUP UNDIVIDED
- [ (Kwb) WOODBINE FORMATION
- LOWER CRETACEOUS [ (Kgy) GRAYSON MARL & MAIN STREET
- [ (Kpwd) PAWPAW FORMATION

NOTES:

1. MAP REFERENCE UNIVERSITY OF TEXAS BUREAU OF ECONOMIC GEOLOGY, DALLAS SHEET, 1972, AND SHERMAN SHEET, 1967.



DESIGNED BY A. MARR	GRAPEVINE DENTON CREEK, ELM FORK, MODIFICATION EMBANKMENT AND AREAL
DRAWN BY L. GOSS	
REVIEWED BY A. MARR	
SUBMITTED BY L. GREEN	INVESTIGATION NO.
ENGINEER	CONTRACT NO.
	DRAWING NUMBER

F
E
D
C
B




LEGEND


- RECENT {  (aal) ALLUVIUM
- PLEISTOCENE {  (qt) FLUVIATILE TERRACE DEPOSITS
- UPPER CRETACEOUS {  (kof) EAGLE FORD GROUP UNDIVIDED
- {  (kwb) WOODBINE FORMATION
- LOWER CRETACEOUS {  (kgy) GRAYSON MARL & MAIN STREET
- {  (kpwd) PANPAW FORMATION

NOTES:

1. MAP REFERENCE UNIVERSITY OF TEXAS BUREAU OF ECONOMIC GEOLOGY, DALLAS SHEET, 1972, AND SHERMAN SHEET, 1967.




REVISING NO.	ACTION	DATE	DESCRIPTION OF REVISION
			U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS
DESIGNED BY A. MARR	GRAPEVINE LAKE DENTON CREEK, ELM FORK, TRINITY RIVER, TEXAS		
DRAWN BY L. GOSS	MODIFICATION OF EMBANKMENT AND SPILLWAY		
REVIEWED BY A. MARR	AREAL GEOLOGY		
SUBMITTED BY M. GREEN ENGINEER	INVITATION NO.	DATE	PLATE 3
	CONTRACT NO.	SHEET NO. OF	



NOTES

1. BORINGS LABELED BA3F AND 3F WERE DRILLED FOR ELECTRIC LOG PURPOSES ONLY - DETAILED LITHOLOGIC LOGS WERE NOT PREPARED
2. FOR DETAILED LOG OF BORINGS SEE PLATES 18 THRU 21
3. FOR GEOLOGIC SECTIONS SEE PLATES 5 THRU 8

V. POLYMER 33




- LEG
- BA46 - B¹ & A¹
 - BA46 - B² & A²
 - BA3F - B¹ & A¹

100 0 10
SCALE OF FE

DESIGNED BY A MARR	GRAPEVIT DENTON CREEK, ELM FORK		
DRAWN BY L GOSS	MODIFICATION OF AND SP		
REVISED BY A MARR	PLAN OF LOCATIONS		
SUBMITTED BY M GREEN ENGINEER		INVITATION NO. OF 	
		CONTRACT NO. OF 	
		DRAWING NUMBER 	


TO ACCOMPANY FINAL FOUNDATION REPORT

F
E
D
C
B



LEGEND

- BA 20 - 8" Ø AUGER, 6" Ø CORE
- BA 40 - 8" Ø AUGER, 4" Ø CORE
- BA 3F - 8" Ø AUGER, 3" FISHTAIL



REV. NO.	DATE	DESCRIPTION OF REVISION

U.S. ARMY ENGINEER DISTRICT, FORT WORTH
CORPS OF ENGINEERS
FORT WORTH, TEXAS

GRAPEVINE LAKE
CENTIN CREEK, ELM FORK, TRINITY RIVER, TEXAS

**MODIFICATION OF EMBANKMENT
AND SPILLWAY**

**PLAN OF BORINGS &
LOCATIONS OF SECTIONS**

DESIGNED BY: A. MARR
 DRAWN BY: L. GOSS
 CHECKED BY: A. MARR


SUBMITTED BY: M. GREEN, ENGINEER

INVITATION NO. DACW83 83 B 0052 DATE: AUG 1983

CONTRACT NO. DACW83 83 C 0180 SHEET NO. 4

PLATE 3

CONTRACT NO. DACW83 83 C 0180




LEGEND

- WOODBINE FORMATION
(CRETACEOUS AGE)
- PREDOMINANTLY SANDSTONE W/ SHALE & SHALY SANDSTONE INTERBEDS
 - PREDOMINANTLY SHALE W/ SANDSTONE & SANDY SHALE INTERBEDS

SPILLWAY CENTERLINE
SCALE: VERT - 1" = 35'
HORIZ - 1" = 35'





PROFILE


- NOTES:**
1. DETAILED LOGS OF BORINGS ARE SHOWN ON PLATE 12 THROUGH 14
 2. || (72 HR) - WATER LEVEL 72 HOURS AFTER COMPLETION OF DRILLING
 3. * - BASE OF WEATHERING

REV. NO.	NO.	ACTION	DATE
DESIGNED BY	GRAPEVINE		
DRAWN BY	MODIFICATION EMBANKMENT AND CENTERLINE		
REVIEWED BY			

8

9

10



F

E

D


C

B

SYN. NO.	ACTION	DATE	DESCRIPTION OF REVISION
U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS			
DESIGNED BY A. MARR	GRAPEVINE LAKE MODIFICATION OF EMBANKMENT AND SPILLWAY		
DRAWN BY L. GOSS	CENTERLINE PROFILE 3		
REVIEWED BY M. GREENE			
SUBMITTED BY M. GREENE	INVITATION NO.	DATE	
ENGINEER	CONTRACT NO.	DRAWING NUMBER	
		SHEET NO.	PLATE 5

8

TO ACCOMPANY FINAL FOUNDATION REPORT



SPILLWAY SECTION B-B
 STATION 15+50
 SCALE: VERT. 1" = 10'
 HORIZ. 1" = 25'

F
 E
 D
 C
 B
 A

1 2 3 4 5

2 3 4 5


F

E

D

C

B




WOODBINE FORMATION
(CRETACEOUS AGE)

LEGEND


-  PREDOMINANTLY SANDSTONE W/ SHALE
(SHALY SANDSTONE INTERBEDS)
-  PREDOMINANTLY SHALE W/ SANDSTONE
(SANDY SHALE INTERBEDS)

ELECTRIC LOG



DESCRIPTIONS
CONTINUED AT BOTTOM
AS SHOWN ON

DESIGNED BY A. MARR	GRAPEVINE LAKE MODIFICATION OF EMBANKMENT AND SPILLWAY		
DRAWN BY L. GOOS	SECTION B-B		
REVIEWED BY M. GREEN	INVITATION NO.	DATE	PLATE 6
SUBMITTED BY MEL GREEN ENGINEER	CONTRACT NO.	DRAWING NUMBER	SHEET NO.



F


E

D

C


B

BM 3F-609
EL 539.36




1 FOR LOCATION OF SECTION C-C SEE PLATE 4
 2 FOR LEGEND AND GENERAL NOTES SEE PLATE 6

REV. OR. NO.	ACTION	DATE	DESCRIPTION OF REVISION
			U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS
DESIGNED BY <u>A. MARR</u>	GRAPEVINE LAKE GENTON CREEK, FLM FORK, TRINITY RIVER, TEXAS		
DRAWN BY <u>L. GOSS</u>	MODIFICATION OF EMBANKMENT AND SPILLWAY 3		
REVIEWED BY <u>M. GREEN</u>	SECTION C-C		
SUBMITTED BY <u>M. GREEN</u> ENGINEER	INVITATION NO.	DATE	
	CONTRACT NO.	SHEET NO.	
	DRAWING NUMBER	PLATE 7	




SPILLWAY SECTION D-D
 SCALE VERT 1" = 10'-0"
 HORIZ 1" = 25'-0"




NOTES :

- 1 FOR LOCATION OF SECTION D-D SEE PLATE
- 2 FOR LEGEND AND GENERAL NOTES SEE PL

DESIGNED BY A MARR	GRAPEVINE L DENTON CREEK ELM FORK, TX MODIFICATIO EMBANKMENT AND SECTION C
DRAWN BY L GOSS	
REVIEWED BY M GREEN	
SUBMITTED BY M GREEN ENGINEER	INVITATION NO. CONTRACT NO. DRAWING NUMBER





LEGEND


- OVERBURDEN
 - SAND, CLAYEY
 - PREDOMINANTLY SANDSTONE W/SHALE AND SHALY SANDSTONE INTERBEDS
 - PREDOMINANTLY SHALE W/SANDSTONE AND SANDY SHALE INTERBEDS
 - CLAY
- PRIMARY WOODBINE FORMATION (CRETACEOUS AGE)
 - GROUND WATER SEEPAGE AREA

NOTES

- 1 SECTIONS A-A AND B-B ARE PRESENTED ON PLATES 11 AND 12 RESPECTIVELY
- 2 CONTOUR INTERVAL = 10 FT



SITE LOG NO.		ACTION		DATE		DESCRIPTION	
DESIGNED BY		GRAPEVINE LAKE					
DRAWN BY		DENTON CREEK, ELM FORK, TRINITY RIVE					
REVIEWED BY		MODIFICATION OF EMBANKMEN					
SUBMITTED BY		AND SPILLWAY					
MEL GREEN		GEOLOGIC MAP OF THE E					
INVITATION NO.		(AS-BUILT)					
CONTRACT NO.							
DRAWING NUMBER							



LEGEND

- | | | |
|---|--|--|
| OVERBURDEN | | SAND, CLAYEY |
| PRIMARY
WOODBINE
FORMATION
(CRETACEOUS
AGE) | | PREDOMINANTLY SANDSTONE W/SHALE
AND SHALY SANDSTONE INTERBEDS |
| | | PREDOMINANTLY SHALE W/SANDSTONE
AND SANDY SHALE INTERBEDS |
| | | CLAY |
| | | GROUND WATER SEEPAGE AREA |

NOTES

- 1 SECTIONS A-A AND B-B ARE PRESENTED ON PLATES 11 AND 12 RESPECTIVELY
- 2 CONTOUR INTERVAL = 10 FT



REV. LOG. NO.	ACTION	DATE	DESCRIPTION OF REVISION
U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS			
DESIGNED BY MARR/BOOS	GRAPEVINE LAKE DENTON CREEK, ELM FORK, TRINITY RIVER, TEXAS MODIFICATION OF EMBANKMENT AND SPILLWAY 3 GEOLOGIC MAP OF THE EXCAVATION (AS-BUILT)		
DRAWN BY A MARR			
REVIEWED BY M. GREEN			
SUBMITTED BY MEL GREEN ENGINEER	INVITATION NO.	DATE	CONTRACT NO. PLATE 9 DRAWING NUMBER SHEET NO. OF

1

2

3

4

5

F

E

D

C

B

A

DISTANCE FROM \downarrow IN FEET

250
200
150
100
50
0
50
100
150
200
250

12+00

13+00

14+00

15+00

EDGE OF EXISTING SPILLWAY APRON STA. 12+32.45

530

520

510

500

490

480

470

NO. 177502 93


1

2

3

4

5



NOTES

1. FOR LOCATION OF CENTERLINE PROFILE A-A SEE PLATE 9
2. FOR LEGEND SEE PLATE 9

A

B

C

D

E

F

1

2

3

4

5

6

7

8

9

CENTERLINE PROFILE A-A

DRAINAGE BLANKET

STRUCTURAL CONCRETE

13+00

14+00

15+00

16+00

SPILLWAY STATIONS IN FEET

2

SYM.	NO.	ACTION	DATE
DESIGNED BY	A. MARR		
DRAWN BY	A. MARR		
REVIEWED BY	M. GREEN		
SUBMITTED BY	MEL GREEN		INVESTIGATOR
ENGINEER			CONTRACTOR
			DRAWING

GRAPE
DENTON CREEK, EL
MODIFICATION (AND SI
CENTERLINE
(AS

TO ACCOMPANY FINAL FOUNDATION REPORT

5

6

7

8

8

9

10

A - A

F

E

D

C

B

STRUCTURAL CONCRETE

48" RIPRAP

15+00

16+00


17+00

REVISING NO.	ACTION	DATE	DESCRIPTION OF REVISION
DESIGNED BY A. MARR			U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS GRAPEVINE LAKE DENTON CREEK, ELM FORK, TRINITY RIVER, TEXAS MODIFICATION OF EMBANKMENT AND SPILLWAY CENTERLINE PROFILE A - A (AS - BUILT)
DRAWN BY A. MARR			
REVIEWED BY M. GREEN			
SUBMITTED BY MEL GREEN ENGINEER			
INVITATION NO.			
CONTRACT NO.			DATE
DRAWING NUMBER			SHEET NO. OF
			PLATE 11

3

8

TO ACCOMPANY FINAL FOUNDATION REPORT



SECTION
SPILLWAY STATI

DISTANCE FROM CE
LOOKING DI

7

8

9

10

F

E

D

C

B

LEGEND

- OVERBURDEN SAND, CLAYEY
- PRIMARY WOODBINE FORMATION (CRETACEOUS) AGE PREDOMINANTLY SANDSTONE W/ SHALE AND SHALY SANDSTONE INTERBEDS
- PREDOMINANTLY SHALE W/ SANDSTONE AND SANDY SHALE INTERBEDS
- STRUCTURAL CONCRETE
- NON-EXPANSIVE BACKFILL
- FILTER SAND
- IMPERVIOUS CLAY BACKFILL
- DRAINAGE BLANKET

400 500 600

N OF SECTION B-B SEE PLATE 9


REV. NO.	ACTION	DATE	DESCRIPTION OF REVISION

DESIGNED BY A. MARR		U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS	
DRAWN BY A. MARR		GRAPEVINE LAKE DENTON CREEK, ELM FORK, TRINITY RIVER, TEXAS MODIFICATION OF EMBANKMENT AND SPILLWAY SECTION B-B (AS-BUILT)	
REVIEWED BY M. GREEN			
SUBMITTED BY MEL GREEN ENGINEER		INVITATION NO.	DATE
CONTRACT NO.		DRAWING NUMBER	
DRAWING NUMBER		SHEET NO. OF	PLATE 12

7

8



TO ACCOMPANY FINAL FOUNDATION REPORT



WATER MAIN




WATER MAIN STATION 12+32.45



NOTES:

FOR GEOLOGIC MAP OF PLAIN AT
 2' EXCAVATION, APPROVAL, AND
 OCCURRED ON THE DATE SHOWN



2

SYM	FIG. NO.	ACTION	DATE
DESIGNED BY	A MARR	GRAPEN	
DRAWN BY	A MARR	DENTON CREEK, ELM	
REVIEWED BY	M GREEN	MODIFICATION C	
SUBMITTED BY	MEL GREEN	AND SP	
ENGINEER		RECORD OF F	
INVITATION		CONTRACT	
DRAWING			

7

8

9

10



F

E

D

C

B



NOTES:

FOR GEOLOGIC MAP OF FOUNDATION SEE PLATE 10
 EXCAVATION, APPROVAL, AND BACKFILL ARE
 OCCURRED ON THE DATE SHOWN IN EACH AREA

REV. NO.	ACTION	DATE	DESCRIPTION OF REVISION
DESIGNED BY A. MARR			U.S. ARMY ENGINEER DISTRICT, FORT WORTH CORPS OF ENGINEERS FORT WORTH, TEXAS GRAPEVINE LAKE DENTON CREEK, ELM FORK, TRINITY RIVER, TEXAS MODIFICATION OF EMBANKMENT AND SPILLWAY RECORD OF FOUNDATION APPROVAL
CHECKED BY A. MARR			
REVIEWED BY M. GREEN			
SUBMITTED BY MEL GREEN ENGINEER		INVITATION NO.	DATE
		CONTRACT NO.	SHEET NO. OF
		DRAWING NUMBER	PLATE 13

7

8

TO ACCOMPANY FINAL FOUNDATION REPORT

2

3

4

5

F

E

D

C

B

A

11 SPA @ 20' 6" = 225' 6"

250' 0"
11 SPA @ 20' 6" = 225' 6"

SPILLWAY
4' 0"

STA 12+32.45

(A)

PATTERN REPEATS

PATTERN REPEATS

PATTERN REPEATS

PATTERN REPEATS

UNDER DRAIN SYSTEM
LINE 8 M.H.

UNDER DRAIN SYSTEM
LINE 8 M.H.

DRAINAGE M.H.

DRAINAGE M.H.



6 SPA @ 20'-0" = 120'-0"

7 SPA @ 20'-0" = 140'-0"

26' 6"

3 SPA @ 20'-0" = 60'-0"

43'-0"



PLAN





2

3

4

5



NOTE:
FOR ALTERNATE ROW SPACING
THE TWO AND THREE ANCHORS
PER ROW DIMENSION IN A
PANEL IS SHIFTED UPSTREAM
UPSTREAM ONE PANEL
SPACE

DESIGNED BY	BA-E	GRAPEVINE DEL MON CREEK, GDM FORN. TR MODIFICATION EMBANKMENT AND CHUTE SLAB PLAN AND SE
DRAWN BY	BA-E	
REVIEWED BY	A MARR	
SUBMITTED BY	MEL GREEN ENGINEER	
INTEGRATION NO	DA663	INVITATION NO DA663 CONTRACT NO DA663 DRAWING NUMBER
DATE	5/20/71	

2

DATA SUMMARY

ST

ECT GRAPEVINE SPILLWAY

WATER DENSITY BS/CU FT	SHEAR DATA							PERMEABILITY		CONSOLIDATION DATA						
	W ₁ %	W _F %	S ₁ %	TYPE TEST	SPECIMEN SIZE INCHES	TEST	σ _m T/SQ FT	σ ₁ T/SQ FT	c T/SQ FT	φ DEGREES	e	K FT/MIN.	P _O T/SQ FT	P _C T/SQ FT	C _C	t _s
<u>ED COMPRESSION TESTS</u>																
115	16.7		100		5.5 X 10.7		0	15.7								
119	14.5		100		5.7 X 9.0		0	47.0								
122	14.2		100		5.2 X 9.4		0	2.2								
137	8.3		95		5.3 X 10.0		0	54.5								
<u>COMPRESSION TEST (1-Pt Q)</u>																
118	15.2		100		5.4 X 10.4		0.25	16.5								
125	12.4		100		5.5 X 10.3		0.35	12.5								
134	8.6				5.6 X 8.9		2.3	43.2								

T - TRIAXIAL COMPRESSION DS - DIRECT SHEAR S
 UC - UNCONFINED COMPRESSION Q - UNCONSOLIDATED UNDRAINED R

TO ACCOMPANY FINAL FOUNDATION REPORT

AD-A173 777

SPILLWAY MODIFICATION GRAPEVINE LAKE TEXAS (U) ARMY
ENGINEER DISTRICT FORT WORTH TX A J MARK JUN 86

2/2


UNCLASSIFIED

F/G 13/2

NL



END
1-87



SUN SIZE SIES	TEST					PERMEABILITY		CONSOLIDATION DATA				REMARKS
		σ_m T/SQ FT	σ_1 T/SQ FT	c T/SQ FT	ϕ DEGREES	e	K FT/MIN.	P_0 T/SQ FT	P_c T/SQ FT	C_c	t_{50}	
5.7		0	15.4									
7.0		0	47.0									
7		0	2.2									
0		0	54.5									
0.7		0.25	16.5									
3		0.25	12.5									
2.9		2.3	43.2									

T - TRIAXIAL COMPRESSION
 UC - UNCONFINED COMPRESSION

DS - DIRECT SHEAR
 U - UNCONSOLIDATED UNDRAINED

S - CONSOLIDATED DRAINED
 R - CONSOLIDATED UNDRAINED

BORING NO.	SAM. NO.	DEPTH OR ELEV. OF SAMPLE	LABORATORY CLASSIFICATION	MECHANICAL ANALYSIS				ATTERBERG LIMITS		SPECIFIC GRAVITY G	NAT WATER CONT %	NATURAL DRY DENSITY LBS/CU FT	COMPACTION DATA		INITIAL
				GRAVEL %	SAND %	FINES %	D ₁₀	LL	PL				OPT WATER %	MAXIMUM DRY DENSITY LBS/CL-FT	
SA100-603 (83/273)		52.1-23.0	CLAY-SHALE W/ALTERNATING LAYERS OF SILT	0	1	99		54	15	2.71	17.0				.5
											17.3				.51
											16.8				.50
											16.7				.4
SA100-603 (83/303)		56.5- 52.4	CLAY-SHALE W/SILTSTONE SEAMS	0	0	100		49	15	2.65	10.7				.28
											10.8				.28
											10.8				.28
											11.2				.28
SA100-603 (83/304)		63.5- 64.4	CLAY-SHALE W/SILT SEAMS	0	1	99		38	13	2.70	10.1				.22
											9.9				.22
											10.2				.22
											10.0				.22

TEST DATA SUMMARY

PROJECT GRAPEVINE SAILWAY

TEST NO.	DRY DENSITY LBS/CU FT	W ₁ %	W _F %	S ₁ %	TYPE TEST	SPECIMEN SIZE INCHES	TEST	SHEAR DATA				PERMEABILITY		CONSOLIDATION	
								G _m T/SQ FT	σ ₁ T/SQ FT	c T/SQ FT	φ DEGREES	e	K FT/MIN.	P ₀ T/SQ FT	P _C T/SQ FT
<u>2 - TRIAXIAL COMPRESSION TEST</u>															
13	111	17.0		90		1.4 X 2.9		0.5	14.80	3.5	33.7				
13	111	17.5		91		1.3 X 2.9		1.5	19.0						
10	112	16.8		92		1.4 X 3.0		3.0	24.1						
10	113	16.7		95		1.3 X 3.0		6.0	27.84						
10	128	10.7		99		1.4 X 3.0		0.5	9.11	2.4	25.0				
10	124	10.8		99		1.4 X 3.0		1.5	11.53						
10	122	10.9		98		1.4 X 3.0		3.0	15.21						
10	122	11.2		101		1.4 X 3.0		4.0	16.45						
10	125	10.1		88		1.3 X 2.9		0.5	9.44	3.7	28.0				
10	121	9.7		85		1.3 X 2.9		1.5	12.60						
10	125	10.1		87		1.4 X 3.0		3.0	21.23						
10	120	10.0		83		1.4 X 3.0		0.0	21.41						

T - TRIAXIAL COMPRESSION
UC - UNCONFINED COMPRESSION

DS - DIRECT SHEAR
O - UNCONSOLIDATED UNDRAINED

TO ACCOMPANY FINAL FOUNDATION REPORT

2

BORING NO.	SAM. NO.	DEPTH OR ELEV. OF SAMPLE	LABORATORY CLASSIFICATION	MECHANICAL ANALYSIS				ATTERBERG LIMITS		FLUIDITY	NATURAL DRY DENSITY (LBS/CU FT)	COMPACTION DATA		INITIAL
				GRAVEL %	SAND %	FINES %	D ₁₀	LL	PL			OPT WATER %	MAXIMUM DRY DENSITY (LBS/CU FT)	
														D15
8A6C-603 (83/297)		22.1- 23.0	CLAY-SHALE W/ALTERNATING LAIERS OF SILT	5	1	94		34	17					19- 53- 54-
8A6C-603 (83/304)		63.5 64.4	CLAY-SHALE W/SILT SEAMS	0	1	99		25	13	2.70	10.2			23- 30- 31-
8A6C-603 (83/306)		73.8- 74.7	SILTSTONE							2.67	7.8			218- 266- 267-
8A6C-603 (83/311)		103.6- 104.5	SILTSTONE							2.69	7.6			17- 18- 17.4
8A6C-603 (83/303)		56.5- 57.4		0	0	100		49	15	2.65	12.3			237- 237- 237-

TEST DATA SUMMARY

PROJECT GRAPEVINE SPILLWAY

TRIAL #	DRY DENSITY LBS/CU FT	W ₁ %	W _F %	S ₁ %	SHEAR DATA				U _{nl} T/SQ FT	O ₁ T/SQ FT	C T/SQ FT	φ DEGREES	PERMEABILITY		CONSOLIDATION	
					TYPE TEST	SPECIMEN SIZE INCHES	TEST	e					K FT/MIN	P _C T/SQ FT	P _C T/SQ FT	
<u>DIRECT SHEAR TEST</u>																
95	113	17.0	22.5	93		3.0 X 3.0		1.5								
96	110	17.2	21.5	89				3.0		0	35.0					
97	113	16.8	22.3	92				6.0								
<u>DIRECT SHEAR TEST</u>																
100	131	9.6	11.7	92		3.0 X 3.0		5.0								
101	139	7.9	13.0	89				5.0		1.2	29.0					
102	131	10.2	11.6	97				5.0								
<u>DIRECT SHEAR TEST</u>																
108	135	7.6	9.7	92		3.0 X 3.0		5.0								
109	136	8.6	10.7	103				5.0								
110	136	8.1	9.6	96				5.0								
<u>DIRECT SHEAR TEST</u>																
112	142	6.1	10.1	91		3.0 X 3.0		1.5		0.5	10.0					
113	141	6.3	9.8	92				3.0								
114	142	6.1	8.0	92				5.0								
<u>DIRECT SHEAR TEST</u>																
125	125	11.1	11.9	97				1.5		0	10.9					
126	128	10.7	13.8	97				3.0								
127	128	10.9	11.9	98				6.0								

T - TRIAXIAL COMPRESSION
UC - UNCONFINED COMPRESSION

DS - DIRECT SHEAR
O - UNCONSOLIDATED UNDRAINED

2
TO ACCOMPANY FINAL FOUNDATION REPORT

DRILLING LOG		DIVISION	INSTALLATION	Hole No.
Grapevine Lake		SWD	Ft Worth	62-100
Spillway				
PROJECT NO. 8A5C-402				
DATE OF LOG				
NAME OF OPERATOR				
DIRECTION OF HOLE				
THICKNESS OF OVERBURDEN				
TOTAL DEPTH OF HOLE				
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS	REMARKS
			56.4 to 57.4	7
			SILTSTONE - hard, massive, mod to well cemented, white and lt gray, shaley.	8
			57.4 to 70.1	9
			SHALE - as shale above except numerous sections of very sandy/silty friable thin seams, mod hard after 60' unhealed fracture @ 59.3 to 59.7' (30'), soft at 65.3' and 65.7' (each less than 0.1" thick)	10
			70.1 to 75.7	11
			SILTSTONE - mod hard/hard, mod cemented, massive, lt. gray to white, some olive gray, shaley, a gray and clean silt section from 70.9 to 71.2, sl. sandy after 74'	12
				13
				14
				15
				16
				17
				18
				19
				20

FOR LOCATION OF BORING SEE PLATE 4

APPROVED BY	A. MARR	DATE	10/10/50
REVISION	A. MARR	DATE	10/10/50
REVISION	M. GREEN	DATE	10/10/50
REVISION	MEL GREEN	DATE	10/10/50

GRAPEVINE
 MODIFICATION
 EMBANKMENT AND
 LOG OF BORING
 MEL GREEN

F

E

D

C

B

FOR LOCATION OF BORING SEE PLATE 4

PROJECT NO. 81-0-180 DISTRICT NO. 1 COUNTY, TEXAS	
DRAWN BY A. MARR	GRAPEVINE LAKE MODIFICATION OF EMBANKMENT AND SPILLWAY
CHECKED BY A. MARR	LOG OF BORING 8A6C-602
DESIGNED BY M. GREEN	DATE AUG 1963
APPROVED BY MEL GREEN	SHEET NO. 18

F

E

D

C

B

A

Well No. **BA6C-603**

DRILLING LOG	SWD	ATTACHMENT	FWD	SHEET	1
LOCATION	GRAPEVINE LAKE	NO. OF FEET OF CORE	8" AUGER	NO. OF SHEETS	3
PROJECT	SPILLWAY	DATE	11 FEB 83	NO. OF CORE BBL	6
CLIENT	USCE	FAILING	1500		
WELL NO.	BA6C-603	TOTAL NO. OF CORE BBL	4	NO. STORED	19
DRILLER	BREWER	TOTAL NUMBER CORE BITES	19		
DIRECTION OF HOLE	0	DATE HOLE STARTED	11 FEB 83	DATE HOLE COMPLETED	15 FEB 83
VERTICAL CORRECTION	108.5'	ELEVATION TOP OF HOLE	538.0		
DEPTH OF HOLE	108.5'				

Alan Man

ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	REMARKS
0.0	2.2	A	SANDSTONE, SOFT, FLAGGY, FINE-MED GRN, BROWN GRAY	DRILLING
2.2	4.5	B	SHALE, SOFT, SLT WEATH, VERY SANDY, NON-CALC, DARK GRAY, SCAT FINE SHELL FRAGMENTS	8" AUGER
4.5	8.9	C	SHALE, UNWEATH, SOFT, MOIST, DARK GRAY w/ THIN LT GRAY SANDY SEAMS, LIGNITIC	6" CORE BBL
8.9	12.9	D	SANDSTONE, SOFT, FINE TO MED GRAINED, WEAKLY TO MOD CEMENTED, NON-CALC, MASSIVE, GRAY	SAMPLES
12.9	45.6	1	SHALE, MOD SOFT, UNWEATH, DARK GRAY TO GRAY, NON-CALC, LIGNITIC TO 18" NUM THIN SAND LENSES, SCATTERED THROUGHOUT	JAR A 0.0-0.3 B 0.3-2.2 C 2.2-4.5 D 4.5-6.0
16.1	17.2	2	SANDSTONE, MOD HARD, GRAY	CARTONS
19.7		3	UNHEALED FRACTURE 45° C	1 6.0 - 6.9 2 11.5 - 12.4 3 17.5 - 18.4 4 22.1 - 23.0 5 24.5 - 30.4 6 37.5 - 38.4 7 41.9 - 42.8 8 46.7 - 47.6 9 51.0 - 51.9 10 56.5 - 57.4 11 61.5 - 64.4 12 68.1 - 69.0 13 72.8 - 74.7 14 79.0 - 79.9 15 84.2 - 85.1 16 92.0 - 92.9 17 98.8 - 99.2 18 103.6 - 104.5 19 105.2 - 106.1
20.1	20.3	4	SILTSTONE, HARD	
23.8	23.9	5	" " " " " "	
31.8	32.0	6	" " " " " "	
25.0	25.8	5	CALCAREOUS ZONE, HARD, LT GRAY	

HOLE WAS E-LOGGED

WATER

BORING LEFT OPEN FOR FUTURE WL OBSERVATION 22 FEB 83 WL 3.3 FT BELOW SURFACE BAIL-DOWN/RECOVERY TEST PERFORMED 23 FEB 83

Well No. **BA6C-603**

DRILLING LOG	SWD	ATTACHMENT	FWD	SHEET	1
LOCATION	GRAPEVINE LAKE	NO. OF FEET OF CORE	8" AUGER	NO. OF SHEETS	3
PROJECT	SPILLWAY	DATE	11 FEB 83	NO. OF CORE BBL	6
CLIENT	USCE	FAILING	1500		
WELL NO.	BA6C-603	TOTAL NO. OF CORE BBL	4	NO. STORED	19
DRILLER	BREWER	TOTAL NUMBER CORE BITES	19		
DIRECTION OF HOLE	0	DATE HOLE STARTED	11 FEB 83	DATE HOLE COMPLETED	15 FEB 83
VERTICAL CORRECTION	108.5'	ELEVATION TOP OF HOLE	538.0		
DEPTH OF HOLE	108.5'				

Alan Man

ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	REMARKS
0.0	2.2	A	SANDSTONE, SOFT, FLAGGY, FINE-MED GRN, BROWN GRAY	DRILLING
2.2	4.5	B	SHALE, SOFT, SLT WEATH, VERY SANDY, NON-CALC, DARK GRAY, SCAT FINE SHELL FRAGMENTS	8" AUGER
4.5	8.9	C	SHALE, UNWEATH, SOFT, MOIST, DARK GRAY w/ THIN LT GRAY SANDY SEAMS, LIGNITIC	6" CORE BBL
8.9	12.9	D	SANDSTONE, SOFT, FINE TO MED GRAINED, WEAKLY TO MOD CEMENTED, NON-CALC, MASSIVE, GRAY	SAMPLES
12.9	45.6	1	SHALE, MOD SOFT, UNWEATH, DARK GRAY TO GRAY, NON-CALC, LIGNITIC TO 18" NUM THIN SAND LENSES, SCATTERED THROUGHOUT	JAR A 0.0-0.3 B 0.3-2.2 C 2.2-4.5 D 4.5-6.0
16.1	17.2	2	SANDSTONE, MOD HARD, GRAY	CARTONS
19.7		3	UNHEALED FRACTURE 45° C	1 6.0 - 6.9 2 11.5 - 12.4 3 17.5 - 18.4 4 22.1 - 23.0 5 24.5 - 30.4 6 37.5 - 38.4 7 41.9 - 42.8 8 46.7 - 47.6 9 51.0 - 51.9 10 56.5 - 57.4 11 61.5 - 64.4 12 68.1 - 69.0 13 72.8 - 74.7 14 79.0 - 79.9 15 84.2 - 85.1 16 92.0 - 92.9 17 98.8 - 99.2 18 103.6 - 104.5 19 105.2 - 106.1
20.1	20.3	4	SILTSTONE, HARD	
23.8	23.9	5	" " " " " "	
31.8	32.0	6	" " " " " "	
25.0	25.8	5	CALCAREOUS ZONE, HARD, LT GRAY	

HOLE WAS E-LOGGED

WATER

BORING LEFT OPEN FOR FUTURE WL OBSERVATION 22 FEB 83 WL 3.3 FT BELOW SURFACE BAIL-DOWN/RECOVERY TEST PERFORMED 23 FEB 83

INSTALLATION		SHEET 2 OF 3 SHEETS
1. NO. AND TYPE OF BPT		
2. BPTON FOR E. POSITION 1-394, 704, 414		
3. MANUFACTURER'S DESIGNATION OF CASE		
4. TOTAL NUMBER OF BPT'S		
5. ELEVATION OF BPT CENTER		
6. DATE HOLE		
7. ELEVATION OF TOP OF HOLE		
8. TOTAL CHARGE OF BPT'S		
9. SIGNATURE OF OPERATOR		
MATERIALS		REMARKS
1. NAME	2. SIZE	3. QUANTITY
Box	7	
1.3'	7	
Box	8	
1.00	8	
Box	9	
6-1'	9	
Box	10	
58.0	10	
Box	11	
1.00	11	
Box	12	
62.0	12	
Box	13	
1.00	13	
Box	14	
6-5'	14	

DRILLING LOG		SHEET 3 OF 3 SHEETS
1. PROJECT		
2. LOCATION		
3. DRILLING AGENCY		
4. HOLE NO. AND NUMBER OF CASES AND ITS NUMBER		
5. NAME OF DRILLER		
6. DIRECTION OF HOLE		
7. THICKNESS OF OVERBURDEN		
8. DEPTH OF HOLE IN FEET		
9. TOTAL DEPTH OF HOLE		
ELEVATION DEPTH (FEET)		DESCRIPTION
80		B2 DRIFT SHALE, SANDY CLAY, GRAY, CRAY
85		
90		6-5' to 9-9' SANDY, VERY SANDY, TO HARD, DARK GRAY, LENT. SANDY, A DEPTH GRADPS INTO PURE SHALE AT 93'
93		93' to 96' SANDSTONE, M. TO HARD, VERY FINE GRAINED, W/ CEMENTED, GRAY
96		96' to 100' SANDY, M. TO SANDY, LAMINATED, DARK GRAY
100		100' to 106' SANDSTONE, SPOTTED, M. TO HARD, VERY FINE GRAINED, WELL CEMENTED, GRAY
108		108' TO D

FOR LOCATION OF BORING SEE

APPROVED BY	DATE
A. MARR	
REVISION	
A. MARR	
APPROVED BY	DATE
M. GREEN	
REVISION	
MEL GREEN	

F

E

D

C

B

A

DRILLING LOG		Division	INSTALLATION	SHEET	
PROJECT		SOUTHWESTERN	FORT WORTH	1 OF 4 SHEETS	
LOCATION		GRAPEVINE DAM			
DRILLING AGENCY		USCE			
NAME OF DRILLER		WYATT			
DATE		12/22/83			
THICKNESS OF OVERBURDEN		4.0			
DEPTH DRILLED INTO ROCK		96.6			
TOTAL DEPTH OF HOLE		100.6			
CLASSIFICATION OF MATERIALS		CORRECTION			
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	DEPTH (ft)	REMARKS
0.0	0.0		CLAY, MEDIUM PLASTICITY, STIFF, MOIST, SANDY, TAN	4.0	1 IMMEDIATELY AFTER RAINING WATER LEVEL TAPED AT -85.0 FT
	2.0		CLAY, MEDIUM TO HIGH PLASTICITY, STIFF, MOIST, SANDY, GRAY.	3.0	- 72 HOURS LATER WATER LEVEL TAPED AT -24.70 FT
	3.0		CLAY, LOW TO MEDIUM PLASTICITY, STIFF, MOIST, TAN TO GRAY.	1.0	2 TAPS A: 60-70 B: 20-30 C: 30-40
	4.0		SANDSTONE, DARK GRAY, VERY FINE GRAINED, COMPACT, MASSIVE, THINLY BEDDED, UNJOINTED, UNFRACTURED, SLIGHTLY WEATHERED TO UNWEATHERED, SOFT.	1.0	3 CARTONS NO CARTON SAMPLES (CORE WAVED TO DEPTH)
	10.0		SHALE, BROWN VERY FINE GRAINED, LAMINATED TO THINLY BEDDED, VERY LIGNITIC FROM 8.0'-12.4', AND FROM 16.2'-16.8' FISSILE, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	1.0	4 DRILLING 0.0-40.0 8" AUGER 40-100.6 4" CORE
	20.0		SANDSTONE, LIGHT GRAY, VERY FINE GRAINED, COMPACT, THINLY BEDDED WITH SHALE STRIBERS DISSEMINATED THROUGHOUT, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	1.0	
	30.0		SHALE, BROWN VERY FINE GRAINED, LAMINATED TO THINLY BEDDED, VERY LIGNITIC FROM 8.0'-12.4', AND FROM 16.2'-16.8' FISSILE, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	1.0	
	40.0		SANDSTONE, DARK GRAY, VERY FINE GRAINED, COMPACT, MASSIVE, THINLY BEDDED, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	1.0	

DRILLING LOG		Division	INSTALLATION	SHEET	
PROJECT		SOUTHWESTERN	FORT WORTH	2 OF 4 SHEETS	
LOCATION		GRAPEVINE DAM			
DRILLING AGENCY		USCE			
NAME OF DRILLER		WYATT			
DATE		12/22/83			
THICKNESS OF OVERBURDEN		4.0			
DEPTH DRILLED INTO ROCK		96.6			
TOTAL DEPTH OF HOLE		100.6			
CLASSIFICATION OF MATERIALS		CORRECTION			
ELEVATION	DEPTH	LEGEND	CLASSIFICATION OF MATERIALS (Description)	DEPTH (ft)	REMARKS
40.0	40.0		SHALE, BROWN VERY FINE GRAINED, LAMINATED TO THINLY BEDDED, VERY LIGNITIC FROM 8.0'-12.4', AND FROM 16.2'-16.8' FISSILE, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	42.0	
	50.0		SANDSTONE, TAN, FINE GRAINED, MASSIVE, WELL INDURATED, UNJOINTED, UNFRACTURED, UNWEATHERED, HARD.	52.0	
	60.0		SHALE, BROWN VERY FINE GRAINED, LAMINATED TO THINLY BEDDED, FISSILE, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	62.0	
	70.0		SANDSTONE, DARK GRAY, FINE GRAINED, COMPACT, MASSIVE, THINLY BEDDED WITH FLUVIAL CROSS BEDDING UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	72.0	
	80.0		SANDSTONE, LIGHT GRAY, FINE GRAINED, MASSIVE, WELL INDURATED, UNJOINTED, UNFRACTURED, UNWEATHERED, HARD.	82.0	
	90.0		SHALE, BROWN VERY FINE GRAINED, LAMINATED TO THINLY BEDDED, VERY LIGNITIC FROM 8.0'-12.4', AND FROM 16.2'-16.8' FISSILE, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	92.0	
	100.0		SANDSTONE, LIGHT GRAY, VERY FINE GRAINED, COMPACT, THINLY BEDDED WITH SHALE STRIBERS DISSEMINATED THROUGHOUT, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT.	102.0	

Well No. BANC 606

W-11 No. BANC 606

SHEET 2 OF 4 SHEETS

DATE 4/29/83

92.4%

REMARKS

W-11 No. BANC 606

DRILLING LOG	SOUTHWESTERN	INSTALLATION	FORT WORTH
PROJECT	GRAPEVINE DAM	DATE	4/29/83
LOCATION	SPILLWAY REPAIR	DEPTH	100.6
DRILLING AGENCY	USCE	DRILLER	R. R. Hudette
WELL NO.	BANC 606	DATE	4/29/83
WELL NAME	WYATT	DEPTH	97.4%
THICKNESS OF OVERBURDEN	4.0		
DEPTH OF LINED INTO ACC	94.4		
TOTAL DEPTH OF HOLE	100.6		

ELEVATION	DEPTH	LEGEND	CLASSIFICATION	PERCENT	REMARKS
80.0	30.0 TO 61.3	SHALE BROWN VERY FINE GRAINED, LAMINATED TO THINLY BEDDED, FISSILE UNJOINTED, VISIBLE SLICKEN-SIDE (S.S.) UNFRACTURED, UNWEATHERED WITH FABRIC PRESERVED THROUGHOUT, WELL INDURATED SANDSTONE SEAM (S.S.) SOFT	22.2	19	
90.0	61.7 TO 62.2	SANDSTONE LIGHT GRAY VERY FINE GRAINED COMPACT THINLY BEDDED WITH SHALE STRINGERS THROUGHOUT, UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT TO MODERATELY HARD IN SECTION	9.8	21	
100.0	62.3 TO 69.6	SANDSTONE DARK GRAY, FINE GRAINED TO MEDIUM GRAINED, COMPACT, THINLY BEDDED, UNWEATHERED, UNJOINTED, UNFRACTURED, SOFT	10.2	22	
110.0	69.6 TO 74.2	SHALE DARK GRAY, VERY FINE GRAINED, LAMINATED TO THINLY BEDDED SANDY FISSILE, UNWEATHERED, UNJOINTED, UNFRACTURED, SOFT	10.2		

DRILLING LOG	SOUTHWESTERN	INSTALLATION	FORT WORTH
PROJECT	GRAPEVINE DAM	DATE	4/29/83
LOCATION	SPILLWAY REPAIR	DEPTH	100.6
DRILLING AGENCY	USCE	DRILLER	R. R. Hudette
WELL NO.	BANC 606	DATE	4/29/83
WELL NAME	WYATT	DEPTH	97.4%
THICKNESS OF OVERBURDEN	4.0		
DEPTH OF LINED INTO ACC	96.6		
TOTAL DEPTH OF HOLE	100.6		

ELEVATION	DEPTH	LEGEND	CLASSIFICATION	PERCENT	REMARKS
120.0	74.2 TO 84.2	SANDSTONE, GRAY VERY FINE GRAINED, COMPACT, THINLY BEDDED, UNFRACTURED THROUGHOUT, UNJOINTED, ARELLACEOUS WITH PROMINENT SHALE SLAMS TO 4 TO 6', 12' TO 18' TO 22' SOFT TO MODERATELY HARD			
130.0	84.2 TO 100.6 (100)	SHALE BROWN, VERY FINE GRAINED, LAMINATED TO THINLY BEDDED, FISSILE UNJOINTED, UNFRACTURED, UNWEATHERED, SOFT			

STRUCTURAL FEATURES

THE SHALE, SANDSTONE CONTACTS APPEAR TO BE RELATIVELY HORIZONTAL BEDDING PLANES IN BOTH THE SHALE AND SANDSTONE HORIZONS APPEAR TO BE FLAT WITH SOME FLUVIAL CROSS BEDDING WITHIN THE SANDSTONES THE ENTIRE SEQUENCE IS UNJOINTED

100.6'

FOR LOCATION OF BORING SEE PLATE 4

2

DESIGNED BY: A. MARR

DRAWN BY: A. MARR

CHECKED BY: M. GREEN

INVESTIGATOR: MEL GREEN

DATE: 4/29/83

PROJECT: GRAP DENON CREEK, E.M. MODIF EMEANKMEN LOG OF B...

F


E

D

C

B

844C-606
 4/29/83
 97.4%



DESIGNED BY A. MARR		DRAWN BY A. MARR		CHECKED BY M. GREEN		APPROVED BY MEL GREEN	
GRAPEVINE LAKE DENISON CREEK, ELM FORK, TRINITY RIVER, TEXAS				US ARMY ENGINEERING CENTER CORPS OF ENGINEERS FORT WORTH, TEXAS			
MODIFICATION OF EMBANKMENT AND SPILLWAY				LOG OF BORING 844C-606			
INVESTIGATION NO. DACW83-83-B-0052		DATE AUG 1983		CONTRACT NO. DACW83-83-C-0180		SHEET NO. 20	

LOCATION OF BORING SEE PLATE 4

DACW83-83-C-0180

F



E

D

C

B

A



Well No. **BAWC-607**

SHEET 2 OF 2 SHEETS
 PROJECT: **GRAPES VINE**
 LOCATION: **FALLING 1500**
 DRILLING AGENCY: **USCC**
 WELL NO.: **BAWC-607**
 DATE: **4/21/83** to **4/25/83**
 DRILLER: **R.R. Audette**

DEPTH (ft)	ROCK	BIT	REMARKS
49.6			
50.0			
52.0	1		
54.5			
58.8	2		
63.2			
69.9	3		
71.0			
74.9	4		
76.4			
80.4	5		
82.7			
84.0	6		
86.0			
88.2	7		
90.0			
92.9			

Well No. **BAWC-607**

DRILLING LOG
 PROJECT: **GRAPES VINE**
 LOCATION: **FALLING 1500**
 DRILLING AGENCY: **USCC**
 WELL NO.: **BAWC-607**
 DATE: **4/21/83** to **4/25/83**
 DRILLER: **R.R. Audette**

SANDSTONE LIGHT GRAY
 GRAY VERY FINE GRAINED
 WEAKLY BEDDED
 UNWEATHERED, UNSTRATIFIED
 SOFT

STRUCTURAL FEATURES
 SHALLOO DIPPING
 ALTERNATE SUB-HORIZONTAL
 BEDDING PLANES WITHIN
 THE SHALE AND SANDSTONE
 HORIZONS ARE NOT
 FULLY DEVELOPED
 WITHIN THE SANDSTONE
 THE ENTIRE SEQUENCE IS
 UNWEATHERED AND UNSTRATIFIED

84.9
 100.0
 110.0
 120.0

FOR LOCATION OF BORING SEE

A MARR GRAPH
 A MARR MODEL
 M. GREEN LOG OF B
 MEL GREEN

2

F

E

D

C

B

No. BAHC-607
 RT. WORTH
 TAILING 1500
 4/21/93 4/25/93
 P. R. Hudette

FOR LOCATION OF BORING SEE PLATE 4

GRAPEVINE LAKE DENTON CREEK, ELM FORK, TRINITY RIVER, TEXAS MODIFICATION OF EMBANKMENT AND SPILLWAY		3
LOG OF BORING 8A4C-607		
A MARR		
A MARR		
M. GREEN		
MEL GREEN		

DACW83-83-0052 AUG 1983
 DACW83-83-0160

PLATE 21

ND
- 87