

AD-A275 783




2

ARMY RESEARCH LABORATORY



# Relationship Between Plasma Energy and Gas Generation in an Electrothermal-Chemical Gun

P. Tran  
G. Wren  
S. Richardson



ARL-TR-327

January 1994

**S** DTIC  
ELECTE  
FEB 22, 1994  
**A**

DTIC QUALITY INSPECTED 2

3300 94-05615



APPROVED FOR PUBLIC RELEASE; DISTRIBUTION IS UNLIMITED.

3 4 2 18 205

## NOTICES

Destroy this report when it is no longer needed. DO NOT return it to the originator.

Additional copies of this report may be obtained from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Road, Springfield, VA 22161.

The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

The use of trade names or manufacturers' names in this report does not constitute indorsement of any commercial product.

# REPORT DOCUMENTATION PAGE

*Form Approved*  
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1. AGENCY USE ONLY (Leave blank)	2. REPORT DATE <p style="text-align: center;">January 1994</p>	3. REPORT TYPE AND DATES COVERED <p style="text-align: center;">Final, Jan 92 - Sep 92</p>	
4. TITLE AND SUBTITLE <p>Relationship Between Plasma Energy and Gas Generation in an Electrothermal-Chemical Gun</p>		5. FUNDING NUMBERS <p style="text-align: center;">WC: 4G031-315-R3-0003</p>	
6. AUTHOR(S) <p>P. Tran, G. Wren, and S. Richardson</p>			
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) <p>U.S. Army Research Laboratory ATTN: AMSRL-WT-PA Aberdeen Proving Ground, MD 21005-5066</p>		8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES) <p>U.S. Army Research Laboratory ATTN: AMSRL-OP-CI-B (Tech Lib) Aberdeen Proving Ground, MD 21005-5066</p>		10. SPONSORING / MONITORING AGENCY REPORT NUMBER <p style="text-align: center;">ARL-TR-327</p>	
11. SUPPLEMENTARY NOTES			
12a. DISTRIBUTION / AVAILABILITY STATEMENT <p>Approved for public release; distribution is unlimited.</p>		12b. DISTRIBUTION CODE	
13. ABSTRACT ( <i>Maximum 200 words</i> )  <p>A scheduled relationship between plasma energy (electrical energy) and the gas generation (decomposition) of the propellant in the combustion chamber of an electrothermal-chemical (ETC) gun is one of the key factors in controlling the ETC interior ballistic cycle. This relationship is investigated by using an inverse analysis model, which computes the gas generation of the propellant to analyze ETC experimental data. A heat loss function is included in the model for this investigation since heat loss is a significant factor in small-caliber guns.</p>			
14. SUBJECT TERMS <p>electrothermal-chemical gun, gas generation, propellant consumed, plasma energy, propellants, guns</p>		15. NUMBER OF PAGES <p style="text-align: center;">28</p>	16. PRICE CODE
17. SECURITY CLASSIFICATION OF REPORT <p style="text-align: center;">UNCLASSIFIED</p>	18. SECURITY CLASSIFICATION OF THIS PAGE <p style="text-align: center;">UNCLASSIFIED</p>	19. SECURITY CLASSIFICATION OF ABSTRACT <p style="text-align: center;">UNCLASSIFIED</p>	20. LIMITATION OF ABSTRACT <p style="text-align: center;">SAR</p>

INTENTIONALLY LEFT BLANK.

## ACKNOWLEDGMENTS

The authors would like to thank Major Kevin Nekula, Dr. Kevin White, and Mr. Todd Rosenberger of the U.S. Army Research Laboratory (ARL) for their helpful suggestions and advice; Dr. Eli Freedman (Eli Freedman and Associates) for supplying the BLAKE code and thermochemical properties; and especially Mr. Jahn Dyvik (FMC Corp.) for providing the experimental data and assistance. In addition, the authors would like to thank the reviewers of this manuscript, Dr. John Powell and Dr. Terence Coffee, for their comments.

Accession For	
NTIS CRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution /	
Availability Codes	
Dist	Avail and/or Special
A-1	

INTENTIONALLY LEFT BLANK.

## TABLE OF CONTENTS

	<u>Page</u>
ACKNOWLEDGMENTS .....	iii
LIST OF FIGURES .....	vii
LIST OF TABLES .....	vii
1. INTRODUCTION .....	1
2. EXPERIMENTAL FIXTURE .....	2
3. NUMERICAL ANALYSIS .....	3
4. RESULTS AND DISCUSSION .....	6
5. CONCLUSIONS .....	16
6. REFERENCES .....	17
DISTRIBUTION LIST .....	19

INTENTIONALLY LEFT BLANK.

## LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
1. An electrothermal-chemical (ETC) gun . . . . .	1
2. Schematic of combustion chamber . . . . .	3
3. Group 1 (shots 7 and 8) - Propellant consumed vs. plasma energy . . . . .	8
4. Group 2 (shots 9–11) - Propellant consumed vs. plasma energy . . . . .	8
5. Group 3 (shots 12 and 13) - Propellant consumed vs. plasma energy . . . . .	9
6. Group 4 (shots 15 and 16) - Propellant consumed vs. plasma energy . . . . .	9
7. Group 5 (shots 17 and 18) - Propellant consumed vs. plasma energy . . . . .	10
8. Group 6 (shots 23–25) - Propellant consumed vs. plasma energy . . . . .	10
9. Group 7 (shots 27 and 28) - Propellant consumed vs. plasma energy . . . . .	11
10. Group 8 (shots 30–32) - Propellant consumed vs. plasma energy . . . . .	11
11. Group 9 (shots 36, 37, and 46–48) - Propellant consumed vs. plasma energy . . . . .	12
12. Group 10 (shots 38 and 40) - Propellant consumed vs. plasma energy . . . . .	12
13. Group 11 (shots 39 and 41) - Propellant consumed vs. plasma energy. . . . .	13
14. Group 12 (shots 43–44) - Propellant consumed vs. plasma energy. . . . .	13
15. Group 13 (shots 195–208) - Propellant consumed vs. plasma energy . . . . .	14
16. Group 13 (shots 195–208) - Plasma energy and propellant consumed vs. time . . . . .	14

## LIST OF TABLES

<u>Table</u>	<u>Page</u>
1. Gun Parameters . . . . .	3
2. Shot Configuration . . . . .	7

INTENTIONALLY LEFT BLANK.

## 1. INTRODUCTION

The electrothermal-chemical (ETC) gun utilizes electrical energy to create a low-mass, high-energy plasma which initiates and (hopefully) controls the vaporization and combustion of the propellant in the combustion chamber. Although the total effect of electrical energy input on the rate of propellant vaporization in the ETC gun is unknown, it is assumed that the gas generation can be controlled by tailoring the delivery of electrical energy to the combustion chamber. Control of the gas generation is required in order to obtain the desired chamber pressure profile to achieve optimal gun performance.

Figure 1 shows the five major components in an ETC gun: (1) the power supply (prime power and intermediate storage batteries); (2) the pulse forming network; (3) the plasma cartridge (capillary); (4) the combustion chamber; and (5) the barrel and projectile. The plasma cartridge (Figure 1) is a tube, usually polyethylene, containing a fuse wire. When high voltage is supplied to the plasma cartridge, the resulting current vaporizes the fuse inside the capillary. Since temperatures of many thousands of degrees are reached in the capillary, the radiation heat flux from the plasma ablates additional material from the capillary wall. The plasma flows into the combustion chamber and ignites the propellant, which generates gas and accelerates the projectile down bore.




Figure 1. An electrothermal-chemical (ETC) gun.

To demonstrate repeatability, control, and predictability of the ETC concept in small-caliber guns, the FMC Corporation under the Electrical Enhancement Factor (EEF) follow-on contract performed a series of firings using 30-mm, subscale experiments for both tank and artillery systems. Many propellants and designs were investigated. However, the propellant considered in this report is a mixture of hydroxylammonium nitrate (HAN) and other components. Additional components were added to increase the viscosity and to maintain uniform performance characteristics throughout the propellant bed. Electrical energy input, loading density, and the specific geometry of the capillary and the propellant chamber were also varied.

A study to determine the relation between the plasma energy input and the gas generation during the plasma injection phase is undertaken using FMC experimental data. The purpose of this study is to obtain the gas generation information for an interior ballistic model of the ETC process and to investigate the control of the pressure-time profile through the delivery of electrical energy.

The relationship between plasma energy (electrical energy) and gas generation (decomposition) of a propellant in an ETC gun is investigated by using an inverse analysis model (Wren and Oberle 1992). The model computes the gas generation of the propellant by incorporating experimental measurements of pressure, projectile travel, and electrical energy, along with the initial charge mass and projectile mass, a table of calculated thermochemical properties (impetus, ratio of specific heat, covolume, and temperature) relative to electrical energy density, and the effect of air in the combustion chamber (since ETC firings can have large initial ullage).

The inverse analysis model uses experimental data of pressure, electrical energy, and projectile travel to calculate a propellant mass consumed at each independent timestep based on energy conservation, whereas a conventional interior ballistic model (such as IBHVG2) uses known burning rates, gun parameters, and propellant characteristics to provide the maximum pressure and muzzle velocity.

## 2. EXPERIMENTAL FIXTURE

A description of the experimental gun parameters is shown in Table 1.

Table 1. Gun Parameters

Gun Fixture:	30 mm, artillery
Travel:	51 calibers
Projectile Mass:	339 g
Chamber Volume:	166 cm <sup>3</sup>
Electrical Energy Input:	30-150 kJ
Propellant:	Two types, both including HAN

The propellant is distributed in the chamber in up to four unit modules, and an ullage tube is used at the center of the propellant chamber to distribute plasma uniformly through the charge. Figure 2 shows a schematic of the combustion chamber for the ETC gun described in Table 1.




Figure 2. Schematic of combustion chamber.

### 3. NUMERICAL ANALYSIS

To investigate the relation between the electrical energy input and the consumed mass of the propellant, an inverse analysis is applied. The inverse analysis computes the decomposition of propellant based on the energy balance equation at the given time:

$$Q = U + W + \text{LOSSES} , \quad (1)$$

where  $Q$  is the total energy available (chemical and electrical),  $U$  is the internal energy of the gas, and  $W$  is the work performed by the gas. Experimentally measured pressure, plasma energy, projectile travel, and the calculated thermochemical properties (Freedman 1982) of the propellant serve as the input parameters used to calculate the energy balance between projectile kinetic energy, gas kinetic energy, internal energy, and heat loss. Lagrange assumptions are used to calculate the pressure gradient. The calculated thermochemistry is assumed to be variable with the electrical energy density, which is the ratio of input plasma energy to consumed propellant mass. The governing equations have been described elsewhere (Wren and Oberle 1992), and only modifications will be discussed in this report.

Initially, the inverse analysis of the experimental data without the heat loss function showed a discrepancy (about 10–15%) in the mass of the propellant consumed at muzzle exit compared to experiment. Since some energy is lost to the barrel and the plasma channel during the combustion process, a calculation for heat loss was added to the inverse code. The energy lost due to heat transfer to the walls is given by a standard heat loss equation (Robbins and Raab 1988):

$$E_h = \int_0^t A_w h (T - T_w) dt, \quad (2)$$

where  $A_w$  is the area of the wall exposed to the propellant gas,  $h$  is the heat transfer coefficient,  $T$  is mean gas temperature, and  $T_w$  is the wall temperature. The (heat transfer coefficient)  $h$  is given by

$$h = \lambda \bar{c}_p \bar{\rho} \bar{v} + h_0, \quad (3)$$

where  $\lambda$ ,  $\bar{c}_p$ ,  $\bar{\rho}$ , and  $\bar{v}$  are the Nordheim heat transfer coefficient, specific heat at constant pressure of propellant gas, mean gas density, and mean gas velocity, respectively, and  $h_0$  is the free convective heat transfer coefficient. The parameter  $\lambda$  is given by

$$\lambda = \left[ 13.2 + 4 \log_{10} (100D) \right]^{-2}, \quad (4)$$

where  $D$  is diameter of the bore and the wall temperature is

$$T_w = \frac{E_h + fE_{br}}{c_{pw} \rho_w A_w D_w} + T_0, \quad (5)$$

where  $C_{pw}$ ,  $\rho_w$ ,  $D_w$  are heat capacity, density of the wall material, and the heat-penetrated thickness of the wall (Robbins 1988), respectively.  $E_{br}$  is the energy loss for work against bore resistance,  $f$  is friction coefficient, and  $T_0$  is the initial temperature of the wall. For this inverse analysis,  $E_{br}$  is assumed to be zero since the tube is smooth bore, and the parameters for the properties of steel (Robbins 1992) are used for the wall material. All input parameters are held fixed in the calculations which follow.

Projectile motion is calculated from radar data. A program was developed to determine the times corresponding to the maximum amplitudes of sine waves. The wavelength of the radar signal inside the gun tube is calculated by

$$\frac{1}{\lambda_g^2} = \frac{1}{\lambda_0^2} - \frac{1}{\lambda_c^2}, \quad (6)$$

where  $\lambda_g$  is the wavelength in the gun tube,  $\lambda_0$  is free-space wavelength, and  $\lambda_c$  is cut-off wavelength. (Vest et al. 1955).

Restating equation (6), we have

$$\lambda_g = \left[ \left( \frac{1}{\lambda_0} \right)^2 - \left( \frac{1}{\lambda_c} \right)^2 \right]^{-\frac{1}{2}}. \quad (7)$$

The cut-off frequency  $f_c$  is

$$f_c = \frac{1.84C}{\pi D}, \quad (8)$$

where  $C$  is the speed of light and  $D$  is the diameter of the gun tube (Evans 1985; Ware and Reed 1958). Because the wavelength is equal to the speed of light divided by the frequency, substituting equation (8) into equation (7) gives

$$\lambda_g = \left[ \left( \frac{f_0}{C} \right)^2 - \left( \frac{1.84}{\pi D} \right)^2 \right]^{-\frac{1}{2}} \quad (9)$$

With the interferometer frequency of 10.525 GHz, the wavelength inside the barrel is 3.4272 cm.

The projectile position at time  $t$  will be:

$$x(t) = \sum_{i=1}^t \frac{\lambda_g}{2 (T_i - T_{i-1})} \delta t + x_0, \quad (10)$$

where  $(T_i - T_{i-1})$  is the travel time for each half wavelength and  $x_0$  is the position of the projectile at starting point.

The calculated times for projectile exit are in agreement with the results obtained from the radar signals and the measured pressure profiles at the muzzle exit. These data are also verified by calculating the velocity of the projectile using a second-order polynomial spline fit method. The percent differences of these velocity computations range from 1–4% compared to the results obtained from the Weibel program (commercial software to calculate velocity from the radar trace). Since the experimental design includes a ullage tube attached to the plasma capillary, there is an initial time delay before the ullage tube ruptures and pressure is generated in the combustion chamber. Observation of the current and voltage histories of the plasma compared to the pressure-time history in the combustion chamber show a time delay of approximately 0.5 ms. Thus, the calculation begins when the pressure gage begins to record.

#### 4. RESULTS AND DISCUSSIONS

The results of the mass consumed versus plasma energy input are divided into 13 groups according to the configurations of the firings as listed in Table 2. The group identification includes the group

number and shot numbers for that group. The ullage dimensions are the inner diameter and wall thickness of the ullage tube, respectively (see Section 2). The capillary dimensions are the inner diameter and length of the polyethylene liner in the plasma capillary.

Table 2. Shot Configuration

Group No. (Shot No.)	Charge Loaded	Ullage Structure	Ullage Dim. ID/t <sup>a</sup>	Cap. Dim. ID/L <sup>b</sup>
1 (Shots 07-08)	Full charge, 1 module	with RTV plug	0.974/0.022	0.25/5.16
2 (Shots 09-11)	Full charge, 1 module	with RTV plug	0.528/0.042	0.25/5.16
3 (Shots 12-13)	Full charge, 1 module	with RTV plug	0.374/0.032	0.188/5.16
4 (Shots 15-16)	Full charge, 1 module	with RTV plug	0.401/0.032	0.188/5.16
5 (Shots 17-18)	Full charge, 1 module	with RTV plug	0.323/0.042	0.188/5.16
6 (Shots 23-25)	Full charge, 4 module	without RTV plug	0.401/0.022	0.25/5.16
7 (Shots 27-28)	Full charge, 4 module	without RTV plug	0.354/0.042	0.25/5.16
8 (Shots 30-32)	Full charge, 4 module	without RTV plug	0.374/0.032	0.25/5.16
9 (Shots 36-37, 46-48)	Full charge, 4 module	with RTV plug	0.374/0.032	0.25/5.16
10 (Shots 38,40)	3/4 charge, empty in rear	with RTV plug	0.374/0.032	0.25/5.16
11 (Shots 39,41)	3/4 charge, empty in front	with RTV plug	0.374/0.032	0.25/5.16
12 (Shots 43-44)	1/2 charge, empty in front	with RTV plug	0.374/0.032	0.25/5.16
13 (Shots 195-208)	Full charge	—	0.455/0.06	0.313/5.16

<sup>a</sup> ID = inner diameter and t = thickness; <sup>b</sup> L = length

Figures 3–15 show the calculated propellant mass consumed versus experimental plasma energy for each group, and Figure 16 shows the plasma energy and the propellant consumed as a function of time for group 13.




Figure 3. Group 1 (shots 7 and 8) - Propellant consumed vs. plasma energy.




Figure 4. Group 2 (shots 9–11) - Propellant consumed vs. plasma energy.




Figure 5. Group 3 (shots 12 and 13) - Propellant consumed vs. plasma energy.




Figure 6. Group 4 (shots 15 and 16) - Propellant consumed vs. plasma energy.




Figure 7. Group 5 (shots 17 and 18) - Propellant consumed vs. plasma energy.




Figure 8. Group 6 (shots 23-25) - Propellant consumed vs. plasma energy.




Figure 9. Group 7 (shots 27 and 28) - Propellant consumed vs. plasma energy.




Figure 10. Group 8 (shots 30-32) - Propellant consumed vs. plasma energy.




Figure 11. Group 9 (shots 36, 37, and 46-48) - Propellant consumed vs. plasma energy.




Figure 12. Group 10 (shots 38 and 40) - Propellant consumed vs. plasma energy.




Figure 13. Group 11 (shots 39 and 41) - Propellant consumed vs. plasma energy.




Figure 14. Group 12 (shots 43-44) - Propellant consumed vs. plasma energy.




Figure 15. Group 13 (shots 195-208) - Propellant consumed vs. plasma energy.




Figure 16 Group 13 (shots 195-208) - Plasma energy and propellant consumed vs. time.

The configuration for this series of firings was changed frequently, especially the centercore ullage of the combustion chamber (see Table 2). The following observations are made from the series of firings studied:

- The cases of partial propellant loads with ullage in the front of propellant chamber give a non-repeatable pressure profile and, as a result, the propellant consumed calculated from the inverse code is variable within a group (see Figures 13 and 14).

- In general, the decomposition rate of propellant in the combustion chamber seems to be a strong function of the centercore ullage configuration in both dimension and material. For the first 40 firings analyzed, no consistent relation between the gas generation and the electrical energy can be drawn. Even within the same group, the inferred mass consumed of the propellant in the combustion chamber was not repeatable with respect to the plasma energy. This suggests that the plasma energy only plays an important role in the ignition of the propellant. In the majority of the cases studied, the amount of propellant consumed at the time that the electrical energy reaches its maximum is approximately 50–60%.

However, utilizing a different design ullage tube and a different HAN-based propellant, firings 195–208 displayed more repeatable results (see Figures 15 and 16). The rate of propellant consumed is more linear in nature. Approximately 65% of the propellant is consumed at the time plasma energy is terminated. The rate of propellant consumption significantly decreases after the termination of plasma energy, suggesting that the plasma is a factor in the combustion process.

For this particular ullage design and propellant (firings 195–208), the average amount of propellant consumed and the plasma energy input during the early stage of the combustion process (to ~2.5 ms) are related by

$$y = 1.76734 - 0.164044x + 0.0116825x^2, \quad (11)$$

where  $y$  is mass of propellant consumed in grams and  $x$  is the plasma energy input in kJ. Plasma energy after this time is not considered to be a controlling factor in the amount of propellant consumed.

## 5. CONCLUSIONS

The relationship between the decomposition of the propellant and plasma energy was studied for a 30-mm ETC gun using two HAN-based propellants. The results from this study suggest that the propellant gas generation rate depends strongly on the design of the cartridge and the properties of the propellant rather than on the plasma energy input. However, the repeatability series (shots 195–208), show a potential for a relationship between the gas generation rate and plasma energy input for the particular gun configuration and propellant.

## 6. REFERENCES

EEF Follow-on Quarterly Review by FMC Corp.

Evans, J. W. "Measurement of Interior Ballistic Performance Using FM/FM Radio Telemetry Techniques." BRL-TR-2699, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, December 1985.

Freedman, E. "BLAKE - A Thermodynamics Code Based on TIGER." BRL-TR-02411, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, July 1982 and private communication.

Robbins, F. W. U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, private communication, 1992.

Robbins, F. W., and T. S. Raab. "A Lumped-Parameter Interior Ballistic Computer Code Using the TTCP Model." BRL-MR-3710, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, November 1988.

Vest, D., J. Andres, B. Grollman, and B. DeMare. "Ballistic Studies With a Microwave Interferometer Part I." BRL-TR-968, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, September 1955.

Ware, L. A. and H. R. Reed. Communication Circuits. New York: John Wiley and Sons, Inc., 3rd ed., 1958.

Wren, G. P., and W. F. Oberle. "An Inverse Analysis of Electrothermal-Chemical (ETC) Gun Experimental Data." BRL-TR-3391, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, MD, September 1992.

INTENTIONALLY LEFT BLANK.

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
2	Administrator Defense Technical Info Center ATTN: DTIC-DDA Cameron Station Alexandria, VA 22304-6145	1	Commander U.S. Army Missile Command ATTN: AMSMI-RD-CS-R (DOC) Redstone Arsenal, AL 35898-5010
1	Commander U.S. Army Materiel Command ATTN: AMCAM 5001 Eisenhower Ave. Alexandria, VA 22333-0001	1	Commander U.S. Army Tank-Automotive Command ATTN: AMSTA-JSK (Armor Eng. Br.) Warren, MI 48397-5000
1	Director U.S. Army Research Laboratory ATTN: AMSRL-OP-CI-AD, Tech Publishing 2800 Powder Mill Rd. Adelphi, MD 20783-1145	1	Director U.S. Army TRADOC Analysis Command ATTN: ATRC-WSR White Sands Missile Range, NM 88002-5502
1	Director U.S. Army Research Laboratory ATTN: AMSRL-OP-CI-AD, Records Management 2800 Powder Mill Rd. Adelphi, MD 20783-1145	(Class. only) 1	Commandant U.S. Army Infantry School ATTN: ATSH-CL (Security Mgr.) Fort Benning, GA 31905-5660
2	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-IMI-1 Picatinny Arsenal, NJ 07806-5000	(Unclass. only) 1	Commandant U.S. Army Infantry School ATTN: ATSH-WCB-O Fort Benning, GA 31905-5000
2	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-TDC Picatinny Arsenal, NJ 07806-5000	1	WL/MNOI Eglin AFB, FL 32542-5000  <u>Aberdeen Proving Ground</u>
1	Director Benet Weapons Laboratory U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-CCB-TL Watervliet, NY 12189-4050	2	Dir, USAMSAA ATTN: AMXSY-D AMXSY-MP, H. Cohen
1	Director U.S. Army Advanced Systems Research and Analysis Office (ATCOM) ATTN: AMSAT-R-NR, M/S 219-1 Ames Research Center Moffett Field, CA 94035-1000	1	Cdr, USATECOM ATTN: AMSTE-TC
		1	Dir, USAERDEC ATTN: SCBRD-RT
		1	Cdr, USACBDCOM ATTN: AMSCB-CII
		1	Dir, USARL ATTN: AMSRL-SL-I
		5	Dir, USARL ATTN: AMSRL-OP-CI-B (Tech Lib)

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	OSD/SDIO/IST ATTN: Dr. L. Caveny Pentagon Washington, DC 20301-7100	5	Director Benet Laboratories U.S. Army Watervliet Arsenal ATTN: SARWV-RD, L. Johnson G. Carafano R. Thierry R. Hasoenbein P. Votis Watervliet, NY 12189
1	Director U.S. Army BMD Advanced Technology Center P. O. Box 1500 Huntsville, AL 35807	3	Commander U.S. Army AMCCOM ATTN: AMSMC-IRC, G. Cowan SMCAR-ESM(R), W. Fortune R. Zastrow Rock Island, IL 61299-7300
1	Chairman DOD Explosives Safety Board Room 856-C Hoffman Bldg. 1 2461 Eisenhower Ave. Alexandria, VA 22331-0600	1	Commander, USACECOM R&D Technical Library ATTN: ASQNC-ELC-IS-L-R, Myer Center Fort Monmouth, NJ 07703-5301
1	Department of the Army Office of the Product Manager 155mm Howitzer, M109A6, Paladin ATTN: SFAE-AR-HIP-IP, Mr. R. De Kleine Picatinny Arsenal, NJ 07806-5000	1	Commandant U.S. Army Aviation School ATTN: Aviation Agency Fort Rucker, AL 36360
1	Commander Production Base Modernization Agency U.S. Army Armament Research, Development, and Engineering Center ATTN: AMSMC-PBM-E, L. Laibson Picatinny Arsenal, NJ 07806-5000	1	Director HQ, TRAC RPD ATTN: ATCD-MA, MAJ Williams Fort Monroe, VA 23651-5143
1	PEO-Armaments Project Manager Tank Main Armament Systems ATTN: AMCPM-TMA, K. Russell Picatinny Arsenal, NJ 07806-5000	1	Headquarters U.S. Army Materiel Command ATTN: AMCICP-AD, Michael F. Fisette 5001 Eisenhower Ave. Alexandria, VA 22333-0001
1	PEO-Armaments Project Manager Tank Main Armament Systems ATTN: AMCFM-TMA-105 Picatinny Arsenal, NJ 07806-5000	1	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-CCS Picatinny Arsenal, NJ 07806-5000
1	PEO-Armaments Project Manager Tank Main Armament Systems ATTN: AMCPM-TMA-120 Picatinny Arsenal, NJ 07806-5000		

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-CCH-T, L. Rosendorf Picatinny Arsenal, NJ 07806-5000	1	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-AES, S. Kaplowitz Picatinny Arsenal, NJ 07806-5000
1	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-CCH-V, E. Fennell Picatinny Arsenal, NJ 07806-5000	1	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-FSA-T, M. Salsbury Picatinny Arsenal, NJ 07806-5000
2	Commander U.S. Army Research Office ATTN: Technical Library D. Mann P.O. Box 12211 Research Triangle Park, NC 27709-2211	6	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-FSE, T. Gora B. Knutelsky K. C. Pan W. Davis C. Dunham A. Graf Picatinny Arsenal, NJ 07806-5000
1	Commander U.S. Army TRAC - Fort Lee Defense Logistics Studies Fort Lee, VA 23801-6140		
1	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-AE, J. Picard Picatinny Arsenal, NJ 07806-5000	6	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-EG, G. Ferdinand F. Naber-Libby R. Lundberg J. Niles R. Moreira W. Morelli Picatinny Arsenal, NJ 07806-5000
5	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-AEE-B, A. Beardell D. Downs S. Einstein A. Bracuti D. Chiu Picatinny Arsenal, NJ 07806-5000	1	Commander U.S. Army Belvoir R&D Center ATTN: STRBE-WC, Technical Library (Vault) Bldg. 315 Fort Belvoir, VA 22060-5606
1	Commander U.S. Army Armament Research, Development, and Engineering Center ATTN: SMCAR-AEE, J. Lannon Picatinny Arsenal, NJ 07806-5000	1	President U.S. Army Artillery Board Fort Sill, OK 73503

<u>No. of</u> <u>Copies</u>	<u>Organization</u>	<u>No. of</u> <u>Copies</u>	<u>Organization</u>
1	Commandant U.S. Army Command and General Staff College Fort Leavenworth, KS 66027-5200	1	Office of Naval Research ATTN: Code 473, R. S. Miller 800 N. Quincy St. Arlington, VA 22217
1	Commandant U.S. Army Special Warfare School ATTN: Rev and Tng Lit Div Fort Bragg, NC 28307	2	Commander Naval Sea Systems Command ATTN: SEA 62R SEA 64 Washington, DC 20362-5101
1	Commander Radford Army Ammunition Plant ATTN: SMCRA-QA/HI Library Radford, VA 24141	1	Commander Naval Air Systems Command ATTN: AIR-954-Technical Library Washington, DC 20360
1	Commandant U.S. Army Field Artillery School ATTN: STSF-TSM-CN Fort Sill, OK 73503-5600	1	Naval Research Laboratory Technical Library Washington, DC 20375
4	Deputy Commander Strategic Defense Command ATTN: SFAE-SD-HVL, S. Smith LTC Kee D. Lianos T. Aden P.O. Box 1500 Huntsville, AL 35887-8801	2	Commander Naval Surface Warfare Center ATTN: J. P. Consaga C. Gotzmer Silver Spring, MD 20902-5000
2	Commander U.S. Army Foreign Science and Technology Center ATTN: AMXST-MC-3, S. LeBeau C. Beiter 220 Seventh St., NE Charlottesville, VA 22901	2	Commander Naval Surface Warfare Center ATTN: K. Kim/Code R-13 R. Bernecker/Code R-13 Silver Spring, MD 20902-5000
1	Commandant U.S. Army Field Artillery Center and School ATTN: ATSF-CO-MW, B. Willis Fort Sill, OK 73503	1	Commander Naval Underwater Systems Center Energy Conversion Dept. ATTN: Technical Library Newport, RI 02840
1	Naval Sea System Command Department of the Navy ATTN: CSEA, CDR Dampier 06KR12 Washington, DC 20362-5101	6	Commander Naval Surface Warfare Center ATTN: Code G33, T. Doran J. Copley Code G30, Guns and Munitions Division Code G301, D. Wilson Code G32, Gun Systems Division Code E23, Technical Library Dahlgren, VA 22448-5000

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
1	Commander Naval Weapons Center ATTN: Code 388, C. F. Price Info Science Div China Lake, CA 93555-6001	2	Director Sandia National Laboratories Combustion Research Facility ATTN: R. Armstrong S. Vosen Division 8357 Livermore, CA 94551-0469
1	OLAC PL/TSTI. ATTN: D. Shiplett Edwards AFB, CA 93523-5000	1	University of Illinois Dept. of Mech./Indust. Engr. ATTN: Professor Herman Krier, 144 MEB 1206 N. Green St. Urbana, IL 61801
10	Central Intelligence Agency Office of Central Reference Dissemination Branch Room GE-47 HQS Washington, DC 20502	1	Johns Hopkins University/CPIA ATTN: T. Christian 10630 Little Patuxent Parkway, Suite 202 Columbia, MD 21044-3200
1	Central Intelligence Agency ATTN: Joseph E. Backofen NHB, Room 5N01 Washington, DC 20505	1	Pennsylvania State University Dept. of Mechanical Engr. ATTN: Dr. K. Kuo 312 Mechanical Engineering Bldg. University Park, PA 16802
5	Director Sandia National Laboratories ATTN: T. Hitchcock R. Woodfin D. Benson S. Kempka R. Beasley Advanced Projects Div 14 Organization 9123 Albuquerque, NM 87185	1	North Carolina State University ATTN: John G. Gilligan Box 7909 1110 Burlington Engineering Labs Raleigh, NC 27695-7909
2	Director Los Alamos National Laboratory ATTN: B. Kaswhia H. Davis Los Alamos, NM 87545	1	SRI International Propulsion Sciences Division ATTN: Technical Library 333 Ravenswood Ave. Menlo Park, CA 94025
1	Director Lawrence Livermore National Laboratories ATTN: M. S. L-355, A. Buckingham P.O. Box 808 Livermore, CA 94550	1	SPARTA ATTN: Dr. Michael Holland 9455 Towne Center Dr. San Diego, CA 92121-1964
		5	FMC Corporation ATTN: Mr. G. Johnson Mr. M. Seale Dr. A. Giovanetti Mr. J. Dyvik Dr. D. Cook 4800 East River Rd. Minneapolis, MN 55421-1498

<u>No. of Copies</u>	<u>Organization</u>	<u>No. of Copies</u>	<u>Organization</u>
3	GT Devices ATTN: Dr. S. Goldstein Dr. R. J. Greig Dr. N. Winsor 5705A General Washington Dr. Alexandria, VA 22312	2	Princeton Combustion Research Laboratories, Inc. ATTN: M. Summerfield N. Messina Princeton Corporate Plaza 11 Deerpark Drive Bldg. IV, Suite 119 Monmouth Junction, NJ 08852
3	General Dynamics Land Systems ATTN: Dr. B. VanDeusen Mr. F. Lunsford Dr. M. Weidner P.O. Box 2074 Warren, MI 48090-2074	2	Science Applications, Inc. ATTN: J. Batteh L. Thornhill 1519 Johnson Ferry Rd. Suite 300 Marietta, GA 30062-6438
2	Alliant Techsystems, Inc. ATTN: R. E. Tompkins J. Kennedy MN38-3300 10400 Yellow Circle Dr. Minnetonka, MN 55343	1	Eli Freedman & Associates ATTN: E. Freedman 2411 Diana Rd. Baltimore, MD 21209
2	Olin Ordnance ATTN: V. McDonald, Library Hugh McElroy P.O. Box 222 St. Marks, FL 32355	1	Veritay Technoigy, Inc. 4845 Millersport Hwy. P.O. Box 305 East Amherst, NY 14051-0305
1	Paul Gough Associates, Inc. ATTN: P. S. Gough 1048 South St. Portsmouth, NH 03801-5423	1	Battelle ATTN: TACTEC Library, J. N. Huggins 505 King Ave. Columbus, OH 43201-2693
1	Physics International Library ATTN: H. Wayne Wampler P.O. Box 5010 San Leandro, CA 94577-0599	2	California Institute of Technology Jet Propulsion Laboratory ATTN: L. D. Strand, MS 125-224 D. Elliot 4800 Oak Grove Dr. Pasadena, CA 91109
2	Rockwell International Rocketdyne Division ATTN: BA08, J. E. Flanagan J. Gray 6633 Canoga Ave. Canoga Park, CA 91304	1	General Electric Co. Defense Systems Division ATTN: Dr. J. Mandzy Mail Drop 43-220 100 Plastics Ave. Pittsfield, MA 01201
		2	SAIC ATTN: Mr. N. Sinha Dr. S. Dash 501 Office Center Drive Fort Washington, PA 19034-3211

No. of  
Copies   Organization

- 2   State University of New York at Buffalo  
Department of Electrical Engineering  
ATTN: Dr. W. J. Sargeant  
James Clark, Maxwell Professor  
Bonner Hall - Room 312  
Buffalo, NY 14260
- 1   Science Application International Corporation  
ATTN: Dr. George Chryssamellis  
8400 Normandale Blvd.  
Suite 939  
Minneapolis, MN 55437

Aberdeen Proving Ground

- 4   Cdr, USACSTA  
ATTN: S. Walton  
G. Rice  
D. Lacey  
C. Herud
- 24   Dir, USARL  
ATTN: AMSRL-WT-P, I. May  
AMSRL-WT-PA,  
T. Minor  
T. Coffee  
A. Juhaz  
K. White  
J. DeSpirito  
J. Knapton  
I. Stobie  
M. DelGuercio  
G. Wren  
S. Richardson  
W. Oberle  
G. Katulka  
AMSRL-WT-PE,  
A. Horst  
P. Tran (5 cps)  
K. Nekula  
F. Robbins  
AMSRL-WT-PC, B. Fifer  
AMSRL-WT-PD, B. Burns  
AMSRL-WT-WD, J. Powell

No. of  
Copies Organization

2 RARDE  
GS2 Division  
Building R31  
ATTN: Dr. C. Woodley  
Dr. G. Cook  
Fort Halstead  
Sevenoaks, Kent TN14 7BP  
ENGLAND

USER EVALUATION SHEET/CHANGE OF ADDRESS

This Laboratory undertakes a continuing effort to improve the quality of the reports it publishes. Your comments/answers to the items/questions below will aid us in our efforts.

1. ARL Report Number ARL-TR-327 Date of Report January 1994

2. Date Report Received \_\_\_\_\_

3. Does this report satisfy a need? (Comment on purpose, related project, or other area of interest for which the report will be used.) \_\_\_\_\_

4. Specifically, how is the report being used? (Information source, design data, procedure, source of ideas, etc.) \_\_\_\_\_

5. Has the information in this report led to any quantitative savings as far as man-hours or dollars saved, operating costs avoided, or efficiencies achieved, etc? If so, please elaborate. \_\_\_\_\_

6. General Comments. What do you think should be changed to improve future reports? (Indicate changes to organization, technical content, format, etc.) \_\_\_\_\_

CURRENT ADDRESS

\_\_\_\_\_  
Organization  
\_\_\_\_\_  
Name  
\_\_\_\_\_  
Street or P.O. Box No.  
\_\_\_\_\_  
City, State, Zip Code

7. If indicating a Change of Address or Address Correction, please provide the Current or Correct address above and the Old or Incorrect address below.

OLD ADDRESS

\_\_\_\_\_  
Organization  
\_\_\_\_\_  
Name  
\_\_\_\_\_  
Street or P.O. Box No.  
\_\_\_\_\_  
City, State, Zip Code

(Remove this sheet, fold as indicated, tape closed, and mail.)  
(DO NOT STAPLE)

DEPARTMENT OF THE ARMY



OFFICIAL BUSINESS

**BUSINESS REPLY MAIL**  
FIRST CLASS PERMIT No 0001, APG, MD

Postage will be paid by addressee.

NO POSTAGE  
NECESSARY  
IF MAILED  
IN THE  
UNITED STATES



Director  
U.S. Army Research Laboratory  
ATTN: AMSRL-OP-CI-B (Tech Lib)  
Aberdeen Proving Ground, MD 21005-5066