

# **Corrosion Potential Monitoring for Polymer Composite Wrapping and Galvanic CP System for Reinforced Concrete Marine Piles**

**David Bailey, Richard Lampo and Vince Hock**

U.S. Army Engineer Research and Development Center  
Construction Engineering Research Laboratory

# Report Documentation Page

*Form Approved  
OMB No. 0704-0188*

Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.

1. REPORT DATE <b>FEB 2010</b>	2. REPORT TYPE	3. DATES COVERED <b>00-00-2010 to 00-00-2010</b>			
4. TITLE AND SUBTITLE <b>Corrosion Potential Monitoring for Polymer Composite Wrapping and Galvanic CP System for Reinforced Concrete Marine Piles</b>		5a. CONTRACT NUMBER			
		5b. GRANT NUMBER			
		5c. PROGRAM ELEMENT NUMBER			
6. AUTHOR(S)		5d. PROJECT NUMBER			
		5e. TASK NUMBER			
		5f. WORK UNIT NUMBER			
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) <b>U.S. Army Engineer Research and Development Center, Construction Engineering Research Laboratory, 2902 Newmark Drive, Champaign, IL, 61822-1076</b>		8. PERFORMING ORGANIZATION REPORT NUMBER			
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)		10. SPONSOR/MONITOR'S ACRONYM(S)			
		11. SPONSOR/MONITOR'S REPORT NUMBER(S)			
12. DISTRIBUTION/AVAILABILITY STATEMENT <b>Approved for public release; distribution unlimited</b>					
13. SUPPLEMENTARY NOTES <b>2010 U.S. Army Corrosion Summit, Huntsville, AL, 9-11 Feb</b>					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT <b>Same as Report (SAR)</b>	18. NUMBER OF PAGES <b>31</b>	19a. NAME OF RESPONSIBLE PERSON
a. REPORT <b>unclassified</b>	b. ABSTRACT <b>unclassified</b>	c. THIS PAGE <b>unclassified</b>			

## **Project Sponsors**

# **DoD Corrosion Prevention and Control**

- Office of Under Secretary of Defense, Office of Corrosion Policy and Oversight
- Deputy Assistant Secretary of the Army Acquisition Policy and Logistics
- Assistant Chief of Staff for Installation Management
- Headquarters, U.S. Army Installation Management Command

# DoD Corrosion Problem



- Piers and wharves
  - Critical facilities
  - \$14.5M maintenance costs
  - Reinforced concrete piles
- Aged and deteriorated
  - Rebar corrosion
  - Spalling concrete

# Repair Options




- Patching
- Polymeric composite wraps
- Pre-fabricated composite shell with CP

# Objective

- Demonstrate and implement innovative technology that provides corrosion protection and impact resistance to reinforced concrete piles in marine environments
- FRP Composite wrap with galvanic CP protection

Demonstration Site

# Kawaihae Harbor Dolphin Piers





Demonstration Site

# Kawaihae Harbor Dolphin Piers



# Pre-Cast Steel Reinforced Concrete Piles




# Demonstration Metrics

- FRP composite pile wrapping
  - Field applied, commercially available
  - Underwater installation
  - Splash zone application (*2.4 meters*)
  - Impact and abrasion resistance
- Galvanic cathodic protection system
  - Integrated anode within wrapped section
- Corrosion potential monitoring

# System Design

- Expanded mesh zinc anode
- Composite board compression panels
- Woven glass fiber wrap


Nominal Thickness	0.685 mm
Tensile Strength	$32.8 \times 10^4$ kN/m <sup>2</sup>
Tensile Load, per ply	580 kg
Comp. Strength	$17.2 \times 10^4$ kN/m <sup>2</sup>
- Bulk zinc anode



# Corrosion Monitoring System

- Silver/silver chloride reference electrodes
  - Three locations per pile
  - Cables protected with PVC conduit
- Remote Monitoring Unit (RMU)
  - Onboard software & data storage backup
  - Instant off, depolarisation measurements
  - PV-powered data transmission
- Shore-side Main Control Unit (MCU)
  - Radio transmission from RMU
  - Data storage
  - Land line accessibility

# Dolphin #2 Piles



## Monitored Piles

-  No wrap, No CP
-  Wrap, No CP
-  Wrap, bulk CP only
-  Wrap, full CP

## Piles with No Monitoring

-  Wrap, full CP
-  No work

# System Installation

- Work restricted to low tide
- Interruptions
  - planned
  - Unplanned
- Dive Crew Coordination



# Shore Side Preparation

## Zinc Mesh Anode / Compression Panels / Electrode Calibration



# System Installation

## Bulk Zinc Anode Attachment and Surface Cleaning



# System Installation Setup



System Installation

# Electrical Continuity & Steel Connections




# System Installation

## Electrical Continuity & Steel Connections



System Installation

# Patching & Securement of Cables



System Installation

# Zinc Mesh Anode & Compression Panels




System Installation

# Zinc Mesh Anode & Compression Panels



# System Installation

## Composite Wrap



# System Installation **Composite Wrap**



System Installation

# Electrical Wiring and Monitoring System



System Installation

# Electrical Wiring and Monitoring System



System Installation

# Electrical Wiring and Monitoring System



## System Installation

# Commissioning & Performance Monitoring

- Baseline readings of reference electrodes
- Reporting of monthly corrosivity potential data
- 6, 9, 12 and 15 month inspection of RMU / MCU components
- Four-Year evaluation

# Dolphin #3

## Time Zero – Baseline Data

Pile #18: Wrap with integrated CP and bulk CP			
On Potentials	Ref. Cell #1 (v)	Ref. Cell #2 (v)	Ref. Cell #3 (v)
Instant On	-0.562	-0.752	-0.433
Native Potentials	-0.407	-0.444	-0.137
Current Output			
System	0.562 amps		
Bulk Anode	0.534 amps		
Mesh Anode	0.270 amps		

Pile #14 - Wrap with no CP			
On Potentials	Ref. Cell #1 (v)	Ref. Cell #2 (v)	Ref. Cell #3 (v)
Instant On	n/a	n/a	n/a
Native Potentials	-0.385	-0.508	-0.503
Current Output			
System	n/a		
Bulk Anode	n/a		
Mesh Anode	n/a		

Pile #17: Wrap with bulk CP			
On Potentials	Ref. Cell #1 (v)	Ref. Cell #2 (v)	Ref. Cell #3 (v)
Instant On	-0.349	-0.794	-0.787
Native Potentials	-0.317	-0.366	-0.370
Current Output			
System	0.505 amps		
Bulk Anode	n/a		
Mesh Anode	n/a		

Pile #16 - Control, no wrap and no CP			
On Potentials	Ref. Cell #1 (v)	Ref. Cell #2 (v)	Ref. Cell #3 (v)
Instant On	n/a	n/a	n/a
Native Potentials	-0.629	-0.629	-0.431
Current Output			
System	n/a		
Bulk Anode	n/a		
Mesh Anode	n/a		

# Dolphin #3

## 1 Month Data

Pile #18: Wrap with integrated CP and bulk CP			
On Potentials	Ref. Cell #1 (v)	Ref. Cell #2 (v)	Ref. Cell #3 (v)
On	-0.678	-0.878	-0.815
Instant Off	-0.665	-0.820	-0.761
IR	0.013	0.058	0.054
Native Potentials	-0.407	-0.444	-0.137
Polarisation	0.258	0.376	0.624
Current Output			
System	n/a		
Bulk Anode	0.103 amps		
Mesh Anode	0.077 amps		

Pile #14 - Wrap with no CP			
On Potentials	Ref. Cell #1 (v)	Ref. Cell #2 (v)	Ref. Cell #3 (v)
On	-0.412	-0.484	-0.478
Instant Off	n/a	n/a	n/a
IR	n/a	n/a	n/a
Native Potentials	-0.385	-0.508	-0.503
Polarisation	n/a	n/a	n/a
Current Output			
System	n/a		
Bulk Anode	n/a		
Mesh Anode	n/a		

Pile #17: Wrap with bulk CP			
On Potentials	Ref. Cell #1 (v)	Ref. Cell #2 (v)	Ref. Cell #3 (v)
On	-0.638	-0.917	-0.905
Instant Off	-0.637	-0.909	-0.900
IR	0.001	0.008	0.005
Native Potentials	-0.317	-0.366	-0.370
Polarisation	0.320	0.543	0.530
Current Output			
System	n/a		
Bulk Anode	0.110 amps		
Mesh Anode	n/a		

Pile #16 - Control, no wrap and no CP			
On Potentials	Ref. Cell #1 (v)	Ref. Cell #2 (v)	Ref. Cell #3 (v)
On	-0.395	-0.480	-0.478
Instant Off	n/a	n/a	n/a
IR	n/a	n/a	n/a
Native Potentials	-0.629	-0.629	-0.431
Polarisation	n/a	n/a	n/a
Current Output			
System	n/a		
Bulk Anode	n/a		
Mesh Anode	n/a		

# Conclusions

- An innovative polymer composite pile wrapping system with integrated CP was demonstrated on two structures
- Initial data collection indicates proper operation of CP system
- Data acquisition has posed some preliminary problems. System currently undergoing upgrade

**Corrosion Potential Monitoring for Polymer  
Composite Wrapping and Galvanic CP  
System for Reinforced Concrete Marine Piles**

**Questions ?**