HENNINGSON DURHAM AND RICHARDSON SANTA BARBARA CA M-X ENVIRONMENTAL TECHNICAL REPORT, CONSTRUCTION.(U) DEC 80 F0470 M-X-ETR-31 AFSC-TR-81-46 F/6 16/1 AD-A095 804 F04704-78-C-0029 UNCLASSIFIED NL 1 (+ 3 41: 40:95:003 VEL

AFSC-TR-81-46





M-X **ENVIRONMENTAL** TECHNICAL REPORT

> **ETR 31** CONSTRUCTION

> > ELECTE MAR 3

> > > D

BUTE IN G. T. STATERIENT A. Approved for public release; Distribut on Unlimited

81 3

3

004

REPORT DOCUMENTATION PAGE	READ INSTRUCTIONS BEFORE COMPLETING FORM
**************************************	3. RECIPIENT'S CATALOG NUMBER
AFSC TR-81-46 AD-A095 804	
4. TITLE (and Subtitle)	5. TYPE OF REPORT & PERIOD COVERED
M-X Environmental Technical Report .	Final Report,
Construction	6. PERFORMING ORG. REPORT NUMBER
AUTHOR(s)	MX ETR 31 B. CONTRACT OF GRANT NUMBER(*)
(14) M-X-ETR-31 (5)	FØ47Ø4-78-C-ØØ29
PERFORMING ORGANIZATION NAME AND ADDRESS Henningson, Durham and Richardson	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
Santa Barbara CA 93010	64312F 2 2 2 2
1. CONTROLLING OFFICE NAME AND ADDRESS Ballistic Missile Office	12. REPORT DATE
Norton AFB CA	22 December 080 /
	227
14. MONITORING AGENCY NAME & ADDRESS(if different from Controlling Office)	15. SECURITY CLASS. (of this report)
	Unclassified
	15a, DECLASSIFICATION/DOWNGRADING SCHEDULE
6. DISTRIBUTION STATEMENT (of this Report)	
Unclassified/Unlimited	
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from	n Report)
18. SUPPLEMENTARY NOTES	
9. KEY WORDS (Continue on reverse side if necessary and identify by block number)	
MX Construction Siting Analysis	
Environmental Report	
•	
	
This report identifies the environmental effects tion of the system. The resultant indirect environmental tion of the system. The resultant indirect environmental tion of the system identified within other ETRs. It tion of the system identified within this report water, materials and personnel as well as the local magnitude of each of these resource requirements.	onmental impacts are described Major effects due to construc- are the requirements for land,
/	<u> </u>
المراجع	

DD 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified 1/12/
SECURITY CLASSIFICATION OF THIS PAGE (When Date Entered)

M-X ENVIRONMENTAL TECHNICAL REPORT: CONSTRUCTION

Prepared for

United States Air Force Ballistic Missile Office Norton Air Force Base California

Acces	sion For	
DTIC Unann	GRA&I TAB ounced fication	
By Distr	ibution/	
Avai	lability	Codes
Dist	Avail an Specia	•

by

HDR Sciences Santa Barbara, California

22 December 1980

DTIC SLECTE MAR 3 1981

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

TABLE OF CONTENTS

				PAGE
Intro	ductio	n		1
1.0	Over	view and	f Summary	3
2.0	M-X	System	Description and Alternatives	5
	2.1 2.2 2.3 2.4 2.5	Altern Altern	uction sed Action atives 1 through 6 ative 7 ative 8	5 5 9 9
3.0	Desc	ription o	f System Components	15
	3.1 3.2 3.3	Protec	ting Base (OB) Complexes tive Shelters Systems	15 17 17
		3.3.1 3.3.2 3.3.3	Designated Transportation Network (DTN) Cluster Roads Support Roads	17 17 17
4.0	Cons	truction	Planning	25
	4.1 4.2		ntial Method rrent Method	25 29
5.0	Cons	truction	Tasks	29
	5.1	Mobili	zation	29
		5.1.1 5.1.2 5.1.3 5.1.4 5.1.5	Water Wells Aggregate Sources Marshalling Yards Construction Camps Temporary Power	29 29 30 30 33
	5.2 5.3 5.4	Road (ting Base (OB) Complex Construction Construction tive Shelter Construction	33 34 36
		5.4.1	Precast Method	36
			5.4.1.1 Excavation 5.4.1.2 Precast Shelter Segments 5.4.1.3 Backfilling	39 39 43

				PAGE
	5.4.2	Mechan	nized Cast-In-Place Method	. 43
		5.4.2.1	Excavation	53
		5.4.2.2	Cast-In-Place Shelter	53
		5.4.2.3	Backfilling	59
	5.4.3	Conven	tional Cast-In-Place Method	59
		5.4.3.1	Excavation	59
		5.4.3.2	Cast-In-Place Shelter	59
		5.4.3.3	Backfilling	64
5.5	Assemi	oly and Ch	neckout (A&CO)	64
5.6		ilization		66

LIST OF FIGURES

NO.		PAGE
2.2-1	System Layout for Proposed Action, Nevada/Utah full basing	8
2.4-1	System Layout for Alternative 7, Texas/New Mexico, full basing	11
2.5-1	System Layout for Portion of Alternative 8, Nevada/Utah split basing	12
2.5-2	System Layout for Portion of Alternative 8, Texas/New Mexico split basing	13
3.0-1	Schematic of M-X System Facilities	16
3.2-1	Protective Shelter Configuration, Plan and Longitudinal Section	18
3.2-2	Protective Shelter Configuration, Cross Sections	19
3.2-3	Protective Shelter Closure	20
3.3.1-1	DTN Typical Section	21
3.3.2-1	Cluster Road Typical Section	22
3.3.3-1	Support Roads Typical Section	24
4.1-1	Schematic of M-X Facilities Development, Sequential	26
4.2-1	Schematic of M-X Facilities Development, Concurrent	28
5.1.2.1	Aggregate Manufacturing Plant	31
5.1.4-1	Construction Camp Facilities	32
5.3-1	M-X System Roads Layout	35
5.3-2	Automated Road Builder	37
5.4.1-1	Precast Concrete Plant	38
5.4.1.1-1	Open Cut Excavation	40
5.4.1.1-2	Open Cut Excavation Final Excavation Stage	41
5.4.1.1-3	Contour Excavation	42
5.4.1.2-1	Liner/Rebar Fabrication Facility	44
5 4.1 2-2	Spiral Weld Pine Mill	45

<u>NO</u> .		PAGE
5.4.1.2-3	Pipemobile	46
5.4.1.2-4	Liftmobile	47
5.4.1.2-5	Tractor-Trailer Transporter	48
5.4.1.2-6	Installing Jumbo	49
5.4.1.3-1	Backfilling Protective Shelter Trench	50
5.4.1.3-2	Pneumatic Backfilling System	51
5.4.2.1	Mechanized Cast-in-Place Concrete Plant	52
5.4.2.1-1	Contour Excavating Machine	54
5.4.2.2-1	Steel Liner/Rebar Transport Trailer Assembly	55
5.4.2.2-2	Pouring Protective Shelter	56
5.4.2.2-3	Slipform Assembly	57
5.4.2.2-4	Form Vibrator	58
5.4.2.2-5	Truck Unloader	60
5.4.2.3-1	Padfoot Compactor	61
5.4.3-1	Conventional Cast-in-Place Concrete Plant	62
5.4.3.1-1	Conventional Excavation	63
5.4.3.3-1	Backfilling	65

LIST OF TABLES

<u>NO</u> .		PAGE
1	Estimates of M-X Construction Workers	2
1.0-1	Construction Resources by Alternative	4
2.1-1	OB Complex Locations and Components for Proposed Action and alternatives	6
2.1-2	Distribution of Protective Shelters by state and	7

LIST OF APPENDICES

		PAGE
Appendix 1	Construction Model	67
Appendix 2	Proposed Action - Construction Layout, Scheduling and Resources	93
Appendix 3	Alternatives 1 through 6 - Construction, Layout, Scheduling and Resources	127
Appendix 4	Alternative 7 - Construction Layout, Scheduling and Resources	131
Appendix 5	Alternative 8 - Construction Layout, Scheduling and Resources	161
Appendix 6	Army Corps of Engineers Conceptual Construction Sequencing	199

INTRODUCTION

M-X deployment and related construction planning are still in the early stages with many detailed decisions yet to be made as outlined by the tiered decision-making process described in Section 1.7.2 of the DEIS. However, certain actions must be taken on an advanced schedule to meet the objective stated by Congress as "... the development of the M-X missile together with a new basing mode for such missile should proceed as to achieve Limited Operational Capability (LOC) for both such missile and such basing mode at the earliest practical date." One of these actions is on an advanced schedule selection of a deployment area or areas.

Construction of the shelter, roads, and bases create significant direct environmental effects which must be analyzed to determine the potential impacts to the natural environment and on the social and economic fabric of the deployment areas.

Construction planning covering personnel and material resource requirements specific in amount, time and place were estimated as described in this report to provide the information used in the environmental analysis reported in the EIS. These estimates were based on knowledge available at the time when this information was required for the DEIS schedule. Since that time more detailed plans have been made and new information has been developed on construction of M-X Basing Components. Using this information, new estimates have been prepared for the total number of workers required to construct the M-X Basing Facility by the Air Force and the Corps of Engineers who will manage facility construction.

In November 1980, a Task Force consisting of representatives of the Corps of Engineers, Air Force Engineers, and Air Force Contract Consultants was convened by the Air Force Regional Civil Engineer M-X at Norton AFB to seek agreement on this estimate for numbers and staging of construction workers. The results of this work are presented in Table 1. The "Task Force" figures represent an essential consensus of the three groups. There is no estimate of peak workers as the DEIS analysis employs averages rather than peak personnel strength. This recent work was completed too late for use in the EIS Analysis although its significance with regard to many aspects of the EIS is acknowledged. (It should be noted that all of the construction personnel estimates are based upon the assumption that each worker will work a standard 40-hour work week. A mitigation measure which is currently being studied is the use of longer work periods such as ten hour work days and six day work weeks. If implemented, this mitigation measure could significantly reduce the number of construction workers required.)

This report presents the basis for the "DEIS" estimates. They will be updated for use in the FEIS analysis by considering the most current plans and estimates at that time.

Table 1. Estimates of M-X construction workers.

	1982	1983	1984	1985	1986	1987	1988	1989
Average ¹								
Task Force	2,035	5,590	9,510		18,560	17,670	12,765	
AF/DEIS	1,150	2,000	4,450	10,800	17,050	15,450	13,050	4,800
Peak²								
Task Force	2,912	6,608	13,440	20,216	22,288	21,560	15,008	8,512
AF/DEIS	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

4106-1

 $^{^{\}circ} {\rm The}$ average number of construction workers that will be present in the field over the course of an entire calendar year.

 $^{^{\}rm i} {\rm The~number~of~construction~workers~that~will}$ be present in the field during the month of peak construction activity.

1.0 OVERVIEW AND SUMMARY

This report identifies the environmental effects caused directly by construction of the system. The resultant indirect environmental impacts are described within the DEIS and detailed within other ETRs. Major effects due to construction of the system identified within this report are the requirements for land, water, materials and personnel as well as the locations, the timing and the magnitude of each of these resource requirements. The proposed and alternative systems are described in Chapter 2.

Chapter 3 describes in more detail each of the individual components which must be constructed. The sequencing of construction of the various parts of the system is contained in Chapter 4. Chapter 5 describes the method of construction of each of the components.

The overall project effects, evaluated in terms of resources required, are very similar for each of the alternatives. Table 1.0-1 summarizes these effects. (Appendices 2 through 5 present a layout schedule and breakdown of the project effects into smaller geographic units for the Proposed Action, and each alternative.)

The differences between the systems in Nevada/Utah and Texas/New Mexico are due, primarily to differences in the lengths of roads required. The ruggedness of terrain in the Nevada/Utah region leads to a more dispersed system and therefore longer roads than in Texas/New Mexico.

Because these overall project effects are similar, it must not be misinterpreted to mean that the environmental impacts are also similar. The same project effects acting in different areas may cause far different impacts. The impacts are discussed within the DEIS.

The design of the M-X system has gone through an evolutionary process that begin with a system of underground tunnels and finally evolved to the current design. Even this design is not final and will undoubtedly be refined further.

The system, as currently designed, will be composed of two operating bases, 200 clusters with 23 protective shelters each, and a system of interconnecting roads. The Proposed Action calls for placing the system in the Great Basin area of Nevada and Utah.

The specific designs of each of the project components are not yet completed and will not be for some time. Numerous studies are currently underway to develop the optimum design for each component as well as the schedule for construction. Moreover, the precise locations for each component have not yet been identified.

This analysis is based upon the preliminary designs and system layouts considered valid at the time of analysis and a representative, conceptual schedule. These component designs may be refined or modified to some extent before actual construction begins. They are considered sufficiently accurate to make an environmental analysis for deployment area selection.

Table 1.0-1. Construction resources by alternative.

CONCERNION	ALTERNATIVE			
CONSTRUCTION RESOURCE	P.A., 1-6	7	8	
Disturbed Area (x 10 ³ acres)	134-164	129-158	136-166	
Water (x 10 ³ acre-ft)	110-134	75-91	93-113¹	
Aggregate (x 10 ³ cubic yards)	49,030-59,926	46,242-56,518	47,900-58,544	
Steel (x 10 ³ tons)	376-416	376-416	377-417	
Cement (x 10 ³ tons)	1,446-1,598	1,446-1,598	1,459~1,613	
Asphaltic Oil $(x 10^3 tons)$	461-564	409-500	441-539	
POL (x 106 gallons)	402-589	662-810	563-689	
Electrical Energy (x 10 ³ MWH)	680-832	905-1,106	832-1,016	

3173

 $^{^1\}text{Water}$ numbers include irrigation for revegetation at shelters for Nevada/Utah region. Without revegetation, water requirements would be 70-100 x 10 3 acre-ft.

2.0 M-X SYSTEM DESCRIPTION AND ALTERNATIVES

2.1 INTRODUCTION

The M-X system consists of two operating base (OB) complexes and a designated deployment area (DDA). The makeup of the OB complexes and the DDA are generally dependent upon the deployment option selected. There are two deployment options for the M-X system and they are full basing and split basing.

Full basing is the deployment of the entire 200 missiles in 200 linear clusters (each cluster contains 23 protective shelters for a total of 4,600 shelters) in a two-state region. There are 2 two-state regions being considered: Nevada/Utah and Texas/New Mexico. Split basing is identical to full basing in that the total number of missiles, clusters and shelters are the same. However, the deployment is in both of the two-state regions, with one-half of the missiles in each region.

The OB complexes are classified as either a first or a second OB complex. The first OB complex always has an operating base (OB), a designated assembly area (DAA), an operating base test site (OBTS), and an airfield. The first OB complex is connected to the DDA by the designated transportation network (DTN). The second OB complex has an OB and an airfield for the full basing option, and it is not connected to the DDA. For split basing, the second OB complex has an OB, DAA and airfield. It is connected to the DDA by the DTN.

The main components of the DDA are the protective shelters, DTN, cluster roads, cluster maintenance facilities (CMFs), and remote surveillance sites (RSSs). Also located in the DDA are area support centers (ASCs), the total number of which is dependent upon whether the full or split basing option is selected. In some of the system alternatives, an ASC may be colocated with an OB complex.

There are nine system alternatives under consideration. Table 2.1-1 shows the OB complex locations and components for these alternatives. The distribution of protection shelters by state and by county for the alternatives is given in Table 2.1-2.

A schedule for construction in the DDA has been developed for each of the alternatives. These schedules describe a logical sequence of construction which begins at a marshalling yard or OB complex for each construction region and progresses at a rate that will allow the IOC and FOC deadlines to be met. The schedules associated with each alternative were used as input to a construction model to derive personnel and constuction resource requirements for construction in the DDA.

2.2 PROPOSED ACTION

The Proposed Action is a full basing deployment in the Nevada/Utah region. The 23 protective shelters in each cluster are arranged in a two-thirds filled hexagonal pattern and spaced a nominal 5,200 ft. apart. The first OB complex is located near Coyote Spring Valley, Nevada. The second OB complex is near Milford, Utah. Figure 2.2-1 shows the system layout for the Proposed Action.

The system ranges east-west from Tonopah, Nevada, to Delta, Utah; and north-south from approximately Eureka to Caliente, Nevada. Other communites in


Table 2.1-1. OB complex locations and components for Proposed Action and alternatives.

ALTERNATIVE	FIRST OB	COMPLEX	SECOND OB COMPLEX		
ALIERNATIVE	LOCATION	SYSTEM COMPONENTS	LOCATION	SYSTEM COMPONENTS	
Proposed Action	Coyote Spring Valley, Nevada	OB, DAA, OBTS, Airfield	Milford, Utah	OB, Airfield	
1.	Coyote Spring Valley, Nevada	OB, DAA, OBTS, Airfield	Beryl, Utah	OB, Airfield	
2.	Coyote Spring Valley, Nevada	OB, DAA, OBTS, Airfield	Delta, Utah	OB, Airfield	
3.	Beryl, Utah	OB, DAA, OBTS,	Ely, Nevada	OB, Airfield	
4.	Beryl, Utah	OB, DAA, OBTS, Airfield	Coyote Spring Valley, Nevada	OB, Airfield	
5.	Milford, Utah	OB, DAA, OBTS,	Ely, Nevada	OB, Airfield	
6.	Milford, Utah	Airfield OB, DAA, OBTS, Airfield	Coyote Spring Valley, Nevada	OB, Airfield	
7.	Clovis, New Mexico	OB, DAA, OBTS, Airfield	Dalhart, Texas	OB, Airfield	
8.	Coyote Spring Valley, Nevada	OB, DAA, OBTS Airfield	Clovis, New Mexico	OB, DAA, Airfield	
No Action	_	_	_	<u> </u>	

3601-2

Table 2.1-2. Distribution of protective shelters by state and county for Proposed Action (PA) and alternatives.

CMAME (CONTINU	ALT	ERNATIV	E
STATE/COUNTY	PA, 1-6	7	8
Nevada			
Esmeralda	138		-
Eureka	323	- 1	
Lander	84		
Lincoln	953	_	920
Nye White Pine	1,324 437		629 36
WILLE FILE			30
Subtotal	3,259		1,585
Utah	-}		
Beaver	189		188
Juab	314		17
Millard	754	-	510
Tooele	84	-	_
Subtotal	1,341		715
Region Total	4,600		2,300
Texas			
		126	14
Bailey]
Castro Cochran		137 61	51
Dallam		690	190
Deaf Smith	! — I	574	242
Hartley	i — J	354	250
Hockley		16	14
Lamb	! !	42	9
Oldham Parmer		74 246	41
Randall		55	
Sherman	·	39	
Swisher		26	
Subtotal	·	2,440	812
New Mexico			•
Chaves		181	
Curry		196	43
De Baca	. —	137	115
Guadalupe Harding		6 215	
Lea		16	17
Quay		342	312
Roosevelt		542	164
Union		225	155
		2,160	1,488
Subtotal			
Subtotal Region Total		₹,600	2,300
	4.600	4.600	2,300 4,600



the general vicinity of the DDA include Austin, Ely, Pioche, and Panaca, Nevada; and Hinckley and Milford, Utah. This system covers an approximate area of 12,200 sq.mi.

Major highways in the area include Federal Aid Primary Routes U.S.50, 6, and 93. State highways include 8A, 25, and 38 in Nevada; and 121 and 257 in Utah. Although not in the immediate area, Interstate 80 from Reno, Nevada to Salt Lake City, Utah; and Interstate 15 from Las Vegas, Nevada to Salt Lake City provide an important means of access to the region.

Roughly paralleling the above Interstate routes are the Union Pacific Railroad east-west mainline to San Francisco, California and another line from Salt Lake City, Utah to Las Vegas Nevada and Los Angeles, California. Also, a spur line runs south from the east-west mainline to Ely, Nevada.

For the Proposed Action, the DTN begins at the first OB complex near Coyote Spring Valley, Nevada and proceeds north to Dry Lake Valley, where it splits to the east and west. The eastern branch continues through Nevada to Utah, where it terminates in Sevier Desert Valley, north of Delta. The western branch continues to Railroad Valley, where it splits again; one portion continuing west to Big Smoky Valley and the other going north to Newark Valley, both in Nevada. This northern portion separates in Newark Valley with one branch proceeding west and terminating in Monitor Valley and the second branch going east and ending in Butte Valley. The total length of DTN is approximately 1,460 mi. About 6,200 mi. of cluster roads are needed.

2.3 ALTERNATIVES 1 THROUGH 6

Alternatives 1 through 6 are similar to the Proposed Action in that they are all a full basing deployment in the Nevada/Utah region using the same DDA. They vary in that there are different locations and combinations for the first and second OB complexes. Figure 2.2-1 also shows the system layouts for Alternatives 1 through 6.

Alternatives 1 and 2 are the same as the Proposed Action in that they have the same location for the first OB complex, near Coyote Spring Valley, Nevada. However, they have different sites for the second OB complex. Alternative 1 has the second OB complex near Beryl, Utah; and Alternative 2, near Delta, Utah. Alternatives 3, 4, 5, and 6 have the first OB complex located in Utah with the second OB complex in Nevada. A site near Beryl, Utah is the location for the first OB complex for Alternatives 3 and 4, while Alternatives 5 and 6 use a location near Milford, Utah. Alternatives 3 and 5 employ the same second OB complex site, near Ely, Nevada; and Alternatives 4 and 6 also use a common second OB complex location, near Coyote Spring Valley, Nevada.

2.4 ALTERNATIVE 7

Alternative 7 is similar to the Proposed Action and Alternatives 1 through 6 in that it is a full basing deployment in a single two-state region. Also, the 23 protective shelters in each cluster are arranged in a two-thirds filled hexagonal pattern and spaced a nominal 5,200 ft. apart. The two-state region used for deployment for Alternative 7 is Texas/New Mexico. The first OB complex is

9

located near Clovis, New Mexico, the second OB complex near Dalhart, Texas. Figure 2.4-1 shows the system layout for Alternative 7.

In Texas/New Mexico, the full basing deployment area is bounded by Roswell, New Mexico on the southwest to approximately Dalhart, Texas on the northeast. Other major cities in the area include Amarillo and Lubbock, Texas. Counties in Texas where the system is proposed include Dallam, Sherman, Hartley, Randall, Oldham, Deaf Smith, Parmer, Castro, Swisher, Bailey, Lamb, Cochran, and Hockley. New Mexico counties include Union, Harding, Quay, De Baca, Roosevelt, Curry, Chaves, Guadalupe, and Lea. This system has a total approximate area of 11,320 sq.mi.

Interstate 40, between Albuquerque, New Mexico and Amarillo, Texas essentially bisects the system. Major Federal Aid Primary Routes include U.S.54, 60, 70, 84, 380, and 385.

The DTN branches from the first OB complex to the DDA in two directions. A northerly branch parallels much of the existing road system and separates frequently to access clusters in Texas and New Mexico. The southerly extension picks up clusters in New Mexico and then turns east to provide access to the remaining clusters in Texas.


The DTN is approximately 1,260 mi. long. About 5,940 mi. of cluster roads are required. Much of the Texas/New Mexico siting region contains section roads at one mile intervals. Where they are available they are used as cluster roads to minimize road construction and environmental impact. Approximately 1,300 mi. of cluster roads will coexist with the present road system. The total road network for Alternative 7 is approximately six percent less than that for the Proposed Action.

2.5 ALTERNATIVE 8

Alternative 8 is a split basing deployment in the Nevada/Utah/Texas/New Mexico region. As is the case with the Proposed Action and all the other alternatives, the 23 protective shelters in each of the 200 clusters are arranged in a two-thirds filled hexagonal pattern and spaced a nominal 5,200 ft. apart. One hundred clusters are located in the Nevada/Utah region with the first OB complex near Coyote Spring Valley, Nevada. The remaining 100 clusters are in the Texas/New Mexico region with the second OB complex near Clovis, New Mexico. The system layout for Alternative 8 is shown in Figures 2.5-1 (Nevada/Utah) and 2.5-2 (Texas/New Mexico).

The Nevada/Utah portion of the system extends from Moapa, Nevada on the south, to Delta, Utah on the north. Other major cities in the area include Caliente, Pioche, and Panaca, Nevada; and Beryl, Milford, Delta, and Hinckley, Utah. White Pine, Nye, and Lincoln counties in Nevada; and Juab, Millard, and Beaver counties in Utah are affected by this alternative. This portion of the system covers an approximate area of 6,450 sq.mi.

The Texas/New Mexico portion extends from southern Chaves County, New Mexico to northern Dallam County, Texas. Other affected counties include Guadalupe, Harding, Lea, Roosevelt, Union, Quay, De Baca, and Curry counties in New Mexico; and Parmer, Bailey, Lamb, Deaf Smith, Hartley, Oldham, Cochran, and







Figure 2.5-2. System layout for portion of Alternative 8. Texas/New Mexico split basing.



Hockley in Texas. Principal cities in the area include Clovis, New Mexico and Dalhart, Texas. Amarillo and Lubbock, Texas lie outside the area, just to the east of the DDA. The Texas/New Mexico portion of the system covers approximately 6,240 sq.mi. for a total of about 12,690 sq.mi. required for this alternative.

Major Federal Aid Primary highways include U.S. Routes 6, 50, and 93 in the Nevada/Utah region; and 54, 87, 380, 60, 70, 84, and 385 in the Texas/New Mexico region. Combined Interstate 40 - U.S. Route 66 approximately bisects the DDA in Texas/New Mexico.

In the Nevada/Utah portion of the system, the DTN originates near Coyote Spring Valley, Nevada and proceeds north to Dry Lake Valley, where it branches to the east and west to access the remaining clusters. Essentially, this system duplicates a portion of the deployment area shown for the Proposed Action with approximately 70 clusters in Nevada and 30 in Utah.

Similarly, in Texas/New Mexico, the DTN follows the same alignment used in the Texas/New Mexico full basing system (Alternative 7). The DDA for Alternative 8 is a portion of the DDA for Alternative 7, with approximately 35 clusters located in Texas and 65 in New Mexico.

A total of 1,380 mi, is estimated for the DTN. Cluster road construction will total about 6,070 mi.

3.0 DESCRIPTION OF SYSTEM COMPONENTS

The construction of the M-X system is a large undertaking encompassing parts of two or four states and requiring approximately eight years to complete. Within the system various types of facilities are needed. The major facilities—two operating base complexes, 4,600 protective shelters, and a variable length of road comprise the main work items for construction (see Figure 3.0-1).

3.1 OPERATING BASE (OB) COMPLEXES

The two OB complexes are referred to as the first and second OB complexes. The major facilities in the first OB complex include the operating base (OB), the designated assembly area (DAA), and the operational base test site (OBTS). Regardless of the siting alternative selected, full or split based, the first OB complex will always contain those major facilities. The second OB complex has only an OB when the siting alternative is full based. When the split based alternative is selected, the second OB complex will also include a DAA. In no case is there even an OBTS located in the second OB complex.

The OB provides operational control, maintenance, supply, rail/air offloading facilities, and other typical base support functions as well as housing and facilities for assigned personnel and families. The operations control center (OCC) will be located on the first OB while the alternate OCC (AOCC) will be located on the second OB. The OB technical support facilities consist of OCC and AOCC, telephone exchange, electronic maintenance labs, missile guidance and control (G&C) system facility, warehouses, electrical/mechanical maintenance facilities, and security response force facility. In addition to these technical facilities, the OB will contain over 100 housing, administration, recreational, and service facilities to support the full-time assigned personnel.

The DAA facilities are designed to support missile, canister, launch, and transporter assembly, to house intermediate-level maintenance, and to provide weapon system storage. The principal facilities of the DAA are the missile assembly buildings (MABs), a munitions facility, and other support areas. Two MABs are planned; one for deployment assembly and the other for maintenance. The MABs consist of a high-bay assembly area, a low-bay storage and receiving area, an attached two-story support area and an outside solid-stage loading pad. The munitions facility is a secure area that stores and provides working areas for processing and assembly of the reentry system and components. The support areas are general storage, service, maintenance, and administrative areas.

The OBTS is a system test facility located in the proximity of the DAA. Its purpose is to: support subsystem and system development tests, processing, integration, and weapon system tests which require facilities located in a geological and climatological respresentative area; support follow-on test and evaluation efforts; perform technical data validation and verification; perform human factors/maintainability tests and evaluations, and support certain training activities. The OBTS will consist of the following facilities: a test-support building which houses test unique equipment; an ASC with a CMF that will be similar to the ones deployed in the operational area and physical security system (PSS) facilities also similar to operational; three PSs with ROSEE as similar to the operational version as is technically possible; cluster roads; primary/secondary access roads; RSS; and data link between the RSS and the PSS facilities.




Figure 3.0-1. Schematic of M-X system facilities.

3.2 PROTECTIVE SHELTERS

Figures 3.2-1 and 3.2-2 show the latest shelter design. The PS is a reinforced concrete tube 171 feet - 3 inches long with an inside diameter of 14 feet - 6 inches and a wall thickness of 1 foot - 9 inches. The inside of the tube has a steel liner 3/8 inches thick. The closure is also made of reinforced concrete with steel liner. Figure 3.2-3 shows the closure in detail.

The two monitoring ports shown in plan in Figure 3.2-1 are 10 feet 6 inches long in the direction of the longitudinal axis of the shelter. The width of the ports is determined by projecting a 90 degree view angle 45 degrees either side of the vertical, perpendicular to the centerline of the tube.

The PS is buried under 5 feet of earth. This earthen berm is retained by a sheet piling headwall at the closure end of the PS.

3.3 ROAD SYSTEMS

The three types of roads that support the M-X system are the designated transportation network (DTN), the cluster roads, and the support roads.

DESIGNATED TRANSPORTATION NETWORK (DTN) (3.3.1)

The DTN serves to connect the OB complex to the DDA for the primary purpose of allowing transportation of the missile/canisters via the road special transport vehicle (RSTV) to the clusters. The DTN stops at the cluster side of the barrier, specifically at the stock fence line.

As presently designed, the DTN is a 24-foot wide road with 5-foot shoulders on either side. It has a 6-inch asphalt surface on a 10-inch aggregate base. Figure 3.3.1-1 is a typical section for the DTN. The DTN has a maximum profile grade of 7 percent and a minimum horizontal radius of curvature of 500 feet.


CLUSTER ROADS (3.3.2)

The cluster road joins the DTN at the barrier and connects the DTN to the cluster. The cluster roads allow the RSTV to proceed from the barrier area to the cluster maintenance facility (CMF) and allow the transporter to proceed from the CMF to the protective shelters in the cluster. The cluster roads include those roads which pass by all 23 shelters and those roads which spur off the main cluster road to each shelter.

The cluster road used for the DEIS is a 27-foot wide road with 5-foot shoulders on either side. It has an aggregate surface depth of either 10 inches or 19 inches, depending upon the type of subgrade it is placed on. Figure 3.3.2-1 is a typical section for cluster roads. The cluster roads, like the DTN, have a maximum profile grade of 10 percent and a minimum horizontal radius of curvature of 500 ft.

SUPPORT ROADS (3.3.3)


The support roads are of three types: access, intercluster, and SALT monitoring port (SMP) roads. The access support roads connect the DTN or the



Source: R. M. Parsons Co., June 1980

1758 A 2

Protective shelter configuration, plan and longitudinal section. Figure 3.2-1.



Protective shelter configuration, cross sections. Figure 3.2-2.




Figure 3.2-3. Protective shelter closure.




Figure 3.3.1-1. DTN typical section.





Figure 3.3.2-1. Cluster roads typical section.

cluster roads to support facilities such as the CMF, the remote surveillance site (RSS), the area support center (ASC), and the power distribution centers. The intercluster support roads connect adjacent clusters with roads over which the transporter or RSTV cannot pass. The SMP support roads permit access from the cluster roads to the top of the shelters to support SMP covers removal/replacement operations.

The support road is a 10-foot wide road with a 5-foot shoulder on either side. The access support road and the intercluster support road have a 6-inch thick aggregate surface. The SMP support road is a graded earth road. Figure 3.3.3-1 is a typical section for support roads. The access and intercluster support roads have a maximum profile grade of 10 percent while the SMP support roads have a maximum profile grade of 20 percent. All three types of support roads have a minimum horizontal radius of curvature of 100 feet.



*SMP SUPPORT ROADS HAVE NO AGGREGATE SURFACE

2722-A

Figure 3.3.3-1. Support roads typical section.

4.0 CONSTRUCTION PLANNING

The construction plan determines the temporal and spacial sequence in which individual project facilities are constructed. The schedule for construction of the two operating base complexes is reasonably well established as is the overall schedule for DDA construction, but the detailed scheduling of the individual segments of the DDA is not established except for the IOC cluster which must be completed first. Two construction planning approaches are being considered. One is referred to as the sequential method and the other as the concurrent method.


For each method, the system is divided into several construction groups (18 in the Proposed Action). The initial group contains the first operating base complex and the clusters designated for initial operational capability (IOC). The differences in the order of construction of the following groups characterize the major differences between the sequential and concurrent methods. (Refer to Appendix 6 for Army Corps Engineers Alternative Conceptual Construction Plans). The environmental and socioeconomic effects of either method are a result of the intensities of the construction activities within each specific region, and not necessarily from the total amount of activity required to construct the entire system, which is the same for both methods. Since the total construction time allowed for completion of the project does not change with either method, the intensity of the construction activities in a region characterizes the differences between the methods. This is because the number of regions that have construction activities occurring simultaneously and the intensity of activity within them is different for the sequential method than for the concurrent method.

4.1 SEQUENTIAL METHOD

The sequential method begins by constructing the first operating base complex and the IOC clusters and then progresses outward. Figure 4.1-1 is a schematic diagram of this method. Generally a large work force is concentrated in a relatively small area (group #1 in the diagram) until work is completed in that group and then moves to the next adjacent group (group #2 in the diagram). A small amount of construction activity overlaps between groups during the move from one group to the next. The work within each group begins with the designated transportation network (DTN) followed by the cluster roads, and ends with the protective shelters and other facilities.

The sequential method has several advantages from an operations point of view. Completing adjacent clusters sequentially, starting from the operating base complex, allows missiles within the same geographical areas to be deployed at approximately the same time. Fewer security and operations personnel are needed since the missiles are located in the same general area. All the utilities within the DTN right-of-way, particularly the C³ system, are connected as they are completed, to the operating base complex.

The operational advantages could be offset by some adverse environmental and socioeconomic effects. Large numbers of construction personnel are concentrated in relatively small areas for a short period of time thus intensifying the impacts rather than spreading them out over a larger area.




Schematic of M-X facilities development, sequential. Figure 4.1-1.

4.2 CONCURRENT METHOD

As is the case with the sequential method, the concurrent method also begins by constructing the first operating base complex and the IOC clusters. However, shortly after construction starts in the IOC clusters, additional construction activities start in other groups in other regions remote from the initial group. This is shown schematically in Figure 4.2-1. (In the diagram all four groups would be constructed at the same time.) The order of construction within a group is the same as the sequential method: that is DTN, then cluster roads, and then protective shelters.

The major advantage of the concurrent method is that the workforce is spread out over several regions which tends to mitigate some of the adverse environmental and socioeconomic impacts associated with the concentrated activity as characterized by the sequential method. The demands for other resources, such as water and electrical energy, are also dispersed over a large area.

The disadvantages of the concurrent method are generally operations oriented. Since completed clusters are not always contiguous, larger security and operations personnel are required. Additionally, it would be necessary to construct the DTN and communications facilities to all groups early in the construction schedule.



Schematic of M-X facilities development, concurrent. Figure 4.2-1.

5.0 CONSTRUCTION TASKS

5.1 MOBILIZATION

Mobilization involves the assembly of personnel, equipment, materials, and support facilities required to construct the M-X system. Included in this activity is the development of the following items:

- o Water wells
- o Aggregate sources
- o Marshalling yards
- o Construction camps
- o Temporary power

WATER WELLS (5.1.1)

Water wells will be developed approximately every 30 mi along the designated transportation network (DTN), at the construction camps and/or concrete plants, and at each cluster. Whenever possible, these wells will be made a part of the permanent water system required for the operation of the M-X system. When the wells are temporary and only required for construction uses, temporary portable distribution and storage facilities will be used. These facilities will be relocated as construction progresses. During construction, the wells will supply domestic and construction requirements. After construction is completed, the major demand will be for domestic use at the operating base complexes.

AGGREGATE SOURCES (5.1.2)

Two types of aggregate sources are required for the project--sand and gravel deposits, and minable rock formations. These sources may or may not be located within the project area. The methods of obtaining the aggregate will be the same whether the sources are located within the project area or not, the only difference being the haul distances required to deliver the aggregate to the manufacturing plants.

Aggregate pits will be used to provide sand and gravel for construction and will be located based upon the latest geotechnical data available. At each location, mining, washing, stockpiling, and loading operations are required to provide material for the production of concrete, railroad ballast, road base and surface courses, and asphalt paving.

When sand and gravel are deficient in size or a higher grade of material is required, quarrying operations will be necessary to provide suitable rock for the manufacturing of additional aggregate.

Aggregate manufacturing plants are used to process quarried rock. This processing includes crushing, washing, sizing, and sorting. Material sizes produced vary from coarse to sand-size aggregate.

During plant operations, the aggregate is washed to remove deleterious materials and the fines produced during crushing. This wash water flows to settling ponds where these materials are removed and the water recirculated through the plant.

Equipment requirements for an aggregate manufacturing plant vary greatly according to the number of different gradations (sizes) of aggregate required. Figure 5.1.2-1 is a diagram of a typical aggregate manufacturing plant that produces sand, aggregate that can be used as a road base or surface, aggregate that can be used in asphalt paving, and aggregate that can be used in concrete. It is estimated that an aggregate manufacturing plant will require an area of five acres for operations.

MARSHALLING YARDS (5.1.3)

Marshalling yards will be developed near the perimeter of the deployment area acting as the receiving and storing sites for equipment and materials. Two main requirements for a marshalling yard are railroad and highway access. Marshalling yards will probably be set up near the operating base locations. Additional marshalling yards are desirable in other regions remote from the operating bases since this will cut down on the haul distances from the yards to construction sites.

Equipment and materials will be received at the marshalling yards and will be inventoried, labeled and put into temporary storage. When needed, the equipment or materials will be trucked to the construction sites. Equipment and materials should be handled a minimum number of times to ensure economy of construction. However, additional storage will be required at the concrete plants and the steel fabrication and assembly areas.


Since most of the materials needed for construction are stored at the marshalling yards at one time or another, it is anticipated that a marshalling yard will require about 650 acres for receiving and storing.

CONSTRUCTION CAMPS (5.1.4)

The construction sites generally will be too remote for workers to locate their families in nearby communities and commute to work on a daily basis, although there will be situations where this is possible. Therefore, temporary construction camps will be established to support the workforce. These camps would not provide housing for worker families or other indirect personnel. Construction workers would either leave their families where they are, or would move them to some community within weekend commuting distance of the construction sites, if possible.

Construction camps would consist of the following temporary facilities: dormitory and lavatories, mess hall and kitchen, recreation building, theater, infirmary, and maintenance shop. Central management offices and a heavy vehicle maintenance yard would be adjacent to the camp, as would be the truck head for receipt of incoming material. All of these personnel facilities would be serviced by a portable sewage disposal plant. The major production facilities would include water wells, a sand and aggregate plant, settling ponds and possibly a concrete plant. Figure 5.1.4-1 presents a conceptual layout of the construction camp and production facilities.

The initial construction camp will be established at the first operating base location. This camp will house the personnel that will construct both the first operating base complex and the initial portion of the designated transportation network (DTN). The first workers will live in self-contained trailer-type units with



}

Figure 5.1.2-1. Aggregate manufacturing plant.

2887 A

Figure 5.1.4-1. Construction camp facilities.

their own water supply, cooling, and sewage disposal. Some of the workers may have to live offsite and commute to work by bus or automobiles. This initial construction camp, with modifications, will be a permanent facility. This camp will have to support approximately 2,500 people during the peak year for construction.

The second construction camp will be established in the initial construction area in the designated deployment area (DDA) soon after the first camp. It will support DTN construction and the development of water wells and aggregate sources. As the construction expands, the erection of concrete plants and the development of material storage areas will be required to support the construction of the cluster roads, protective shelters, and other DDA facilities. Some of the facilities in the construction camp could become permanent if the camp is located where an area support center (ASC) will be. The remaining facilities will be relocated to another area.

The number of construction camps varies with the siting alternative. Generally there will probably be up to 18 total camps required with a maximum of about 3,500 people at a given camp during the peak period of construction. It is estimated that about 25 acres will be needed for each camp.

TEMPORARY POWER (5.1.5)

Temporary power for construction will probably be provided by diesel-powered generators, since most of the existing utility distribution systems are either not adequate to provide for the construction demands or do not have powerlines near the camps. As construction progresses on both the M-X system and proposed local power projects, permanent power facilities will be added and could be a source for power in construction areas.

5.2 OPERATING BASE COMPLEX CONSTRUCTION

There are two operating base (OB) complexes required for the M-X system. These are referred to as the first OB and the second OB. Associated with the OB complexes are a designated assembly area (DAA) and an operational base test site (OBTS). The first OB complex always includes a DAA and an OBTS. The second OB complex includes a DAA only when the siting alternative is a split based system but it never includes an OBTS.

The structures in the operating base complexes are expected to fall into four different categories: buildings with concrete walls and floors, buildings with concrete block walls and concrete floors, steel structures, and housing structures of wood and stucco. Before any buildings can be constructed, the roads and utilities, including water and power, must be available at the site. A rail spur must also be available. The contractor support area (CSA) will have to be partially completed, and temporary housing set up. Large supplies of basis building materials will have to be brought in by rail or truck, including crushed stone, cement, sand, wood, and plywood, some of which will have to be stored in suitable buildings. Water will have to be available for concrete, dust control, and general construction.

It is anticipated that normal building, construction methods will be used in the OB complexes. An exception could be in the construction of the protective shelters at the OBTS. Discussion of the construction methods for protective shelters can be found in Section 5.4.

33

5.3 ROAD CONSTRUCTION

There are three types of roads required for operation of the M-X system. These are the designated transportation network (DTN), the cluster roads, and the support roads. The length of each of these types of roads varies with the siting alternative and is discussed in Section 5 of this report. The different roadway widths and structural sections required for each type of road have not been finally determined. Further discussion on this subject can be found in Section 3.3 of this report.

The DTN connects the operating base complexes to the clusters, terminating at the barrier for each cluster. As presently conceived, it will have an asphalt surface on top of an aggregate base. The cluster roads connect each cluster to the DTN at the barrier and each protective shelter within the cluster. These roads are designed with an aggregate surface. The support roads provide access around the cluster barrier, provide access to the protective shelter for removal of the monitoring ports, and, whenever possible, provide intercluster access. The support roads have an earth surface. Figure 5.3-1 shows the layout for these roads.

Road construction is a process whereby a strip of land is improved to provide a driveable surface for access. The major operations in the construction are: surveying, clearing and grubbing, grading, drainage, scarifying and recompacting, aggregate base or surface, fine grading, and asphalt concrete surface (DTN only).

The first step in road construction is to have a surveying team go to the designated road corridor and survey, or lay out, the physical location of the road on the ground. After the alignment for the proposed road is identified, the strip of land is cleared and grubbed. Clearing and grubbing is an operation performed to remove all vegetation, boulders, debris, etc., from the proposed road corridor.

Once the corridor is cleared, earth-moving equipment is brought in to perform the rough grading operation. Grading is done to reshape the existing terrain into the roadway cross section along the proposed alignment to the approximate vertical profile. The roadway is designed, to the maximum extent possible, such that all excavated material will be used in the embankments so that no material will have to be wasted, or borrowed from areas outside of the roadway corridor. As the roadway is brought to the proposed vertical profile, the embankment is compacted to a density greater than the naturally existing soil, to create a solid foundation for the proposed road. To get the required density, moisture is added to the soil to form a compressible mixture that can be compacted in layers by tractors pulling heavy rollers and tampers. In areas where the roadway is excavated from existing ground, the underlying material is scarified (loosened by a plowing operation) and recompacted to the necessary density.

While rough grading is in progress, drainage structures are constructed at locations specified in the design. Drainage structures are located to accommodate both existing drainage ways that cross the road alignment, and runoff carried by the ditches along the roadway. Each drainage structure is analyzed and designed to function properly with the hydrology and hydraulics of the basin through which the roadway passes.




Figure 5.3-1. M-X system roads layout.

Ì

The roadway is now fine-graded to the more exact dimensions required for the final roadway cross section. The travel way is crowned, the shoulders shaped and the ditches are smoothed to drain efficiently.

After the roadway has been fine-graded, the final pavement structure is constructed for the cluster roads and the DTN. The pavement structure in the case of cluster roads will consist of a dense layer of aggregate. DTN roads will be comprised of a similar layer of aggregate with an asphalt surface course.

The appropriate traffic control and informational signs, and pavement markings (stripes, etc.) are installed to complete the road. As a final operation, the seeding and revegetation of disturbed roadway embankments and ditches is being considered.

The fundamental procedure for road construction described above typically uses conventional equipment (tractors, dozers, scrapers, etc.), performing each task as a separate operation. Also under consideration for the M-X roads system, is an automated road builder (see Figure 5.3-2) capable of finish grading, stabilizing, and compacting a 24-ft wide road section in one pass, at speeds up to 180 ft per minute.

5.4 PROTECTIVE SHELTER CONSTRUCTION

The protective shelter is a steel-lined, reinforced concrete tube approximately 171 feet long with an inside diameter of about 14 ft and an outside diameter of about 18 feet (see Figures 3.2-1 and 3.2-2). Since there are 4,600 identical protective shelters required for the system, there are several methods of construction possible. The methods presently being considered are precast, mechanized cast-in-place, and conventional cast-in-place. Since the precast and mechanized cast-in-place methods require the use of special equipment and techniques currently being developed, a test program will be conducted in 1981, to demonstrate their capabilities. The conventional cast-in-place method would use equipment and techniques that are commonly employed in concrete construction.

PRECAST METHOD (5.4.1)

Precast concrete construction is a method in which individual segments of the protective shelter are built at a centrally located plant, transported to the shelter sites, and assembled. The precast plant is set up near the construction camp and is portable, moving to several locations during the construction period. Aggregate sources and water wells are nearby. Storage areas for cement, steel, flyash, and other materials are adjacent to the plant. Figure 5.4.1-1 illustrates a representative precast concrete plant.

Precast plants produce all the concrete segments and closures necessary to complete the protective shelters. There are basically four different types of segments required. One type is the end segment with one end of the tube solid and the other end open. Another segment is the normal type, both ends open. The third type of segment is the same as the normal segment except that it has a SALT monitoring port. All three of these segments have a constant cross section. The final type is a transition segment which is the segment next to the closure. It is a transition segment because it transitions from the constant cross section type to the closure.




Figure 5.3-2. Automated road builder.






Figure 5.4.1-1. Precast concrete plant.

The major work items involved in the precast method are: excavating the trench and the ramp, pouring, transporting, and placing the precast sections; and backfilling the site.

Since many of the work items are repetitious and require the moving and/or placing of heavy articles or large quantities, the opportunity for developing specialized equipment is very real. In fact, there are many companies presently engaged in studying the possibility of using some of the special equipment discussed later on in this article.

Excavation (5.4.1.1)

Two methods of excavating the trench and the ramp for the protective shelter are open cut excavation and contour excavation. Open cut excavation can be used for part or all of the shelter trench and for all of the ramp. If the open cut method is used for only part of the trench, the remaining excavation is performed by the contour method.

Open cut excavation involves the use of a special machine which excavates a trapezoidal shaped section as shown in Figure 5.4.1.1-1. When this method is used for all the shelter trench excavation, the bottom of the trench is at the invert of the concrete shelter. Precast concrete pads, or cradles, are then placed in the trench (see Figure 5.4.1.1-2) and the precast shelter segments are set on these pads.

Contour excavation also uses a special machine. If the contour excavation method is used for the shelter trench, excavating down to the springline of the concrete shelter section would still be done by the open cut method. Then the contour excavating machine would cut a semicircular trench with a radius equal to the outside radius of the concrete shelter, as shown in Figure 5.4.1.1-3. The precast shelter segments are placed in the contoured trench, using the precast concrete pads as in the open cut excavation.

In both the open cut and contour methods of excavation, the excavated material is carried to the surface by conveyors, where it is stockpiled for use in the backfilling operation.

Precast Shelter Segments (5.4.1.2)

The precast method generally follows these procedures. First, cages of reinforcing steel and steel liners are assembled and moved to the casting area where forms are placed around the cages and concrete poured into the forms. After the concrete is vibrated to remove air pockets and to distribute the concrete evenly around the reinforcing steel, the concrete segment remains undisturbed until the concrete is hard enough for the forms to be removed. After removal of the forms, the shelter segments are stored until the concrete reaches its maximum strength and then transported to the protective shelter sites on special vehicles. Upon delivery to the site, the segments are placed in the previously excavated trench and mated to the abutting segment.

Several types of special equipment are necessary to manufacture, deliver, and place the precast protective shelter segments.





Figure 5.4.1.1-1.

Open cut excavation.



Open cut excavation final excavation stage. Figure 5.4.1.1-2.




Figure 5.4.1.1-3. Contour excavation.

Special equipment capable of making the reinforcing steel/steel liner cages are needed. Figures 5.4.1.2-1 and 5.4.1.?-2 are conceptual drawings of what these facilities might be.

The precast protective shelter segments could weigh anywhere from 250 to 310 tons, depending upon the segment. In order to load/unload and transport these segments, special equipment is required. One piece of equipment that could load the shelter segments onto the transport vehicle at the precast plant and unload the segments at the shelter site is called a pipemobile or a liftmobile. Figures 5.4.1.2-3 and 5.4.1.2-4 are examples of this type of special equipment. The heavy weight of a precast segment also dictates the use of a special transport vehicle. Figure 5.4.1.2-5 is a drawing of what a tractor-powered transport vehicle might look like.

Once the precast segments have been unloaded at the shelter site, the next job is to place them in the trench. The piece of special equipment required to perform this is an installing jumbo. Figure 5.4.1.2-6 is a drawing representing what this machine would look like.

After the segments are in place the final items of work on the concrete shelter itself include grouting the segments together: welding together the steel liners inside each shelter segment, installing the egress beams and rails, completing the headwall, and installing the closure. Some of these work items could be performed with special machines or equipment.

Backfilling (5.4.1.3)

One of the final construction items is the backfilling of the shelter trench. While the backfill is being placed, it must also be compacted. A pneumatic backfilling system is ideal for this job since it places and compacts the backfill in one operation. Figure 5.4.1.3-1 is a schematic drawing of a shelter trench being backfilled. The pneumatic backfilling system is shown in more detail in Figure 5.4.1.3-2.

MECHANIZED CAST-IN-PLACE METHOD (5.4.2)

Mechanized cast-in-place construction is a method whereby the protective shelter is completely formed and poured at each of the shelter sites. The concrete plants required to support the cast-in-place method are more numerous than that for the precast method. This is because the concrete is hauled by batch trucks to the site and there is a maximum time limit for placing the concrete once it has been mixed. This time limit can be translated into a mileage, or distance requirement, which sets the number of concrete plants needed for a particular deployment alternative. It is estimated that between 100 and 200 concrete plants will be used for the mechanized cast-in-place method. Construction camps are not located at every concrete plant, but are situated basically the same as in the precast method. The concrete plants are still near aggregate sources and water wells; however, the construction camp area is the primary location for storing cement, steel, flyash, and other materials required for construction. Figure 5.4.2-1 is a schematic drawing of a typical mechanized cast-in-place concrete plant.

The major work items for the mechanized cast-in-place method are excavating the trench and the ramp, forming and pouring the concrete shelter, and backfilling





Figure 5.4.1.2-1. Liner/rebar fabrication facility.



Source: R. A. Hanson Co. Inc., May 1980.

Figure 5.4.1.2-2. Spiral weld pipe mill.

Figure 5.4.1.2-3. Pipemobile.





Figure 5.4.1.2-4. Liftmobile.



43

SOURCE: R. M. PARSONS CO., JUNE 1980

1846 A 2

Figure 5.4.1.2-5. Tractor-trailer transporter.




Figure 5.4.1.2-6. Installing jumbo.




Figure 5.4.1.3-1. Backfilling protective shelter trench.




Figure 5.4.1.3-2. Pneumatic backfilling system.




Figure 5.4.2-1. Mechanized cast-in-place concrete plant.

the site. As is the case with the precast method, it is anticipated that specialized equipment will be used.

Excavation (5.4.2.1)

Excavating the trench and the ramp for the mechanized cast-in-place method is similar to that for the precast method. All of the ramp is excavated by open cut. The shelter trench is excavated to the springline of concrete shelter by open cut with the remainder accomplished by contour excavation.

Open cut excavation uses the same special machine as in the precast method (see Figure 5.4.1.1-1). Other equipment is available to perform this type of excavation. This equipment, such as scrapers or bulldozers, is normally associated with highway construction. The biggest disadvantage of a scraper or a bulldozer is that they require a large area to operate in.

The contour excavation of the remainder of the shelter trench is performed in the same manner as for precast construction. Figure 5.4.2.1-1 is a more detailed drawing of the contour excavating machine illustrated in Figure 5.4.1.1-3. The semicircular trench is the outside form for the bottom half of the concrete shelter.


Cast-In-Place Shelter (5.4.2.2)

In the mechanized cast-in-place method, reinforcing steel and steel liners are fabricated and delivered to the concrete plant where they are assembled in segments approximately 45 feet long. The steel liner/rebar assemblies are transported to the shelter site, placed in the contoured trench, and welded together, thus becoming the inside form of the concrete shelter. Then the special slipform machine is positioned over the trench, the concrete is trucked in from the concrete plant, and the shelter is poured. The concrete is vibrated in the forms to evenly distribute it around the reinforcing and eliminate any voids. The forms are removed much earlier than in the precast method, since the shelter is already in place and the only load it has to withstand is its own weight.

As with the precast operation, special equipment is required for the mechanized cast-in-place method.

The same special equipment used in making the reinforcing steel/steel liner cages in the precast method (see Figures 5.4.1.2-1 and 5.4.1.2-2) can be used in the mechanized cast-in-place method. The steel liner/rebar assemblies, or segments, must be hauled from the concrete plant to the shelter site. Figure 5.4.2.2-1 illustrates a type of transport vehicle that could be used.

The pouring of the concrete shelter involves several types of special equipment. Figure 5.4.2.2-2 is a schematic drawing of a shelter site showing the machinery required in pouring the concrete. Some of the special equipment illustrated in this drawing are the slipform assembly, the form vibrator, and the truck unloader. The purpose of the slipform assembly is to move along the shelter trench providing the top, outside form as the concrete is poured. The slipform assembly is shown in more detail in Figure 5.4.2.2-3. The form vibrator moves along with the slipform assembly vibrating the forms and the concrete. Figure 5.4.2.2-4 is a detailed drawing of a type of form vibrator. The truck unloader moves alongside



GRADER BLADÉ DEPTH CONTROL WHEELS

2634.A-2

SOURCE: R. A. HANSON CO. INC., MAY 1980

Figure 5.4.2.1-1. Contour excavating machine.




Figure 5.4.2.2-1. Steel liner/rebar transport trailer assembly.




Figure 5.4.2.2-2. Pouring protective shelter.





Figure 5.4.2.2-3. Slipform assembly.



Form vibrator.

Figure 5.4.2.2-4.

2672·A·1

 ϵ_{i} R

SOURCE: R. A. HANSON CO. INC., MAY 1980

the shelter trench. The concrete batch trucks drive onto the truck unloader and dump the concrete into the hopper. From the hopper the concrete is then distributed into the forms by a conveyor. Figure 5.4.2.2-5 is a drawing of a type of truck unloader that could be used.

Backfilling (5.4.2.3)

The backfilling of the shelter trench can be accomplished in the same manner as in the precast method. Refer to Figures 5.4.1.3-1 and 5.4.1.3-2 for details of the pneumatic backfilling system. If the excavation of the shelter trench and ramp is performed by scrapers and bulldozers, then the same equipment would be used in backfilling. Additionally, compaction equipment would also be required. This would probably be a padfoot compactor, another type of equipment common to highway construction (see Figure 5.4.2.3-1).

CONVENTIONAL CAST-IN-PLACE METHOD (5.4.3)

Conventional cast-in-place construction is a method in which the protective shelter is completely formed and poured at each of the shelter sites. In that regard it is the same as the mechanized cast-in-place method. Except for the use of fixed forms instead of slipforms, the conventional cast-in-place method could be almost identical with the mechanized cast-in-place. However, for the purposes of this report, it is assumed that the conventional cast-in-place method uses no special equipment unless it is absolutely required. The number and location of the concrete plants are the same as for the mechanized cast-in-place method. Figure 5.4.3-1 is a schematic drawing of a typical concrete plant for the conventional cast-in-place construction method. As in the case of the mechanized cast-in-place method, the major items of work for the conventional cast-in-place method are excavating the shelter trench and the ramp, forming and pouring the concrete shelter, and backfilling the site.

Excavation (5.4.3.1)

Excavating the shelter trench and the ramp for the conventional cast-in-place method is done by established techniques used in most highway construction. Scrapers and bulldozers are the most common types of equipment used. Figure 5.4.3.1-1 illustrates how the excavation is accomplished at a shelter site. A trapezoidal shaped section is excavated, similar to that for the precast method. The excavated material is carried by the scraper to an area adjacent to the trench, but far enough away to allow for construction of the shelter. The bulldozer is used for finer excavation. When the trench or ramp excavation gets close to the final elevation, the bulldozer is used in place of the scraper. Bulldozers are also used to excavate the side slopes and sometimes they are required to push the scrapers.

Cast-In-Place Shelter (5.4.3.2)

As in the mechanized cast-in-place method, the reinforcing steel and the steel liners are fabricated and delivered to the concrete plant site. The reinforcing steel and steel liners are then assembled in segments about 45 feet long and transported to the shelter site. Forms are set in the trench and the steel liner/rebar assemblies are then placed and become the inside forms of the concrete shelter. The concrete is trucked in from the concrete plant and is pumped into the forms. The concrete




Figure 5.4.2.2-5. Truck unloader.




Figure 5.4.2.3-1. Padfoot compactor.

F 5 3




Figure 5.4.3-1. Conventional cast-in-place concrete plant.

. 904




Figure 5.4.3.1-1. Conventional excavation.

and the forms are vibrated throughout the pour to insure that the concrete is evenly distributed and to eliminte voids. The forms are removed after a predetermined time, in which the concrete has gained enough strength to support its own weight.

A minimum amount of special equipment is assumed to be used in the forming and pouring of the concrete shelter. The special equipment used to fabricate the reinforcing steel and steel liners for the precast and the mechanized cast-in-place methods is also applicable for the conventional cast-in-place method (see Figures 5.4.1.2-1 and 5.4.1.2-2). Since these assemblies are not fabricated at the shelter site, a transport vehicle, such as the one illustrated in Figure 5.4.2.2-1 for the mechanized cast-in-place method, is used.

The setting of the forms is done by conventional methods using cranes to place the forms in the trench. The concrete is pumped from batch trucks into the forms by conventional concrete pumps in prevalent use in highway and building construction. Removing the forms is also done with cranes.

Backfilling (5.4.3.3)

Backfilling the shelter trench is done by conventional methods using the scrapers and bulldozers that performed the excavation. Figure 5.4.3.3-1 is a representation of the backfilling operation. The compactor used is shown in Figure 5.4.2.3-1.

5.5 ASSEMBLY AND CHECKOUT (A&CO)

The A&CO effort encompasses not only the clusters and their associated missiles, vehicles, facilities, etc., in the DDA, but also all the technical and contractor support facilities and subsystems at the operating base complexes.

The purpose of A&CO is to install all components and subsystems of the M-X Weapons System and assure that the system operates properly.

The A&CO function begins with the acceptance of facilities from the construction contractor and receipt of weapon system components/subsystems from the manufacturer, and continues through final acceptance by the using command. A&CO operations begin at the time that facilities are available, and generally include receipt and inspection of system components, acceptance of facilities and any equipment already installed, installation of components/subsystems, checkout and integration of subsystems, system integration, demonstration of acceptable operation, turnover to the user, and preparation for operational use.

A&CO activities are conducted both by contractor personnel and by the Air Force military and civilian personnel. Their activities begin with site preparation, and continue through the time that the last operational missiles are turned over and accepted by the Strategic Air Command.

Since A&CO will follow construction, no special facilities for personnel support are expected to be required since existing construction camp facilities can be used.




Figure 5.4.3.3-1. Backfilling.

5.6 DEMOBILIZATION

At the close of construction operations, construction personnel and equipment will be moved out. Water wells used for construction will be capped and locations permanently marked. Aggregate pits and mines will be closed. Haul roads, campsites, maintenance yard sites will be returned to their original state to the extent possible. Permanent facilities will be turned over to operational personnel. It should be noted that this demobilization phase will overlap, in part, the assembly and checkout (A&CO) phase, until final demobilization.

APPENDIX 1

CONSTRUCTION MODEL

- 1.0 Introduction
 - 1.1 Facility and Scheduling Requirements
 - 1.2 Scheduling Procedures
 - 1.2.1 Construction Activities
 - 1.3 Method of Estimating Construction Resource Quantities in the DDA
 - 1.3.1 Design Parameters
 - 1.3.2 Computer Resources Model
 - 1.4 Method of Estimating Construction Resource Quantities for Operating Base Complexes
 - 1.4.1 Operating Base Construction Personnel
 - 1.4.2 Operating Base Construction Materials

LIST OF TABLES

1.1-1 M-X facilities included in the 1982 fiscal year budget 1.3.1 - 1Construction rates for protective shelters 1.3.1-2 Construction rates for DTN and cluster roads 1.3.1 - 3Equipment requirements, protective shelters 1.3.1-4 Equipment requirements, roads Basic system construction data 1.3.2 - 11.3.2-2 Project construction effects in Texas/New Mexico, group 1 1.3.2 - 3Impact of shelter construction on group 1 1.3.2-4 Impact of DTN construction on group 1 1.3.2-5 Impact of cluster road construction on group 1 1.3.2-6 Total project construction effects in Texas/New Mexico 1.4.1-1 Sample manhour estimating sheet 1.4.1-2 Summary of operating base complex facilities

CONSTRUCTION MODEL

The purpose of the construction model is to assemble M-X system design parameters provided by the Air Force and estimate the quantities of the major resources required to complete construction of the system. Estimates of construction quantities have been developed for each alternative for the purpose of comparison. The design of the major system components are described in Section 3. This design data was used in conjunction with a conceptual construction schedule to project both the incremental use of resources over time and the total quantity of resources required. The construction model also develops a spatial disaggregation of the construction quantities over the deployment area. Thus, the temporal and spatial disaggregation of the required construction resources such as water, personnel, and cement can be used to assess potential impacts of M-X construction.

The method was developed in order to make preliminary estimates of personnel and construction materials based upon preliminary facilities' designs and a conceptual construction schedule. It was prepared prior to completion of the final system design and the final construction plan because the socioeconomic analysis of the environmental impacts of the M-X project needed an estimate of those factors as base input data. The model was geared to providing data in the form needed for the socioeconomic analysis.

This appendix first presents the construction sequencing and schedule requirements. This is followed by a description of the methodology used by the construction model to arrive at the quantity estimates. A summary comparison of the construction requirements associated with each alternative is presented in Section 1.

PRECEDING PAGE BLANK-NOT FILLED

1.1 FACILITY AND SCHEDULING REQUIREMENTS

Construction is scheduled to begin at the first operating base (OB) complex in 1982. The current military construction project (MCP) for fiscal year 1982 contains money for construction of facilities shown in Table 1.1-1. It should be noted that personnel estimates for OB complex construction that were developed for the DEIS do not reflect all of the facilities contained in the MCP. The most recent MCP data will be incorporated in the FEIS.

Initial operating capability (IOC) is scheduled for July 1986. Facilities that would provide IOC include 10 missiles, 230 shelters, and the first OB complex. Full operating capability (FOC) is scheduled for December 1989.

The above schedule is designed to allow deployment of approximately 5 missiles per month beginning in 1986 and ending in mid-1989 with 200 missiles deployed.

1.2 SCHEDULING PROCEDURES

At the time this model was developed, no firm construction schedule was established. A number of different scheduling options were being studied. (Refer to Section 4 for a discussion of scheduling options.) The schedule used for this analyses is therefore a conceptual schedule which is representative of the sequence of activities that would occur, regardless of which schedule is ultimately selected. It is not, however, a fixed schedule. The work in any particular area would be the same or may be scheduled two or three years earlier or later. The intensity of construction activity should be about the same as would actually occur.

The first OB will serve as the starting point for construction of the system. All work will proceed outward into the DDA from this OB. The DDA has been divided into a number of construction regions, each of which is subdivided into construction groups. Work will occur concurrently in each of the regions, proceeding from one construction group to the next within each region. The DTN will be constructed first in each segment in order to provide a roadway between the bases and the closest cluster groups. Over the roadway, equipment and materials will be moved that will be used to set up the construction camps, aggregate plants and concrete plants. Construction crews will initially be housed in temporary quarters on the OB and will successively move to the first temporary construction camp as work progresses. Similarly, construction material processing facilities, such as aggregate and concrete plants, will be portable and will be moved along with the construction crews as they proceed from one construction camp to the next. To minimize the amount of travel within a construction group, camps will be located roughly at the center of each construction group. Each segment contains approximately 12 to 15 clusters. Camps are located approximately 50 miles apart. Aggregate pits and quarries are located at sites identified by Fugro as having suitable natural material. Aggregate and concrete plants will be sited adjacent to these pits and quarries.

Once the camp and material source facilities are operational, personnel, equipment, and materials will be brought in to begin construction of the cluster roads and shelters. As this work proceeds, construction of the next portion of the DTN will begin and the camp for the next construction group will be set up. As

Table 1.1-1. M-X facilities included in the 1982 fiscal year budget.

FACILITIES

Roads in the DAA

Roads from the DAA to the OBTS

Unpayed construction roads from the DAA to various locations in the dirst DDA to be payed later for use as a DTN)

Pariroads from public source to and throughout the DAA

Water instribution supply, DAA

Wastewater system, DAA

Solid waste disposal facility, DAA

Storm drainage system, DAA

1,100 kw diesel power generating plant, DAA

Buried electrical conduit system, DAA

Werhead electrical loop system, DAA and to OBTS

Substation and switching station, DAA

Jentral heating and cooling plant, DAA

Communications conduit network, DAA

Integrated office building, DAA

SATAF vehicle maintenance facility, DAA

Shops facility, DAA

Warerouses (2), DAA

men field storage area

Stading area, CAA

Transporter mobile launcher assembly area, DAA

Convoy makeup area, DAA

Terminativ, TAA

Tire Station. B

Construction support

Construction tamps 2), DAA and 1st DDA

Fridge granes 21 MAB), DAA

shelters are completed in the first group, the crews will move to the next camp. All temporary facilities will be dismantled when work in an area is completed and reassembled in another location. This type of "leap frog" pattern will continue until the entire system is completed.

CONSTRUCTION ACTIVITIES (1.2.1)

This article presents a more detailed description of activities and sequencing associated with the major system facilities.

First Operating Base Complex (1.2.1.1)

- 1. Survey crews layout locations for temporary housing, aggregate pits, concrete plants, etc., with survey crews temporarily housed in local communities.
- 2. Begin construction of temporary housing.
- 3. Survey crews layout OB, OBTS, airfield, MAB, and support community.
- 4. Set up aggregate pits and quarries and concrete plants, drill water wells, and begin bringing in equipment and construction personnel.
- 5. Begin clearing and grubbing.
- 6. Construct contractor support area (CSA) and complete temporary housing.
- 7. Once all of the above are completed, construction of the permanent facilities can begin.
- 8. Marshalling yards and railroad depot facilities for construction of the roads and shelters will be established at the base and must be completed by the time construction of the DTN begins.

Second Operating Base Complex (1.2.1.2)

Construction of this base complex need not be completed until late in the project schedule. The site, however, will be used as a CSA and depot facility for construction of portions of the roads and shelters. The construction sequence will be the same as for the first OB complex for items 1 through 8 (second OB has no OBTS). Actual construction of the permanent facilities will begin at a later date, however.

Roads and Shelters (1.2.1.3)

1. With crews operating from temporary housing at the first OB, survey crews layout DTN between the OBTS and the IOC area. The IOC area will be constructed first but the sequence of construction operations for the remaining groups will be the same. The first OB and the second OB will each serve as the starting point for a construction regions.

- 2. Begin rough grading (cuts and fills) roadways (DTN and clusters), cross culverts where necessary, while compacting in situ areas to required density.
- 3. As soon as roadways are completed to the extent that heavy equipment can move into the area, shelter construction can begin.
- 4. As construction progresses away from the OB complex, it will become feasible to build construction camps. These camps will be located near the centroid of a given construction group, thereby holding the distance traveled to and from the construction sites to a minimum.
- 5. As clusters and/or groups of clusters are completed, shelter construction crews will move to new construction groups and camps.
- 6. As the heavy equipment is removed from the completed clusters, the fine-grading of the cluster roads can be completed. This work will move along behind the shelter construction crews.
- 7. After the heavy equipment required for shelter construction is moved to a new segment of DTN road and all construction traffic in the road has ceased, the DTN in the completed area can be fine-graded and paved. Upon completion of the paving operation, that segment of DTN is complete and the construction sequence is repeated until all roadways, shelters, and clusters are complete.

1.3 METHOD OF ESTIMATING CONSTRUCTION RESOURCE QUANTITIES IN THE DDA

The purpose of the construction model is to estimate, using basic design parameters, construction sites and available working days, quantities of resources associated with construction of major facilities in the DDA. The estimating procedure is to break down each of the major system components, such as shelters or roads, into individual construction tasks. The schedules, personnel and materials required for each task are then computed individually. Total system requirements are the sum of the requirements for the individual tasks.

DESIGN PARAMETERS (1.3.1)

The major design parameters include shelter design, road design and shelter spacing. The shelter design used in the model was developed in June 1980 by the Ralph M. Parsons Co. This design was for the horizontal loading dock concept which used 624 cubic yards (cy) of concrete and 85 tons of steel per shelter. Typical sections for both the cluster roads and DTN roads are presented in Section 3 of this report. A 5,200 foot spacing between shelters was used for all alternatives analyzed.

Estimates of direct construction personnel are based upon crew sizes and rates of construction developed for major construction activities. The rates for construction of shelters and roads are presented in Tables 1.3.1-1 and 1.3.1-2 respectively. The types of trucks and other major equipment used in construction of the facilities are presented in Tables 1.3.1-3 and 1.3.1-4. The number of trucks used was

Table 1.3.1-1. Construction rates for protective shelters.

ITEM	RATE/C	REW/DAY	CREW SIZE
Surveying	2.5	acres	5
Excavation	4,520	су	4
Backfill	6,400	сy	12
Compacted Subgrade	260	су	5
Stope Stabilization	5,460	sy	2
Rock Excavation	300	су	3
Concrete Forms	900	SFCA	6
Reinforcing Steel	2	tons	6
Placing Concrete	50	су	9
Fencing	150	LF	6

3241-1

Table 1.3.1-2. Construction rates for DTN and cluster roads.

ITEM	RATE/CREW	/DAY	CREW SIZE
Surveying	0.33	miles	5
Clearing and Grubbing	3	acres	۲.
Scarify and Recompact	15,000	e7.	15
Roadway Excavation	3,000	су	7
Embankment	3,000	сy	7
Rock Excavation	1,000	су	4
Aggregate Base/Surface	920	сy	8
Bituminous Surfacing	1,500	tons	10
Prime Coat	46	tons	1
Drainage	1	each	8
Overbead Transmission	4	miles	3
Fine Grading	12.5	acres	3
Underground Transmission	5	miles	5

3242-1

Table 1.3.1-3. Equipment requirements, protective shelters.

ITEM	TYPE I EQUIPMENT
Surveying	Carry-all
Excavation.	Scraper
Backfill	Dozer
Compacted Subgrade	Compactor
Slope Stabilization	Dozer
Rock Excavation	Dozer with Ripper
Concrete Forms	_
Reinforcing Steel	-
Placing Concrete	Concrete Pump
Fencing	Flatbed Truck

Table 1.3.1-4. Equipment requirements, roads.

ITEM	TYPE I EQUIPMENT	TYPE II EQUIPMENT
Surveying	Carry-all	
Clearing and Grubbing	Dozer	_
Scarify and Recompact	Motor Grader	Compactor
Roadway Excavation	Scraper	_
Embankment	Motor Grader	Compactor
Rock Excavation	Dozer with Ripper	_
Aggregate Base/Surface	Motor Grader	Compactor
Bituminous Surfacing	Paver	Roller
Frime Coat	Spray Truck	-
Drainage	Backhoe	Pipelayer
Overhead Transmission	Flatbed with Crane	
Underground Transmission	Backhoe	
Fine Grading	Motor Grader	Compactor

calculated using average hauling distances, truck capacities and estimates of the amount of material that must be hauled per day.

The estimates of crew sizes and rates of construction were derived from standard construction estimating guides including, Dodge Manual (1978), Means Building Construction Cost Data (1980), and Caterpillar Performance Handbook (edition 11).

COMPUTER RESOURCES MODEL (1.3.2)

The initial input to the construction resources model consists of a listing of the number of shelters and miles of DTN and cluster roads associated with each construction group. A beginning and end date for construction of each component is specified which would allow the IOC and FOC requirements to be met. Table 1.3.2-1 presents as an example this basic input data for the Texas/New Mexico full deployment alternative using a conceptual construction schedule.

The design parameters, rate of construction and basic system input data are used to generate the required quantities of construction resources. Table 1.3.2-2 presents, for construction group 1, a summary of the resources required for system construction. Tables 1.3.2-3 through 1.3.2-5 present the detailed calculations required to generate resource quantities. To illustrate the method of calculation, personnel requirements for 1985 will be derived.

As shown in Table 1.3.2-2, the total number of direct construction workers needed in 1985 is 1,342. This figure is the personnel needed to construct 72 shelters. 30 miles of DTN and 251 miles of cluster roads in 1985. The personnel figures represent the average number of persons that would be needed over the course of a year. (Another way of describing it would be total man-year required.) They should not be interpreted to mean that number of people would work continually for the entire period. Many factors will cause the number of workers to vary considerably over the course of a year, including weather, material availability, and construction scheduling. The number of persons required during peak periods or slack periods may be as much as 30 percent or 40 percent higher or lower than the yearly averges Those figures do, however, represent the total personnel requirements for the year. The model generated data on yearly averages because the socioeconomic analysis, for which these estimates were proposed, is based upon average yearly requirements. Table 1.3.2-3 presents data associated with shelter construction in Group 1. Column A lists the tasks required to construct shelters. For each of these tasks personnel requirements have been calculated. For example, 5 acres of land must be surveyed and construction staked per shelter. This unit value is shown in Column B. The total area which must be surveyed for shelter construction in group 1 during 1985 is 72 shelters at 5 acres each, or a total of 359 acres as shown in Column C. The rate at which a survey crew can complete the work is 2.5 acres per shift per crew per day as shown in Column D. The number of persons which comprise a survey crew is 5 as shown in Column E. The required number of crews in 1985 is determined by dividing the total amount of work in Column C by the amount of work which a crew can perform in a year, or

359 acres of surveying
$$\frac{.}{.}$$
 260 working days $\frac{.}{.}$ 2.5 acres $\frac{.}{.}$ 0.55 crews

The total number of persons required to complete the surveying task for shelter construction in Group 1 during 1985 is 0.55 crews, shown in Column F, multiplied by

Table 1.3.2-1. Basic system construction data.

	NUMBER OF	MILES	MILES	SHEL	TERS	27	rn	CLUSTE	R ROADS
JROUP	SHELTERS	OTN	CL. ROADS	START1	END	START	END	START	END
- 	345.	072.	446.	24-1985	25-1987	26-1984	20-1985	49-1384	42-1986
2	322.	052.	416.	16-1985	38-1987	16-1984	12-1985	40-1384	18-1990
3	345.	141.	446.	10-1987	28-1988	10-1985	40-1985	42-19R5	35-1987
4	345.	097.	446.	40-1987	20-1989	40-1986	40-1987	31-1987	40-1386
5	437.	169.	564.	20-1984	10-1986	12-1983	12-1984	20-1983	22-1989
6	184.	094.	238.	18-1985	21-1987	30-1984	32-1985	50-1984	28-1986
7	184.	J64.	238.	20-1986	34-1987	28-1985	18-1986	38-1985	11-138
3	207,	052.	267.	42-1986	31-1988	21-1986	36-1986	13-1386	24-1981
9	299.	230.	386.	51-1987	30-1989	40-1986	36-1987	10-1987	37-1988
10	230.	054.	297.	12-1988	36-1989	14-1987	46-1987	16-1987	12-1389
11	368.	155.	474.	34-1985	51-1987	1-1985	1-1986	20-1985	10-138
	391.	371.	505.	28-1986	25-1988	28-1985	20-1986	45-1385	42-198
. 3	368.	294.	475.	20-198	15-1989	48-1985	48-1986	12-1986	18-199
14	184.	049.	238.	30-1987	4-1989	48-1986	40-1987	12-1987	38-196
15	301.)67.	505.	12-1988	50-1989	12-1987	46-1987	10-1987	21-1969

Trates are read in weeks and year; i.e., 24-1985 is the 24th week of 1985.

Table 1.3.2-2. Project construction effects in spacing map #1617-6 texture critical system 5200 ft. Spacing map #1617-6

GUANTITY PER YEAR

PERSONNEL						
	182 (1342	1945	384.	0	0	
	524. 2587 524. 3111.	37 2266 1. 5377.	225. 5602	0 2095	2095	Summary Construction
	646. 3957. 646. 4603.	3825 3. 8428	447. 8875	0.	0 8975.	RESOURCES TABLES
						,
						BY CONSTRUCTION GROUP
	0. 6109.	18154	5062	0	0	
			67360.	27363	£7357	BY YEAR
		45 133	37	0	0	
			215.	215	215	
			0	Ö	0	
00 00 00 00		335 335	335	332	335	
			(Ċ	c	
	2002	121.	3123	3123	3123	
00 00 00 00			1			
0 00 00 00			0	0	0	
00 00 00	<u>. </u>	1224	1224	1224	1224	
0 00 00			81	0	0	
00 00		986 26	466	486	466	
00 00						
0 00			09	c	c	
00		7.5 285	345	345	345	
00						
0			0	С	0	
MILES OF CLUSIER RD		21 21	72	7.5	7.2	
INCREMENTAL 0 11	11	251 183	c ¿	0 3	0 7 6 7	
	11		Ĉ.	c	0	

THROUGH WORK DAY Table 1, 3.2-3. IMPACT OF SHELTERS CONSTRUCTION OF GROUP1 (bade 1)

O IN YEAR 1986

JEL SYSTEM	(E) (CREW () 50000E +01 () 40000E +01 () 12000E +01 () 20000E +01 () 20000E +01 () 20000E +01 () 60000E +01 () 50000E +01 () 50000E +01	(K) REGUIRED EQUIPMENT 0 10911E+01 0 53162E+00 ** ** ** ** ** ** ** ** ** ** ** ** *
E TEXZNM LINEAR GRID FU SPACING MAP #1617 F	CONSTRUCTION RATE /CREW SHIFT 0. 25000E+01 0. 45200E+01 0. 45200E+01 0. 26000E+03 0. 36000E+03 0. 90000E+03 0. 90000E+03 0. 90000E+03 0. 15000E+03 0. 15000E+03 0. 15000E+03 0. 15000E+03 0. 15000E+03	CREW /CREW 0.10000E+01 0.10000E+01 *
PROJECT ALTERNATIVE TEX/NM LINEAR GRID FULL 5200 FT SPACING MAP #1617 E	TDTAL CONSTRUCTION WATER (GAL) * 0. 6154BE+08 0. 17250E+07 0. 65406E+05 * * 0. 82973E+07 0. 00000E+00	TYPE 1 REQUIRED EQUIPMENT 0 5528BE+00 0 10911E+01 0 10632E+01 0 34506E+02 0 10361E+02 0 10361E+02
PROJECT A	REGUIRED WATER JAL (GAL) (GAL) * 0 48000E+02 0 48000E+02 0 25000E+00 * 0 18500E+03 0 18500E+03 0 0 00000E+03	(H) TYPE 1 EQUIPMENT CREW 0 10000F + 01 0 20000E + 01 0 20000E + 01 0 10000E + 01
: 72	101Al 101Al 0.35938E+03 0.12823E+07 0.12823E+07 0.25163E+07 0.25163E+05 0.25163E+05 0.4050E+05 0.4050E+05 0.1365E+07 0.1365E+03 0.1365E+03 0.1365E+03	#EQUIRED CDNSTRUCTION PERSONNEL. 7764RE+01
R MILES OF ROAD ON DAYS= 260	CONSTRUCTION CONSTRUCTION GUANTITY/MILE OUN SHELTER 0.50000E+03 0.15400E+03 0.36400E+03 0.16400E+03 0.16400E+03 0.16400E+03 0.165000E+03 0.165000E+03 0.165000E+03 0.165000E+03 0.165000E+03 0.165000E+03 0.165000E+03 0.165000E+03 0.165000E+03	REGULRED CREWS 0 55288E+00 0 10911E+01 0 77058E+00 0 13162E+00 0 18429E+00 0 18429E+00 0 34501E+01 0 11749E+01 0 24917E+01 0 24917E+01 0 10367E+01
TERS	HOURS/SHIFT = B WORK DAYS/SHIFT = SHIFTS/DAY = 1 SHIFTS/DAY = 1 DESCRIPTION SURVEYING EXCAVATION BACKFILL COMPACTED SUBGRADE SUBPE STABILIZATION ROCK EXCAVATION ROUNGRETE FORMS FINCING DUST CONTROL REVEGETATION	BESCRIPTION SURVEYING EXCAVATION ACKFILL COMPACTED SUBCRADE SLOPE STABILIZATION ROCK EXCAVATION CONCRETE FORMS RETHORCING CONCRETE FINCING DUST CONTROL REVEGETATION

O IN VEGE 1 200 THROUGH WORK DAY Table 1.3.2-3. IMPACT OF SHELTERS CONSTRUCTION ON GROUP! (page 2)

E	(D)	DJREG LZ BOR	0 27444E+01	0 43644E+01	0 14677E+02	0 28159F+01	0 96755E+00	0 24603E+01	0 33910E+02	0 71527E+02	0 36E00E+02	0, 15237E+02	C 51227E+02	0 27179E+02	0. 27383E+03
TEXAMP LINEAR GRID F		FERSONNET	*	p	0. 56298F+01	0 15779F+00	0 59896E+00	*	*	0 73430E+00	0 575005+01	0 28706E+00	0 16211E+02	0.31996E+02	0. 61365E+02
PROJECT ALTERNATIVE TEXANM, TREAC 0010 5000 FT SPACING MAP #1617 F	(0)	REQUIRED	*	*	0 56298E+01	0 15779E+00	0 598766+00	*	\$	0 73430E+00	0 57500E+01	0 28706E+00	0 16211E+02	0 31996E+02	0 61365E+02
PROJECT	Ţ	TRIPS	*	*	0 12000E+02	0 12000E+02	0 12000E+02	מ	*	0 10000E+01	0. 30000E+01	0. 10000E+01	0 12000E+02	0 12000E+02	*
. 72	(I)	DISTANCE /TRIP (MILES)	*	*	O. 15000E+02	0.1500CE+02	0.15000E+02	*	*	0 30000E+03	O. 50000E+02	O. 30000E+03	0.10000E+02	0 10000E+02	*
ON DAYS: 260	n (I	CAPACITY / TRUCK	***	*	0.73000E+02	0 73000E+02	0.14000E+03	*	*	0. 32000E+02	0 10000E+02	0 13020E+04	0.27000E-02	0. 54000E-02	*
NUMBER OF SHELTERS OR NUMBER OF COUSTRUCTION HOURSYSHIFT = 8	WURN DAYS/SHIFT = SHIFTS/DAY = 1	DESCRIPTION	SURVEYING	EXCAVATION	BACKFILL	COMPACTED SUBGRADE	SLOPE STABILIZATION	ROCK EXCAVATION	CONCRETE FORMS	REINFORCING STEEL	PLACING CONCRETE	FENCING	DUST CONTROL	REVEGETATION	TUTALS

EL PERSONNEL 7DAY WATER USF 7) (GAL)			+0+ +0+3623010 0 +0+ +0+3623010 0 0 +0+	400 0 0000 F + 10	00+ 340+25 c - 70+	104 (01774) 0 601		-04 0 13826E+07	104 C 57246E+06	+04 0 19246E+07	+04 0 13968E+07	+05 0 10274E+08
PEPSONNEL WATEP USLZDAY (GALZDAZ)	0 317766+03	C 630654 +03	0 406901 101	00/01/36871 0	50 3225 CO	0 49000F+04	Gur 25501 0	0 53176F 04	0 220188 194	0 74023E+04	0 53724E+04	0 39517E+05
WATER USE ZPERSONZDAY (GALZPERS≭DAY)	0 74000E+02	0 85000E+02	0. 85000E+02 0. 85000E+02	0 85000E+02	0 85000E+02	0 85000F+02	0 B2000E+02	O. 85000E+02	0. 85000E ±02	0 B5000E+02	0 B5000E+02	*
CONTRACTED PERSONNEL	0 46995E+01	0.741948+01	0.25291E+02 0.47870E+01	0 164485+01	0 41826E+01	0 57647E+02	0 121096+03	0 62569E+02	0 25903E+02	0 870865+02	0 63204E+02	0 46551E+03
DFSCRIFTION	SURVEYING	EXCAVATION	BACKFILL COMPACTED SUBGRADE	S. OPE STABILIZATION	RUCH EXCAVATION	CONCRETE FORMS	REINFORCING STEEL	PLACING CONCRETE	FENCING	DUST CONTROL	REVEGETATION	FOTALS

THROUGH WORK DAY Table 1.3.2-4. IMPACT OF NEW DIN CONSTRUCTION ON GROUP! (page 1)

0 IN YEAR 1986

(page 1) Numbèo os sustitos no	00 00 11 M		7 1351 080	MIN YOU GET ALTERNATIVE TOXYNIM	NA CINEAB COID CHE	M 3 L M
1, ~ >	DAYS=	Or.		SZOO FT SPACTI		
DESCRIPTION	CONSTRUCTION QUANTITY/MILE DR SHELTER	TOTAL QUANTITY	REGUIRED WATER JUNIT MATERIAL (GAL)	TOTAL CONSTRUCTION WATER (GAL)	CONSTRUCTION RATE /CREW SHIFT	PERSONNEL /CREW
SURVEYING CLEARING & GRUBBING SCARIFY AND RECOMPACT	0. 10000E+01 0. 78000E+01 0. 20000E+05		0 24200E+04 0 32000E+02	* 0 56874E+06 0 19283E+08	1	100.00
RDAD EXCAVATION EMBANKMENT ROCK EXCAVATION	0.15000E+05 0.15000E+05 0.61000E+03	0,45196E+06 0,45196E+06 0,18380E+05	0, 48000E+02	* 0 21694E+08 *	0.30000E+04 0.30000E+04 0.10000E+04	0. 70000E+01 0. 70000E+01 0. 40000E+01
AGGREGATE BASE BITUMINGUS SURFACING	0. 54600E+04 0. 46500E+04		0, 26000E+03 *	0.42773E+08 *		0. B0000E+01 0. 10000F+02
	0.17000E+02	0.51222E+03 0.15065E+03	* *	* *	0.46000E+02 0.10000E+01	0 10000E+01 0 E0000E+01
OVERHEAD TRANSMISSION DUST CONTROL	0.10000E+01		* 0 11200E+06	* 0.14173E+08	0.40000E-01 0.70000E+01	
FINE GRADING REVEGETATION	0 12400E+02 0 60000E+01				0. 12500E+02 0. 10000E+02	0. 30000E+01 0. 30000E+01
	*	*	*	0 99389E+08	*	*
DESCRIPTION	REQUIRED CREUS	(G) REGUIRED CONSTRUCTION PERSONNEL	TYPF 1 EQUIPMENT /CREW	TYPF 1 REGUIRED EGUIPMENT	TYPE 2 EQUIPMENT /CREW	TYPE ? REQUIRED EQUIPMENT
,	0 35117E+00	0 17559E+01	0 10000E+01	0 35117E+00	*	
CLEARING & GRUBBING	0. 30130E+00					
SCARIFY AND RECOMPACT ROAD EXCAUATION	0.15452E+00	0.23177E+01	0, 70000E+01	0 10816E+01	0,20000E+01 0,10000E+01	0 30903E+00
	0 57943E+00					
ROCK EXCAVATION	0.70691E-01		0 10000E+01	0 70691E-01	**	* * * * * * * * * * * * * * * * * * * *
BITUMINGUS SURFACING	0.35925E+00	0.35925E+01				0 71849E+00
	0 42828E-01	0 428286-01	-			
,	0. 57943E+00		_		0 10000E+01	0 57943E+00
OVERHEAD TRANSMISSION DUST CONTROL	0.28972E+01 0.49532E-01	0 86915E+01 0 69532E-01	0 10000E+01	0 28972E+01 0 69537E-01	* 12	* *
FINE GRADING REVEGETATION	0.11496E+00 0.69532E-01				0 20000F+01	0 22992E+00 *
	*	001407025	•	0 950046401		0 495071 101
	¥	U STUDELTU	ż		r	

THROUGH WORK DAY Table 1.3.2-4. IMPACT OF NEW DIN CONSTRUCTION ON GROUP! (page 2)

0 IN YEAR 1986

PROJECT ALTERNATIVE TEX/NM LINEAR GRID FULL SYSTEM	5200 FT. SPACING MAP #1617 -E			
NUMBER OF SHELTERS OR MILES OF ROAD = 30	NUMBER OF CONSTRUCTION DAYS= 260	HOURS/SHIFT = B	WORK DAYS/SHIFT = 5	SHIF IS/DAY \Rightarrow 1

	DESCRIPTION	CAPACITY /TRUCK	DISTANCE /IRIP (MILES)	TRIPS	REQUIRED TRUCKS	REQUIRED TRUCK PERSONNEL	TOTAL DIRECT LABOR
	SURVEYING	*	1	*	*	*	0_17559E+01
	CLEARING & GRUBBING	0 14500E+01	0 15000E+02	0.12000E+02	0 51949E-01	0, 51949E-01	0 15585€+01
	SCARIFY AND RECOMPACT	0 35000E+03	0 15000E+02	0 12000E+02	0.55184E+00	0.551B4E+00	0.28696E+01
	ROAD EXCAVATION	*	*	*	*	*	0. 40540E+01
	EMBANKMENT	0. 73000E+02	0 15000E+02	0. 12000E+02	0.19844E+01	0.19844E+01	0. 60404E+01
	RUCH EXCAVATION	*	*	*	*	*	0. 28276E+00
	ACCREGATE BASE	0 40000E+02	0 40000E+02	0. 60000E+01	0. 26364E+01	0, 26364E+01	0. 81385E+01
	BITUMINGUS SURFACING	0 12000E+02	0 40000E+02	0. 60000E+01	0 74843E+01	0 74843E+01	0.11077E+02
	PRIME COAT	0 80000E+01	0 40000E+02	0. 60000E+01	0.41043E-01	0, 41043E-01	0. 83871E-01
	DEAINAGE	0 50000E+01	0 30000E+03	0. 10000E+01	0.11589E+00	0, 11589E+00	0.47513E+01
	OVERHEAD TRANSMISSION	0 10000E+01	O 30000E+03	0. 10000E+01	0.11589E+00	0.11589E+00	0 BB074E+01
	DUST CONTROL	0 72000E-02	0. 15000E+02	0.16000E+02	0.42250E+01	0.42250E+01	0. 42946E+01
	FINE GRADING	0 14500E+01	0 15000E+02	0.16000E+02	0.61939E-01	0. 61939E-01	0. 406BZE+00
	REVEGETATION	0 54000E-02	0 15000E+02	0.16000E+02	0.80477E+01	0. B0477E+01	0. B2563E+01
84	101ALS	*	*	*	0.25316E+02	0 25316E+02	0. 62379E+02

DESCRIPTION SURVEYING CLEARING ROUBBING	CONTRACTED PERSONNEL 0 29849E+01	WATER USE /PERSON/DAY (GAL/PERS*DAY) 0 B5000E+02	PERSONNEL WATER USE/DAY (GAL/DAY) 0.25372E+03	PERSONNEL WATER USE (GAL) 0. 65967E+05
SCARIFY AND RECOMPACT ROAD EXCAVATION EMBANKHENT .	0 48783E+01	0, 85000E+02	0 41465E+03	0.10781E+06
	0 68952E+01	0, 85000E+02	0 58609E+03	0.15238E+06
	0 10269E+02	0, 85000E+02	0 87283E+03	0.22694E+06
RUCK EXCAVATION	0 48070E+00	0 85000E+02	0.40859E+02	0, 10623E+05
ACCREGALE BASE	0 13835E+02	0 85000E+02	0.11740E+04	0 30576E+06
BITUMINDUS SURFACING	0 18831E+02	0 85000E+02	0.16006E+04	0, 41616E+06
PRIME COAF	6. 14258E+00	0 85000E+02	0 12117E+02	0 31510E+04
DPAINAGE	0 80773E+01	0 85000E+02	0 68657E+03	0 17851E+06
OVERHEAD TRANSMISSION	0 14973E+03	0 85000E+03	0 12727E+04	0 33089E+04
DUST CONTROL	0 73007E+01	0 85000E+02	0 62056E403	0 16135406
FINE GRADING	0 69159E+00	0 85000E+02	0 58785E402	0 15.84E+05
REVEGE FATION	0 14036E+02	0 85000E+02	0 11930E404	0 31019E+06
	0 10504E+0.3	*	0 901378 +04	0 23436E+07

THROUGH WORK DAY Table 1.3.2-5. IMPACT OF CLUSTER CONSTRUCTION ON GROUP!

0 IN YEAR 1986

	PROJECT ALTERNATIVE TEXZNM LINEAR GRID FULL SYSTEM 5200 FT SPACING MAP #1612 E
(page 1)	NUMBER OF SHELTERS OR MILES OF ROAD = 251 NUMBER OF CONSTRUCTION DAYS= 260 HOURS/SHIFT = 8 WORK DAYS/SHIFT = 5 SHIFTS/DAY = 1

DESCRIPTION	CONSTRUCTION QUANTITY/MILE OR SHELTER	TOTAL	REGUIRED WATER /UNIT MATERIAL (GAL)	TOTAL CONSTRUCTION WATER (GAL)	CONSTRUCTION RATE /CREW SHIFT	PERSONNET. ZCREW
	:	- 1		,	į.	107.100007
SURVEYING				• 1		TO LEGODOS O
CLEARING AND GRUBBING	0 81000E+01		0 24200E+04	0.4928BE+07		
SCARIFY AND RECOMPACT	0.21700E+05	0.54563E+07	0 32000E+02	0 17460E+09	0. 15000E+05	0. 15000E+02
ROAD EXCAVATION	0. 7:00:0E+04	0 17601E+07	*	*	0.30000E+04	0 .70000E +01
EMBANKMENT	0 7:000E+04	0 17501E+07	0 4B000E+02	0 84485E+08	0. 30000E+04	0, 70000F+01
ROCK EXCAVATION	0.35000E+03	O 88005E+05	*	*	0_16000E+04	0, 40000E+01
AGGREGATE BASE		0.15388E+07	0 19500E+03	0 30007E+09	0.92000E+03	O BOOOOE +01
BITUMINOUS SURFACING		_			0 00000E+00	0 000000E+00
PRIME COAT		O 00000E+00		0. 00000E+00	0. 00000E+00	0. 000000E+00
DRAINAGE			*	*	0 10000E+01	0, B0000E+01
HADEBORDIND TRANSMISS			zh.	*		
STORY OF THE STORY			9 97000E+05	0 4405E+08		
JSI CONTROL		O. IISIOETO				
FINE GRADING	0. 13500E+02					
REVEGETATION	0. 60000E+01	0. 15087F+04	0 00000E+00	0 000000E+00	0 10000E+02	0.30000E+01
0 1410				007362767	*	
		(
		$\widehat{\sigma}$				
		REGUINED	TYPE 1	TYPE 1	TYPE 2	TYPE ?
	REGUIRED	CONSTRUCTION	EGUIPMENT	REGUIRED	EQUIPMENT	REGUIRED
DESCRIPTION	CREWS	PERSONNEL	/CRFW	EQUIPMENT	/CREW	EQUIPMENT
SURVEYING	0 29306E+01	0 14653E+02	0 10000E+01	0 29306E+01	*	*
CLEARING AND GRUBBING					*	*
SCARIFY AND RECOMPACT			0 70000E+01		0. 20000E+01	0 27981E+01
ROAD EXCAVATION		0. 15796E+02	0. 30000E+01		*	*
EMBANKMENT			O. 20000E+01		0. 20000E+01	0, 4:5131E+01
RUCK EXCAVATION			0, 10000E+01		*	*
AGGREGATE BASE	0.64333E+01				0. 20000E+01	0. 12867E+02
TUMINGUS SURFACING				*	0.00000E+00	*
PRIME COAT	*	*		*	0. 00000E+00	*
DRAINAGE	0.48355E+01	0 38684E+02		0. 48355E+01	O. 10000E+01	0.48355E+01
UNDERGROUND TRANSMISS			0 10000E+01	0.19342E+02	0. 10000E+01	0 19342E+02
DUST CONTROL	0.87038E+00		0, 10000E+01	0 B7038E+00	*	*
FINE GRADING		0. 31334E+01	0. 10000E+01	0, 10445E+01	*	*
REVEGETATION	0 SE026E+00	0.1740BE+01	0.10000E+01	0. 58026E+00	*	*
(CO. Table
IUIALS	*	0 2/3/4E+03	*	0 59935E +02	*	O THEORY TOR

PROJECT ALTERNALIVE TEXZAM LINEAR GRID FULL SYSTEM 5200 FT SPACING MAP #1A17 E 251 NUMBER OF SHELTERS OR MILES OF ROAD NUMBER OF CONSTRUCTION DAYS: 260 S Œ

HOURS/SHIFT --WORK DAYS/SHIFT = SHIFTS/DAY == 1

(bade 2)

DF SCRIP FION	CAPACITY / TRUCK	DISTANCE ZIRIP (MILES)	TRIPS	REQUINED TRUCKS	REGUTSED TRUCK PEPSONNET	TOPAL DIRECT LABOR
SURVEYING CLEARING AND GRUBBING SCARIFY AND RECOMPACT	# 0 14500E+01 0 35007E+03	0 15000£ 402 0 15000£ 402	0 12000E + 02 0 12000E + 03	\$ 45020F+00 0 49966F+01	0 45020E+00 0 4996E+01	1
ROAD EXCAVATION EMBANKMENT	* 0 73000E+02	* 0 15000f +02	# 0 12000E+02	# 0 77279E+01	# 0 77279F+01	
ROCK EXCAVATION AGGPFGATE DASE	* 0 40000E+02	* 0 40000E+02	* 0 600000 +01	* 0 24661E+02	# 0 24461E+02	0 34621E+00 0 76127E+02
BITUMINDUS SURFACING		0 000000 +00	00+300000 0	* *		ax ab
BRAINAGE	0 50000E+01	0 3000001+03		0 96709E+00	0 967096+00	
UNDERGROUND TRANSMISS	0 5000000+01					
DUST CONTROL		0 10000E+92	0 12000E+02	0 50369E+02	0 50369E+02	0 51246E+02
FINE GRADING REVEGETATION	0 54000E 02			_		
101ALS	*	•	*	0 17966E+03	0 17966E+03	0 45340E+03
	(<u>V</u>					
	TOTAL	MATER USE ZPERSONZDAY	PERSONNE 1 MATER USE ZDAY	PERSONNEL WATER USE		
DESCRIPTION	PERSONNEL.	(GAL/PERS*DAY)	(GAL/DAY)	(JV5)		
SNIAINO						
CLEAPING AND GRUBBING	0 22760E+02					
SCAPILY AND PECUMPACT ROAD EXCAVATION	0 26853E+02	0 85000E+02	0 37545£404 0 22825F+04	0 97818E+08 0 59345E+06		
EMBAUPH NE				0 88379E+06		
PUCK EXCAVATION						
ANGERCALE BASE BITTHMINDES SUBSACTMO	0 00000F400	0 800000 400	0 11000F+05	0 28601E+07		
PPIME COAT						
PRAINAGE	-					
UNIDERCROUND TRANSMISS						
DUST CONTROL		0 B5000E+02		0 19251E+07		
FINE GRADING REVEGETATION	0 15519E+03	0 85000E+02	0 00120F403 0 13191E+05	0 14391E+06 0 34296F+07		
FOTAL S	0 77078E+03	1 11	0 655168+05	0 17034E+08		

¹Total contracted personnel includes all construction related persons who will be associated with the project. It includes Corps of Engineers personnel, construction camp personnel, maintenance and supervisory personnel as well as all direct labor. 5 persons shown in Column E, or 2.76 persons. Fractions of crews and fractions of people are shown to account for the fact that a particular task may not require a full crew for an entire year. For example, where a table shows a requirement for 0.5 crews this is interpreted to mean that one crew would be required for six months. If five persons were required for that particular crew, the table would read 2.5 persons and this would represent a requirement for 5 persons for a six month period. Similarly, a requirement for 2.5 crews for a year would actually be interpreted as requirement for 3 crews for 10 months each.

The construction personnel requirements associated with shelter construction in 1985 are determined by summing the requirements for each of the tasks as shown in Column G.

In addition to the persons directly involved with construction, persons required to drive the construction relacles must be included. For example, the number of truck drivers associated with the backfill task in shelter construction has been determined by taking the total quantity of backfill shown in Column C of Table 1.3.2-3, and dividing it by 260, the number of working days in a year. This gives the quantity of backfill which must be moved per day. This daily amount is divided by the capacity of a truck shown in Column L. The number of trips that a truck can make is shown in Column N and is based on the trip distance, reasonable average speeds and maintenance down times. The required number of trucks as shown in Column O, is equal to the amount of backfill which must be moved daily, divided by the product of the capacity of the truck multiplied by the number of trips possible in a day. There is one driver per truck, therefore the required truck personnel shown in Column P, equals the number of trucks. The total direct labor shown in Column ${\mathcal Q}$ is equal to the sum of construction workers and truck drivers. The total contracted personnel shown in Column R is equal to 170 percent of the total direct labor. This multiplier of 170 percent is comprised of the following factors:

Direct Labor	100%
Workers for construction of miscellaneous facilities (CMF, etc.)	20%
Concrete plant operators	10%
Contractors staff	₹05
Contingency	10%
Army Corps of Engineers inspectors	10%
Total	170%

The personnel shown in Column R of Table 1.3.2-3 is required for construction of shelters in Group I during 1985. The total personnel is the sum of requirements associated with shelters, DTN and cluster roads as shown by the totals of columns R rables 1.3.2-3, 1.3.2-4 and 1.3.2-5. This total is equal to the value shown for personnel in Group I during 1985 on Table 1.3.2-2. A summary presenting the totals for all the construction groups in Alternative 7 is shown in Table 1.3.2-6.

In a manner similar to the calculation of personnel, the requirements for each of the construction resources was determined. The following qualifications should

Table 1.3.2-6. Tital Publicationsympoution referra

i		1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	AADC	OUANTILY PER YE	YFAP	1
A PARLOTTE AND STATES	* p * 1	77 03 07	चित्र । इ.स. । इ.स. ।	4 3	1861	1 988	6861
		7541.		11461.	13824.	11552.	1509.
Television of the contract of	2547.	5172.	11711.	12544.	20425. 62473.	1 408.5.	7273.
ofstrower arfa(a) The stroman	8444. 8444.	7571.	21644.	30500. 63155.	12243. 95398.	22209. 117696.	4311.
TIPLIBLE							
STEVEL(1900) [VOOCWENTAL	· ·	11153.	ል ላ ተ ላ አ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ ነ	75297.	103977.	112092.	44889.
TVACE A LEGAL OF THE CONTROL OF THE		ж2. я2.	127.	553.	757.	823. 2541.	330.
ASP4AL[C1%5*1]00) 	557.	688. 1345.	2233. 3544.	1018. 4505.	1268. 5864.	n. 5864.	0. 5864.
ASSECT (*10.0) ASSECT ASSECT ASSECTION AS	1643.	3223.	2670. 13496.	2	11491.	5211.	177.
	2403.	2514.	8052.	1831.	4636.	21437.	21437.
FF40(140/1814000) TWO FF4F4FATAL OF4FF4FATAF	ė e	178.	709. 885.	1172. 2083.	15.10.	1783. 5505.	714. 5219.
PROTECTIVE SHELLERS INCOPACITAL COMINALIVE	ć.	121.	523. 655.	886. 1540.	1213.	1319.	528. 4500.
Clear attached Control of the contro	44	119.	474.	225. 988.	273.	1261.	1261.
to added to the district of the second of th	112.	138.	986. 1523.	1740.	1634.	1015.	29.

^{*} Car Charter Charter and

Y

HENNINGSON DURHAM AND RICHARDSON SANTA BARBARA CA M-X ENVIRONMENTAL TECHNICAL REPORT. CONSTRUCTION.(U) DEC 80 F047(M-X-ETR-31 AFSC-TR-81-46 AD-A095 804 F/6 16/1 F04704-78-C-0029 NL UNCLASSIFIED 2053 AU A096802

be noted, however. Water quantities shown do not include water for revegetation. Aggregate includes only quantities used for base and surface courses in road construction. Aggregate for concrete and for asphalt pavement are not included. Steel quantities include both reinforcing and plate steel. The personnel figures include only the construction workers themselves. None of their dependents are included. Also not included are additional personnel who may move into the area as a result of employment opportunities associated with M-X, but who would not work on the project itself. These are referred to as indirect workers. For a complete discussion of overall poplation impacts of the project, including construction worker dependents and indirect workers, refer to the technical report on economics, ETR #27.

1.4 METHOD OF ESTIMATING CONSTRUCTION RESOURCE QUANTITIES FOR OPERATING BASE COMPLEXES

Quantities of construction resources for base complexes were developed by estimating the requirements of each structure or component which comprises the base complex. These quantities were then disaggregated over the period of construction.

OPERATING BASE CONSTRUCTION PERSONNEL (1.4.1)

Estimates of construction personnel involved with the base complex were developed by the build up of trade skill requirements by structure. Table 1.4.1-1 presents an example estimating sheet which contains the amount of time required by each trade to complete the phases of building construction. This type of estimate was developed for each structure in the base complex, and disaggregated over the period of construction. A summary of the structures for which manpower estimates were derived is presented in Table 1.4.1-2. With regard to scheduling in full basing alternatives, construction of the OBTS and DAA, which are included in the first OB complex, begins in 1982. Construction of the first OB proper begins in 1983. Construction of the second OB begins in 1985. The manpower estimates developed for the OB complexes include inspectors provided by the Army Corps of Engineers, and a 10 percent contingency. For split basing alternatives, construction of the OB in Nevada/Utah begins in 1982 and construction of the OB in Texas/New Mexico begins in 1983. Tables presenting the estimates of direct base construction personnel are contained in Appendices B through F. As with the DDA, no dependents or indirect workers are included.

OPERATING BASE CONSTRUCTION MATERIALS (1.4.2)

The total amounts of materials associated with base construction were estimated by TRW and contained in their memo dated May 2, 1980. These total quantities were disaggregated over the construction period based on a reasonable estimate of phased construction. The construction quantities are presented in Appendices B through F.

Table 1.4.1-1. Sample manhour estimating sheet.

				-						hours	man hours	14,603 16,063	cellaneous =	Total = Total + 10 percent misce]]
715	616	66	715	2.236	5.0	59	260	243		259	319	4,710	4,217	Totals
:	,				:						49		452	Parking Areas
													372	Landscaping and Vegetation
		ĝ.												
7.45	_													н. V. А. С.
			7.45											Plumbing and Sprinklers
				2,236										Electrical
					5.0									Roofing
		_										388		Roof Framing
	•					59	266	243				1,152		Interior Walls and Floors
										· -	·			Pouring and Finishing (Upper Slabs)
												388		Form Work (Upper Slabs)
										187	187	936	1,683	Pouring (Exterior Walls and Columns)
	596											1,789	596	Form Work (Exterior Walls and Columns)
										72	36		285	Pouring and Finishing Slab
	20												29	Grading/Reinforcing Slab
	30							,		·····	91		30	Pouring Concrete Footings
											20		40	Footing Excavation
														Rough Grading
												59		Building Lavout
ZECHVAICVE	EGN MORKER	MORKER SHEETMETAL	SILEELLIER	EFECTRICIAN	ROOFER	MORKER INSULATION	COAEBING EFOOB	PAINTER	ргазтекек	CEWENT MASON	OPERATOR OPERATOR	САВРЕИТЕЯ	ГУВОКЕК	PHASE OF PROJECT

Table 1.4.1-2. Summary of operating base complex facilities. 1

FACILITY	COMPONENT STRUCTURE	FACILITY	COMPONENT STRUCTURE
First OB	Airfield Roads and parking Concrete buildings Concrete block buildings Metal buildings Wood and stucco housing Utilities Rail spur	DAA	Roads and utilities Heavey vehicle assembly MAB - assembly MAB - maintenance Re-entry system Flammable storage Segregated storage magazine Storage igloos
Second OB	Golf course Airfield Roads and parking		Secondary guard building Rail spur Cannister storage pad
	Concrete buildings Concrete block buildings Metal buildings Wood and stucco housing		Missile stage storage Cannisterized missile storage Ordinance storage
	Utilities Rail spur Golf course	CSA	Rail transfer General stores
ASC	Oormitory Vehicle storage Materials and spare parts Softball field and 4 tennis courts		Shops electrical, etc. Battery shop storage and disposal Electrical test and maintenance
	Helicopter pad Helicopter hanger Vehicle maintenance shop	OBTS	Vehicle maintenance MOB office supplies Test support building
	Gymnasium Roads and utilities		Cluster maintenance facility Security alert facility
			Remote surveillance site Roads Utilities

As contained in the DEIS, this will be updated in the FEIS to reflect the proposed FY82 MCP.

APPENDIX 2

PROPOSED ACTION, NEVADA/UTAH FULL BASING WITH OB COMPLEXES NEAR COYOTE SPRING VALLEY, NEVADA AND MILFORD, UTAH.

LIST OF FIGURES

- 2-1 System layout with construction plan for Proposed Action, Nevada/Utah full basing.
- 2-2 First OB complex construction schedule for Proposed Action, Nevada/Utah full basing.
- 2-3 Second OB complex construction schedule for Proposed Action, Nevada/Utah full basing.
- 2-4 DDA construction schedule for Proposed Action, Nevada/Utah full basing.

LIST OF TABLES

- 2-1 Average direct personnel requirements for Proposed Action, Nevada/Utah full basing.
- 2-2 Average construction personnel requirements for Proposed Action, Nevada/Utah full basing.
- 2-3 Average A&CO personnel requirements for Proposed Action, Nevada/Utah full basing.
- 2-4 Average operations personnel requirements for Proposed Action, Nevada/Utah full basing.
- 2-5 Total construction resources for Proposed Action, Nevada/Utah full basing.
- 2-6 Total OB complex construction resources for Proposed Action, Nevada/Utah full basing.
- 2-7 Total DDA construction resources for Proposed Action, Nevada/Utah full basing.
- 2-8 Total DDA construction resources by group for Proposed Action, Nevada/Utah full basing.

PRECEDING PAGE BLANK-NOT FILED

PROPOSED ACTION

Description

The Proposed Action calls for full basing deployment in the southern and east-central parts of the Nevada/Utah siting region, with the first OB complex located near Coyote Spring Valley, Nevada and a second OB complex near Milford, Utah.

Construction Scenario

The construction plan used in the analysis of the full basing system deployed in Nevada/Utah (Proposed Action) is shown in Figure 2-1. Six to ten concrete plants would be required in a total of 20 different locations. Colocated with these plants would be construction camps, marshalling yards/staging areas, and life support facilities. The exact locations for these plants/camps will be determined based primarily on the following criteria: water availability, aggregate availability, and minimum haul distances.

OB Complex Construction

A construction camp will be established at each of the two OB complexes. The major construction item originating from these two camps is building construction; such as concrete and concrete block structures, metal structures, and wood frame structures.


When the scheduling for the OB complexes was established, it was intended that construction would begin at the first OB complex in 1982 and would be complete in 1986. Construction of the second OB complex would begin in 1985 and end in 1989. There are studies in progress which may change this preliminary scheduling.

For the Proposed Action, the first OB complex is near Coyote Spring Valley, Nevada. Most of the construction in the first year will be concentrated in the DAA, OBTS, and at the airfield. A portion of the DTN connecting the DAA to the DDA will also be constructed from the camp in the OB complex. Construction in the OBTS and at the airfield should be completed by 1984, with the rest of the construction years devoted to the remainder of the DAA and the OB. All technical facilities at the first OB complex must be complete by the end of 1985 to meet IOC in 1986. Figure 2-2 shows the construction schedule for the first OB complex.

The second OB complex for the Proposed Action is near Milford, Utah. Since this complex does not have to be operational for IOC, construction will not be at as an accelerated rate as for the first OB. All construction activity will be at the OB and airfield, since there is no DAA or OBTS associated with the second OB complex. Figure 2-3 shows the construction schedule for the second OB complex.

DDA Construction

The key construction items originating from the DDA plants/camps are DTN roads, cluster roads, and protective shelters. The range of DTN road mileage constructed from any one plant/camp is between 50 and 150 mi. Between 100 and 500 mi of cluster roads can be constructed from a plant/camp. The number of






Figure 2-2. First OB complex construction schedule for Proposed Action, Nevada/Utah full basing.

SECOND OB COMPLEX	1985	1986	1987	1988	1989
<u>OB</u>					
AIRFIELD					
COMMUNITY CENTER					
WORK CENTER					
LIVING AREA					
RECREATION AREA					

Figure 2-3. Second OB complex construction schedule for Proposed Action, Nevada/Utah full basing.

protective shelters built from a plant/camp ranges from 100 to 450. These construction ranges occur because no constant construction rates were used for each group.

Eighteen construction groups were established for scheduling purposes. Each group contains from 6 to 19 clusters. The construction groups were combined to form six general regions. To meet schedules and minimize the total personnel in any area at a given time, construction operations would be conducted concurrently in the six regions, as indicated by the construction path arrows. These construction operations will be pursued in accordance with the schedule shown in Figure 2-4.

Work would begin at Coyote Spring Valley, where the first OB complex construction terminates, then proceed north to Dry Lake and Delamar valleys, progress through Utah and Nevada, and end in Sand Springs Valley. By late 1984, construction would be occurring simultaneously in all six regions. Construction will peak in 1986. This sequence is planned to permit Intermountain Power Project (IPP) construction to sequentially follow local M-X construction and, thus, turn the cumulative impacts of both projects in the immediate region into a lower peak over a longer period. An attempt has been made to integrate the M-X construction with planned majo, projects. Schedule changes for specific construction groups for the Proposed Action could be made.

Construction Resource Requirements

Table 2-1 shows the average direct personnel required for any given year. This table includes construction, assembly and checkout (A&CO), and operations personnel. The peak year for construction personnel occurs in 1986 with approximately 17,000 required. A&CO personnel requirements peak over a three-year span, 1986-1988, with approximately 6,000 people required in each of the years. The peak for operations personnel will occur at final operational capability (FOC) in 1989, and remain constant thereafter. This number will be approximately 13,000. Tables 2-2, 2-3, and 2-4 give a more detailed breakdown of construction, A&CO, and operations personnel requirements, respectively.

The total construction resources for the Proposed Action are shown in Table 2-5. Generally, the peak year requirement for most of the construction resources occurs in 1987. Except for personnel, incremental and cumulative quantities are shown for each resource. The personnel numbers represent average direct construction personnel only. No water for revegetation was included. The disturbed area includes OB complex, protective shelter, and road construction, but does not include the areas associated with temporary construction facilities, such as marshalling yards, water wells, aggregate pits, etc. Reinforcing steel and steel shapes comprise the total steel quantities. Quantities for aggregate include road construction only.

OB Complexes

Table 2-6 shows the total construction resources for both OB complexes. There is no peak year for all of the construction resources. This does not occur for several reasons. The two OB complexes are generally constructed during different years, with only the two middle years of the total eight-year span having a construction overlap. The two OB complexes are very different in size and makeup.




Figure 2-4. DDA construction schedule for Proposed Action, Nevada/Utah full basing.

Table 2-1. Average direct personnel requirements for Proposed Action, Nevada/Utah full basing.

				_	PERSO	NNEL				
DESCRIPTION	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991
Construction	!									
DDA ¹	1	100	2,150	8,400	14,500	13,400	11,600	4,050		-
First OB Complex ²	1,150	1,900	2,300	2,000	1,200		į			;
Second OB Complex ³		1		400	1,350	2,050	1,450	750		
Subtotal	1,150	2,000	4,450	10,800	17,050	15,450	13.050	4.800		
A & CO DDA 1		50	100	1,750	3,150	3,150	3,100	3.100	50	
First OB Complex ² Second OB Complex ³	1	350	900	1,800	2,850	2,850	2,800	2,650	50	
Subtotal		400	1,000	3,550	6,000	6,000	5,900	5.750	100	
Operations First OB Complex ² Second OB Complex ³	;		1,250	2,500	2,750 1,400	5,000 2,800	6.250 4.250	7.500 5,700	7,500 5.700	7,500 5,700
Subtotal	1		1,250	2,000	5,150	7,800	10,500	13,200	13,200	13,200
TOTAL	1,150	2,400	6.700	16.850	28,200	29,250	29,450	23,750	13.300	13,200

¹Designated deployment area (DDA) includes protective shelters (PS), area support centers (ASC), designated transportation network (DTN), cluster maintenance facilities (CMF), remote surveillance sites (RSS), and cluster roads (CR).

 $^{^2}$ First OB complex includes operating base (OB), designated assembly area (DAA), operational base test site (OBTS), and airfield.

Second OB complex includes OB and airfield.

Table 2-2. Average construction personnel requirements for Proposed Action, Nevada/Utah full basing.

GROUP			CONS	TRUCTION	PERSONN	EL		
NUMBER 1	1982	1983	1984	1985	1986	1987	1988	1989
1		100	950	1,600	250			
2				50	1,700	150		
3			200	1,350	1,650	350		
4	! 			1	150	1,350	1,400	
5					ļ	150	1,300	1,050
6	i I		550	1,800	1,200	ł	}	
7					600	1,450	700	
8				150	1,150	1,350	50	
9			350	1,200	2,400	600	ļ	
10					100	1,000	2,000	700
11			50	750	1,250	50		
12	·					1,200	1.000	50
13)	100	1,250	2,300	1,300
14				650	1,100	Í		
15	!		50	750	1,450	250	}	
16				100	1,150	400		
17	i			ļ	250	1,550	950	
18					ļ	750	1.750	950
Subtotal		100	2.150	8,400	14,500	13,400	11.600	4,050
First OB Complex:	1,150	1.900	2,300	2,000	1,200	į		
Second OB Complex ³				400	1.350	2,050	1,450	750
Total	1.150	2,000	4,450	10,800	17,050	15,450	13.050	4,800

See Figures 2-1 and 2-4.

²See Figure 2-2.

³See Figure 2-3.

Table 2-3. Average A&CO personnel requirements for Proposed Action, Nevada/Utah full basing.

GROUP				A & CO P	ERSONNEL			
NUMBER 1	1983	1984	1985	1986	1987	1988	1989	1990
1	50	40	330	60				
2			10	. 360	400	30		
3		10	280	360	80			
4				30	320	380		
5			}		30	350	800	
6	1	20	370	260				
7			}	130	340	180		
8	}		30	250	320	20		
9	ĺ	10	250	520	140			
10		}	ĺ	20	230	540	550	
11		10	160	270	10			
12					280	260	30	50
13				30	300	620	1,000	
14			140	230				
15		10	160	320	60			
16			20	250	100			
17				60	360	250		
18		Į			180	470	720	
Subtotal	50	100	1,750	3.150	3,150	3,100	3,100	50
First OB Complex ² Second OB Complex ³	350	900	1.800	2,850	2,850	2.800	2,650	50
Total	400	1,000	3,550	6,000	6,000	5,900	5,750	100

See Figures 2-1 and 2-4.

See Figure 2-2.

³See Figure 2-3.

Table 2-4. Average operations personnel requirements for Proposed Action, Nevada/Utah full basing.

EMPLOYMENT			OPERATI	ONS PER	SONNEL	
ТҮРЕ	1984	1985	1986	1987	1988	1989
First OB Complex						
Officer Enlisted Civilian	100 950 200	200 1,925 375	300 2,900 550	400 3,850 750	500 4,800 950	600 5,750 1,150
Subtotal	1,250	2,500	3,750	5,000	6,250	7,500
Second OB Complex						
Officer Enlisted Civilian			100 1,100 200	200 2,200 400	350 3,250 650	450 4,400 850
Subtotal			1,400	2,800	4,250	5,700
Total	1,250	2,500	5,150	7,800	10,500	13,200

NOTE: Operations employment will continue at 1989 levels throughout the operating life of the project.

Table 2-5. Total construction resources for Proposed Action, Nevada/Utah full basing.

CONSTRUCTION			QU	ANTITY F	ER YEAR			
RESOURCES	1982	1983	1984	1985	1986	1987	1988	1989
Personnel	1,150	1,992	4,400	10,722	17,075	15,303	13,017	4,821
Water (AF)								
Incremental	380	890	6,133	18,376	20,669	23,075	14,295	3,201
Cumulative	380	1,270	7,403	25,779	46,448	69,523	83,818	l i
Disturbed Area (Acres)								
Incremental	1,740	3,317	10,907	26,566	32,631	36,461	22,926	5,484
cumulative	1,740	5,057	15,964	42,530	75,161	111,622	134,548	140,03
Materials								
Steel (Tons)		1	}			i		
Incremental		850	3,539	30.112	121.399	82,982	107,242	50 06
, Cumulative		850	4,389		155,900			
Concrete (CY*1,000)								
Incremental		150	189	365	1,094	794	924	430
Cumulative		150	339	704	1,798	2,592	3,516	
Asphalt (TNS*1,000)								
Incremental		121	1,491	1,836	1.979	2.035	397	100
Cumulative		121	1,612	3,448	5,427	7,462	7.859	_
Aggregate (CY*1,000)				_				
Incremental	140	363	3,659	11,921	10,395	13,630	6.988	649
Cumulative	140	503	4,162	16,083	26,478	40,108		
Prime Coat (TNS)								
Incremental		144	6,725	7.816	7,898	8.864	2.438	850
Cumulative		444	7,169	14,985	22,883	31,747	34,185	
Fencing (LF*1,000)								
Incremental			45	505	1,938	1,308	1,727	807
Cumulative			45	550	2,488	3.796	5.523	6.330

Personnel numbers are yearly averages.

3315_2

Table 2-6. Total OB complex construction resources for Proposed Action, Nevada/Utah full basing.

CONSTRUCTION			QU	ANTITY F	ER YEAR			<u></u>
RESOURCES	1982	1983	1984	1985	1986	1987	1988	1989
Personnel ¹	1,150	1,900	2,300	2,400	2,550	2,050	1,450	750
Water (AF)								
Incremental	380	620	750	820	940	800	570	280
Cumulative	380	1,000	1,750	2,570	3.510	4.310	4.880	5 160
Disturbed Area (Acres)								
Incremental	1,740	3,000	3,600	470	1.530	2,240	<u>'</u>	1
cumulative	1,740	4.740	8.340		10.340	12 580		;
Materials								
Steel (Tons)				ł		Ì	1	}
Incremental		850	1,000	880	990	720	500	250
, Cumulative		850	1,850	2,730	3,720	4,440	4,940	5,190
Concrete (CY*1,000)							-113-23	9,200
Incremental		150	170	150	210	190	140	70
Cumulative		150	320	470	680	870	1,010	1,080
Asphalt (TNS*1,000)				1	- 000		1,010	1,000
Incremental								
Cumulative			280 280	240 520	150 670	240 910	170	100
			260	320	870	910	1,080	1,180
Aggregate (CY*1,000) Incremental							1	
Cumulative	140	220	260	290	330	290	210	100
	140	360	620	910	1,240	1,530	1.740	1,840
Prime Coat (TNS)	1							
Incremental			2,300	1,980	1,210	2,300	1,610	850
Cumulative			2,300	4,280	5,490	7.790	9.100	10,250
Fencing (LF*1,000)		ĺ		j				
incremental			5	40	23	()	29	15
dumulative -			5	45	68	68	97	112

Personnel numbers are vearly averages.

DDA

The total resource requirements associated with construction of the DDA for the Proposed Action are shown in Table 2-7. Incremental and cumulative quantities are shown for each item except personnel. Water quantities are for concrete, dust suppression, compaction, and construction personnel use. It does not include water required for revegetation. The disturbed areas are the result of construction of protective shelters and roads. Disturbed areas associated with construction of temporary facilities, such as marshalling yards, wells, aggregate pits, etc., are not included. The steel quantities presented include both reinforcing and plate steel. The quantities shown for aggregate are for road construction only. Table 2-8 is identical to Table 2-7 except that it shows the construction resources required for each construction group.

Table 2-7. Total DDA construction resources for Proposed Action, Nevada/Utah full basing.

		QUANT	ITY PER YE	EAR			
CONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1988	1989
Personnel 1	92	2,100	8,322	14,525	13,252	11.567	4,071
Water (AF)	1	1	,	{		1	!
Incremental	270	5,383	17,556	19,729	22,275	13,725	2,92
Cumulative	270	5,653	23,209	42,937	65,212	78,938	81,86
Disturbed Area (Acres)		-,	,,	1,	1	1,	,
Incremental	317	7,307	26.096	31,101	34,221	22,926	5.48
Cumulative	317	7.624	33,720		99,042	121,968	127,45
Steel (TNS)		.,	1	1	}	-22,000	1 , 10.
Incremental	1	2.539	29.232	120,409	182,262	106.742	49.818
Cumulative	1	2,539	31,770	152,179	234,441	341,182	391,000
Concrete (CY 1.000)	1	2,000	02,	152,113] -01,111	341,102	351,550
Incremental	1	19	215	884	604	784	366
Cumulative		19	233	1,117	1.721	2,505	2,870
Asphalt (TNS 1.000)	i	13		1,11	1,.21	2,505	, 2,5,0
Incremental	121	1,211	1,596	1,829	1,795	227	l
Cumulative	121	1.332	2.928		6,553	6,780	}
Aggregate (CY 1,000)	121	1,332	2,928	4,758	0,333	0,780	
Incremental	143	3.399	11,631	10,065	13,340	6.778	549
	143			25.238	38,578		45,90
Cumulative	143	3,542	15,173	25,238	38,378	45,356	45,90
Prime Coat (TNS)	1	4 405	5 000	6.688	0 504	900	
Incremental	444	4,425	5,836	1	6,564	820	
Cumulative (1.000)	444	4,870	10,706	17,394	23,958		{
Fencing (LF (1,000)	j			, ,,,,			
Incremental		40	465	1,915	1,308	1,698	792
Cumulative	<u> </u>	40	505	2,421	3,729	5,427	6,219
Protective Shelters		1		1			
Incremental	j	30	344	1,417	968	1,256	586
Cumulative	T.	30	374	1,790	2,758	4,014	4,600
Miles of DTN Roads		1		1	1	_	ļ
Incremental	26	260	343	393	386	49	1
'umurative	26	286	630	1.023	1,409	1,458	:
Miles of Muster Roads			1		1		
.ncremental		323	1,594	1,294	1.335	1,0 64	90
umulative		3 23	1,917	3,211	5,046	6,110	6,200

Personnel numbers are yearly averages.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAM FULL MASIMS.

QUANTITY PER YEAR

GROUP 1 (PAGE 1 OF 18)

CINSTRUCTION 19	PERSONNEL 1	MATER (AF) INCREMENTAL		PISTURBLD ARFA (ACRES) INCREMENTAL		HATERIAI S	SIFEI (TNS)	INCRIMENTAL	CINCRE FE (CV*1000)	INCREMENTAL	CURM ATIVE	ON THREE CONTRACTOR IN THE SECOND SEC		(000	CUMULATIVE 1	•			TACING F F JOSO	CURIUM ATTIVE	PROTECTIVE SMELTERS	INCREMENTAL	CARGE AT 1 VE	HILES OF DIN RUADS	UNCRUMENTAL CUPIMENT IVE	HITES OF CLUSINE RD	INCIRINFINIA
1983	92	270		317	317.							121	121	!	143		444	444							% %		
1984	941	2096	0	3155	3439		1	2539		13	19	150	623		1961		576	1050	C.	40		30	e E		5 03		300
1985	1589	1768		3010	6449		1	15362	!	113	1:35				2415				5 V C	502		111	- - - -				8.1
9861	273	159	: :	316	6765		i	3584		56	158								67	342		42	753				
1987																											
1988																											
1989																											

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROFOSED ACTION,
MEVADA/UIAM TULL DASLING.

GROUP 2 (PAGE 2 OF 18)

				GUAN I	GUANTITY PLR YEAR		
CONSTRUCTION RESOURCES	1983	1.384	9861	1986	1961	1.2448	1989
PERSONNET 1			 8 	1681	1699	8	
WATER (AL) THEPT PLINTAL CURIULATIVE			95	3125 3220	2115 5335	71 5406	
DISTURBED AREA (ACRES) INFRIMENTAL CURBEATIVE			115	4663 4775	3468 8243	142 8384	
MATERIALS							
SDEE CINS) FNCREMONIAL				8698 8696	15114 23811	1604 25415	
CONCRETE COVIDOD) INCREMENTAL CONTROL MINISTER				\$ \$ \$ \$	111	12 107	
ACHALLONS*1000) TNCREMENTAL CUMMATIVE			£ £	354 396	R(3 4 7.9		
MORRIGATE (CY*1000) INCREMENTAL ABREE ATTOR			88	1914	1064		
PRIMEGUAL (INS) THEREM NEAL			981 931 139	1292	105.		
THE TREATMENT FROM THE PRINCE OF THE PRINCE				BC1	240 379	404	
PROTECTIVE SHELTERS IFICOT HENIAL CURNIALIA				191 191	0167	61	
THES OF DIA POODS TREET BRIDE COURTAINS				58	8.01		
THE CONTROLLED TO THE TOP THE STATE OF THE S				₹ ₹ -	1727		

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING. AUANTITY FER YEAR

43,

				NEVADA	NEVADA/UTAH FULL BASING.	SKUUT TUR T TU	tose action,	i most
				GUAN	QUANTITY PER YEAR	AS.		(PAGE 3 OF 18)
CHASTRUCTION RESOURCES	1983	19614	1985	1986	1987	1 208	6861	
PLPSONNEL 2		165	13.4	1649	3.84			
UNIER (AF) INCHIPENIAL CUMUI ATIVE		486 486	3229 3715	1403 5118	175 5313			
DISTURBLE AREA (ACRES) INCREMENTAL CUMULATIVE		570 570	4794 5365	2523	387 82758			
MATERIALS								
SHELLINS) INCHEMENTAL CUMMANTEVE			22.69 22.69	18759 21028	4387 25415			
(INGRETETCY+1000) INGREMENTAL CUMHAATIVE			27	138 154	32 187			
AGHIALTONS+1000) INCH MENTAL		219	919					
ACCORDER CONTROL INCREMENTAL COMPLETENTAL		752	7288 2542	438				
FILTIME COAT (TNS) INCPEMENTAL COPEULATIVE		661 661	8651 662	•				
CUMPLATIVE			žž	863 863	70			
PROTECTIVE SHELTERS IN PERMINAL CURNULATUS			2.7	221 247	38 888			
HILES OF DIN RUADS INCREMENTAL CORNI ACTOR		47	7.					
HILES OF CLUSTER PD INCHEMENTAL			29 (2)	77.				

¹PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAN FULL BASING OF CONTINITY FER YEAR

GROUP 4 (PAGE 4 OF 18)

	CO	4991	1985	1986	1981	9861	1989	
CONSTRUCTION RESOURCES	1483							
PERSONNEL.)			152.	1355.	1405.		
MATER (AF) INCREMENTAL CURULATIVE				447.	2748	1151.		
DISTURBED AREA (ACRES) INCREMENTAL CUMULATIVE				524	4213. 4738	2088. 6 826.		
MATERIALS								
STEEL (TNS) INCREMENTAL CURRENT VE					5218. 5218.	16287. 21505.		
CONCRETE (CY*1000) INCREMENTAL CUMULATIVE					38 34 36	120. 158.		
ASPHALT (TNS*1000) INCREMENTAL CURIUL ATTVE				201.	101.			
ACCREGATE (CY+1000) INCREMENTAL CUMULATIVE				236. 236.	1878.	320. 2442.		
PRIMECOAT (TNS) INCREMENTAL CUMULATIVE				734. 734.	371. 1105.			
FENCING (FELOOD) INCREMENTAL CORREATIVE					83.0	259.		
PROTECTIVE SHELTERS INCHEMENTAL CUMULATIVE					61.	172 253		
MTES OF DTN RUADS INCREMENTAL CUNULATIVE				43	88 89			
MILES OF CLUSTIR RD INCH MENTAL CUMULATIVE					2007	64. 164.		

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING

			,	NEVADA/	UTAH FULL BY	SKOUP FOR PR	NET DOS CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING	GROUP 5
				GUANT	QUANTITY PER YEAR	∆ R	!	(PAGE 5 OF 18)
CINS FRUCT ION RESOURCES	1983	1984	1985	1986	1987	1980	1989	
PERSONNEL 1					136	1313	1044	
MATER (AF.)					i			
INCREMENTAL CUPIULATIVE					407	2770.	739.	
DISTURBED AREA (ACRES)					<u>.</u>		910	
CUPIULATIVE					477.	44137.	1394	
MATERIALS						j L		
STEEL (INS)								
CHANK ATTAIN						4568	13057	
CONCRETE (CY*1000)						4568	17395.	
INCREMENTAL						Ç	96	
AGPHALT (TNS#1000)						Š	129.	
INCREMENTAL					283	2553		
ACCREGATE (CY+1000)					183	407.		
INCREMENTAL					.10	9		
PREGNATOR					215.	2005	2108.	
INCREMENTAL					977	i		
CUPILICATIVE					199	1476		
INCREMENTAL								
CUMMANTIVE						ĕĕ	207. 200.	
PROTECTIVE SHELTERS								
CUPRILATIVE						Š	133	
10 min						ž	207.	
INCREMENTAL								
CUMULATIVE					8 8	45 56 56		
HILES OF CLUSTER RD								
FNCHENENTAL						950	ć	
COPIAL TOTAL						800	279	

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING. (RIANTITY PER YEAR

GROUP 6 (PAGE 6 OF 18)

!							
CINSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1906	1989
PLIKSIJNINEI ¹		569.	1700.	1203.			
MATER (AL) INCREMENTAL CURNILATIVE		1566. 1566	3171.	701. 5458.			
DISTURBED AREA (ACRES) INCREMENTAL CUMMATIVE		2122.	4929.	1393. 8445.			
MATERIALS							
STEEL (TNS) INCREMENTAL			9625.	15790.			
CUMPLE AT IVE			9625	25415.			
CUNCRE IN CATALOGO INCREMENTAL			7.	116.			
CUPROLATIVE ASPHALI (INS+1000)			÷				
INCREMENTAL		338.	165.				
CUMULATIVE ACCRECATE (CY+1000)		3,08	300				
INCREMENTAL		1022.	2034				
CUMULAT I VE		1022	3056.				
PRIMECDAT (TNS)		***	607				
CHEST ATTOR		1234	1836				
FRCINGLE*1000)							
INCREMENTAL CURRILATIVE			183	404			
PROTECTIVE SHELTERS			;	į			
INCREMENTAL CURULATIVE			: : ::	299			
HILES OF DIN RUADS INCREMENTAL CUMULATIVE		22	100				
MILES DE CLUSTER RD INCREMENTAL CUMULATIVE		102	301 103				

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING. GIVANTITY PER YEAR

GROUP 7 (PAGE 7 OF 18)

				TAIN TO	GUANILIA I'I'N TUNA	¥ .	
CONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1788	6861
PLESONNE I				029	1429	6.7.3	
WALER (AF) INCHEMENTAL CUMULATIVE				1711	2080 3772	396 4187	
DISTURBED AREA (ACRES) INCREMENTAL CUMULATIVE				2309.	3387	787.	
MATERIALS							
SHEL (TNS)							
CUMULATIVE					10635	19550.	
CONCRETE (CY*1000)					ş	7	
CUMULATIVE					78	144	
ASPHALT (TNS+1000)				Č			
CUMULATIVE				361			
ACCREGATE (CY*1000)							
CURU ATIVE				0.110	1235 2345		
PRIMECRAT (TNS)							
TNCREMENTAL				1394			
COMMINALINE EL NOTRE CLER 1000				1374			
INCREMENTAL					169.	147	
CURIULATIVE					16.2	311	
PROTECTIVE SMELTERS							
INCPEMENTAL					125	105	
CUMULAT I VE					175	2,50	
MHES OF DYN ROADS INCREMENTAL COMOLATIVE				38 38			
NULES OF CLUSIFR RD INCREMENTAL				108	dod		
				: :			

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION NEVADA/UTAH FULL BASING

MUANTITY PER YEAR

GROUP 8 (PAGE 8 OF 18)

	1983 1984	1985	1986	1987	1988
PFRSONNEL 1		153	1145	1363.	67
WATER (AF) INCREMENTAL		450	269B	1001	37.
CUNULATIVE		450	3147	4148	4187
DISTURBED AREA (ACRES)		,			į
INCHEMENTAL		527	4540.	1865. 6405.	/B. 6483.
MATERTALS					
SIEEL (TNS)					
INCREMENTAL			2125	16540	805
CONCRETE (CV*1000)				0001	0000
INCREMENTAL			16	121	7.
CUNIULATIVE			16	137.	661
ASSTRACT CONSTRUCTOR INCREMENTAL		202	179		
CUMULATIVE		202	381		
ACCREGATE (CY+1000)			2001	ţ	
CUNULATIVE		237	2140	2345	
PHIMECUAL (INS)		1			
CUMUL ATTVE		738.	656		
11 NC ING (1 F# 1000)					
INCREMENTAL CURULATIVE			, e	263 297	E E
PROTECTIVE SHELTERS			į	i	;
CUMULATIVE			33	220	230
HILES OF DIN RUADS					
INCREMENTAL CUMULATIVE		<u> 5</u>	88		
MILES OF CLUSILR RD INCREMENTAL			277	že	
CUNIU ATIVE			277	310	

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING

GROUP 9 (PAGE 9 OF 18)

								(PAGE 9 OF 18)
				GCANT	GUANTITY PER YEAR	ZV.		
CONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1908	1989	•
PFRSONNEL.		344.	1185	2396.	575.			
MATER (AF) INCREMENTAL CURNILATIVE		994.	3101	2280. 6376.	335 6 711.			
DISTURBED AREA (ACRES) INCREMENTAL CURULATIVE		1210	4664 5875	4002	666. 10543.			
MA FERTALS								
STEEL (TNS) INCREMENTAL CUMULATIVE				25687	7548. 33235.			
CINCREMENTAL INCREMENTAL CUMULATIVE				189	55.			
ASPHAL I (TNS#1000) INCREMENTAL CUMULATIVE		369 387	76 465					
AGGREGATE (CY*1000) INCREMENTAL CUMULATIVE		555. 555	2341	875 3771				
FRIMECUAL (TNS) INCREMENTAL UNCREMENTAL		1422	979 1700					
INCINCIPATION INCREMENTAL CONTULATIVE				409	120. 529			
PROTECTIVE SHELTERS JNCRFMENIAL CUMULATIVE				308	99 371			
MILES OF DEN ROADS INCREMENTAL CUMULATIVE		84	44 100					
MILES OF CLUSTER AD INCREMENTAL CUMULATIVE		, 55	368	143				

PERSONNEL MUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING

		TABLE 2-8.	TOTAL DDA CO	NSTRUCTION R	ESOURCES BY /UTAH FULL B	GROUP FOR PR ASTRG	TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADDA/UTAH FULL BASING	GROUP 10
				GUANT	QUANTITY PER YEAR	AR.		(PAGE 10 OF 18)
CUNSTRUCTION	1983	1984	1985	1986	1987	1788	1989	
PT-KSONNE1.				06	957	2002	717	
UNTER (AL.) INCREMENTAL CURULATIVE				235 235	2578 2813	2457 5271	418 5689	
DISTURBED AREA (ACRES) INCREMENTAL CUMULATIVE	a			276 276	3654 3930	4113	830 8872	
MATERIAI S								
STFEL (TNS) INCREMENTAL COMULATIVE						17962	9408 27370	
CONCRETE (CY*1000) INCREMENTAL CURBLATIVE						22.2	69 201	
AGPHALT (TNS*1000) INCREMENTAL CUMULATIVE				106	350 456			
ACGREGATE (CY*1000) INCREMENTAL CUMULATIVE				124	1792	1274 3121		
PRIMECOAT (TNS) INCREMENTAL CUMULATIVE				387 387	1279 1666			
FENCTING (CF. 1000) INCHEMENTAL COMULATIVE						2466 2706	150 435	
PROTECTIVE SHELTERS INCREMENTAL CUMULATIVE						Ī.	111 94(
MLES OF DIN ROADS JUCREMENTAL CURULATIVE				22	2.8			
MILES OF CLUSTER RD TRUCKFRENTAL CURIN ATTYR					20% 20%	Pot 434		

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING

QUANTITY PER YEAR

GROUP 11 (PAGE 11 OF 18)

PERSONRES PERSONNEL WATER (AF) INCREMENTAL CUPULATIVE INCREMENTAL CUPULATIVE PSTUBBE D AREA (ACRES) INCREMENTAL CUPULATIVE MATERIALS SIFEL (TNS) INCREMENTAL CUPULATIVE	1983 1984 42 124 124 145 145	42 764 24 1726 24 1850 24 1855 45 2549 45 2694 45 1955	1986 1262 1262 1262 193 193 19326 19326	43. 25. 3137. 49. 49. 49. 49. 1936.	1,788	1989
CRINCRE FE CCY 1000) INCREPIENTAL CUNTULATIVE ASSHALT CINS 1000)				11 S.		
INCREMENTAL CURULATIVE ACCREGATE (CY*1000) FOCKET GATE (CY*1000)	5 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6		-	c		
CUMULATIVE CUMULATIVE PROTECTIVE SHELTERS INTREBLITAL CUPIULATIVE MITES OF DIN RUADS INTREPLINIAL	-		240	1804		
CUMULATIVE HIN ES OF CLUSIFR RD INCREMENTAL CUMULATIVE	-	a 35	S			

PERSONNEL MUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING.

QUANTITY PER YEAR

GROUP 12 (PAGE 12 OF 18)

1989	41.	24. 3375.	48. 5216.		543	15640.	4	115								٥	249		\$	184			
1,700	760	564.	1121. 5168.		12708	15097.	73.	111.								505	240		0;1	178			
1987	1182	2786. 2786.	4046. 4046.		2389	2387	<u>5</u>	10	316	316.		1889))	1156.	1156.	30	E		533	Ŕ		€ ₹	248
1986																							
1985																							
1984																							
1983																							
CONSTRUCTION RESOURCES	PERSONNEL 1	WATER (AF) INCREMENTAL CUMULATIVE	DISTURRED AREA (ACRES) INCREMENTAL CUMULATIVE	MATERIALS	STEEL (TNS) INCREMENTAL	CUMULATIVE	I UNCHE LE LE VILLOGUI I NERE MEN FAL	CUMU ATIVE	ASPHAL I (TNS*1000) INCREMENTAL	CUMULATIVE	ACCRECATE (CY+1000)	CHACKERINIAL	PRIMECUAT (FNS)	INCREMENTAL	COMOLATIVE	INCREMENTAL	CUMULATIVE	PROTECTIVE SHELTERS	INCREMENTAL	CUMULATIVE	MILES OF DIN ROADS	INCREMENTAL CURULATIVE	NILES OF CLUSTIR RD INCREMENTAL CUNULATIVE

PERSONNEL MUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING. QNANTITY PER YEAR

GROUP 13 (PAGE 13 OF 18)

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING.
QUANTITY PER YFAR

GROUP 14 (PAGE 14 OF 18)

CUNSTRUCTION 19	PFRSUNNI'I	MAIER (AF) INCREMENTAL	CURIULATIVE	DISTURBED AREA (ACRES)	CUPIULATIVE	MATERIALS	STEEL (TNS)	INCREMENTAL	CUMULATIVE	CONCRETE (CY+1000)	INCREMENTAL	CUPILIAT I VE	ASPHAL 1 (TNS*1000)	INCREMENTAL	CUPILIA.AT1VE	ARGREGATE (CY*1000)	INCREMENTAL	COPPOLATIVE	THE CLOSE OF THE STATE OF THE S	CURINI ATTVE	11 NC 1NG (1 F * 1000)	INCREMENTAL.	CUPILLATIVE	PROTECTIVE SHELTERS	INC.REMENTAL	CURICALIVE	HILES OF DIN RUADS	SNOREM NIAL CURALATIVE	de careino lo sustan	INCREMENTAL
1983 1984																														
1985	639	1751	1751	9398	2398									344	344		1160	0911	0240	BC (1	•							१ १		V (1)
1986	1085	1018	2769	1793	4191			11720	11730		98	98					385	1545				187	187		130	138				69
1987																														
1780																														
1989																														

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING.

GROUP 15 (PAGE 15 OF 18)

YE AR	
PFR	
QUANTITY	

1989 1989																								
1987	231	135 3750	268 5813			3037		22	129									₹	280		36. 20.7			
1986	1439	1503 3615	2587 55 45			14558		107	101				658	1016				232	202.		171			107
1985	740	1996 2112	2819 2956								202	3.35	1301	1443		1033	1854						इ६	22
1984	40	116 116	137. 137.								25	350	1-9	14		161	17.1						==	
1983			_																					
CONSTRUCTION	PERSONNEL ¹	MATER (AF) INCREMENTAL CUMULATIVE	DISTURBED AREA (ACRES) INCREMENTAL CURULATIVE	MAIFRIAIS	GIFEL (TNS)	TNCREMENTAL	CONCRETE (CY#1000)	INCREMENTAL	CUNULATIVE	ASSEMBLE OF THE RESERVED TO 1 TO	INCRE MENTAL	CURIOLATIVE	INCREMENTAL	CURIDIATIVE	PRIMECOATCINS	INCREMENTA	CUMMAINT	INCREMENTAL	CUMMATIVE	PROTECTIVE SHELTERS	DNCPLPR NTAF CURBLATIOL	MILES OF DIN ROADS	INCREM NIAL CUROLATIVE	THE BLOW CLUSTER RD

1 PERSONNEL NUMBERS ARE YEARLY AVERAGES.

GROUP 16 (PAGE 16 OF 18)

OUP FOR PROPOSED ACTION. SING.	•
TAB.E 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FUR PROFUSED ACLIENT. NEVADA/UTAH FULL BASING.	CLIANTITY DED VEAR
TOTAL DDA	
TAB.E 2-8.	

1983 1984 1785 1986 1987 1989 1989	85, 1167. 410.	AL 250. 2095. 239. 250. 2344. 2583	1EA (ACRES) 2793. 3205. 474. AL 273. 3498. 3972.		7225 PSC7	6354. 1	ţ	47. 37.		112	112 260.	C1C1 CC) (0001+A	132		410	410. 952.	1000)	101	;	, o c .	.57	•	IAL SA					
CONSTRUCTION RESOURCES	PERSONNEL 1	WATER (AF) INCREMENTAL CURULATIVE	DISTURBED AREA (ACRES) INCREMENTAL CUMULATIVE	MATERIALS	STEEL (TNS)	INCREMENTAL	CONCRETE (CY*1000)	INCREMENTAL	CUNKA AT I VE	NEW TANGETON TO TANGE WEIGHT OF TANGE WEIGHT O	CUNIA,ATIVE	ACCREGATE (CY#1000)	INCREMENTAL	CUMULALIVE	INCREMENTAL	CUMMALATIVE	I'S NC INC (LF * 1000)	INCREMENTAL CUMULATIVE	PROTECTIVE SHELTERS	INCREMENTAL	CUPRILATIVE	HILES OF DIN ROADS	INCREMENTAL	CUNULATIVE	MILES OF CLUSTER HD	INCREMENTAL	INCREMENTAL CUMB AT I VE	INCREMENTAL CUMIN AT IVE

PERSONNEL MUMBERS ARE YEARLY AVERAGES.

TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAH FULL BASING.

QUANTITY PER YEAR

GROUP 17 (PAGE 17 OF 18)

CONSTRUCTION	1983	1984	1985	1986	1981	1788	. 6861	
RESOURCES								
PERSONNEL I				258	1538	725		
WATER (AF)								
INCREMENTAL				751	2617	539		
CUMULATIVE				751	3627	4167		
DISTURBED AREA (ACRES)								
INCREMENTAL				606	4404	1072		
CUMULATIVE				903	5387	6459		
HATERIALS								
STEEL (TNS)								
INCRE PENTAL					7404	12146		
CUMULATIVE					7404	19550		
CONCRETE (CY+1000)								
INCREMENTAL					10 u	F3		
COMPLATIVE ACREAL TAINS 1900)					r.	* * * * * * * * * * * * * * * * * * * *		
INCREMENTAL				906	89			
CUMULATIVE				308	375			
ACCREGATE (CY+1000)								
INCHEMENTAL				412	1772			
CUMMATIVE				-	2334			
THE CHAIL CHASE				1123	275			
CUMULATIVE				1125	1360			
FINCING (FF LOCK)								
INCREMENTAL					118	193		
CUMMANTIVE					=======================================	<u>.</u>		
PROTECTIVE SHELTERS					•			
IN I					è	143		
CUPRI, ATTOE					È	530		
MILES OF DIM RUMPS								
INCREMENTAL				ર્ટ્સ	<u> </u>			
MILES OF CLUSTER RD INCREMENTAL				Ξ	::00			
CUPRA AFTOF				z	O.E.			

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

		TABLE 2-8.	TOTAL DDA CO	NSTRUCTION R NEVADA	TION RESOURCES BY GROUP : NEVADA/UTAH FULL BASING.	GROUP FOR PI	TABLE 2-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PROPOSED ACTION, NEVADA/UTAM FULL BASING.	GROUP 18 (PAGE 18 OF 18)
				GUANT	QUANTITY PER YEAR	AR		· !
1								
CENSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1788	1989	
PLRSONNEL 1					763.	1752.	.666	
MATER (AL)					2080	2542	547	
CUMULATIVE					2080	4621	5168	
DISTURBED AREA (ACRES)	_				2877	4141	1087	
CUMULATIVE					2877.	7018	8105	
MAIERIALS								
STEEL (TNS)								
INCREMENTAL						13075	12320	
CONCRETE (CV+1000)						13073	£3413.	
INCREMENTAL						96	06	
CONTRACTOR						9,	. (81	
INCREMENTAL					372			
CUMULATIVE					372			
ACCIDED TO CY 1000)								
CUMULATIVE					1398	2203		
PRIME GOAT (TNS)					1			
INCHEMENTAL					1360			
CUMULATIVE					0901			
: I NC ING (I F # 1000)								
INCREMENTAL					c	מטיג	196	
CUNIN, ATTUF					c	208	404	

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

145 299

5.5

79.6 40.4

22

2 2

FILES OF DIN ROADY, JPK REMEMAN CUPIN ATTAT

PROTECTIVE SHELTERS IN: HI M! N/A!

PROPERTY OF CONTROL OF

APPENDIX 3

ALTERNATIVES 1 THROUGH 6, NEVADA/UTAH FULL BASING WITH OB COMPLEXES AT VARIOUS LOCATIONS.

ALTERNATIVES 1 THROUGH 6

Description

These alternatives use the same basic DDA layout as the Proposed Action, but different OB complex locations. Alternative 1 has the first OB complex near Coyote Spring Valley, Nevada, and the second OB complex near Beryl, Utah. Alternative 2 also has the first OB complex near Coyote Spring Valley, Nevada, but the second OB complex is near Delta, Utah. The first OB complex is located near Beryl, Utah, for both Alternatives 3 and 4. The second OB complex is located near Ely, Nevada for Alternative 3, and near Coyote Spring Valley, Nevada for Alternative 4. Alternatives 5 and 6 have the first OB complex located near Milford, Utah. The second OB complex is near Ely, Nevada for Alternative 5, and near Coyote Spring Valley, Nevada for Alternative 6.

Construction Scenario

The construction plan used for Alternatives 1 through 6 is almost identical to the plan for the Proposed Action, as shown in Figure 2-1 of Appendix 2. The same number of concrete plants, construction camps, marshalling yards/staging areas, and life support facilities are required. Minor adjustments are needed because of the alternate OB complex locations.

OB Complex Construction

The construction scenario described in Appendix 2 for the OB complexes for the Proposed Action is also valid for Alternatives 1 through 6. The only variation is the location for each of the OB complexes.

DDA Construction

Since the DDA is identical for the Proposed Action and Alternatives 1 through 6, there is no significant change to the construction plan for the DDA. Selection of different clusters for IOC could revise the construction schedule shown in Figure 2-4 of Appendix 2.

Construction Resource Requirements

Table 2-1 through 2-8 of Appendix 2 apply to Alternatives 1 through 6, as well as the Proposed Action. See Appendix 2 for the discussion of the construction resource requirements for the Proposed Action.

PRECEDING PAGE BLANK-NOT FILMED

APPENDIX 4

ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING WITH OB COMPLEXES NEAR CLOVIS, NEW MEXICO AND DALHART, TEXAS.

LIST OF FIGURES

- 4-1 System layout with construction plan for Alternative 7, Texas/New Mexico full basing.
- 4-2 First OB complex construction schedule for Alternative 7, Texas/New Mexico full basing.
- 4-3 Second OB complex construction schedule for Alternative 7, Texas/New Mexico full basing.
- 4-4 DDA construction schedule for Alternative 7, Texas/New Mexico full basing.

LIST OF TABLES

- 4-1 Average direct personnel requirements for Alternative 7, Texas/New Mexico full basing.
- 4-2 Average construction personnel requirements for Alternative 7, Texas/New Mexico full basing.
- 4-3 Average A&CO personnel requirements for Alternative 7, Texas/New Mexico full basing.
- 4-4 Average operations personnel requirements for Alternative 7, Texas/New Mexico full basing.
- 4-5 Total construction resources for Alternative 7, Texas/New Mexico full basing.
- 4-6. Total OB complex construction resources for Alternative 7, Texas/New Mexico full basing.
- 4-7 Total DDA construction resources for Alternative 7, Texas/New Mexico full basing.
- 4-8 Total DDA construction resources by group for Alternative 7, Texas/New Mexico full basing.



ALTERNATIVE 7

Description

Alternative 7, full basing deployment in Texas/New Mexico, has the first OB complex near Clovis, New Mexico, and the second OB complex near Dalhart, Texas.

Construction Scenario

The construction plan used in the analysis of the full basing deployment in Texas/New Mexico (Alternative 7) with operating base complexes near Clovis, New Mexico and Dalhart, Texas is shown in Figure 4-1. It is estimated that between four and seven concrete plants would be required in a total of 16 different locations. Construction camps would be colocated with the concrete plants. Water availability, aggregate availability, and minimum haul distances will be the final determining factors in the exact locations for these plants/camps.

OB Complex Construction

The need for construction camps at the OB complexes for the full basing deployment in Texas/New Mexico is not the same as in the Nevada/Utah region. The first OB complex near Clovis will require a construction camp, but the second OB complex near Dalhart will not. The proximity of the DDA and its construction camp in construction group number 11 (see Figure 4-1) to the second OB complex will allow the construction camp to be used for both the DDA and the OB complex.

The construction scheduling for the OB complexes was identical to that for the Proposed Action. The first OB complex near Clovis, would be constructed between 1982 and 1986. Construction of the second OB complex near Dalhart, will be between 1985 and 1989. Studies now in progress may change this preliminary scheduling.


Additionally, the construction scenario for the OB complexes for Alternative 7 is identical with that for the Proposed Action (see Appendix 2) with the exception, as stated above, that the second OB complex will be built from the construction camp associated with the DDA in group number 11.

Figures 4-2 and 4-3 show the construction schedules associated with the first and second OB complexes, respectively.

DDA Construction

Protective shelters and DTN and cluster roads are the major construction items that originate from the plants/camps. A range of between 150 and 400 protective shelters could be built from a plant/camp. The range of DTN road mileage built from a plant/camp is between 50 and 150 mi. Between 200 and 550 mi of cluster roads can be constructed from a plant/camp. These number ranges differ from those discussed for the Proposed Action because different construction rates were used.

Fifteen construction groups with from 8 to 19 clusters are organized into three general regions. The schedule for construction is shown in Figure 4-4. Construction



ignee 4-1. System layout with construction plan for Alternative 3. from New Nexton tall bestna.




Figure 4-2. First OB complex construction schedule for Alternative 7, Texas/New Mexico full basing.




Figure 4-3. Second OB complex construction schedule for Alternative 7, Texas/New Mexico full basing.

GROUP NUMBER	NUMBER OF CLUSTERS	1983	1984	1985	1986	1987	1988	1989
5	19							
6	8							
7	8							
8	9							
9	13							
10	10							
1	15	_						
2	14							
3	15							
4	15							
11	16							
12	17							
13	16							!
14	8							
15	17			 				

2003-A

Figure 4-4. DDA construction schedule for Alternative 7, Texas/New Mexico full basing.

137

31

would begin at the first operating base complex located near Clovis and progress to construction group number 5 by 1983. By 1985, construction would be occurring in all three of the regions. Detailed schedules and milestones will be established following final review of inputs and additional engineering.

Construction Resource Requirements

Table 4-1 shows that the peak demand for construction, assembly and checkout (A&CO), and operations personnel occurs in 1987-1988 with approximately 30,000 persons employed. Personnel requirements for construction peak in 1987 with approximately 16,000 employees. Similar to the Proposed Action, A&CO personnel requirements peak over a three-year span, 1986-1988, with about 6,000 people needed in each of the years. Operations personnel will reach about 13,000 by late $198^{\rm o}$, and remain constant thereafter. Tables 4-2, 4-3, and 4-4 give a more detailed breakdown for each of these types of personnel requirements.

Table 4-5 shows the total construction resources required for Alternative 7. Most of the construction resources reach a peak year demand in 1987. The same conditions apply to Alternative 7 as they did to the Proposed Action, as discussed in Appendix 2.

OB Complexes

The total construction resources required for both OB complexes are shown in Table 4-6. As is the situation with the Proposed Action, there is no one common peak year for all the construction resources. Except for two years of overlapping construction, the two OB complexes are constructed during different years.

DDA

The total resource requirements associated with construction of the DDA for the Texas/New Mexico full basing deployment are shown in Table 4-7. Water requirements include water for dust suppression, concrete, and direct employees, but not for revegatation. The disturbed areas include construction of protective shelters and roads but not temporary facilities, such as aggregate pits. Table 4-8 shows the construction resources required for each construction group.

Table 4-1. Average direct personnel requirements for Alternative 7, Texas/New Mexico full basing.

DESCRIPTION					PERS	ONNEL				
	1982	1983	1954	1985	1986	1987	1988	1989	1:000	1991
Construction										
DDA ¹		950	2.600	100	12,050	13 900	11 750	11,000	!	
First OB Complex:	1 150	1,900	2,400	2,000	1,200				!	
Second OB Complex			İ	200	1,350	2.050	1.450	750	1	
Subtotal	1,150	2,850	5,000	19,300	14,600	15,950	13,200	1 350		
A & CO DDA:	• • • •				-				ļ	
First OB Complex:		50	100	1,750	3,150	3,150	3.100	3,100	r 50	
Second OB Complex'		350	900	1,800	2,850	2.850	2.800	2,650	50	
Subtotal		400	1,000	3,550	5.000	6.900	5.96n	5,750	100	
Operations								i		
First OB Complex?			1 250	2,500	3,750	5,000	3,250	7.500	7,500	7.500
Second OB Complex		i		l	1,400	2.800	1,250	5,700	5.700	5.700
Subtotal	· ·	 	1,250	2.500	5.150	7.800	10.500	13.200	13.200	3.200
Total	1.150	3.250	7.250	16,350	25,750	29,750	29.600	23.300	13.300	13.200

 $^{^{1}\}mbox{DDA}$ includes PS, ASC, DTN, CMF, RSS, and CR.

First OB complex includes OB, DAA, OBTS, and airfield. The possibility of using the existing airfield at Clovis exists, but was not considered for this analysis.

^{&#}x27;Second OB complex includes OB and airfield.

Table 4-2. Average construction personnel requirements for Alternative 7, Texas/New Mexico full basing.

CAMP			COV	STRUCTI	ON PERS	ONNEL		
NUMBER 1	1982	1983	1984	1985	1986	1987	1988	1989
1			200	1,350	1,950	400		
2	İ		250	1,350	1,400	550	j	
3			200	600	850	1,250	850	
4					50	1,200	2,300	400
5		950	2.000	2,000	200		1 -,	
6			150	1,150	1,000		•	
7				200	1,250	700		
8					850	1,500	50	
9					50	750	1,850	650
10						500	1,350	800
11				1,200	2,150	1,050	ĺ	
12				200	1,450	2,200	500	
13				50	800	1,500	1,650	250
14					50	800	1,250	50
15	<u> </u>					900	1,950	1,450
Subtotal	1	950	2,600	8,100	12,050	13,900	11,750	3,600
First OB Complex	1,150	1.900	2,400	2,000	1,200			
Second OB Complex ¹				200	1,350	2,050	1,450	750
Tota.	1,150	2.850	5,000	10,300	14,600	15.950	13,200	4,350

See Figure 4-1 and 4-4.

See Figure 4-2.

*See Figure 4-3.

Table 4-3. Average A&CO personnel requirements for Alternative 7, Texas/New Mexico full basing.

GROUP NUMBER 1			A &	CO PERS	ONNEL			
NUMBER*	1983	1984	1985	1986	1987	1988	1989	1990
1			250	800	150			
2			350	400	300			
3				300	350	350	100	
4					150	300	600	
5	50	100	800	350				1
6			250	300				
7	·			300	300			
8					400	250		
ą					150	300	50∩	}
10						200	500	
11			100	450	450	100		l
12]		250	400	450	100	
13					500	400	300	
14		ļ				250	250	
15]				500	750	50
Subtotal	50	100	1,750	3,150	3,150	3.100	3,100	50
First OB Complex ²	350	900	1,800	2,850	2,850	2,800	2,650	50
Second OB Complex³								
Total	400	1,000	3,550	6,000	6,000	5,900	5,750	100

2172-1

¹See Figures 4-1 and 4-4.

²See Figure 4-2.

³See Figure 4-3.

Table 4-4. Average operations personnel requirements for Alternative 7, Texas/New Mexico full basing.

		OPE	RATIONS PI	ersonnel		
FMPLOYMENT TYPE	1984	1985	1986	1987	1988	1989
FIRST OF COMPLEX						
Officer	100	200	30C	400	50°	60C
Enlisted	950	1,925	2,900	3,850	4,800	5,750
Civilian	200	375	550	750	950	1,150
Subtotal	1,250	2,500	3,750	5,000	6,250	7,500
SECOND OB COMPLEX						
Officer			100	200	350	450
Enlisted			1,100	2,200	3,250	4,400
Civilian			200	400	650	850
Subtotal			1,400	2,800	4,250	5,700
Total	1,250	2,500	5,150	7,800	10,500	13,200

2173-1

NOTE: Operations employment will continue at 1989 levels throughout the operating life of the project.

Table 4-5. Total construction resources for Alternative 7. Texas/New Mexico full basing.

CONSTRUCTION			QU	ANTITY F	ER YEAR			
RESOURCES	1982	1983	1984	1985	1986	1987	1988	1989
Personnel ¹	1,150	2,834	4,981	10,278	14.414	15.874	13,102	4,259
Water (AF)								
Incremental	380	3,217	5,922	15,554	20,494	21,225	13,636	2,503
Cumulative	380	3,597	9,519	23,073	45,567	66,792	80,428	82,931
Disturbed Area (Acres)								
Incremental	1,740	6,444	11,171	22,110	32,030	34,483	22,208	4.311
cumulative	1,740	8,184	19,355	41,465	73,495	107,978	130,186	134,497
Materials	ĺ				•	l		
Steel (Tons)		Ì		[•	}		 	1
Incremental]	850	12,163	45,362	76.287	103,797	112,592	45,139
, Cumulative		850	13,013	58.375	134,662	238,459	351,0 51	396 , 190
Concrete (CY*1,000)								
Incremental		150	252	477	763	947	963	400
Cumulative	}	150	402	879	1,642	2,589	3.552	3.952
Asphalt (TNS*1,000)								
Incremental		657	968	2,443	1,198	1,508	170	100
Cumulative		657	1,625	4,068	5,266	6.774	6.944	7,044
Aggregate (CY*1,000)								
Incremental	140	1.863	3,483	8,910	12,210	11,781	6.421	277
Cumulative	140	2.003	5, 186	14,396	26,606	_38,387	14.308	45.085
Prime Coat (TNS)								
Incremental	}	2,403	4,414	10,032	5.041	3,936	1.310	350
Cumulative		2,403	7,217	17,249	22,290	29,226	30,806	01.386
Fencing (LF*1,000)								
Incremental			183	748	1,321	1,640	1.812	729
Cumulative	1		183	931	2,152	3,792	5,604	6.030

Personnel numbers are yearly averages.

Total OB complex construction resources for Alternative 7, Texas/New Mexico full basing. Table 4-6.

CONSTRUCTION			QU.	ANTITY P	ER YEAR			
RESOURCES	1982	1983	1984	1985	1986	1987	1988	1989
Personnel ¹	1,150	1,900	2,400	2,200	2,550	2,050	1.450	750
Water (AF)								
Incremental	380	620	750	820	950	800	570	280
Cumulative	_380	1,000	1,750	2.570	3,520	4,320	4,890	5,170
Disturbed Area (Acres)								
Incremental	1,740	3,000	3,600	470	1,530	2,240		[
cumulative	1,740	4,740	8,340	8,810	10,340	12.580		L
Materials								
Steel (Tons)		}		}	1	ŀ		}
Incremental		850	1,000	880	990	720	500	250
, Cumulative		850	1,850	2,730	3,720	4.440	4,940	5.190
Concrete (CY*1,000)								
Incremental		150	170	150	210	190	140	70
Cumulative		150	320	470	680	870	1,010	1,080
Asphalt (TNS*1,000)								
Incremental			280	240	150	240	170	100
Cumulative		ŀ	280	520	670	910	1.080	1.180
Aggregate (CY*1,000)								
Incremental	140	220	260	290	330	290	210	100
Cumulative	140	360	620	910	1.240	1.530	1.740	1,840
Prime Coat (TNS)								
ncremental			2,300	1,980	1.210	2.200	1.610	350
-amulative		! : .	2,300	1.280	5, 490	7.700	ļ	10,250
Fencing (LF*1,000)								
aucremental	}	İ	.5	10	23	, [20	. ~
'amutative			.5	15	38	38	29 37	15

Table 4-7. Total DDA construction resources for Alternative 7, Texas/New Mexico full basing.

		QUANT	ITY PER Y	EAR			
CONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1988	1989
Personnel ¹	934	2,581	8,078	11,864	13,824	11,652	3,509
Water (AF)	1		ĺ	1	1	1	1
Incremental	2,597	5,172	14,734	19,544	20,425	13,066	2,223
Cumulative	2,597	7,770	22,504	42,047	62,473	75,538	77,762
Disturbed Area (Acres)			1		,	,	
Incremental	3,444	7,571	21,640	30,500	32,243	22,208	4,311
Cumulative	3,444	11,015	32,655	63,155	95,398	117,606	121,91
Steel (TNS)	1		1			}	
Incremental	1	11,163	44.482	75,297	103,077	112,092	44,889
Cumulative	!	11,163	55,645	130,942	234,019	346,111	391,00
Concrete (CY *1,000)				1			
Incremental		82	327	553	757	823	330
Cumulative		82	409	961	1,718	2.541	2,870
Asphalt (TNS*1,000)		1			<u> </u>	}	1
Incremental	657	688	2,203	1,048	1,268		i
Cumulative	657	1,345	3,548	4,595	5,864	1	-
Aggregate (CY *1,000)	į			i			
Incremental	1,643	3,223	8,620	11,880	11,491	6,211	17
Cumulative	1,643	4,866	13,486	25,365	36,857	43,067	43,24
Prime Coat (TNS)	1						1
Incremental	2,403	2,514	8,052	3,831	4,636	1	,
Cumulative	2,403	4,917	12,969	16,801	21,437		
Fencing (LF *1,000)				1	1		
Incremental	i	178	708	1,198	1,640	1,783	714
Cumulative		178	885	2,083	3,722	5,505	6,219
Protective Shelters				1	1		
Incremental		131	523	886	1,213	1,319	528
amulative		131	655	1,540	2.753	4.072	4.60
diles et STN Roads		1.40		205	0.50		
.ncremental	141	148	474	225	273		
murative	141	289	763	988	1,261		
hos d Huster Roads	1.40	20.5	000	1 740	1 004	1 015	0/
Incremental	142	395	986	1,740	1.634	1.015	29
imulative	142	537	1,523	3,263	4,897	5,912	5,94

the the commons are rearily averages

4001-1

TABLE 4-3. TOTAL DDA CONSTRUCTION RESOUNCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

GROUP 1 (PAGE 1 OF 15)

CHANTITY PER YEAR

CHALLATIVE DISTIBLED AREA (ACRES) 14 CREWELTIVE CHALLATIVE WATTPIALS STEEL(THS) INCHEMENTAL THILLATIVE CHALLATIVE CHALLATIVE CHALLATIVE CHALLATIVE	187. 524. 524. 545.	1342. 2587. 3957. 4603. 6109.	1945. 2266. 5377. 3875. 8428. 18154. 24763.	386. 225. 5602. 447. 8875. 29325. 29325.	
ASPALITITYS*1000) [MCREMENTAL CUMGLATYNE CUMGLATYNE CUMGLATYNE CUMGLATYNE INCREMENTAL CUMGLATYNE CUMGLATYNE CUMGLATYNE CUMGLATYNE CUMGLATYNE CUMGLATYNE CUMGLATYNE	195. 195. 298. 298.	135. 1703. 2002. 1703. 1724.	1121. 3123. 289.	8 1. 6 5 5 -	
PROTECTIVE SHELTERS 14CREWEITAL CUMILATIVE CUMILATIVE 17CREWENTAL CUMULATIVE CUMULATIVE INCREMENTAL INCREMENTAL	42.	72. 72. 30.	214. 284. 193.	60. 345.	

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 4-8. TOTAL DNA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

GROUP 2 (PAGE 2 OF 15)

,	 	! ! ! ! !	1	DIANT	OHANTITY PER YFAP	d		
CDMS Form Literal	96.1	# H T T T T T T T T T T T T T T T T T T	ō i	1984	- !	1988	1989	
เป็นหมริศษย์		253.	1364.	1402.	526.			
WATER (AF) Luchemental Cimulative		708. 708.	2541.	1474.	306.			
DESTUDBED AKEN (ACRES) INCREMENTAL COMMENTATIVE		924.	4027.	2536.	609. 8096.			
Majgotads								
SPEPL(TVS) FYCPSMFHTAG CUHHLYTIVE			6154.	14119.	6897.			
TOTAL TATE OF THE PARTY OF THE			47.	104.	51.			
AVPLANTAL CONTRACTOR C		196.	45.					
GOODIAN GOODIA		43B.	1741.	650.				
AVITATION IN TAIL AND AND AND AND AND AND AND AND AND AND		718.	156. 884.					
INTRACE HTAG			101.	225. 326.	110.			
PROTECTIVE SHELTERS INCREWENTAL CUMILLATIVE			75.	166.	81.			
MILES OF OTH POADS INCHEMPMTAL		42.	10.					
MILES OF CLUSTFO ON INCREMENTAL. CHAIRATIVE		34.	276.	106. 416.				

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

GROUP 3 (PAGE 3 OF 15)

	1989		e v				81. 215.				1/5. 46f.	129. 345.		
1	1948	9 30	498.	970.		13997.	21			;	4	36		
QUANTITY PFR YEAR	1997	1842.	1973.	3382.		18328. 18328.	135.		890. 3499.	;	292.	216.		1.45
DISANT	1086	833.	2167.	3300.					1664.					
	2985	.484.	1688. 1688.	2060.				656.	946.	7397. 2397.			141.	ć
	1084													
	1083													
	NC) LODISAGE	Towns and	MATSE (AF) INDEFENIAL CASTVE	DISTUBRED AMEA (ACRES) INCREMENTAL CHAVILATIVE	MATERIALS	STEEL(TVS) INCREMENTAL CHAULATIVE	CONCRETE COLVERNO INCREMENTAL CONCRETER	ASP4AET(THS*1900) INCREMENTAL CUMULATIVE	AGGPFCATE (FY*1000) INCREMENTAL CUHBLATIVE	PPT4ECOAT(TNS) T4CP5MF4TAL CU4UCATIVE FFNCTVG(LF41000)	INCHEMENTAL COMPLATIVE	PROTECTIVE SHELTERS I (Cor of other) C: purit, A IVE	WILES OF BITA DOADS INCOFWENTAL CIMILATIVE	ue e419075 go 5571∎

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

		TABLE 4-8.	TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.	NSTRUCTION RE TEXAS/N	SOURCES BY (GROUP FOR AL JLL BASING.	TERNATIVE 7,	GROUP 4 (PAGE 4 OF 15)
•				QUANTITY P	CHANTITY PER YEAR			
# O 10		1984	1985	9861	1987	8861		
PERSONNEL 1	• • • •		} 	56.	1209.	2292.	386.	i bo e o araba a ababo e o e a e a de ababa a a e a
WATER (AE) 19CRFWENTAL CIMULATIVE				164.	2839.	2633. 5636.	225. 5861.	
NISTURBED AREA (ACRES) INCPEMENTAL CHMULATIVE				192.	4084.	4455.	647. 9178.	
MATERIALS								
STEFL(TNS) INCREMENTAL CUMBLATIVE					2618. 2618.	21645.	5062. 29325.	
CONCRETE (CY*1000) INCREMENTAL					19.	159.	37. 215.	
ASPUALTO (ASPIDAR) INCREMENTAL CUMULATIVE				74.	377.			
AGGRETATE(CY*1000) INCPFMENTAL TUMILATIVE				87.	1889.	1284.		
PRIMEDIATIONS TRUE CUMPERENTAL CUMPERTINE				270.	1379.			
FENCINCIDENTIONS) INCREMENTAL CHARLATIVE					42. 42.	3.00 to 1.00 t	81. 466.	
PROTECTIVE SHELTERS INCREMENTAL CHMULATIVE					31.	255. 285.	60. 345.	
MILES OF DTU ACADS INCREMENTAL CUMULATIVE				14.	91.			
MILES OF CLUSTED 3D INCHESENTAL CUMPLESTIVE					236.	210.		

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

JETTON RESOURCES BY GROUP FOR ALTERNATIVE 7.

GROUP 5 (PAGE 5 OF 15)

	T.	TABLF 4-8. TO	TAL DDA CONS	TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE (). TEXASONEW MEXICO FULL BASING.	TION RESOURCES BY GRAIP FOR ALTEXASONEW MEXICO FULL BASING.	ROUP FOR ALT LI BASING.	ERNATIVE
			1	GUANTIT	QUANTITY PEH YEAR	A P.	;
C)NSTBUCT (ON RESOURCES	1983	т Ф Ф	1945	1986	1987	886	
TankCSddd	934.	2008.	2024.	8			
#AIFH (AF) 14C0FWENTAL C1M(H.ATTVE	2597.	3538. 6135.	1648.	110.			
DISTURBED AREA (ACRES) INCORNERTAL CHALLATIVE	3444.	5518. 8962.	2995. 11957.	214.			
MATENTALS							
STFFL(FVS) INTHEMENTAL CHAUGATIVE		11163.	23512.	2470.			
CONTRETE (CV*1.00) INCREMENT INCREME		я2.	173.	18.			
ASPIALT (INS*1000) INCREMENTAL CHAULATIVE	657.	128.					
ACCRECATE (C.4*1000) INCREMENTAL CUABLETIVE	1643.	2257.	4374.				
PPINECONT(TIS) INCREMENTAL CHAOLATIVE	2403.	470.					
FENCTUGCLF*1000) INCREMENTAL CHAHLATIVE		174. 178.	374.	39.			
PROTECTIVE SHELTERS INCORPORTAL CHATLATIVE		131.	277.	70.			
MILES OF OTH ROADS INCREMENTAL COMMIGATIVE	141.	29.					
MILES OF CLUSTF9 RO THY PEMENTAL THY ULATIVE	142.	345. 448.	76.				

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

		TABLF 4-8.	TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE ITEXAS/NEW MEXICO FULL BASING.	HSTRUCTION R	ION RESOURCES BY GROUP FOR AL TEXAS/NEW MEXICO FULL BASING,	GROUP FOR AL FULL BASING,	TERNATIVE 7,	GROUP 6	
;		1	1 1 1 1 1	DUANT	OHANTITY PER YE	YEAR		(PAGE 6 OF 15)	
CONSTAURTION RESOURCES	1993	1984	1985	1986	1987	8861	6861	·	
PERSONNEL 1	; ; ; ; ; ;	138.	1129.	968.	17.	 			
MATER (AF) IVOSEMENTAL CIMULATIVE		403.	2143.	1009.	10.				
DESTUBBED AREA (ACRES) LACREMENTAL CUMMICATIVE		482.	3169.	1738. 5390.	20.				
MATEPIALS									
STEEL (TWS) 14CREAFNTAL CHAULATIVE			5598.	9819.	222.				
CONTRACTOR DEVENDENCE THEORY OF			41.	72.	115.				
COCCUPANA TABLE TO COCCUPANA TABLE T		168. 168.	269.						
AGGRETAR (TYRIDOD) TWO PERSTAN TURODATIVE		219.	1311.	440.					
TALLAND CONTRACTORS OR AND AND AND AND AND AND AND AND AND AND		614.	984. 1599.						
TELEGRAPHEN (TELEGRAPHEN)			 	156. 245.	240.				
PROTECTIVE SHELTERS INCOPATIATAL CUMILATIVE			65. 85.	116.	3.				
MIDES OF OTH PUADS INCREMENTAL		36.	5A.						
MILES OF CLUSTER PD INTREMEDIATIVE		4 4	163.	77.					

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

GROUP 7 (PAGE 7 OF 15)

				DUANT	DUANTITY PER YEAR	A		(PAGE 7 OF 15)	
CONSTRUCTION RESOURCES	1983	***	1985	1986	1987	886	6861		
PFR534NEL 1			215.	1243.	689.				
MATER (AF) Increental Combative			603.	2711.	543. 3254.				
DISTURNED AMEA (ACRES) INCOEMENTAL CJMHLATIVE	•		782.	3270.	994.				
MATEPTALS									
STEEL(TVS) INCREMENTAL COMBRATIVE				7524.	8116. 15640.				
CONCRETE(CY*1000) INCREMENTAL COMUGATIVE				55.	60. 115.				
ASPARTTTAS*1000) LACKEMENTAL COMULATIVE			175.	122.					
ATGOFTATE(CY*1000) INCHEWENTAL			369. 369.	1297.	140.				
PPI4ECOATCT4S) INCHEMENTAL CU4CLATIVE			641.	447. 1088.					
FENCT45(LF41000) INCPF4ENTAL CUMULATIVE				120.	129.				
PROTECTIVE SHELTERS INCHFWFNTAL, CUM-II,ATTVE,				 	95. 184.				
MILES OF DIN ROADS INCREMENTAL COMULATIVE			σ. α. ~	26. 64.					
MILES OF CLUSTFO AD INCREMENTAL			27.	188.	23. 238.				

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

GROUP 8 (PAGE 8 OF 15)

				OUANT	QUANTITY PER YEAR	A		(PAGE 8 OF 15)
NO STRUCTION RESOURCES	1983	1984	1985	1986	1987	8 tr 6 t	1989	
PFRSOUNEL 1				837.	1467.	39.		
MATER (AF) INCREMENTAL COMPLETIVE				1978. 1978.	1447.	23.		
DISTUBBED AREA (ACRES) INCREMENTAL COMBLATIVE				2858. 2858.	2521.	45.		
MATFRIALS								
STEEL(T4S) INCREMENTAL CUMULATIVE				1692.	15396.	508.		
CONCRETE (FY&1000) IMPREMENTAL CUMULATIVE				12.	113.	4. 129.		
ASP4ALT(TAS+1000) INTPEMENTAL CUMULATIVE				242.				
AGGGESATE (CYF1000) TACHERERIA GUAUGATIVE				1332.	586.			
PRESENTATIONS TO THE THE PROPERTY OF THE CONTRACT OF THE PROPERTY OF THE PROPE				88 83 4.				
FENCTUG(LF#1030) Jugnemar Cumilative				27.	245. 272.	8. 280.		
PROTECTIVE SHELTERS INCOUGHT HAL Camulative				20.	191.	207.		
WILES OF THE BOADS INCREMENTAL				52. 52.				
WILES OF CLOSTER PO INCHAMONTAL CHAULATIVE				171.	96.			

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

þ

TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

GROUP 9 (PAGE 9 OF 15)

QHANTITY PER YEAR

1 1 1							
CONSTRUCTION RESOURCES	1983	1001	1985	1986	1987	1988	1989
PERSONNEL.				20.	739.	1834.	633.
MATSR (AF) IVOPUFITAL CIMILATIVE				85 P	1921.	2168.	369. 4515.
DISTURBEN AREA (ACRES) INCREMENTAL CHMULATIVE				58. 68.	2841.	3650.	733.
MATERIALS							
STEGLITAS) TACREMENTAL					191.	16918.	8306. 25415.
CONCRETE (CY*1)OO) INCREMENTAL					<i>::</i>	124.	61.
ASPHALT (FASA1009) THEREMYNTAL				26.	113.		
AGGRETATE (CYF1000) INCHEMENTAL COMULATIVE				31.	1408.	1089.	
PRIMECOAF(TWS) INCREMENTAL				96. 94.	414.		
FENCIPETON) FENCIPETON) CACHEMENTAL CUMHIAFIVE						269.	132. 404.
PROTECTIVE SHELTERS INCREMENTAL					2.	199.	98. 299.
MILES OF DIM DOADS INCREMENTAL				.	24. 30.		
WILES OF CLUSTER OD TROREMENTAL CUMILATIVE					208. 208.	178. 386.	

TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS, NEW MEXICO FILL PASSING.		
TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE TEXAS, NEW MEXICO FILL NASING	~	
TABLE 4-8. TOTAL ODA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNAT TRAS/NEW MEXICO FILL BASING	IVE	
TABLE 4-8. TOTAL ODA CONSTRUCTION RESOURCES BY GROUP FOR ALTER TEXAS/NEW MEXICO FILL BASING	ž	
TABLE 4-8. TOTAL ODA CONSTRUCTION RESOURCES BY GROUP FOR AL	=	
TABLE 4-8. TOTAL ODA CONSTRUCTION RESOURCES BY GROUP FOR TEXACYNEW MEYTOR FILL BASIN	¥	٧
TABLE 4-8. TOTAL ODA CONSTRUCTION RESOURCES BY GROUP TEXAS/NEW MEXICO FILL BA	50	5
TABLE 4-8. TOTAL ODA CONSTRUCTION RESOURCES BY O	ROUP	- BA
TABLE 4-8. TOTAL ODA CONSTRUCTION RESOURCES E	~	-
TABLE 4-8. TOTAL ODA CONSTRUCTION RESOURCE	S	1
TABLE 4-8. TOTAL DDA CONSTRUCTION RESOU	RCE	Ĕ
TABLE 4-8. TOTAL DDA CONSTRUCTION RE	Sou	3
TABLE 4-8. TOTAL DDA CONSTRUCTION	æ	×
TABLE 4-8. TOTAL DDA CONSTRUCT	8	XX
TABLE 4-8. TOTAL DDA CONSTRI	35.	-
TABLE 4-8. TOTAL DDA CONS	181	
TABLE 4-8. TOTAL DDA	No	
TABLE 4-8. TOTAL	¥00	
TABLE 4-8. TOT	₹	
TABLE 4-8.	101	
TABLE	4-8.	
T AE	3,6	
	TAE	

		TABLE 4-8.	TOTAL DDA CO	TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.	TION RESOURCES BY GROUP FOR AL TEXAS/NEW MEXICO FULL BASING.	ROUP FOR AL	TERNATIVE 7,	GROUP 10
;				DUBNT	OUBNITY PER YEAR	# #		(FAGE 10 OF 15)
, c _ s	1983	1984	1985	1986	1987	686	686	
PERSTAREL T	; ; ; ;		• • • • • • • •	: : : : : : : : : : :	486.	1340.	764.	
MATER (AF) INCOFAFNIAL CUMULATEVE					1328.	1883.	583. 3794.	
DISTUMBED AREA (ACRES) INCREMENTAL CHMULATIVE					1827.	3082.	1076.	
WATERIALS								
STEEL (TUS) [NOPERENTAL CHULATIVE						10418.	9132.	
CONTRACTOR TATABLE TO TATABLE TO TO TO						76.	67.	
AND ABLICIAN (1900) INCHEMENTAL CHAULATIVE					251. 251.			
ACGPECATE (CY*1009) INCREMENTAL CU*(CATIVE					886. 886.	1091.	136.	
APTHEMINEDU APTHEMINEDU APTHEMINEUR AND ARTHUR				918.				
FFWCLVGCLF*1000) INCHEMENTAL COMMINATIVE						156.	145. 311.	
PROTECTIVE SHELTERS INTRINGUENTAL CIMULATIVE						123.	107.	
MILES OF OTH ROADS INCREMENTAL CHAULATIVE					54.			
MILES OF CLUSIED OF INCREMENTAL					97.	178.	22.	

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 4-8. TOTAL DDA CONSTRUCIION RESOURCES BY GROUP FOR ALTERNATIVE 7. TEXAS/NEW MEXICO FULL BASING.

		TABLE 4-8. T	OTAL DDA COP	STRUCTION R	TABLE 4-8. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.	ROUP FOR ALT ILL BASING.	ERNATIVE 7,	GROUP 11
;				OHANTITY	CHANTITY PER YEAR			(PAGE 11 0F 15)
CONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	9861	1989	
PERSONNEL "			1197.	2130.	1054.			
MATER (AF) IMCPEMFNTAL CHMULATIVE			2849.	3112.	809. 6771.			
DISTURNED APEA (ACRES) INCREMENTAL CUMULATIVE			3844.	5059. 8903.	1492.			
HATERIALS								
STEEL(TVS) INCREMENTAL CHUDLATIVE			2908. 2908.	15802.	12570.			
COCHATCH TO COCHAT			21.	116.	230.			
COOLEANT TERMINATE			712.	721.				
ACCASIANTE (CTATOGO) INTRANTAL CUMINISTRANTAL			1708.	1846.	193.			
ANITATIONAL DATE OF THE PROPERTY OF THE PROPER			2603.	32. 2635.				
TALLES			46. 45.	251. 298.	498.			
PROTECTIVE SHELTERS I TORF WE WITAL CUMILATIVE			8. W 4. 4.	186.	148. 368.			
MILES OF OTH ROADS INCREMENTAL COMULATIVE			153.	2.				
MILES OF CLUSTER AN TAIRENTAL CUMULATIVE			142.	300.	32.			

PERSONNEL MUMBERS ARE YEARLY AVERAGES.

		TABLE 4-8.	TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL DASINS.	STRUCTION RE TEXAS/N	TION RESOURCES BY GROUP FOR A TEXAS/NEW MEXICO FULL DASING.	ROUP FOR ALT	ERNATIVE 7,	GROUP 12 (PAGE 12 OF 15)
				DUANT	QUANTITY PER YEAR			
CONSTRUCTION	1993	1944	1985	1986	1987	1988	1989	
PFR SOUNFL!			204.	1438.	2218.	467.		
MATER (AF) INCREWENTAL CUMPLATIVE			587. 587.	2897.	2479.	272.		
DISTURBED AREA (ACRES) INCREMENTAL CUMULATIVE			751.	4416.	4217.	541.		
MATERTALS								
STEEL(TNS) INCREMENTAL CUMBLATIVE				5717.	21389.	5129. 33235.		
CONCRETE(CY*1900) LUCREMENTAL CHMULATIVE				42. 42.	157.	45.		
ASPHALT(TAS*1000) Incremental Cuqulative			184.	146.				
AGGRESATE(CY*1000) TNCRFMENTAL CU4ULATIVE			352. 352.	1951.	1175.			
PRIMECONT(TNS) INCREMENTAL CUMBLATIVE			672.	535.				
FENCTAG(LF*1000) INCREMENTAL CUMULATIVE				91.	340.	97.		
PROTECTIVE SHELTE'S 1vC'FMENTAL CUMULATIVE				67.	252.	72. 391.		
MILES OF DTN ROADS INCREMENTAL CHMULATIVE			40.	31.				
MILES OF CLUSTER RD INCREMENTAL CUMPLATIVE			27.	291.	192.			

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 4-8. FOTA DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

GROUP 13 (PAGE 13 OF 15)

ļ				OUANTI	QUANTITY PER YEAR	æ	0 1 2 1 2 3 4 6 6 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	• • • • • • • • • • • • • • • • • • •
CONSTRUCTION 19 RESOURCES	1983	1984	1985	1986	1987	8 86 1	. 6861	
1 TankCsdad			16.	795.	1492.	1642.	226.	
WATER (AF) Inchemental Chalbative			47.	2174.	2538.	1257.	132.	
DISTURATO AREA (ACRES) TYCKEMENTAL CHMJLATIVE			55. 55.	2986. 3041.	4045.	2318.	261. 9566.	
MATERIALS								
STEELITAS) INCRPWFATAL CUKULATIVE					8728. 8728.	19589.	2962. 31280.	
CONTRATE(TV+1000) INDKERMENTAL OUKDATIVE					64.	144.	22.	
ASPHALT(TNS*1900) INCREMENTAL TUHULATIFE			21.	416.				
AGGRETATE(CT#1000) THORPMENTAL CUMULATIFE			25.	1447.	1652.	297.		
PRIMERONAT(TAS) INCREMENTAL COMBLATIVE			77.	1521. 1598.				
FFMT14G(LF+1000) INCPFWFN1AL CUMULATIVE					139.	312. 450.	47.	
PROTECTIVE SHELTERS INCREMENTAL CHARLATIVE					193.	230.	35. 36#.	
MILES OF OTS GOADS TYCHEMENTAL CHALLATTER			ů.	80.				
MIDES OF CIRSTED OF INCREMENTAL				157.	270.	49.		

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

Table 4.9. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICO FULL BASING.

;

	-	able 4. 3.	TOTAL DDA CON	Table 4.3. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE TEXAS/NEW MEXICO FULL BASING.	TON RESOURCES BY GROUP FOR ALTEXAS/NEW MEXICO FULL BASING.	ROUP FOR ALT	ERNATIVE 7,	GROUP 14	
				OUANT	QUANTITY PER YEAR	G A		(PAGE 14 OF 15)	
CINSTAUTEUN RESOURCES	1983	1984	1 185	1986	1987	1989	1989		
FERTILITE TO THE TOTAL THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO THE TOTAL TO T	; ; ; ; ; ; ;	; ; ; ; ; ;		10.	R10.	1235.		9	
MATSP (AF) INCREMENTAL CHMBLATIVE				29.	1615.	1432.	22. 3098.		
DISTURPED AREA (ACRES) INCREMENTAL CIMILATIVE				* * *	2366.	2420.	4864.		
HATERIALS									
STEEL(TAS) INCREMENTAL CLASSING					3559. 3559.	11580.	501. 15640.		
COMMERCIAL CONTRACTOR					26.	85. 111.	4.		
ANTABLE LANGE 1000 FANDEMENTAL CUMULATIVE				13.	215.				
AGGRETATE(CY*1000) INCREMENTAE CUMULATIVE PRIMECOAT(TWS)				15.	1019.	705.			
INCREMENTAL CHANDATIVE FENCING(LE #1000) INCREMENTAL CHANDATIVE				47.	786. 833. 57. 57.	184. 241.	2 8 .		
PROTECTIVE SHELTERS INCREMENTAL COMPLATIVE					42.	136.			
ATES OF OTAL BORDS INCREMENTAL				<i></i>	45.				
Alles of cluster of					123.	115.			

PERSONNEL MUMBERS ARE YEARLY AVERAGES.

	-	TABLE 4-8. TO	TAL DDA CONS	TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR ALTERNATIVE 7, TEXAS/NEW MEXICA FULL BASING.	TION RESOURCES BY GROUP FOR ALTEXAS/NEW MEXICO FULL BASING.	OUP FOR ALTE L BASING.	RNATIVE 7,	GROUP 15
				OUANT	OUANTITY PER YEAR	A.R.		(PAGE 15 OF 15)
CONSTRUCTION	1983	1984	1985	1986	1987	1988	1989	
PERSONNEL 1	1	1			. 688	1965.	1462.	3
MATFK (AF) INCOFWERTAL CHMULATIVE					2391.	2910.	893. 6194.	
DISTURBED AREA (ACRES) INCHEMENTAL CHABLATIVE					3399.	4726.	1750. 9875.	
*ATERIALS								
STEEL(THS) INCREWENTAL CUMULATIVE						14310.	19925. 33235.	
CONCRETE(CY#1000) INCREMENTAL COMULATIVE						105.	139.	
ASPHALT(TNS*1000) INCREMENTAL CUMULATIVE					312.			
AGGREGATF(CY*1000) INCREMENTAL CUMULATIVE					1670.	1747.	40. 3456.	
PPI4ECOAT(TNS) INCREMENTAL CO4ULATIVE					1139.			
FEWCTUG(LETTOOD) INCHEUFNIAL COMULATIVE						228. 228.	301.	
PROTECTIVE SHELTERS INCOPPHENTAL COMPLATIVE						168.	223. 391.	
MILES OF OTH WORDS INCOSMENTAL CHONICATIVE					67.			
MIRS OF THERE OF THE TRANSPORT OF THE TR					213.	285. 438.	, 505.	

PERSONNEL MUMBERS ARE YEARLY AVERAGES.

APPENDIX 5

ALTERNATIVE 8, NEVADA/UTAH/TEXAS/NEW MEXICO SPLIT BASING WITH OB COMPLEXES NEAR COYOTE SPRING VALLEY, NEVADA AND CLOVIS, NEW MEXICO.

LIST OF FIGURES

- 5-1 System layout with construction plan for portion of Alternative 8, Nevada/Utah split basing.
- 5-2 System layout with construction plan for portion of Alternative 8, Texas/New Mexico split basing.
- 5-3 First OB complex construction schedule for portion of Alternative 8, Nevada/Utah split basing.
- 5-4 Second OB complex construction schedule for portion of Alternative 8, Texas/New Mexico split basing.
- 5-5 DDA construction schedule for portion of Alternative 8, Nevada/Utah split basing.
- 5-6 DDA construction schedule for portion of Alternative 8, Texas/New Mexico split basing.

LIST OF TABLES

- 5-1 Average direct personnel requirements for portion of Alternative 8, Nevada/Utah split basing.
- 5-2 Average direct personnel requirements for portion of Alternative 8, Texas/New Mexico split basing.
- 5-3 Average construction personnel requirements for portion of Alternative 8, Nevada/Utah split basing.
- 5-4 Average construction personnel requirements for portion of Alternative 8, Texas/New Mexico split basing.
- 5-5 Average A&CO and operations personnel requirements for portion of Alternative 8, Nevada/Utah split basing.
- 5-6 Average A&CO and operations personnel requirements for portion of Alternative 8, Texas/New Mexico split basing.
- 5-7 Total construction resources for portion of Alternative 8, Nevada/Utah split basing.
- 5-8 Total construction resources for portion of Alternative 8, Texas/New Mexico split basing.

- 5-9 Total OB complex construction resources for portion of Alternative 8, Nevada/Utah split basing.
- 5-10 Total OB complex construction resources for portion of Alternative 8, Texas/New Mexico split basing.
- 5-11 Fotal DDA construction resources for portion of Alternative 8, Nevada/ Utah split basing.
- 5-12 Total DDA construction resources for portion of Alternative 8, Texas/ New Mexico split basing.
- 5-13 Total DDA construction resources by group for portion of Alternative 8, Nevada/Utah split basing.
- 5-14 Total DDA construction resources by group for portion of Alternative 8, Texas/New Mexico split basing.

ALTERNATIVE 8

Description

Alternative 8, split basing, proposes a first OB complex near Coyote Spring Valley, Nevada with a second OB complex near Clovis, New Mexico. Split basing denotes dividing the required 200 clusters into several deployment regions. The alternative under consideration will distribute the clusters among the four states of Nevada, Utah, Texas, and New Mexico.

Construction Scenario

The construction plan used in the analysis of the portion of Alternative 8 for the Nevada/Utah region with the first OB complex near Coyote Spring Valley, Nevada, is shown in Figure 5-1. The construction plan for the Texas/New Mexico portion of Alternative 8, with the second OB complex near Clovis, New Mexico, is shown in Figure 5-2.

For the split basing deployment portion in Nevada/Utah, five to seven concrete plants would be required in a total of nine different locations. In the Texas/New Mexico portion, four to six concrete plants would be needed in a total of eight different locations. Colocated with these plants would be the construction camps, marshalling yards/staging areas, and life support facilities. The exact locations for these plants/camps will be determined based on the following criteria: water availability, aggregate availability, and minimum haul distances.

OB Complex Construction


Each of the OB complexes will have a construction camp for the building construction, such as concrete and concrete block structures, metal structures, and wood frame structures.

The first OB complex, near Coyote Spring Valley, Nevada, contains an OB, DAA, OBTS, and an airfield. Construction is scheduled to start in 1982, and to be completed in time for IOC in 1986. As is the case with the Proposed Action, most of the construction in the first year will be concentrated in the DAA, OBTS, and at the airfield. A section of the DTN connecting the DAA to the DDA will also be constructed from the camp in the OB complex. Construction in the OBTS and at the airfield should be completed by 1984. The construction schedule for the first OB complex is shown in Figure 5-3.

The second OB complex, near Clovis, New Mexico, contains an OB, DAA, and an airfield. Split basing is the only deployment alternative that requires a DAA in the second OB complex. Construction is scheduled to begin in 1983 and continue through to 1987. The second OB complex does not have to be operational for IOC. Figure 5-4 shows the construction schedule for the second OB complex.

DDA Construction

The key construction items originating from the DDA plants/camps are DTN roads, cluster roads, and protective shelters. The length of the DTN road constructed from a plant/camp is between 50 and 200 mi. Between 300 and 750 mi



ACSP

11.




Figure 5-3. First OB complex construction schedule for portion of Alternative 8, Nevada/Utah split basing.




Figure 5-4. Second OB complex construction schedule for portion of Alternative 8. Texas New Mexico split basing.

of cluster roads can be constructed from a plant/camp. The number of protective shelters built from a plant/camp ranges from 200 to 400.

Eight construction groups were combined in two general regions to produce the schedule in Figure 5-5 for the Nevada/Utah portion of Alternative 8. Construction would begin at the first OB complex in 1982, and progress to Construction Group Number 1 by 1983. The early 1984 construction would be occurring in both of the regions. The construction period for a group ranges from two and one-half to three years.

For the Texas/New Mexico portion of Alternative 8, seven construction groups, containing between 12 and 16 clusters were combined in two general regions. Construction operations for this representative system were analyzed in accordance with the schedule shown in Figure 5-6. Construction would begin at the second OB complex in 1983 and by mid-1985 would be occurring in both regions. Changes to the construction schedule could be made.

Construction Resource Requirements

Tables 5-1 and 5-2 show the average direct personnel required for Alternative 8 for any given year in Nevada/Utah and Texas/New Mexico, respectively. The peak year for construction personnel occurs in 1985-1986 for Nevada/Utah, with approximately 8,000 workers, and 1986-1987 for Texas/New Mexico, with approximately 9,000 workers. The average construction work force for split basing would peak in 1986 with approximately 17,000 personnel required. These numbers coincide with those for the Proposed Action. The combined A&CO personnel requirements peak over a four-year span, 1986-1989, with about 7,000 people needed in each of the years. Combined operations personnel peak in 1989, at the time of FOC, with over 13,000 people required. Both A&CO and operations personnel required for Alternative 8 exceed the requirements for the Proposed Action. This is because the second OB complex for Alternative 8 has a DAA, whereas it does not for the Proposed Action. Tables 5-3, 5-4, 5-5, and 5-6 give a more detailed breakdown of personnel requirements for construction, A&CO, and operations.

The total construction resources for Alternative 8, split basing in Nevada/Utah and in Texas/New Mexico are shown in Tables 5-7 and 5-8, respectively. For Nevada/Utah the incremental construction resources quantities peak in a span from 1985 to 1986. The incremental quantities for construction resources for Texas/New Mexico also peak over a span of two years, 1986-1987. Generally, the cumulative construction resources requirements for Nevada/Utah/Texas/New Mexico (Alternative 8) are higher than for the Proposed Action because there is a DAA located in the second OB complex.

OB Complexes

Tables 5-9 and 5-10 show the total construction resources for the first OB complex (Nevada/Utah) and the second OB complex (Texas/New Mexico), respectively. The first OB complex is constructed between 1982 and 1986, with the peak year requirements generally occurring in 1984. The second OB complex is constructed between 1983 and 1987, with 1985 generally being the peak year for construction resources.

GROUP NUMBER	NUMBER OF CLUSTERS	1983	1984	1985	1986	1987	1988	1989
1	10							
6	17							
7	14							
8	9						-	
5	10							
4	15				_			
3	13							
2	12							
			<u> </u>					
			\ \ 					
							•	
			,					
		<u> </u>						

Figure 5-5. DDA construction schedule for portion of Alternative 8, Nevada/Utah split basing.

GROUP NUMBER	NUMBER OF CLUSTERS	1983	1984	1985	1986	1987	1988	1989
1	12							
2	15							
3	15							
4	15							
5	16							
б	15							
7	12							
				' 				
1		l			_	ļ	ŀ	ł

3223-A

Figure 5-6. DDA construction schedule for portion of Alternative 8, Texas/New Mexico split basing.

i.

Table 5-1. Average direct personnel requirements for portion of Alternative 8, Nevada/Utah split basing.

DESCRIPTION					P	ERSONNEL	•			
2230	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991
Construction DDA ¹ First OB Complex ²	1,100	100 1,850	1,900 2,400	6,200 2,050	6,750 1,250	6,350	4.500	1.200		
Subtotal	1,100	1,950	4,300	8.250	8,000	6,350	4,500	1.200		-
A & CO DDA ¹ First OB Complex ²		50 25 0	100 700	1,350 1,350	2,300 2,150	1,650 2,150	900 2,100	950 2.000	50	
Subtotal		300	800	2,700	4,450	3,800	3,000	2,950	50	
Operations First OB Complex ²			1,250	2,450	3,700	4.950	6.250	7,400	7,400	7,400
TOTAL	1,100	2,250	6,350	13,400	16,150	15,100	13.750	11.550	7,450	7,400

2250-3

 $^{^{1}\}mbox{DDA}$ includes PS. ASC. DTN. CMF. RSS. and CR.

 $^{^2\}mbox{First OB complex includes OB. DAA, OBTS, and airfield.}$

Table 5-2. Average direct personnel requirements for portion of Alternative 8, Texas/New Mexico split basing.

		• -		PERSCUNEL							
PERSONAL TOTAL	1882	1983	1081	1985	1986	1987	1085	1858	1099	1891	
: Structi :: 1894::											
en en en en en en en en en en en en en e	:	t ton			2.000		6.800 j	2,650	:		
	†		1.19%	4.350	** *****	J. 1150	e.80)	2,650		1	
1 1 1 1 X		÷	7.10			1	Į.	2,150 2,000	56 50		
		1.5	700	1,750	1 14 je je je j	2 050	4.50	1,150	150		
		• • • • • • • • • • • • • • • • • • • •		1,250	1 1.400	5.700	 4 850	i i	1	6.08/	
	; I	1 15 -	156		†			 12 ×50	1 .		
	<u> </u>	l	L	l		!	1	·	1	<u>, 565 -</u>	

Table 5-3. Average construction personnel requirements for portion of Alternative 8. Nevada/Utah split basing.

GROUF	CONCERTOR PERSONSEL									
NUMBEE:	1982	1983	1044	1931	1916)	1.487	1988	1986		
<u>:</u>		1.00	1.000	1.500	150			·		
2					2		1.00	2400		
. 5		,			7.55	1.50	i 800			
-4		ĺ	[5]	7	1, 150			1		
· 5			"/ TH"	1 7.0	<i>F</i> 1	į				
, R			₹. etc	1, (8)	1.75	i				
7				25)	1,19		from			
5							466	7.00		
Sintetai		1000	V.35 6	1.4	. 1		4 50	: fant		
First Ob Complex:	1,100	1.850	2 40.	1 50	in a	I.	į			
Mat:	1.100	1.970	9.3%			1 11	1 3.0	1 20		

2551-1

"See Figures 5-1 and 5-5

iden Figure 5-0

Table 5-4. Average construction personnel requirements for portion of Alternative 8, Texas/New Mexico split basing.

GROUP	CONSTRUCTION PERSONNEL											
NUMBER!	1982	1983	1984	1985	1986	1987	1988	1989				
1			100	1.200	1,950							
2	1 :			450	1,850	1,750		1				
3	i				700	2,000	1,500	į į				
4	į į		į			450	2,100	1.250				
ā) ;			300	1,900	1.900		!				
6					350	1,950	1.500	i				
7						100	1,700	1 400				
Subtotal				1,950	6,750	8,150	6.800	2,650				
Second Ob Complex		300	1,850	2,400	2,000	1.200						
Tetal		300	1,950	4,350	8,750	9.350	6.806	2,650				

5566-2

¹Sec Figures 5-2 and 5-6.

¹See Figures 5-4.

Table 5-5. Average A&CO and operations personnel requirements for portion of Alternative 8, Nevada/Utah split basing.

ſ	GROUP NUMBER OR	A & CO AND OPERATIONS PERSONNEL										
 	EMPLOYMENT TYPL ¹	1982	1983	1984	1985	1986	1987	1988	1.4-3	1.09		
	1		50	50	400	200	5.0			:		
	2		Ì				100	350	4.50			
	3	1				300	450	260	50			
	.,	,			200	600	350					
	5			1	400	250	:00	1				
3	6	ļ		50	250	600	200	!				
ń	7	1			100	250	400	150				
< .	8 		<u> </u>	<u> </u>	<u> </u>	<u> </u>		. 200	45-			
	Subtoral	T.	50	100	! 1,350	2,300	1.650	76,0	95c			
•	First DB Complex?		250	700	1 350	2,150	2,150	2 . 40	2,300			
	retai		300	800	2,700	4.450	0.809	3, 600	2 95)	3.		
	First OB Complex:			1		1						
3	Three		i	100	200	300	400	5.43	300	300		
Ė	Enlistei		İ	950	1.900	2,850	3.800	1 8000	5 700	5.706		
=	Civilian	: •		200	350	550	750	25.1	301	1.100		
÷	, Total			1,250	2,450	3,710	4,950	3 25°	7 100	7.40		

Then Figures 5-1 and 5-5.

tem Figure 5-3

Note operations employment will continue at 1980 levels throwness the genetics \dots to the project.

Table 5-6. Average A&CO and operations personnel requirements for portion of Alternative 8, Texas/New Mexico split basing.

	SE SUP NUMBER!		A &	CO AND	OPERAT	IONS PE	PSONNEL			
	TABE OB EMELTOAMEZE	1982	1983	1984	1985	1986	1987	1088	1989	1996
	:			400	460			}		
	2				190		580	306		
	3						170	500	400	
	4	ļ		i				370	700	
S	5.				200	,	580	370		[
تند							170	500	400	
<	7							160	€50	50
	Subtotal			400	850		1.500	2,200	2.150	50
	Second OF Committee		250	700	1.350	2,150	2,150	1.100	2,500	50
	Tetal		250	700	1,750	3,000	3,650	4,300	4,150	100
	second OF									
PAULONE	Officer				100	200	300	400	500	500
	ralisted]		950	1,850	0,850	3,700	4,650	4,650
	ivilian				200	350	550	750	500	900
_	Terman				1.250	2,400	3,700	4,850	6,050	6.050

that Engages 5-2 and 5-6.

See Elmane 2-4.

therations employment will continue at 1989 levels throughout the operating $\ldots t_{\ell}$ of the project.

Table 5-7. Total construction resources for portion of Alternative 8, Nevada/Utah split basing.

CONSTRUCTION			QU	ANTITY P	ER YEAR			
RESOURCES	1982	1983	1984	1985	1986	1987	1988	1989
Personnel ¹	1,100	1,971	4,314	8,274	7,993	6,323	4,450	1,208
Water (AF)		-				•		
Incremental	360	947	5,696	11,672	10,346	8,671	5,387	704
Cumulative	360	1,307	7,003	18,675	29,021	37,692	45,0°9	43,783
Disturbed Area (Acres)								
Incremental	1,670	3,339	10,513	16,687	15,528	14,057	8,934	1,399
cumulative	1,670	5,009	15,522	32,209	47,737	61,794	70,728	72,127
Materials								
Steel (Tons)			}					l
Incremental		820	3,086	36,327	51,265	50,972	40,443	15,586
, Cumulative		820	3,906	40,233	91,498	142,470	182,913	198.769
Concrete (CY*1,000)								
Incremental		140	195	410	463	374	297	116
Cumulative		140	335	745	1,208	1,582	1,879	1,995
Asphalt (TNS*1,000)								
Incremental		160	1,233	1,217	1.004	256	132	
Cumulative		160	1,393	2,610	3,614	3,870	4.002	
Aggregate (CY*1,000)								
Incremental	130	388	3,450	6.924	5,588	4,784	2,686	
Cumulative	130	518	3,968	10.892	16,480	21,264	23.950	
Prime Coat (TNS)								
Incremental		387	5,733	5.321	4.315	935	188	
Cumulative		587	6,320	11.841	16,156	17,091	17,579	
Fencing (LF*1,000)			 	 				
Incremental			37	604	831	811	240	25:
-'umulative			37	641	1.472	2,283	643 2.026	254 0,180
Darganna numbers ire	L	1	<u> </u>	1 7.1		2,200	البــــــــــــــــــــــــــــــــــــ	710 2

Personnel numbers are yearly averages.

Table 5-8. Total construction resources for portion of Alternative 8, Texas/New Mexico split basing.

CONSTRUCTION			QU.	ANTITY P	ER YEAR			
RESOURCES	1982	1983	1984	1985	1986	1987	1988	1989
Personnel 1		300	1,933	4,326	8,711	9,294	6,811	2,658
Water (AF)								
Incremental		110	885	5,748	12,701	11,546	8,984	1,782
Cumulative		110	995	6,743	19,444	30,990	39,974	41,756
Disturbed Area (Acres)								
Incremental		570	3,607	10,913	18,157	17,993	14,625	3,402
cumulative		570	4,177	15,090	33,247	51,240	65,865	69.267
Materials								
Steel (TNS)								
Incremental			740	3,315	38,188	65,561	57,278	33,369
, Cumulative			740	4,055	42,243	107,804	165,082	198,45
Concrete (CY*1,000)								
Incremental		1	140	197	424	568	420	24
Cumulative			140	337	761	1,329	1,749	1,99
Asphalt (TNS*1,000)		· ·						
Incremental			110	1,309	1,333	546	304	
Cumulative			110	1,419	2,752	3.298	3.602	
Aggregate (CY*1,000)								
Incremental		40	359	3,429	7,582	6,257	4,783	23
dumulative		40	399	3.828	11.410	17.667	22,450	22.68
Frime Coat (TNS)								
neremental			403	6.073	5,947	2,580	1,113	
Cumulative			403	6.476	12.423	15,003	16,116	
Fencing (LF*1,000)			<u> </u>	1				
incremental				38	635	1,058	911	53
/mmulative				38	673	1,731	2,642	0.17
Tersennel numbers are		1	!]		3324-

ersennel numbers are yearly averages.

Table 5-9. Total OB complex construction resources for portion of Alternative 8, Nevada/Utah split basing.

CONSTRUCTION			QU	ANTITY P	ER YEAR			
RESOURCES	1982	1983	1984	1985	1986	1987	1988	1989
Personnel ¹	1,100	1,850	2,400	2,050	1,250			
Water (AF)								
Incremental	360	590	780	680	390			
Cumulative	360	950	1,730	2,410	2,800			ļ. <u>. </u>
Disturbed Area (Acres)								
Incremental	1,670	2,920	3,750	<u> </u>			-	
cumulative	1,670	4,590	8,340					
Materials								
Steel (TNS)								
Incremental		820	1,050	880	520			
, Cumulative		820	1,870	2,750	3,270			
Concrete (CY*1,000)							1	
Incremental		140	180	150	90			
Cumulative		140	320	470	560			
Asphalt (TNS*1,000)								
Incremental			250	210	130			
Cumulative			250	460	590			
Aggregate (CY*1,000)								
Incremental	130	200	270	230	140			
'umulative	130	330	600	830	970			
Prime Foat (TNS)			!					
(noremental			2,140	1,840	1,120			
Camitative			2,140	3,980	5,100		<u> </u>	
fencing - LF*1,000)								
incremental			5	40	23			
Commitative			- 5	45	-38			

Personner numbers are learly averages.

Table 5-10. Total OB complex construction resources for portion of Alternative 8, Texas/New Mexico split basing.

CONSTRUCTION			Qt	JANTITY I	PER YEAR			
RESOURCES	1982	1983	1984	1985	1986	1987	1988	1989
Personnel 1		300	1,850	2,400	2,000	1,200		
Water (AF)								
Incremental		110	640	- 830	710	400		1
Cumulative		110	750	1,580	2,290	2,690		
Disturbed Area (Acres)								
Incremental		570	3,320	4,200		}	· ·	
cumulative		570	3,890	8,090			<u> </u>	
Materials								
Steel (Tons)		ļ	1	1				
Incremental			740	950	800	460		
, Cumulative			740	1,690	2,490	2,950		
Concrete (CY*1,000)								
Incremental			140	180	150	90		
Cumulative			140	320	470	560		
Asphalt (TNS*1,000)		1						
Incremental		Ì		250	210	130		
Cumulative				250	460	590		
Aggregate (CY*1,000)								
Incremental		40	230	300	250	140		
Cumulative		40	270	570	820	960		
Prime Coat (TNS)								
Incremental				2,200	1,840	1,060		
Cumulative				2,200	1,040	5,100		
Fencing (LF*1,000)								
Incremental					10	23		
Cumulative					40	63		

Personnel numbers are vearly averages

DDA

The total resource requirements for the DDA construction in Nevada/Utah and in Texas/New Mexico are shown in Tables 5-11 and 5-12, respectively. Except for personnel, incremental and cumulative quantities are shown for each resource. Water quantities include requirements for concrete, dust suppression, compaction, and construction personnel, but not for revegetation. Disturbed areas include construction of protective shelters and roads, but not temporary facilities such as aggregate pits, etc. Reinforcing steel and plate steel make up the steel quantities. The quantities shown for aggregate include only road construction. There is no one peak year for all of the construction resources for either Nevada/Utah or Texas/New Mexico. Tables 5-13 and 5-14 show the construction resources required for each construction group for the Nevada/Utah region and the Texas/New Mexico region, respectively.

Requirements for certain resources, such as concrete and steel, are the same for Alternative 8 (Nevada/Utah/Texas/New Mexico) and the Proposed Action (Nevada/Utah). This is because these resources as used in the construction of the protective shelters and both the deployment systems have the same total number of shelters, 4,600. Requirements for other resources, such as aggregate, vary between the two deployment systems because the total length of road systems are different.

Table 5-11. Total DDA construction resources for portion of Alternative 8, Nevada/Utah split basing.

	1	QUANTITY	PER YEAR				
CONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1988	1989
Personnel ¹	121	1,8 4	6,224	6,743	6.323	4,450	1,208
Water (AF)			1	İ		I .	
Incremental	357	4,916	10,992	9,956	8,671	5,387	704
Cumulative	357	5,273	16,265	26,222	34,893	40,280	40,984
Distributed Area (Acres)							
Incremental	419	6,763	16,687	15,528	14,057	8.934	1,39
√umulative	419	7,182	23,869	39.397	53,454	62,388	63,78
Steel (TNS)		!				•	
Incremental		2,036	35,447	50,745	50,972	40,443	15,85
Cumulative		2,036	37,483	88,229	139,201	179,644	195,50
Oncrete (CY *1.000)			,			,	, - ,
Incremental		15	260	373	374	297	11
Cumulative		15	275	648	1.022	1,319	1.43
sphalt (TNS *1,000)				1		- •	- ,
Incremental	160	983	1.007	874	256	133	
Cumulative	160	1,143	2,150	3.024	3,280	3,413	
Aggregate (CY *1,000)						-,	
Incremental	188	3,180	6.694	5.448	4.784	2.686	
Cumulative	188	3,368	10,062	15,510	20,293	22,900	
Prime Coat (TNS)		. ,			1,	,	
Incremental	587	3,593	3,681	3.195	935	488	
Cumulative	587	4,179	7.860	11,055	11.990	12.478	
Fencing (LF *1,000)		-,	1	1 11,500	11,000	15,110	
Incremental		32	564	807	811	643	25
dumulative	ı	32	596	1,403	2,214	2.857	3.11
Protective Shelters	T				,		
Incrementai		24	417	597	300	476	18
'mulative		24	441	1,038	1.638	2,113	2,30
hiles of DTM Touds			• • •	.,	4.038		2.00
'ncremental	25	211	217	188	55	29	
'amalative	35	246	162	350	705	734	
hles of Tuster Roads	., 0	-10	.02	0		, , ,	
Incremental		331	. 901	722	733	413	
Jumulative		331	1,232	1,054	2,687	3,100	
			.,				

Sectionne, numbers tre nearly tverages.

Total DDA construction resources for portion of Alternative 8, Texas/New Mexico split Table 5-12. basing.

		QUANTITY I	PER YEAR			
CONSTRUCTION RESOURCES	1984	1985	1986	1987	1988	1989
Personne.	83	1,926	6.711	8,094	C.811	2.658
Water (AF					- ,	_,_,
Incrementa.	245	4,918	11,991	11.146	8,984	1.78
Cumulative	245	5,163	17,154	28,300	37,284	39.066
Disturbed Area (Acres)		İ			i	
lncremental	287	6,713	18,157	17,993	14.625	3,40
Cumulative Steel (TNS)	287	7,000	25,157	43,150	57,775	61,17
Incremental		2,365	27 200	65 101	5.5.050	20.00
Cumulative			37,388	65,101	57,278	33,369
Concrete (CY*1000)		2,365	39,753	104,854	162,131	195,500
Incremental		17	274	470		0.4
Cumulative		17		478	420	24
Asphalt (TNS *1,000)		17	292	770	1,190	1,43
Incremental	110	1,059	1 1 100	43.6	1	
Cumulative	110		1,123	416	304	
Aggregate (CY*1,000)	110	1,169	2,293	2,709	3,013	
Incremental	129	3.129	7,332	6 117	4 700	
Cumulative	129	3,129		6,117	4,783	23:
Prime Coat (TNS)	. 129	3,236	10,590	16,707	21,490	21.72
Incremental	403	3,873	4 107	1		
Cumulative	403	4.276	4,107	1,520	1,113	
Fencing (LF*1,000)	403	4,276	8,383	9,903	11,016	
Incremental		3.0				
Cumulative		38 38	595	1,035	911	531
Protective Shelters		36	632	1,668	2,579	3,110
Incremental		28	440	700		
Cumulative		28 28	440	766	674	393
Miles of DTN Roads		26	468	1,234	1,907	2,300
Incremental	24	228		00		
Cumulative	24	252	242	89	65	
Miles of Cluster Roads	24	252	493	583	648	
Incremental		308	982	000	700	
Cumulative		308		920	723	38
subulative		308	1,291	2,210	2,933	2,971

TABLE 5-13. TOTAL DDA COMSTRUCTIOM RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8, NEVADA/UTAH SPLIT BASIMG

GROUP 1

				NEVADA/I	NEVADA/UTAH SPLIT BASIMG QUANTITY PER YEAR	AS I'MG		•	(Page 1 of 8)
CUNTRUCTION RESOURCES	1983	1984	1985	1986	1987	1984	6861	1990	
FT RESORING \$	121	PAR	6861	155.					
STORE (AF) INCREMENTAL TOTAL ALIVE	357 357	2350	1494	90. 4291					
DESTURBLED AREA (ACRES) FINCREMENTAL CURBLATTOR	419	3412	2594 6425	180					
MATERIALS									
COEFFECTNOS TROBERRADO COMOLACTOR		2036 2036	15477 17514	2036. 19550.					
CONCRETE CONTROLON TELEPORTECION COROLINATORI		55	6.01 6.01	15.					
ACTION OF COMPANY CONTRACTOR OF CONTRACTOR O	160	267 408							
ACCRECABLETY STOOD THOUGH	E 18	1392	619						
PRAFF CONTACTOR STATES	/H/:	9.78							
PROTEST OF ORDER PROTEST OF ORDER PROTEST OF ORDER OF OR		<u> </u>	\$ 6.00 6.00 6.00 6.00 6.00 6.00 6.00 6.00	dE dE					
PROTECTIVE SHELTERS THE BEHALD OF COMPUTATION		÷ 5.	9 X 2 Z	7.4 01.5					
POLES OF The Court of the State	t	÷ .							
			3						

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

1

TABLE 5-13. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8, NEVADAYUTAH SPLIT BASING.

GROUP 2

				GUANT	QUANTITY PER YEAR	۸R		(Page 2 of 8)	of 8)
resistate Pares RESOURCES	1983	1984	9861	1,986	1961	80.16.1	1989	1940	
t n 02 (27 of b)	!			218	941	1576	213		
TNO AT THE TOTAL TRICKER AT TAKE				640	2260	1749.	299. 494B.		
DESTUBBLED AND A CACREST TREPT OF THE PREST				751. 751.	3366 4117	9978 709 6	594. 7690.		
SIM BUM S									
CHELL CHEST						1	90.2		
CHOIL ALIVE					1450	16725	23460		
CONTRACTOR OF THE STATE OF THE					Ξ	112	49		
Company of the state of the sta					:	1.5.3	172		
Arabida (Thra Toolaa) (Meret Sept 26				982	35.7				
CORDH ALLST				588	620				
100 14 CALL 1 CA 8 CO CA 1 CA 1 CA 1 CA 1 CA 1 CA 1 CA 1 C				GEE	1613	5.75			
करा हुन मध्य है।				SICE.	1951	₩////			
				10167	4.5.6				
CH - II ATT'I				1025	15,47				
The Man Man Tologon					:	5			
							373		
PROTECTIVE SHELTERS									
TO THE PERMITTENANCE OF THE PE					22	127	79		
The Experience				1.74	6 1.				
4.30 (4.00)					•				
The state of the s									
					ř Ş	<u> </u>			

1PERSONNEL NUMBERS ARE YEARLY AVERAGES.

GROUP 3 (Page 3 of 8)

TABLE 5-13. TOTAL DRA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8, NEVADAZULAH SPLIT GASING

			TNVIE	QUANTILY PER YEAR	AR		1	
\$ 3 de 10 de	1.204		9861	1967	algal.	1989	0661	ļ
1 1 2 2 2		97	7.54	1870	7111			
11 - 15 - 15 - 15 - 15 - 15 - 15 - 15 -		200	2046	2505. 4 858	455 5313			
is respect only (ACRES) the open below a responsible		564 564	285 4 3097	4274	904 8275			
7. A. C. A.								
OH DEST				15169 15169	10247 25415			
report III for a bodo o include III for a bodo				==	77.			
FIRST CONTROLLED STATES AND STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECULAR STATES AND SECURITARISTS A			337 410	437				
		100	1321	1477				
Figure 1.A.C. Communication of the communication of		0.5	1531	27 1598				
				1 E C	404			
ROTECTIVE SHELTERS				1.20	F.4 79.00			

PERSONNEL NUMBERS AFT. YEARLY AVERAGES.

TABLE 5-13. TOTAL NOA CONSTRUCTION PESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8, NEVADA/UITAN SPLIT BASING

\$ 400as

			GUANTITY	GUANTITY PER YEAR	NR AN				(Page 4 of 8)
ERRCH CONTRACTOR	1.26.4	: <u>}</u>	4861	7861	1.282	067.1 6861 88	0661		
								:	:
The state of the s	4	*	2139	1501					
7 - 7 - 7 - 7 - 7 - 7 - 7 - 7 - 7 - 7 -	781	1846.	3119	1085					
The distribution of ACRES) The second of th	1 5 6 1 5 6 1	92279 9228	4999 7678	1926 9603					
- -									
1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1			16072	13059					
			=======================================	21.2					
	2:	- 5	10% 57%						
	14. A.	< ::	1771	1111					
	55		438.						
			1.65.1						
			\$ 5 \$. 8.	23.1 43.5					
PROTECTIVE SWELTERS			Ē	• •					
6			ij	· •					
-			-						

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 5-13. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8, NEVABLE 5-13.

GROUP 5

				GUANT	QUANTETY PER YEAR				(Page 5 of 8)	5 of 8)
HE FORTER	1963	1284	1.382	1986	1987	1.788	1989	1990		
T F to a Suffice		4/1	1717	634						
A TAN THE STATE OF		1038	9779 3771	386 4177						
PERTPURSO P. API A. (ACRES) TO SEPTIMENTAL FORDER AT I VE.		1383 1383	4190 5714	757 6471.						
इ.स्टान १ थर										
THELLINGS TO PRIMEN			11342	8208						
Compliantage			11342	19550						
TREET OF CLUM			£ 9	60						
(1997) - 100 (1997				†						
WHITH HERDE.		1000	E-24							
1.00 A 1.		ī.	. / ೬							
17 10 11 10 10 10 10 10 10 10 10 10 10 10		1777	16.64	1.7						
くこくまでも		1.35		0000						
1.00										
The state of the s		4 3	1,,1							
		\$	1.17.5							
-			1	1.7						
			31	111						
PPOTECTIVE SHELTERS										

PEPSONNEL NUMBERS ARE YEARLY AVERAGES.


TABLE 5-13. TOTAL DEA CONSTRUCTION RESOURCES OF CROUP FOR PORTION OF ALTERNATIVE 8, NEVADA/UTAN SPLIT BASING

;

GRBUP 6

				iNVati	GUANTITY PER JEAS	35			(Page 6 of 8)	0 8
The Charles of the Ch	1 5 7	1.884	10.6	1986	1987	1 83	6990	1720		
RESOURCES		440	tood	1763	304					
10 - 10 - 10 - 10 - 10 - 10 - 10 - 10 -) 401 140.†	\$22 4 7-8-6	1415	17.7					
to a stage to And A (ACRES) Training of the John A CLAS		1619	8608 7853	2580 10433	325 10786					
M84 1944										
March March 1942 Ann Amhrach			84508 84508	20612 292 4 0	3995 33235					
The Part of the Comment of the Comme			Ş Ş	151 215	244					
POLICE CONTROL DESCRIPTION OF THE PRINCIPLE OF THE PRINCIPLE OF THE PRINCIPLE OF THE POLICE OF THE P		405 405	2.3							
DE DAN MARTINA DE DAN MENTAN		8098 8098	70.00	3830						
Company of the Compan		1780	orde etc.							
Section 1 to 1 to 1 to 1 to 1 to 1 to 1 to 1			3 2 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	1978 4 85	60%					
PROTECTIVE SHELTERS			<u> </u>	740 741	7.64.					
			-							

HERS ARE YEARLY AVERAGES.



F ALTERNATIVE 8,	
FOR PORTION O	
TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE	MEVADA/UTAH SPLIT BASING
DDA CONSTRUCTION	NEVADA
TABLE S-13. TOTAL	

GROUP 7

				GUAN	QUANTITY PER YEAR	PIER YEAR			(Pege 7 of 8)
ONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1788	1989	1790	
FERSONAL I			268	1080.	1893.	471.			
UNIER (A) INCREMENTAL CURBERATIVE			768.	2258 3027	2293. 5319.	246. 5606.			
DISTURBED ARTA (ACRES) INCREMENTAL CURBULATION			956. 956.	3406.	3844. 8206.	569. 8775.			
NATERTALS									
STEEL CRASS		,		1100	17104	7440			
CURIN A FIVE				3816.	20452	27.370			
TANCHE LITTER TO THE TANCE OF THE PRINCIPAL COMPANIANT AND THE PARTY OF THE PARTY O				90 0	126.	47.			
2444NL1 (1NS (1000)				ę	5				
TENTIN MINISTER			6. 6.	144					
ACRE 0ATE (C.C. 1000)				;					
THETA PRICES			5 C C C	1527	3147				
PROPERTY CONTINUES									
ORRONALSI CORRESPONDE			1007	925 1					
taper the case a tooley				;	i				
CHRR 21 CZ				3.5	1 20 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	435			
PROTECTIVE SHELTERS									
arsa ad incretos concretos estas				5 e e	101	\$ ij			
ARESTON POLICE OF CONTRACTOR O				7 2					
For Strategiese Communication of the Strategiese Communication of				:	-				

¹PERSONNEL NUMBERS ARE YEARLY AVERAGES

FABLE 5-13. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8,	
6	
PORTION	
FOR	
GROUP	BASING
Ą	Ξ
RESOURCES	NEVADA/UTAH SPLIT BASING
CONSTRUCTION	NEVA
PDA	
TOTAL	
TABLE 5-13.	

GROUP 8

	F	TABLE 5-13.	TOTAL DDA CU	TOTAL DDA CONSINCTION RESOURCES OF GROOM NEVADA/UTAH SPLIT BASIN	NEVADA/UTAH SPLIT BASING	SASING		GC + C + C + C + C + C + C + C + C + C +	6
				CHANNI	QUANTITY PER YEAR	2			
CHAST RUC TERM	1983	1984	1985	1986	1961	906.1	1989	1990	
T - Radacing of					85.	1607.	693.		
UNIER (AF) INCREMENTAL CUMMATIVE					251. 251.	2697.	405.		
DISTURBED AREA (ACRES) INCREMENTAL CUMULATIVE					295. 295.	4483.	803. 5582.		
MATERIALS									
ICH STATE OF STATE						8474	9121.		
CHERRY AT 172. CINCREPTO (A) THURSEPTON (A)						62.	129.		
Atartan, 1 CINS 1 (OO) INCREMENTAL					113.	138. 246.			
ACHEGA FL (CYV 1000) INCH PEHTAL					19.	1064. 1977.			
COPIN A CLANA CONTRACTOR CONTRACT					413. 413.	A148.			
LUMBA ATTOO) H NGJAGUB TOO) BM 83 PR 83 M						135	280.		
PROTECTIVE SHELTERS TREATED TO THE CONTRACT OF						100	107		
PROPERTIES THEORY OF THE STATES THEORY OF THE STATES THEORY OF THE STATES THE STATES OF THE STATES O					5.5	23			
80 (1) (1) (1) (1) (1) (1) (1) (1) (1) (1)						22.5			

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 5-14, TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8, TEXAS/NEW MEXICO SPLIT BASING.

GUANTITY PER YEAR

	CONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1988	1989
245. 2905. 1 245. 3150. 4 287. 4170. 3 2365. 23 110. 364. 17 117. 17 129. 2085. 2 129. 2085. 2 403. 1331. 403. 1734. 38. 38. 38. 28. 28. 28. 28. 28. 28. 28. 28. 28. 2	ERSONNEL		83	1221	1933			
245. 3150. 4 287. 4190. 3 2365. 23 110. 364. 117. 17. 129. 1936. 2 129. 1936. 2 129. 1936. 2 129. 1936. 2 28. 28. 28. 28. 28. 28. 28. 28. 28. 28.	ATER (AF)		. 40	6	1784			
287. 4190. 3 2897. 4190. 3 2365. 231 110. 364. 17 110. 364. 17 129. 2085. 2 129. 2085. 2 129. 2085. 2 28. 38. 38. 38. 38. 28. 28. 28. 28. 28. 28. 28. 28. 28. 2	CUMULATIVE		24.5	3150	4935			
287, 4170, 3 2365, 21 2365, 21 110, 364 110, 474 1129, 1956, 2 129, 1956, 2 129, 1956, 2 129, 1956, 2 28, 28 28, 28 24, 78 250	ISTURBED AREA (ACRES.)							
2365. 21 2365. 23 110. 364. 110. 474. 110. 364. 110. 364. 110. 364. 110. 364. 110. 364. 110. 364. 110. 38. 28. 28. 28. 24. 78. 24. 78. 250.	INCREMENTAL		287	4190	3152			
2365. 21 2365. 23 110. 364. 110. 474. 110. 474. 129. 2085. 2 129. 2085. 2 129. 2085. 2 28. 28. 28. 28. 28. 28. 28. 28. 28. 28.	CUMULATIVE		287	4477	7629			
2365. 23 2365. 23 2365. 23 110. 364. 110. 474. 129. 1956. 2 129. 1956. 2 129. 1931. 403. 1131. 403. 1734. 28. 28. 28. 28. 28. 28. 28. 28.	ATERIALS							
2365. 21 2365. 23 2365. 23 110. 364. 110. 474. 129. 2085. 2 403. 1331. 403. 1734. 38. 38. 38. 28. 24. 78. 250.	TEEL (TMS)							
2365. 23 110. 364. 110. 364. 110. 474. 110. 474. 1129. 2085. 2 129. 2085. 2 129. 2085. 2 28. 28. 28. 28. 28. 28. 28. 28. 28. 28.	INCREMENTAL			2365	21095			
110. 364 110. 364 110. 474. 1129. 1936. 2 103. 1331. 403. 1331. 403. 1734. 28. 28. 24. 78 250	CUMULATIVE			2365	23460.			
110. 364. 110. 364. 110. 474. 1129. 1956. 2 403. 1331. 403. 1734. 38. 38. 24. 78 250	DNCRETE (CY+1000)							
110. 364. 110. 364. 110. 474. 129. 2085. 2 129. 2085. 2 403. 1734. 403. 1734. 28. 28. 28. 28. 24. 78. 24. 78. 250.	INCREMENTAL			17	155			
110, 364, 110, 474, 110, 474, 129, 1996, 2 129, 2085, 2 2 8 38, 38, 38, 38, 38, 38, 38, 38, 38, 3	CUMULATIVE			17	172			
110. 364. 110. 474. 129. 1956. 2 403. 1734. 403. 1734. 403. 1734. 28. 28. 24. 78. 250.	SPHALT (TNS+1000)							
110. 474. 129. 1956. 2 129. 2085. 2 403. 1331. 403. 1734. 38. 38. 38. 28. 28. 28. 28. 28. 28. 28. 28. 28. 28.	INCREMENTAL		110.	364				
129, 1956, 2 129, 2085, 2 403, 1331, 403, 1734, 38, 38, 38, 38, 38, 38, 38, 38, 38, 38,	CUMULATIVE		110	474				
129. 1956. 2 129. 2085. 2 403. 1331. 403. 1734. 38. 38. 38. 28. 28. 28. 28. 28. 28. 28. 28. 28. 2	CCREGATE(CY+1000)							
127 2085 2 403 1331 403 1734 38 38 38 28 24 78 24 78 250	INCREMENTAL		129	1956.	651			
403 1331. 403 1734. 38 38 38 38 38 38 38 38 38 38 38 38 38 3	CUMULATIVE		129	2085	2736.			
403 1331. 403 1734. 38 38 38. 28 28 28 28 28 24 78 24 102 250	RIMECOAT(TNS)							
24 78 28 28 28 28 28 28 28 28 28 28 28 28 28	INCREMENTAL		403	1331				
24 28 28 28 28 28 28 28 28 28 28 28 28 28	CUMULATIVE		403	1734				
24 28 38 28 28 28 28 28 28 28 28 28 28 28 28 28	ENCING (LF+1000)				,			
24 78 28 28 28 24 78 24 26 25 25 25 25 25 25 25 25 25 25 25 25 25	INCREMENTAL.			æ	336			
28 28 28 24 78 24 102 0	CUMULATIVE			g B	373			
28. 28. 24. 78. 24. 102.	ROTECTIVE SHELTERS							
28 24 78 24 102 0	INCREMENTAL			38	248			
24 78 24 102 0	CUMULATIVE			28	276			
24 78 24 102 0	THES OF DIN SOADS							
24 102			ċ	ş				
5 62	COMPANIATION AL		4 4 0	8 0				
250								
250	ILES OF CLUSTER RD							
	INCREMENTAL			250	106			

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

TABLE 5-14. JOTAL DDA CONSTRUCTION RESOURCES RY GROUP FOR PORTION OF ALTERNATIVE 8, TEXAS/NEW MEXICO SPLIT BASING.

į

GROUP 2 (PAGE 2 OF 7)

QUANTITY PER YEAR

CONSTRUCTION RESOURCES	1983	1984	1985	1986	1987	1988	1989	
PERSONNEL.			430	1837	1758.			
WATER (AF)								
INCREMENTAL			1234	3540	1274.			
CUMULATIVE			1234	4824	6609			
DISTURBED AREA (ACRES)								
INCREMENTAL			1527.	5549	2382.			
CUMULATIVE			1527	7075	9458			
MATERIALS								
STEEL (TNS)								
INCREMENTAL				7884	21441			
CUMULATIVE				7884	29325			
CONCRETE (CY+1000)								
INCREMENTAL				58.	157.			
CUMULATIVE				28	215.			
ASPHAL T (TNS+1000)								
INCREMENTAL			453	105				
CUMULATIVE			403.	228.				
AGGREGATE (CT+1000)			1		,,,,			
CIBER ATTOE			202	2127	2385			
PRIMECOAT (TNS)			2	210				
INCREMENTAL			1658	383				
CUMULATIVE			1658	2040.				
FENCING(LF+1000)								
INCREMENTAL				125	341			
CUMULATIVE				125	466.			
PROTECTIVE SHELTERS								
INCREMENTAL				93	252			
CUMULATIVE				93	345			
MILES OF DIN ROADS								
INCREMENTAL CUMULATIVE			B 8	23 20 120				
MILES OF CLUSTER RD INCREMENTAL CLAMM ATIVE			2,28	377	946			
			į	2				

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

GROUP 3 (PAGE 3 of 7)

TABLE 5-14. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8,"
TEXAS/NEW MEXICO SPLIT BASING.

QUANTITY PER YEAR

1987 1988 1989	1982. 1504.	3566. 1002. 5511. 6513.	5611. 1916. 8028. 9943.			10394, 18931, 10394, 29325,	i	76. 139. 76. 215.		4 · · · · · · · · · · · · · · · · · · ·	***		3480. 3603.	159.	2720.		165. 301. 165. 466.		122 223				.001	377. 20. 426. 446.	
1986	679.	1945. 1945.	2417.							700.	700	1119.	1119.	2561.	2561.							121	.161	4. 4. 6. 6.	į
1985																									
1984																									
1983			G																						
CONSTRUCTION RESOUPTES	PERSONNEL 1	MATER (AF) INCREMENTAL CUMULATIVE	DISTURBED AREA (ACRES) INCREMENTAL CUMULATIVE	MATERIALS	STEEL (TNS)	INCREMENTAL CLARK ATTUR	CONCRETE (CY+1000)	INCREMENTAL	ASPHALT (TNS+1000)	INCREMENTAL	CUMULATIVE ACOBEDATE(CV+1000)	INCREMENTAL	CUMULATIVE	PRIMECIAL (INS) INCREMENTAL	CUMULATIVE	FENCING(LF+1000)	CUMULATIVE	SECTION SECTIO	INCREMENTAL	CUMULATIVE	MILES OF DTN ROADS	INCREMENTAL	COMOLATIVE	MILES OF CLUSTER RD INCREMENTAL CUMULATIVE	

PERSONNEL NUMBERS ARE YEARLY AVERAGES

1

GROUP 4 (PAGE 4 OF 7)

TABLE 5-14. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8, TEXAS/NEW MEXICO SPLIT BASING.

QUANTITY PER YEAR

1983 1984 1985 1986 1987 1988 433 2100. 1189 3477. 1189 3477. 1189 3426. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 12903. 132. 152. 152. 152.	
1985 1986 1987 433. 1189. 1189. 1622. 1622. 1622. 1622. 163. 783. 783. 783. 783. 783. 783. 783. 78	
1986 1987 433. 1189. 1189. 1622. 1622. 1622. 1622. 1622. 183. 783. 783. 783. 783. 783. 783. 783. 7	
1987 1189. 1189. 1189. 1622. 1622. 1622. 1622. 1884 1884 1884 1884 1884 1884	
2100. 2477. 4666. 5562. 7183. 7183. 95. 95. 95. 95. 152. 152.	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
	205. 205. 152. 152.
1251. 729. 729. 5395. 1449. 8632. 29329. 29329. 121. 215. 215. 215. 345.	261. 466. 193 345

TABLE 5-14. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8. TEXAS/NEW MEXICO SPLIT BASING.

GROUP 5 (PAGE 5 OF 7)

QUANTITY PER YEAR

PFSOURCES	PERSONNEL 1	MATER (AF) INCREMENTAL CUMMLATIVE	DISTURBED AREA (ACRES) INCREMENTAL CURULATIVE	HATERIALS	STEEL (TNS)	INCREMENTAL COMMATIVE	CONCRETE (CY+1000)	INCREMENTAL	CUMULATIVE	INCREMENTAL	CUMULATIVE	ACCRECATE (CY+1000)	INCREMENTAL	PRIMECOAT (TNS)	INCREMENTAL	CUMULATIVE	FENCING(LF#1000)	CUMULATIVE	PROTECTIVE SHELTERS INCREMENTAL	CURULATIVE	MILES OF DTN ROADS	INCREMENTAL	CUMULATIVE	MILES OF CLUSTER RD
	275.	778 778	799 797							242	242		468	804	984	884						52	52	,
	1915.	3700. 4478	5765. 6762.			8409		62.	95	90	3 3 3 3 3 3		2525	5443	204	1088	į	134	0	66		12	64	
	1875.	1359.	2540. 9302.			22871.		168.	230				263	3436			i	498	249	368				;

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

GROUP 6 (PAGE 6 OF 7)

ALTERNATIVE	
5	
FOR PORTION	BASING.
GROUP GROUP	SPL 17
•	9
IDIAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE	TEXAS/NEW MEXICO SPLIT BASING.
5	
1	

ļ				QUAN	GUANTITY PER YEAR	EAR	
CONSTRUCTION RESOURCES	£861	1984	1985	9861	1861	9847	1989
PERSONNEL 1				347.	1961.	1504.	
MATER (AF) INCREMENTAL CUMULATIVE				971.	3505. 4476.	1002. 5478.	
DISTURBED AREA (ACRES) INCREMENTAL CUMALATIVE				1274.	5540. 6814.	1916. 8729.	
MATERIALS							
STEEL (TNS) INCREMENTAL CUMULATIVE					10394.	18931.	
CONCRETE (CY*1000) INCREMENTAL CUMULATIVE					76. 76.	139.	
ASPHALT (TNS+1000) INCREMENTAL CUMULATIVE				263. 263.	16. 279.		
INCREMENTAL CURULATIVE BETWEEDAT (TAG)				605.	2328.	3057	
TRINGCENENTAL CUMULATIVE FENCING: FF1000:				960.	60. 1020.		
INCREMENTAL					165.	301	
PROTECTIVE SHELTERS INCREMENTAL CUMULATIVE					122. 122.	223. 345.	
MILES OF DIN ROADS INCREMENTAL CUMULATIVE				8 8 9 9	60		
MILES OF CLUSTER RD INCREMENTAL CUMULATIVE				84 89.	377.	20. 446	

PERSONNEL MUMBERS ARE YEARLY AVERAGES.

(PAGE 7 OF 7) GROUP 7

TABLE 5-14. TOTAL DDA CONSTRUCTION RESOURCES BY GROUP FOR PORTION OF ALTERNATIVE 8, TEXAS/NEW MEXICO SPLIT RASING.

DUANTITY PER YEAR

CONSTRUCTION RECOURCES	PERSONNEL ¹	MATER (AF) INCREMENTAL	CUMULATIVE	DISTURBED AREA (ACRES) INCREMENTAL	CUMULATIVE	MATERIALS	STEEL (TNS)	INCREMENTAL	CONCRETE (CV+1000)	INCREMENTAL	CUMULATIVE	INCREMENTAL	CUMULATIVE	ACCREGATE (CY+1000)	CURRENTAL	PRIMECDAT (TNS)	INCREMENTAL	COMOCALIVE	INCREMENTAL	CUMULATIVE	PROTECTIVE SHELTERS	INCREMENTAL	CUMULATIVE	MILES OF DIN ROADS	CUMULATIVE	MILES OF CLUSTER RD INCREMENTAL
1983																										
1984																										
1985																										
1986																										
1987	98	254	254	298	29B							114	114.	•	134		417.							U F	25.	
1988	1702.	3503	3757.	5232	5530.			6511.	1170	48.	48.	304	419.	000	2439		1113.	0561	104	104.		77.	77.	5 7	90.	318.
1989	1407.	1053	4810.	1953.	7484.			16949.	2010	124	172.			Ċ	2670				270.	373.		199	276.			38

PERSONNEL NUMBERS ARE YEARLY AVERAGES.

1817

APPENDIX 6

ARMY CORPS OF ENGINEERS CONCEPTUAL CONSTRUCTION SEQUENCING

- 1. M-X operational construction sequential DDA development.
- 2. M-X EIS construction sequence concurrent development.
- 3. M-X EIS construction sequence Texas/New Mexico.

OVERVIEW MX Operational Construction Sequential DDA Development

The Sequential Development Approach described herein is based on the preferred "precast concept" of shelter construction. The precast concept centralizes the production of precast concrete protective structure segments thereby reducing the number of construction personnel at each shelter site.

Precast plant logistical studies indicate that seven precast facilities can produce the required segments for the total number of shelters to be constructed. Each precast plant, supported by adjacent "main" construction camps and aggregate quarries, is appropriately sited to support the construction of groups of shelters in a general geographical area. Additional "satellite" camps to house field construction personnel will be located in areas remote from the precast plants.

The Sequential Development Approach initiates Operational MX Facility Subsystem Construction in one location and progressively extends the construction area to complete shelters in accordance with MX deployment schedules. The Designated Transportation Network (DTN) provides the interconnecting link for construction material/equipment supply from railheads on commercial railroads and for operational missile deployment from the OB/DAA. A schematic diagram of the approach is shown in Figure 1.




Figure 1. Schematic Diagram of Sequential Development

Although it is possible to locate the initial effort (Area I) in any of the designated valley areas, the Dry Lake Valley geographical area has been established as the preferred first development area in the construction scenario presented hereinafter. This area has an available railhead at Pioche, Nevada and, for initial missile deployment, is in close proximity to the OB/DAA proposed for Beryl, Utah.

The Sequential Devleopment Approach uses DTN road construction (base course provides construction roads) to open-up areas of shelter construction and provide a specific route for construction traffic. Aggregate plants and water wells supporting DTN construction will be located along the DTN route at intervals of approximately 30 miles. A schematic of initial construction into Area I is shown in Figure 2.

Step 1 - Construct marshalling yard at railhead

Step 2 - Establish DTN alignment Step 3 - Construct water wells

Step 4 - Open aggregate quarries

Step 5 - Construct DTN (base course)




Figure 2. Sequencing Initial Construction

The first leg of the DTN opens Area I for mobilization (precast plant, aggregate quarries, water wells and construction camps) and shelter construction. As shelters in Area I are being constructed, the DTN will be extended to open subsequent areas of shelter construction as required to meet scheduled completion dates. Figure 3 shows subsequent construction as sequential development progresses.




Figure 3. Subsequent Construction

Table 1 identifies the activities/events (by calendar year) of the sequential development approach extended through all seven geographical locations to meet scheduled shelter completion dates. As shown in Table 1, this approach uses sequenced precast plants, construction camps and marshalling yards to maximize support facility utilization, minimize contractor interferences, and avoid missile deployment activities. Figure 4 shows the staging of construction support facilities including the relocation of precast plants.




Figure 4. Staging Construction Support Facilities

Table 1. Yearly Activities/Events

		lable 1. leari	lable 1. rearry Activities/ Events		
	CY 1983	CY 1984	CY 1985	CY 1986	
AREA I	b Construct marshal- ling yard at Pioche, Nevada construct water wells and storage tanks for camps and road constr. copen aggregate quarries for road construction construct DTN roads construct Con-	o Connect to existing water system to support precast plant o Open aggregate quarries to support precast plant o Set up precast plant and begin production o Begin construction of sitework and horizontal shelters	o Complete 230 shel- ters & turnover for A & CO o Continue cluster road and sitework o Continue horizontal shelter construction	o Complete balance of shelters in Area I o Construct final DTN surface o Relocate precast plant to Area IV	
AREA II	struction camps	1		o Complete 820 shelters and turnover for A & CO	1
AREA III		o Start marshalling yard at Delta, Utah o Develop water wells for Area III camps and road construction o Construct DTN roads	o Complete marshalling o yard at Delta, Utah o Open aggregate quarries o Start set-up batch & precast plants o Construct Construction camps	o Complete batch & precast o Start shelter production & installation	

NOTE: CY 1987, 1968, 1989 & ANEN IZ, II, JII., & III. TO COME LATERS.

ARES ...

The contracting strategy in the Sequential Development Approach calls for support facilities construction and operations contractor(s), DTN construction and maintenance contractor(s), and primary shelter construction contractor(s). The approach is flexible enough to permit various alternatives or combinations of contracting strategies. As a baseline, the following is being used for Operational Construction planning purposes:

- Contractor(s) for construction and operation of all support facilities (water wells, aggregate quarries, marshalling yards, precast plants, construction camps). Water, aggregate, and precast concrete segments (including cement, fly ash, reinforcing) will be "Government Furnished" under these contracts.
- 2. Contractor(s) for DTN construction and maintenance with road interfaces at the OB/DAA site boundary and at area precast plants.
- 3. Contractor(s) for shelter construction including shelter roads, linear grid roads and DTN trunk roads.

The number of contracts depends on the size of contracts selected to optimize construction management, competitive bidding, and work force utilization. In general, however, the Sequential Development Approach will allow flexible packaging of contracts.

M-X EIS

CONSTRUCTION SEQUENCE

CONCURRENT DEVELOPMENT

The Concurrent Development Sequence of construction is an alternative which will lessen the impact of the effort upon the socio-economic, transportation and environmental resources of the region. As with other alternative construction sequences, the concurrent development alternative is scoped to meet the IOC and FOC completion dates, which are considered to be firm. Any modification of the schedule will be reflected in either the IOC or FOC dates.

The specific location of the initial effort will be dependent upon the location of the principal, or first, Operating Basé. Within the Operating Base, there will be a contractors' support camp to be built in FY82. At the same time, construction roads and water wells must be started into the initial group of clusters, as well as the building of a construction camp in this area near the Operating Base and construction of a marshalling yard at the closest railhead. These are the basic initial activities necessary during FY82 to meet the IOC deadline.

The next effort will begin in FY83 in the establishment of concrete facilities for either precast or cast-in-place activities in the area containing the first group of shelters. Also, during FY83 work would commence in three other areas of the region with the development of marshalling yards, construction camps and precast facilities or storage facilities for steel, cement, sand and gravel for cast-in-place shelters. Concurrently, the construction of the road system into an adjacent valley and its clusters will begin, providing access to each shelter road. All future construction would proceed in an orderly manner during succeeding Fiscal Years from these four areas. In order to accomplish this effort, it is planned to build construction camps within or adjacent to the group of valleys.

The impacts of construction will thus be spread over four areas of the region. This would reduce the severity of the impacts upon items such as community cohesiveness, public services, economic stability, water and natural resources as well as the entire transportation, and supply system.


The general descriptions above are considered applicable regardless of the location of the Operating Base. However, in order to be more definitive, some basic assumptions are discussed below.

In order to accomplish the construction necessary to meet the immediacy of the IOC and the slightly longer term FOC, every effort must be made to be ready to start constructing shelters in FY84. Such shelter construction requires that FY82-83 preparatory construction contracts be effected if access to the work areas for equipment, personnel and material is to be provided. Meeting the two goals of (1) optimum use of resources in the construction area, and (2) the least impact to the social, economic and environmental resources will require a reduced density over a larger area. Therefore, a deployment to two separate areas during FY82 are considered appropriate to obtain the best use of supply

facilities and utilities, followed in FY83 with two additional work centers. Accordingly, DTN, construction camps, and marshalling yards are to be provided under the FY82-83 programs.

In the event that limited funding precludes full preparation as described above during FY82, it will be necessary to concentrate upon supporting the IOC (1st 10 clusters). The sketch below illustrates each of these efforts:

SCHEMATIC FOR INITIAL DEPLOYMENT



The construction of the Primary DTN, from the MOB through the first Deployment Area, marshalling yard, and Construction Contractor Support Camps must be completed in FY82. This is an ongoing effort into new Deployment Areas each succeeding Fiscal Year. The next sequence of events will be the construction of Secondary (Cluster) roads, Pre-Cast-Plant etc. in the 1st Deployment Area and construction of additional facilities including more marshalling yards in succeeding deployment areas during FY83. These actions will be repeated during succeeding Fiscal Years as new Deployment Areas are opened up by the DTN. This will be followed in FY84 by the building of Shelters in the 1st Deployment Area. This is shown in the following Table.

TABLE I INITIAL CONSTRUCTION

FY83

FY84

FY82

Primary DTN - MOB thru 1st
Deployment Area
Const. Contractor Support Camps
1 at MOB
1 in 1st Deployment Area
Marshalling Yard

Secondary Roads

1st Deployment Area
Pre-Cast Plant
Marshalling Yards
Power and Comm.
DTN (Cont.) New Areas
Const. Camps New Areas

Shelter Construction
1st Deployment Area
DTN Continuation - New Areas
Const. Camps - New Areas
Secondary Roads - New Areas
Marshalling Yards - New Areas
etc.

For succeeding Fiscal Years the amount of construction activities is directly dependent upon the number of shelters programmed in each fiscal year. Therefore, all the items shown in TABLE I under FY82 must be started . two years prior to construction of the shelters. Similarly, all items listed under FY83 must be started one year before the shelters are started in each area.

The basic factors which entered into determining the construction sequence are listed below:

- 1. The DTN/Secondary routes will be used as construction access roads and will consist of a sub base without a surface and will be completed prior to need of road by subsequent contractors.
- 2. Access will be provided for the shelter construction contractor to each shelter site in his contract. (Eliminated cross-country uncontrolled haul road routes by several contractors.)
- 3. Provides routes, on a road bed, for pre-cast transporter to deliver pre-cast sections to stockpile at each shelter site. At the same time, these routes will be utilized for delivery of all other materials and buses for transporting workers.
- 4. Road work requires greater amounts of water. Therefore, road contractors would drill water wells at intervals within valleys. Wells would then be utilized later by other construction contractors but pumped at lesser rates.
- 5. Power and communications will be constructed in road right-of-way, and will be in place when shelters are turned over to Weapons System Contractor for Installation and Check-out.
- 6. In support of IOC (and later), SACSO vehicles carrying components of the missile between DAA and DDA can utilize unsurfaced DTN.

- 7. Construction Contractor Support camps must be set up by the support contractor. Initially, one is required at the MOB, and one in the First Deployment Area. In the Deployment Area, location of support camp will be centrally located, adjacent to pre-cast plant/marshalling area.
- 8. This sequence should result in significant savings in construction contract bids (mobilization costs reduced--access roads, water wells in proximity already available.)

The sequencing described above will allow an orderly approach for; opening up new valleys and providing construction access, allow flexibility in setting up design and construction packages, provide a means for opening up additional deployment areas, utilizing additional supply routes (for both people and materials), and spreading the impacts more widely thus lessening the adverse effects.

One of the driving forces in the sequencing of construction will be the availability of water and the ability of obtaining a permit for its use. The amounts of water necessary will vary dependent upon the activity. However, the amounts of water required for dust control on the road network exceed all other requirements by orders of magnitude. The magnitude of the quantities required for this purpose dictate the use of dust palliatives as a means of reducing water use. Road construction requires the next highest water demand, followed by shelter backfill. With this Concurrent Development sequencing, these water demands would not be concurrent, but would be phased in succeeding construction seasons, e.g., DTN road in FY 1, cluster roads in FY 2 and shelter construction in FY 3. Thus permitting some of the wells to be pumped at lesser rates over a longer period of time. Quantities of water required for domestic water at the construction camps are comparatively insignificant and will not be pumped at as large a rate as those needed for road and shelter construction.

Incorporating water wells into the construction sequencing indicate the following:

- a. 1st fiscal year (construction season): Construct primary DTN, unpaved: The DTN road contractor would drill wells at intervals under his contract to provide water for road construction. Assume a variable interval from 10 to 30 miles dependent upon availability of water well locations. Wherever possible, these wells would serve other contractors in later fiscal years (construction seasons).
- b. 2nd fiscal year (construction season) construct secondary cluster roads: The cluster road contractor would drill additional wells under his contract as needed, perhaps one well for every two clusters, to provide water for road construction. These wells would then be in place to serve the shelter contractors, including the potential for a portable batch plant for the cast-in-place option.
- c. 3rd fiscal year (construction season) construct shelters: The shelter construction contractors would utilize the same wells previously drilled by the road contractors in the cluster proximity.

The advantages of this sequencing program as related to the water resource are:

1. providing water in the proximity of the shelter sites; 2.reducing peak demands on each well by spreading water requirements over more than one construction season (roads/shelters); 3. is compatible with the cast-in-place option and may ease permitting by virtue of the fact that well locations can be pinpointed earlier in the design process (along road routes and cluster locations).

MX - EIS

CONSTRUCTION SEQUENCE

TEXAS-NEW MEXICO

This sequencing is scoped to meet the IOC and FOC completion dates, which are considered to be firm. Any modification of the schedule will result in a change to either the IOC or FOC dates.

The specific location of the initial effort will be dependent upon the location of the principal, or first Operating Base. Within the Operating Base, there will be a contractors support camp built in FY-82. At the same time, construction roads and water wells must be started into the initial group of clusters. A marshalling yard for transhipment of material will be located during the first year. The accommodation of the construction force will result in impacts upon items such as community cohesiveness, public services, economic stability, water and natural resources as well as the entire transportation and supply system.

In order to accomplish the construction necessary to meet the immediacy of the IOC and the slightly longer term FOC, every effort must be made to be ready to start constructing shelters in FY-84. Such a shelter construction schedule requires that FY 82-83 preparatory construction contracts for roads and communications be effected if access to the work areas for equipment, personnel and material is to be provided.

The following presents not only the Construction Sequence but also some basic data and construction notes considered pertinent for this discussion.

A. Construction Sequence (200 Clusters)

1. Parameters

- a. Construct 200 clusters.
- b. Start construction in following sequence:

FY-84	26 clusters
FY-85	28 clusters
FY-86	38 clusters
FY-87	69 clusters
FY-88	39 clusters

c. Complete 10 clusters (minimum) by Jan 85.

2. Assumptions

- a. Construct 100 clusters in each state.
- b. Limited roadway construction to start in FY-82.
- c. For ease of reference and in conformance with funding sequence in A.l.b. above, clusters are assimilated in five groups as shown on attached sketch. Obviously, many other grouping arrangements are possible. As sequenced, construction begins closest to Cannon AFB and proceeds in an orderly counter-clockwise direction. Because of the multiplicity of highways, the prospect of interference between contractors is small.

3. FY 80-81

Concerted effort regarding title search, property survey, negotiations, condemnations, and all other operations related to real estate acquisition.

4. <u>FY-82</u>

- a. Enlarge Cannon AFB, construct MAB, OBTS, and complete MOB facilities. Cannon AFB appears to be a superior selection as an MOB location due to rail service, the juncture of U.S. highways 60, 70 and 84, and its proximity to a majority of the 200 clusters. One hundred twenty (120) clusters encircle and are within 75 miles of Cannon AFB.
- b. Establish marshalling yard at Cannon AFB. Considering that (1) the average haul distance from Cannon to 120 clusters is 35 miles over flat terrain, (2) there are excellent secondary and tertiary road systems, and (3) there are rail systems in four directions. a single, large, all-encompassing marshal yard should suffice for the construction of the 120 clusters in Groups I. II, III. and V.
- c. Set up quarry operations to produce flexible base material and concrete aggregates for Groups I and II clusters.
- d. Establish life support facilities southwest of Cannon AFB near Elida, New Mexico. The impact upon available housing and other life support facilities will be greatest during the construction of New Mexico sites, which are farthest from the large population centers. Facilities at Elida would receive support from Clovis, NM (40 miles) and Roswell, NM (65 miles) and would be convenient to construction of Groups I, II, and III.
- e. Construct DTN roads to Group I (26 clusters in New Mexico). There are state highways which meet configuration requirements leading from Cannon AFB and from U.S. 60 to Group I clusters.

5. FY-83

- a. Construct DTN roads to Group II (28 clusters in New Mexico).
- b. Construct cluster roads Group I.

6. FY-84

- a. Construct Group I shelters (26 x 23).
- b. Construct Group II cluster roads.
- c. Construct DTN to Group III (15 clusters in NM 23 in TX).
- d. Provide for the production of flexible base materials and concrete aggregates around and west of Dalhart. TX.
- e. Construct secondary operating base with all contingent features near Dalhart. TX.
- f. Establish marshalling yard near Dalhart, TX for northern 80 clusters.

7. FY-85

- a. Construct Group II shelters (28 x 23).
- b. Construct Group III cluster roads.
- c. Construct DTN roads to Group IV (69 of 80 clusters: 31 in NM -49 in TX).

8. FY-86

- a. Construct Group III shelters (38 x 23).
- b. Construct Group IV cluster roads.
- c. Construct DTN roads to Group V (11 from Group IV 28 in TX Group V).

9. FY-87

- a. Construct Group IV shelters (69 x 23).
- b. Construct Group V cluster roads.

10. FY-88

Construct Group V shelters (39 x 23).

B. <u>Construction Sequence</u> (100 Clusters)

1. Parameters

- a. Construct 100 clusters.
- b. Start construction in following sequence:

FY-84	13 clusters
FY-85	14 clusters
FY-86	19 clusters
FY-87	35 clusters
FY-88	19 clusters

c. Complete 10 clusters (minimum) by Jan 85.

2. Assumptions

- a. Construct 50 clusters in each state.
- b. Limited roadway construction to start in FY-82.
- c. For ease of reference and in conformance with funding sequence in B.1.b. above, clusters are assimilated in five groups as shown on attached sketch. Obviously, many other grouping arrangements are possible. As sequenced, construction begins closest to Cannon AFB and proceeds in an orderly counter-clockwise direction. Because of the multiplicity of highways, the prospect of interference between contractors is small.

3. FY 80-81

- a. Concerted effort regarding title search, property survey, negotiations, condemnations, and all other operations related to real estate acquisition.
- b. Accelerated E&D effort to meet compressed scheduling of advertisement and award of construction contracts for FY-82.

4. FY-82

- a. Enlarge Cannon AFB, construct MAB, OBTS, and complete MOB facilities. Cannon AFB appears to be a superior selection as an MOB location due to rail service, the juncture of U.S. highways 60, 70 and 84, and its proximity to 100 clusters (50 in each state), all within 75 miles and in a circular pattern around Cannon AFB.
- b. Establish marshalling yard at Cannon AFB. Considering that(1) the average haul distance from Cannon to 100 clusters is

35 miles over flat terrain, (2) there are excellent primary, secondary, and tertiary road systems, and (3) there are rail systems in four directions, a single, large, all-encompassing marshal yard should suffice for the construction of the 100 clusters.

- c. Set up quarry operations to produce flexible base material and concrete aggregates for Groups I, II and III clusters.
- d. Establish life support facilities southwest of Cannon AFB near Elida, New Mexico, if required. The impact upon available housing and other life support facilities will be greatest during the construction of New Mexico sites, which are farthest from the large population centers. Facilities at Elida would receive support from Clovis, NM (40 miles) and Roswell, NM (65 miles) and would be convenient to construction of Groups I and II.
- e. Construct DTN roads to Group I (13 clusters in New Mexico). There are state highways which meet configuration requirements leading from Cannon AFB and from U.S. 60 and U.S. 70 to Group I clusters.

5. FY-83

- a. Construct DTN roads to Group II (14 clusters in New Mexico).
- b. Construct cluster roads Group I.

6. FY-84

- a. Construct Group I shelters (13 x 23).
- b. Construct Group II cluster roads.
- c. Construct DTN to Group III (4 clusters in NM 15 in TX).
- d. Provide for the production of flexible base materials and concrete aggregates north of Clovis, NM.
- e. Provide life support services in the NE quadrant, if required, near Frione or Hereford, TX.
- f. Establish a second marshalling yard near Hereford, TX, if required.

7. FY-85

a. Construct Group II shelters (14 x 23).

- b. Construct Group III cluster roads.
- c. Construct DTN roads to Group IV (35 clusters in TX).

8. FY-86

- a. Construct Group III shelters (19 x 23).
- b. Construct Group IV cluster roads.
- c. Construct DTN roads to Group V (19 clusters in New Mexico).

9. FY-87

- a. Construct Group IV shelters (35 x 23).
- b. Construct Group V cluster roads.

10. FY-88

Construct Group V shelters (19 x 23).

C. Construction Notes

- 1. This plan addresses the establishment of two major marshalling yards for the receipt, storage, and dissemination of Government-furnished materials and equipment, and for contractor logistical usage. The contractor would have the latitude to establish other intermediate marshalling locations for his own usage.
- 2. The number and location of quarries being operated should be the operating contractor's prerogative, and hence a matter of economics, becoming a function of moving expense between quarries versus Rail distance.
- 3. A survey of current and near future (5 years) availability of cement (including low-alkali) should be made to determine the feasibility or necessity of Government stockpiling and furnishing of cement and steel.
- 4. There are a number of shut-down air bases in the general area, namely Webb AFB at Big Spring, Walker AFB at Roswell, etc. which may become usable as operating bases or marshalling yards in the event of a significant shift in cluster location.

5. Dust Control

a. Dust control measures will be necessary during construction for safety and physiological reasons. It should be noted, however, that the New Mexico-Texas High Plains area is extremely prone to continuous and unobstructed winds, which, together with sandy, silty and arid soil conditions, result in frequent sand and dust storms.

b. Accordingly, dust and sand drifts may be expected to accumulate in depressed areas and at shelter entrances creating a continuing maintenance problem.

D. Roads

1. New Roads

- a. Construction of the DTN should be stage construction. Ideally, roadways should be built to top of base course, wrapped up with an emulsion seal as a dust palliative, and opened to construction traffic for compaction. For rapid construction, ease of repair, and economy, a double bituminous surface treatment is recommended for surfacing.
- b. Subgrade soil conditions range from predominantly CL materials, with Liquid Limits ranging from 35-50, west of Amarillo, to sandy CL material and clayey sand (LL = 20-30) southward towards Lubbock and Cannon AFB. Both the Corps of Engineers and the Texas Highway Department have utilized lime-stabilization of these subgrade materials on construction projects in this area.

2. Existing Roads

- a. Examination of large-scaled County road maps reflect a definite pattern regarding the secondary paved roads and the tertiary graded and drained open-surfaced roads in the project area in Texas; these roads are orientated North-South and/or East-West in practically every instance, and are usually located along "section" (one square mile) lines or multiples of section lines. In the more northerly counties, the roads are less extensive with much larger distances (10 miles or more) between roads in some areas. Some southerly counties, however, are practically covered with a highly developed network of N-S and E-W roads one mile apart in each direction.
- b. Superimposing cluster roads over these county roads indicate 10 to 20 new road crossings per cluster. Assuming an average of 15 new road crossings per cluster, and 2 new drainage structures per crossing, an order of magnitude of 6,000 new drainage structures would be indicated and would be required. Additional drainage structures will be needed where DTN roads intersect existing roads, and where new roads block significant drainage areas or encounter gulleys, creeks, streams, etc. Total drainage structures will probably exceed 10,000 structures. Conceding the use of small diameter pipe or multiples thereof, in most instances, still a significant effect on the culvert pipe industry will result.
- c. These structures will change drainage patterns, concentrate flows, increase erosion, and increase downstream deposition to some

indeterminate degree. They will also prevent deterioration of project roads and permit use of project roads during inclement weather. If project roads are to intersect existing roads at grade, vertical clearance of new culverts will be a problem at many sites since existing drainage ditches are rather shallow, particularly on unpaved roads.

d. Relocation of some rural telephone and power lines will be necessary for vertical clearance of large vehicles on project roads. In ranching areas, some new fencing will be required to maintain control of livestock where roads intersect existing fences.

3. Roadway Design

Considering the extremely short design period remaining prior to FY-82 road construction, and recognizing that field investigation and survey for roadway design will be severely limited, consideration should be given to a Design and Construct type contract (1-step, 2-Step, performance spec, etc). The contractor would be given configuration and strength guidelines and have the latitude to make field deviations to avert obstructions and seek more advantageous field conditions.

E. Life Support Facilities

- 1. The requirement for a life support contractor is not as great in the Texas-New Mexico area as other remote areas due to the proximity of food, shelter, and other support facilities. This is particularly true in West Texas where the worker-farmer-rancher traditionally and habitually commutes comparatively long distances for services, supplies, and employment. Nevertheless, the impact of the relocation of upwards of 100,000 contractor and support personnel with dependents will require augmenting of available life services, especially in the New Mexico areas. Life support facilities will be of most urgency at the outset of construction operations, when the bulk of the New Mexican clusters are sequenced for construction, and to allay the initial psychological impact.
- 2. Obviously, the great bulk of housing and support facilities will have to come from either existing communities in the area or from temporary construction camps. Mobile homes would probably be the most inexpensive and easiest way of constructing temporary camps, whether or not they are within the city limits of local communities; streets, utilities and trailer pads are easy and fast construction, and the mobile homes will have salvage value at the end of construction. Water, telephone and electrical power for life support facilities during construction does not seem to be a significant problem in the New Mexico-Texas area providing the proper planning, coordination and

funding is consummated with local authorities. Sewage collection and treatment could be a sizable problem for some areas; the most palatable solutions appear to be package treatment plants or truck transport to existing treatment plants for processing in accord with prearranged fee. Another alternative which should be explored is land treatment of raw sewage, which is sometimes utilized in this area, notably in Lubbock, Texas. Trailer camps would also be relocatable to different areas within the entire construction site during the construction of the project. Zoning and spacing arrangements may be worked out within townships with some residual benefit to the latter by including provisions for leaving the utilities in place for township use and development after construction of the project is completed.

F. Water Supply

- 1. The single most critical factor affecting the selection, and subsequently, sequencing of construction operations is the availability of adequate water supply. All proposed sites are located in the High Plains area and are underlain by the Ogallala Formation. The area is used primarily for cattle grazing with substantial amounts of irrigated agriculture featuring soybeans, sorghum, and some cotton and wheat.
- 2. According to the USGS, the demand for surface water, primarily for irrigation, will triple by 2020. This increased demand will result from the ongoing and projected depletion of the ground water supply. The water in storage in the Ogallala aquifer is being depleted at an approximate rate of 3.5 million acre-feet per year. Since current surface water supplies are insignificant, and annual rainfall is low (16 18 inches), recharge to the aquifer is very small. The amount of recoverable water in the Ogallala aquifer was estimated at 140 million acre-feet in 1967. Average depth to water increased by 40 feet to a depth of about 150 feet from the middle 60's to the middle 70's; similarly, an average well depth of 200 feet may be projected for the middle 80's.
- 3. Summary: Although ample construction water is locally available, there are continuing studies being made, and the local populace are aware of a growing and future water problem. Resistance to further depletion may be expected; alternative use of purchased water should be considered.

