

AD-A105 081

CONSTRUCTION ENGINEERING RESEARCH LAB (ARMY) CHAMPAIGN IL F/G 13/2  
PRETREATMENT OF WASTE DISCHARGES FROM IMPROVED ARMY TACTICAL EQ--ETC(U)  
AUG 81 R FILECCIA, S KLOSTER, L BENSON  
CERL-TR-N-107

UNCLASSIFIED

NL

1 OF 1  
GSA (DA)



END  
DATE  
FILMED  
10-81  
DTIC

construction  
engineering  
research  
laboratory

LEVEL 11



United States Army  
Corps of Engineers  
...Serving the Army  
...Serving the Nation


12  
TECHNICAL REPORT N-107

August 1981

Oil Pollution Control at Military Installations

PRETREATMENT OF WASTE DISCHARGES FROM IMPROVED  
ARMY TACTICAL EQUIPMENT MAINTENANCE FACILITIES

AD A105081



by  
R. Fileccia  
S. Kloster  
L. Benson  
M. Kamiya  
J. Matherly

DTIC  
ELECTE  
OCT 6 1981

A



Approved for public release; distribution unlimited.

81 10 5 080

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official indorsement or approval of the use of such commercial products. The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

**DESTROY THIS REPORT WHEN IT IS NO LONGER NEEDED  
DO NOT RETURN IT TO THE ORIGINATOR**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

14 REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CERL-TR-N-107	2. GOVT ACCESSION NO. AD-A105081	3. RECIPIENT'S CATALOG NUMBER (9)
4. TITLE (and Subtitle) PRETREATMENT OF WASTE DISCHARGES FROM IMPROVED ARMY TACTICAL EQUIPMENT MAINTENANCE FACILITIES.		5. TYPE OF REPORT & PERIOD COVERED FINAL rept.
7. AUTHOR(s) R. Fileccia, S. Kloster, L. Benson M. Kamiya, J. Matherly		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. ARMY CONSTRUCTION ENGINEERING RESEARCH LABORATORY P.O. Box 4005, Champaign, IL 61820		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS (11) 405		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 4A762720A896-02-009
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) (12) 44		12. REPORT DATE August 1981
		13. NUMBER OF PAGES 39
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Copies are obtainable from the National Technical Information Service Springfield, VA 22151		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) waste water military vehicles oil wastes cleaning		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report describes (1) field investigations into the use of commercial cleaning equipment for Army tactical equipment maintenance operations and (2) an evaluation of wastewater pretreatment requirements for sanitary sewer discharge. Included is an analysis of raw wastewater characteristics, an evaluation of commercial cleaning equipment performance, and the development of design criteria for wastewater pretreatment. Also described is the field verification of these criteria at a pilot test facility that used a commercially packed, gravity oil/water separator. It was determined that operation-		

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

Block 20 continued.

ally reliable commercial cleaning equipment is available to the Army that can perform all required maintenance cleaning tasks without cleaning aids. It was also determined that wastewater pretreatment requirements could be stated in terms of total suspended solids and free oil removal to predetermined levels, if low hydraulic overflow rates and relatively long detention times are used.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)


## FOREWORD

This report was prepared for the Directorate of Military Programs, Office of the Chief of Engineers (OCE), under Project 4A762720A896, "Environmental Quality for Construction and Operation of Military Facilities"; Task Area 02, "Pollution Abatement Systems"; Work Unit 009, "Oil Pollution Control at Military Installations." The applicable QCR is 3.01.004. The OCE Technical Monitor is Mr. Walt Medding.

The study was conducted by the Environmental Division (EN) of the U.S. Army Construction Engineering Research Laboratory (CERL). Dr. R. K. Jain is Chief of CERL-EN. Valuable contributions were made by former CERL employees Ms. C. Watson and Mr. E. Lubieniecki, and by Directorate of Facilities Engineering (DFAE) personnel and members of the 2nd Battalion/77th Armored at Fort Lewis, WA. Their cooperation in this effort is greatly appreciated.

Special appreciation is extended to Mr. Mark Massarik, former Sanitary Engineer, Fort Lewis, and Mr. David Hanke, present Sanitary Engineer, Fort Lewis, for their administrative and technical assistance.

COL Louis J. Circeo is Commander and Director of CERL, and Dr. L. R. Shaffer is Technical Director.



## CONTENTS

	<u>Page</u>
DD FORM 1473	
FOREWORD	3
LIST OF TABLES AND FIGURES	5
1 INTRODUCTION.....	7
Background	
Objective	
Approach	
Scope	
Mode of Technology Transfer	
2 TRACKED VEHICLE MAINTENANCE FACILITY.....	9
Background	
Facility Description	
3 CRITERIA FOR EQUIPMENT SELECTION.....	11
Cleaning Equipment	
Wastewater Treatment Equipment	
4 PRELIMINARY CLEANING EQUIPMENT EVALUATION AND WASTEWATER CHARACTERIZATION.....	13
Initial Testing	
Test Procedures	
Wastewater Characterization Tests	
Initial Test Results	
Wastewater Characteristics	
Sedimentation Test	
5 PHASE 2 INVESTIGATION.....	20
Wastewater Treatment Unit Description	
Pilot Facility Description	
Test Procedures	
Analytical Results	
Summary of Phase 2 Testing Results	
6 PHASE 3 INVESTIGATION.....	27
Pilot Facility Description	
Test Procedures	
Analytical Results	
7 CONCLUSIONS.....	35
APPENDIX A: Experimental Method for Quantitatively Differentiating Between Free, Emulsified, and Dissolved Oil in Wastewater	36
APPENDIX B: Summary of All Observed Water Usage Data and Cleaning Times Obtained During Study	38
DISTRIBUTION	

## TABLES

<u>Number</u>		<u>Page</u>
1	Effluent Quality Criteria	12
2	Initial Cleaning Test Data	15
3	Data Summary of Wastewater Characteristics	16
4	Sedimentation Column Data	18
5	Details of Pilot Oil/Water Separator	20
6	Observed Water Usage and Cleaning Times for Several Types of Tactical Equipment	24
7	Water Usage Data	24
8	Wastewater and Separator Effluent Characterization Data	25
9	Summary of Observed Water Usage and Cleaning Times	28
10	Kerosene Consumption in Gallons by Cleaning Machine Type	31
11	Data Summary of Pilot Oil/Water Separator Performance	32
12	Tactical Equipment Cleaning Using Existing Wash Facilities	34

## FIGURES

1	Tracked Vehicle Maintenance Facility	10
2	Percent Total Suspended Solids Removal With Column Depth and Settling Time	19
3	Percent Suspended Solids Removal -- Overflow Rate Analysis	19
4	Percent Suspended Solids Removal -- Detention Time Analysis	19
5	Oil/Water Separator	21
6	Pilot Maintenance Cleaning Facility	22
7	Expanded Pilot Maintenance Cleaning Facility	27
8	Total Suspended Solids in Separator Effluent vs Synthesized Maximum Hourly Potable Water Flow	33
9	Total Oil and Grease in Separator Effluent vs Synthesized Maximum Hourly Potable Water Flow	33



## PRETREATMENT OF WASTE DISCHARGES FROM IMPROVED ARMY TACTICAL EQUIPMENT MAINTENANCE FACILITIES

### 1 INTRODUCTION

#### Background

Oily wastewater from Army tactical equipment maintenance operations originates principally from the improper handling and storage of new and waste oils, from equipment washing operations, and from various other maintenance activities that generate wastes that must be stored or treated. An FY77 survey of oil pollution control problems at Army installations identified the need for improved waste oil handling systems in the Table of Organization of Equipment (TOE) maintenance areas, especially those areas handling tracked equipment. This study also pointed out that heavy maintenance cleaning operations (e.g., the cleaning of engines, engine compartments, and other equipment components) performed on existing washrack facilities were inefficient and consumed large quantities of potable water. Existing high-volume, low-pressure wash hose systems also invariably required the use of solvents and industrial and domestic detergents. Under these conditions, the construction of effective wastewater treatment units at each individual washrack site did not appear to be practical or economical if a large number of sites had to be considered.<sup>1</sup>

Since 1975, the U.S. Army Construction Engineering Research Laboratory (CERL) has been trying to identify facility requirements for centralized vehicle washing and wastewater treatment systems and to identify improved in-motorpool maintenance facilities.<sup>2</sup> This latter research effort developed the concept of the tracked vehicle maintenance facility. The principal purpose of this facility was to provide a dedicated space within the hardstand area where all cleaning tasks essential to tracked vehicle maintenance operations, including oil changing, could be performed efficiently. These facilities (as designed for Fort Lewis, WA) also would handle wet maintenance requirements for all types of TOE wheeled equipment. This concept would make it possible to control wastes generated by tracked vehicle maintenance operations.

The main sanitary engineering concerns in the design of the tracked vehicle maintenance facility for military use are: (1) the selection and evaluation of commercial high-pressure, low-volume cleaning equipment capable of meeting all anticipated service conditions without the need for solvents or other cleaning aids, and (2) an analysis of wastewater treatment requirements for effluent discharge to an installation's sanitary sewer system.

<sup>1</sup> Consolidated Facilities for Washing Tactical Vehicles, Engineer Technical Note (ETN) No. 77-14 (Office of the Chief of Engineers [OCE], 10 August 1977).

<sup>2</sup> ETN 77-14; and R. Fileccia, J. Benson, and J. Matherly, In-Hardstand Tactical Vehicle Maintenance Facilities -- Concept Design and Preliminary Recommendations for Wastewater Treatment, Interim Report N-67/ADA067985 (U.S. Army Construction Engineering Research Laboratory [CERL], March 1979).

## Objective

The objective of this study is to evaluate the performance of commercial cleaning equipment under field conditions and to analyze the requirements for the treatment of the resultant wastewaters for discharge to an installation's sanitary sewer system.

## Approach

This study had three phases:

1. Field tests were conducted to determine if commercial equipment could perform all the required maintenance cleaning tasks without cleaning aids. During this same period, the physical and chemical characteristics of the wastewaters were determined. Based on an analysis of these data, preliminary design criteria for wastewater treatment were developed.

2. A pilot cleaning facility which had a commercially packed, gravity oil/water separation unit was tested to validate the preliminary design criteria and to further evaluate the performance of commercial equipment.

3. The pilot cleaning facility was physically expanded to determine the hydraulic capacity of the separation unit and to confirm, if possible, estimates made of the maintenance frequency for the treatment unit. Quantitative measurements of maintenance cleaning times and potable water usage corresponding to the use of existing wash facilities were collected for comparison.

All phases of this study were conducted at the 2nd Battalion/77th Armored motorpool, Fort Lewis, WA.

## Scope

The intent of this investigation was not to perform an exhaustive evaluation of all types of commercial cleaning machines or oil/water separation equipment currently on the market, but to identify those items of commercially available equipment that could potentially meet the performance criteria established for these items in the concept design of the tracked vehicle maintenance facility.

## Mode of Technology Transfer

The results of this study will impact on Evaluation Criteria for Water Pollution Prevention Control and Abatement Programs, Army Technical Manual 5-814-8 (30 July 1976).

## 2 TRACKED VEHICLE MAINTENANCE FACILITY

### Background

As presently designed, TOE maintenance facilities require that virtually all wet maintenance operations, such as oil changing and equipment cleaning, be performed on the surrounding concrete hardstand under conditions that make effective pollution control both difficult and expensive. The problem becomes especially acute when tracked vehicle maintenance operations are considered. To carry out these operations, large quantities of new and waste oils must be handled under the most primitive conditions. In addition, most maintenance cleaning tasks use high-volume, low-pressure wash hoses. Mainly as a result of these conditions, considerable quantities of waste oil are often discharged to the storm water collection system via the washrack drain. The use of existing washrack facilities for maintenance cleaning also means that soaps, detergents, and solvents such as diesel fuel are used, further complicating the wastewater treatment problem. Since the washrack facility also invariably drains a large portion of the adjacent hardstand area -- which may reach a size of 7 acres (2.8 hectares) or more -- the design of wastewater pretreatment units for effluent discharge to an installation's sanitary sewer system is generally impractical unless the existing washrack is extensively modified at the same time.

### Facility Description

The concept of the tracked vehicle maintenance facility was developed to correct the conditions described above. As designed for Fort Lewis, the facility (Figure 1) essentially consists of a canopied service platform raised above the general hardstand area. This prevents stormwater intrusion from adjacent hardstand areas. The service platform is divided into two functional areas: an oil changing area and a maintenance cleaning area.

#### *Oil Changing Area*

As designed, all oil changing is done within a lighted service pit equipped with a sliding waste oil collection funnel. The funnel, which is sized to contain a quantity of oil equal to the maximum combined crankcase and transmission capacity of an M-88 tracked vehicle, discharges into a collection trough. This trough is connected by rigid 4-in. (10.2-m) piping to a 1000-gal (3790-L) underground waste oil storage tank. The funnel has a hinged two-section cover which ensures a watertight seal when the funnel is opened during cleaning operations or oil filter drainage. The waste oil inlet at the bottom of the collection funnel is protected by a reinforcing bar screen (at the funnel entrance) and a commercial-type drain plate (fitted into the bottom of the funnel at the waste drain entrance). This combination of screen and plate is designed to prevent the waste oil drainage system from being clogged by dropped tools, rags, bolts, etc.

The sliding waste oil collection funnel was designed so it has only limited movement within the service pit. This lets it act as a vehicle positioner for the M-60 tank. Vehicle position is important when servicing this vehicle type because the engine pack (engine and transmission) can only be




Figure 1. Tracked vehicle maintenance facility.

removed after the gun has been rotated. The vehicle must be positioned to protect the canopy columns from being damaged when the gun turret is rotated.

#### *Maintenance Cleaning Area*

Maintenance cleaning can be done either with the vehicle in position over the service pit or in the maintenance cleaning area proper. The service pit area is used mainly to clean the engine compartments and vehicle undercarriages. The main maintenance cleaning area is used for equipment inspection cleaning, and to prepare exterior vehicle surfaces before painting or before cleaning engine packs and other large components. Engine packs are moved from the service pit to the adjacent maintenance cleaning area by a 7-1/2 ton (3405 kg) capacity traveling bridge crane. Wastewater produced by the wash equipment is conveyed to the wastewater pretreatment unit by area drains located in both the main cleaning area and at the bottom of the service pit. These discharges then go into a wastewater pretreatment unit located outside the maintenance facility area. The cleaning equipment is on a service island which has a waste receptacle for used filters, worn parts, and other litter generated during vehicle servicing.

### 3 CRITERIA FOR EQUIPMENT SELECTION

#### Cleaning Equipment

Cleaning equipment needed for the proposed tactical equipment maintenance facilities was evaluated based on the following performance criteria:

1. Can efficiently clean large equipment items at low water delivery rates, preferably less than 5 gpm (19 L/min) without the use of soaps or detergents.
2. Can efficiently fine-clean vehicle exteriors.
3. Is simple to operate and as maintenance-free as possible.
4. Is of rugged construction.
5. Is operationally safe.
6. Can produce significant reductions in maintenance cleaning times.
7. Will not damage vehicle exterior surface finishes or components.

Hot water wash equipment was selected for evaluation over conventional steam cleaning equipment on the basis of safety considerations, ease of operation, versatility, and superior cleaning potential. Units manufactured by several different commercial equipment suppliers were considered; although no equipment damage was ever reported during the testing period, a thorough evaluation of this factor and its variation with cleaner operational parameters was beyond the scope of this study.

#### Wastewater Treatment Equipment

For the purposes of this study, criteria for the design or selection of equipment for treating wastewater discharge were:

1. The treatment process had to produce an effluent suitable for discharge to an installation's sanitary sewer system. For an installation such as Fort Lewis, where the facilities' anticipated hydraulic inputs into the sanitary sewer system were of secondary importance, effluent quality requirements were defined in terms of pH value, total suspended solids, total oil and grease, biochemical oxygen demand, and heavy metal concentrations. A complete list of effluent criteria used in this study is in Table 1.
2. The treatment process had to be operationally simple and easy to maintain.
3. The required frequency at which maintenance was to be performed was to be kept to a practical minimum.

Table 1  
Effluent Quality Criteria\*

Constituent	Concentration (mg/L) or Unit
Total suspended solids	300 max 200 avg
Total oil and grease	100 max 50 avg
pH	6.0-9.0
BOD <sub>5</sub> **	400 max 300 avg

\*Effluent shall not contain any visible sheen; effluent produced shall be compatible with and not interfere with an installation's domestic wastewater treatment processes.

\*\*The 5-day biochemical oxygen demand.

#### 4 PRELIMINARY CLEANING EQUIPMENT EVALUATION AND WASTEWATER CHARACTERIZATION

##### Initial Testing

For initial testing purposes, a Hotsey Model 840 hot water washer rated at 4 gpm (15.2 L/min) under an operating pressure of 1200 psi ( $8.27 \times 10^6$  Pa) was used.<sup>3</sup> The unit was powered by a 10-hp (7.46-kW) gasoline-driven water-pump motor and a kerosene-fired boiler. Burner fuel was delivered by an electric motor operating off a 110-V, 60-Hz source.

The unit was installed in one bay of a seven-bay vehicle washrack facility in the 2/77th Armored Battalion motorpool. Tests were done from 26 to 28 February 1979, when the battalion was preparing for an Inspector General visit.

The water used by each piece of equipment cleaned was measured by a 1-in. (25.4 mm) Badger cold water meter, Model Number SC-ER-C.<sup>4</sup> Since all vehicle wash bays drained into a common collection trough, wastewater produced by hot water washer operations was segregated from adjacent sources by enclosing three sides of the test bay with sandbags lined with sheets of polyethylene. Grab and composite samples were taken at a drainage point formed at one corner of the sandbag wall.

##### Test Procedures

###### *Equipment Cleaning Tests and Wastewater Sampling*

Cleaning tests were begun by positioning a vehicle or component to be cleaned completely within the prepared test bay. When the test started, an initial water meter reading and start time were recorded. All cleaning tests were done with boiler water temperatures maintained in the range of 150 to 170°F (66 to 77°C). No special cleaners or solvents were used.

Grab and composite wastewater samples were collected periodically throughout each cleaning operation for wastewater characterization and sedimentation analysis. Samples for oil and grease analyses were collected in 1-L, wide-mouth glass jars. Grab samples for other analyses were collected in 100-ml, wide-mouth plastic bottles. Composite samples were made up at the test site using a 9-L glass collection bottle. Collected samples were analyzed using the laboratory facilities at the Fort Lewis sewage treatment plant. Heavy metal and free-oil specific gravity sample analyses were done at CERL.

<sup>3</sup> Hotsey Corporation, Englewood, CO.

<sup>4</sup> Badger Meter Manufacturing Co., Milwaukee, WI.

### Analytical Procedures

All analyses were performed in accordance with Standard Methods for the Examination of Water and Wastewater, with the following exceptions:<sup>5</sup>

1. Total Dissolved Solids: total dissolved solids were determined with a Myron L. Company total dissolved solids meter<sup>6</sup>

2. Free, Emulsified, and Dissolved Oils: a test method to quantitatively differentiate between free, emulsified, and dissolved oils was devised by CERL and used on a trial basis during these analyses. This test method is given in Appendix A.

3. Sedimentation Characteristics: a sedimentation test was done to determine the settling characteristics of a wastewater suspension produced during the exterior cleaning of an M-60 tank using a method proposed by Eckenfelder.<sup>7</sup> To perform the test, a plexiglass column 3.5 in. (88 mm) in internal diameter and 48 in. (1219 mm) long was used. Sampling ports were provided at 6, 24, and 36 in. (152, 609, and 914 mm) below the initial fill level of the column. Testing was done by collecting about 9 L of a composite sample, making a determination of its initial suspended solids concentration, and pouring the sample into the column to a level 6 in. (152 mm) above the uppermost sampling port. Samples for total suspended solids were then periodically extracted at all three sample ports using 10-ml, broken-tipped pipettes.

4. Oil Specific Gravity: the specific gravity of skimmed oil obtained during the sampling program was determined using a glass 10-ml pycnometer.

### Wastewater Characterization Tests

Wastewaters produced by several specific maintenance cleaning operations were analyzed for pH, total suspended solids, volatile suspended solids, total oil and grease, settleable solids, chemical oxygen demand, and 5-day biochemical oxygen demand (BOD<sub>5</sub>). Total and dissolved heavy metal concentrations (cadmium, chromium, nickel, lead, zinc, and iron) produced by cleaning the engine compartment of an M-60 tank were determined on a composited wastewater sample.

### Initial Test Results

Initial results showed that all maintenance cleaning tasks could be done by commercial equipment without soaps or detergents. Water usage data and cleaning times for the various items of equipment processed during the test period are given in Table 2. The cleaning unit itself, however, malfunctioned several times over the evaluation period and had to be repaired by Directorate

<sup>5</sup> Standard Methods for the Examination of Water and Wastewater, 14th Edition (American Public Health Association, American Water Works Association Water Pollution Control Federation, 1975).

<sup>6</sup> Myron L. Company, Carlsbad, CA.

<sup>7</sup> W. W. Eckenfelder and D. L. Ford, Water Pollution Control-Experimental Procedures for Process Design (Pemberton Press, 1970), pp 62-65.



of Facilities Engineering (DFAE) personnel. In general, it was concluded that the unit under evaluation was unreliable for military use.

Table 2  
Initial Cleaning Test Data

Vehicle/ Equipment	Item(s) Cleaned	Number of Observations	Cleaning Times (minutes)			Water Use, gal (L)		
			Max	Min	Avg	Max	Min	Avg
M-60 tank	Vehicle exterior	1	62			178(673)		
	Engine compartment	1	30			72(272)		
	Engine pack	3	67	25	42	81(306)	42(158)	65(246)
M-88 medium retriever	Vehicle exterior	1	22			71(268)		
Jeep	Vehicle exterior engine interior	5	20	5	14	69(227)	37(140)	49(185)
5-ton truck	Vehicle exterior	1	22			80(302)		
Truck, van & tractor	Vehicle exterior	2	31	25	28	90(340)	56(211)	73(276)

\*) gal = 3.785 L

### Wastewater Characteristics

Table 3 summarizes the data collected on the physical and chemical analyses of the wastewater generated during the several maintenance cleaning operations investigated during the initial test period.

Several observations relative to this analysis are:

1. The extremely high grease and oil concentrations found during the engine pack cleaning operation were caused by oil spilling directly onto the cleaning area when oil filters were removed from the engine pack.

2. Although most of the oil appeared to be readily separable, the data showed that at least one operation (engine compartment cleaning) produced a wastewater with a significant emulsified oil content. It is believed that these emulsions are mechanically stabilized by fine particulate matter in the wastestream.

3. Values obtained for biochemical oxygen demand are characteristic of a weak domestic sewage.

4. The ratio of chemical oxygen demand to biochemical oxygen demand indicates that there is a considerable quantity of refractory organics, including oils, in the wastestreams.

5. Heavy metal concentrations in the wastewaters are acceptable for discharge to the sanitary sewer system.

6. The pH value and concentrations of dissolved inorganic materials, measured in terms of total dissolved solids, are within acceptable limits for effluent discharge to the sanitary sewer system.

7. As expected, concentrations of total oil and grease and total suspended solids varied considerably with the type of equipment components cleaned.

Table 3  
Data Summary of Wastewater Characteristics

Activity	Constituent or Condition	Sample Type	Concentration (mg/L) or Unit
Engine pack cleaning (including filter removal)	Total grease & oil	Grab	17061
		Grab	18855
		Avg	17958
	pH	Grab	7.6
		Grab	8.0
		Grab	7.5
		Composite	7.5
	Total suspended solids	Composite	2260
	Settleable solids	Composite	6.2 (ml/L)
	% Volatile solids	Composite	27
Exterior cleaning (M-60 tank)	Total dissolved solids	Composite	135
	COD	Composite	1020
	Temperature		17.5°C
	Total grease & oil	Grab	412
		Grab	1022
		Avg	717
	pH	Grab	7.7
		Grab	7.7
	Total suspended solids	Grab	5900
		Grab	2975
		Avg	4438

Table 3 (Cont'd)

Activity	Constituent or Condition	Sample Type	Concentration (mg/L) or Unit				
Exterior cleaning (M-60 tank)	Total grease & oil	Grab	3448				
		Grab	664				
		Avg	2056				
	pH	Grab	7.3				
	Total suspended solids	Grab	2375				
	Settleable solids	Grab	7.0 (ml/L)				
	COD	Grab	2250				
	BOD	Grab	250				
	Total dissolved solids	Grab	160				
	Engine compartment cleaning (M-60 tank)	Total grease & oil	Grab	664			
pH		Composite	7.5				
Total suspended solids		Composite	957				
Settleable Solids		Composite	0.25 (ml/L)				
COD		Composite	1800				
BOD		Composite	192				
Total dissolved solids		Composite	160				
Engine compartment cleaning (M-60 tank -- special run)		Total grease & oil	Grab	553			
	Emulsified oil	Grab	557				
	Dissolved oil	Grab	11				
Heavy Metals							
Sample	Cd	Cr	Ni	Pb	Zn	Fe	Basis
Total heavy metals	0.86	0.08	0.11	0.05	1.2	7.2	mg/L
Dissolved Heavy Metals	0.017	0.012	0.02	0.005	<0.005	2.5	mg/L
EPA-proposed Pretreatment standards For metal plating Industrial category (Max/30-day avg)	1.0/0.5	4.2/1.6	3.6/1.8	0.8/0.4	3.4/1.5	--	mg/L

### Sedimentation Test

The results of the sedimentation test conducted on a composite wastewater sample of 3680 mg/L initial total suspended solids concentration are given in Table 4 and Figures 2, 3, and 4, respectively. These data indicate that a sedimentation basin under ideal conditions would need an overflow rate of less than 100 gpd/sq ft (4080 L/day/m<sup>2</sup>) and a detention time in excess of 8 hours to meet the average total suspended solids effluent criteria of 200 mg/L (95 percent removal) under the test initial suspended solids loading.

Table 4  
Sedimentation Column Data\*

Height ft (m)	Time (min)	Total suspended solids (mg/L)	% Total suspended solids Removal
0.5 (0.2)	15	1830	50
	30	1110	70
	60	1020	72
	120	680	82
	240	420	89
2.0 (0.6)	15	1960	47
	30	1570	57
	60	1250	66
	120	1120	70
	240	760	79
3.0 (0.9)	15	2330	37
	30	2060	44
	60	1520	59
	120	1300	65
	240	1170	68

\*Initial Total suspended solids = 3680 mg/L




Figure 2. Percent total suspended solids removal with column depth and settling time.




Figure 3. Percent suspended solids removal -- overflow rate analysis.




Figure 4. Percent suspended solids removal -- detention time analysis.

## 5 PHASE 2 INVESTIGATION

During Phase 2 of this study, commercially available hot water washing equipment was evaluated further to determine (1) the water usage and cleaning times required for various types of tactical equipment, and (2) the performance of a commercially available oil/water separator in the pretreatment of wastewater generated during tactical equipment cleaning operations.

### Wastewater Treatment Unit Description

A packed gravity oil/water separator designed and manufactured by ERC/Lancy Inc., St. Paul, MN was selected for field evaluation. The unit consists of a rectangular steel basin separated into two distinct areas: a presettling area for the separation of readily separable solids and free oils, and an area housing a corrugated plate interceptor (CPI) package for the removal of fine solids and dispersed oils. Separated oils are contained on the surface of the basin to a depth established by the elevation of an adjustable skimmed oil weir. Discharges over the weir are conveyed by pipe to an external skimmed oil holding tank. Specific details and a schematic diagram of the unit are in Table 5 and Figure 5, respectively.

Table 5  
Details of Pilot Oil/Water Separator

Type	Packed gravity
Model	600.25 BPR w/presettling chamber
Manufacturer	ERC/Lancy Inc., St. Paul, MN
CPI pack	1/4 full unit
Effective surface area (horizontal projection)	125 sq ft (11.6 m <sup>2</sup> )
Plate spacing	3/4 in. (19.1 mm)
Rated capacity (70°F, differential specific gravity = 0.1)	
for 30 micron particles -- 10 gpm (37.8 L/min)	
for 60 micron particles -- 38 gpm (143.8 L/min)	
Maximum storage capacities	
Readily separable solids -- 48 cu ft (1.4 m <sup>3</sup> )	
Fine solids -- 20 cu ft (0.6 m <sup>3</sup> )	
Free oil (before overflow to storage) -- 150 gal (567.8 L)	




Figure 5. Oil/water separator.

#### Pilot Facility Description

The oil/water separator was tested at the 2/77th Armored Battalion motor-pool. To simulate anticipated field conditions, a reinforced concrete slab was constructed by DFAE personnel immediately adjacent to the existing motor-pool wash facilities. The slab was designed to keep storm water runoff away from adjacent hardstand areas during rainfall. To make the task of cleaning vehicle undercarriages easier, the bridge portion of an Armored Vehicularly Launched Bridge (AVLB) was placed perpendicular to the long axis of the slab; this made it impossible to clean engine packs on the slab surface. Wastewater drained from a concave curvature in the slab's surface to an integrally constructed concrete collection trough on the slab's downstream side. Wastewater collected in the trough was then conveyed via PVC pipe to the nearby pilot oil/waste separator. Figure 6 shows the layout of the pilot facility.

All equipment was cleaned with a hot water washer and without detergent. Initially, a kerosene-fired, gasoline engine unit (Hotsey Model 5800) adjusted to deliver 5.5 gpm (20.8 L/min) at 1100 psi ( $7.58 \times 10^6$  Pa) pressure was used. The unit was discontinued midway through the testing period because of continual mechanical breakdown. In its place, a kerosene-fired, electrically driven unit (Hydroblitz<sup>8</sup> Model 1500) rated at 3 gpm (11.4 L/min) at 700 psi ( $4.8 \times 10^6$  Pa) pressure was used. This latter unit, much simpler in design than the former, performed satisfactorily during the remainder of the test period. Wash water temperature for both units was maintained at between 150 and 170°F (66 and 77°C).

<sup>8</sup> Hydro Systems Company, Cincinnati, OH.




Figure 6. Pilot maintenance cleaning facility.

### Test Procedures

The testing program collected data on the following parameters:

1. Water usage and cleaning times for various items of tactical equipment.
2. Average and peak daily water usage.
3. Oil/water separator effluent quality.
4. Sludge accumulations per unit of flow volume.
5. Skimmed oil volumes and characteristics.
6. Oil/water separator maintainability characteristics.

Water usage data were collected by taking readings from a potable water meter placed between the potable water source and hot water washer. Equipment cleaning times were determined by noting the start and stop times for each equipment type cleaned. Effluent quality was measured by taking grab and composite samples periodically throughout a given day's operation. Influent grab and composites were also collected intermittently to characterize wastewater inputs to the separator and for comparison with results of the initial wastewater characterization. No attempt was made to directly relate influent and effluent sampling times because of the intermittent nature of the cleaning operation.



Collected samples were analytically tested mainly by taking measurements of total and volatile suspended solids, total oil and grease, and pH value. Less frequently, analyses were made of chemical oxygen demand, BOD<sub>5</sub>, and influent and effluent wastewater temperatures.

Average sludge accumulation per unit volume of flow was determined by making an indirect measurement of sludge depth and noting the total volume of water used to the time of measurement. Sludge volume was computed by assuming that the measured depth was uniform over the surface area of the primary sedimentation basin.

### Analytical Results

#### *Tactical Equipment Cleaning Operations*

Data on cleaning times and water usage per equipment type were collected from 19 to 21 September, 24 to 26 September, and 4 to 5 October 1979. A data summary is in Table 6.

#### *Hourly and Daily Water Use*

Table 7 gives the water usage data corresponding to each day's cleaning activity. The data indicate that the maximum 1-hour flow should not exceed about 150 gal (569 L) per cleaning machine; the average hourly flow per machine measured over a typical 8-hour period should not exceed 100 gph (379 L/hour). Based on this latter figure and a 3 gpm (11.4 L/min) machine, the maximum average use rate for the machine is 61 percent. From these data, it is estimated that the maximum daily use rate per cleaning machine will not exceed 70 percent and the average daily usage will not exceed 50 percent.

#### *Wastewater Characteristics and Oil/Water Separator Performance*

Table 8 summarizes wastewater and oil/water separator effluent characteristics. For the flow rates produced by the cleaning equipment -- i.e., 5.5 gpm (20.8 L/min) and 3 gpm (11.4 L/min), respectively -- the data indicate that the pilot wastewater treatment unit removed a 92 percent of the total suspended solids, 95 percent of the influent total oil and grease, and 79 percent of the influent chemical oxygen demand. These figures are based on the average values of influent and effluent concentrations obtained from an analysis of grab samples.

Table 6

Observed Water Usage and Cleaning Times for Several  
Types of Tactical Equipment

Tactical Equipment Type	Number of Observations	Water Usage, gal (L)			Cleaning Times (minutes)		
		Max	Min	Avg	Max	Min	Avg
Jeeps	28	60(227)	2(7)	24(90)	23	2	13
APC	11	107(404)	35(132)	65(246)	74	22	42
2-1/2 ton truck	8	50(189)	15(56)	33(124)	27	10	19
Gamma goat	5	59(223)	13(49)	36(136)	42	8	21
Goer	5	191(722)	27(102)	83(314)	150	14	62
Generators	4	44(166)	8(30)	22(83)	25	10	20
MILVAN	2	110(416)	34(128)	72(272)	50	14	32
5-ton truck	2	104(393)	36(136)	70(264)	67	22	45
AVLB	1	----	76(287)	----	----	35	----
M-578 retriever	1	----	36(136)	----	----	20	----

Table 7

## Water Usage Data

Date	24-hour Flow volume gal (L)	Flow, gph (4 hour)	
		Max 1-hour	Avg 8-hour
9/19	1242 (4700)	144 (546)	97 (368)
9/20	881 (3334)	116 (440)	90 (368)
9/21	--	118 (447)	83 (315)
9/24	582 (2202)	95 (360)	82 (311)
9/15	441 (1669)	39 (148)	--
9/26	69 (261)	53 (201)	46 (174)
10/4	2000 (7570)	120 (455)	110* (417)

\* Based on 4-hour data.

Table 8

### Wastewater and Separator Effluent Characterization Data

#### Total Suspended Solids (mg/L)

<u>Characteristic</u>	<u>Influent</u>	<u>Effluent</u>
No. of grab samples	8	8
Maximum	4118	548
Minimum	163	100
Average	2005	171
Average of composites	1379	103

#### Volatile Suspended Solids (mg/L)

<u>Characteristic</u>	<u>Influent</u>	<u>Effluent</u>
No. of grab samples	8	8
Maximum	1105	308
Minimum	295	50
Average	721	109
Composite average	---	64

#### pH Value

<u>Characteristic</u>	<u>Influent</u>	<u>Effluent</u>
No. of samples	7.00	8.00
Maximum	7.95	7.61
Minimum	4.80	6.05
Composite	6.81	6.80, 6.45

#### Grease and Oil (mg/L)

<u>Characteristic</u>	<u>Influent</u>	<u>Effluent</u>
No. of samples	9	
Maximum	2599	147
Minimum	268	about 0
Average	821	41

#### Chemical Oxygen Demand (mg/L)

<u>Characteristic</u>	<u>Influent</u>	<u>Effluent</u>
No. of grab samples	2	2
Average	1692	348
Average of Composites	2763	311

#### Temperature

<u>Characteristic</u>	<u>Influent</u>	<u>Effluent</u>
Average ( $^{\circ}\text{C}$ )	22.3	21.6
Average ( $^{\circ}\text{F}$ )	72.0	70.9

#### Miscellaneous Data

Average effluent  $\text{BOD}_5$  -- 49 mg/L

Sludge volume -- 1.9 cu ft ( $0.05 \text{ m}^3$ ) in 10,110 gal (38 266 L)

Average skimmed oil specific gravity -- 0.94

Average % oil in skim -- 54% single composite

### *Projected Frequency of Sludge Removal*

Based on a measured sludge accumulation of 1.9 cu ft ( $0.5 \text{ m}^3$ ) in 10,110 gal (38 266 L), an average usage rate of 50 percent, an assigned readily separable sludge storage capacity of 48 cu ft ( $1.4 \text{ m}^3$ ) and the potential use of two 3 gpm (11.4 L/min) machines at the cleaning facility, sludge would have to be removed from the separator every 18 weeks on the average.

### Summary of Phase 2 Testing Results

As a result of the Phase 2 testing program, the following information was obtained:

1. Commercial hot water wash equipment was available that can meet the maintenance criteria given in Chapter 3.
2. Adequate cleaning of all tactical equipment and large components can be achieved at flow rates as low as 3 gpm (11.4 L/min) under operating pressure and temperature conditions of 700 psi ( $4.8 \times 10^6 \text{ Pa}$ ) and 150 to 170°F (66 to 77°C).
3. A commercial oil/water separator is available that can meet the established effluent criteria when operating under a hydraulic overflow rate of between 35 and 63 gpd/sq ft (1428 to 2570 L/day/ $\text{m}^2$ ).
4. Sludge storage capacities of the pilot oil/water separation unit appear to satisfy installation maintainability requirements.

## 6 PHASE 3 INVESTIGATION

This phase of the investigation determined the maximum hydraulic capacity of the pilot oil/water separation unit before effluent quality became unacceptable for discharge to the sanitary sewer system. In addition, hot water wash equipment from another manufacturer was evaluated, and further data were collected on cleaning performance and water usage. Cleaning performance and water used to carry out maintenance cleaning operations were tested using existing washrack equipment. These data were necessary to quantitatively compare the two methods for cleaning Army tactical equipment.

### Pilot Facility Description

To increase the hydraulic loading to the treatment unit, the pilot facility was expanded to three bays by connecting the drainage of two existing wash pads to the separator as shown in Figure 7. All three of the wash pads were equipped with hot water wash equipment. Two of the pads had Big Rig<sup>9</sup> equipment operating at a flow of 3 gpm (11.4 L/min), a pressure of 750 psi ( $5.1 \times 10^6$  Pa), and a boiler temperature maintained at between 150 and 170°F (66 to 77°C). The third wash point was equipped with the same Hydroblitz Model 1500 as before. A potable water meter was placed between the incoming potable water line and the cleaning machine at each respective wash point.




Figure 7. Expanded pilot maintenance cleaning facility.

<sup>9</sup> American Kleaner Manufacturing Co., Inc., Pico Rivera, CA.

## Test Procedures

Test procedures for determining cleaning performance characteristics, potable water usage and oil/water separator performance were the same as those used in Phase 2. To determine the cleaning performance of existing washrack facilities, a 1-1/2 in. (38 mm) Badger<sup>10</sup> cold water meter was plumbed into an existing washrack riser pipe for potable water use measurement. The military users were then requested to clean several items of tactical equipment and components using the available 2-in. (51-mm) diameter wash hose (supplemented, if necessary, by any cleaning agents), scrub brushes, etc. that they required. Cleaning times, potable water usage, and solvent usage were recorded for each piece of equipment or component processed.

## Analytical Results

### *Evaluation of Cleaning Equipment*

Both types of machines cleaned very well without cleaning aids. The machine manufactured by American Kleaner, Inc., however, required periodic maintenance during the test programs. The machine manufactured by Hydroblitz, Inc., did not require maintenance at any time during the evaluation.

### *Tactical Equipment Cleaning and Potable Water Usage*

Cleaning times and potable water usage were measured for 170 items of tactical equipment and various components (Table 9). Kerosene usage was 101 gallons (42 L). The distribution of kerosene usage by machine indicates the degree of operational dependability found for each machine type (Table 10).

Table 9

### Summary of Observed Water Usage and Cleaning Times

Vehicles/ Equipment	Item(s) Cleaned	No. of Observations	Cleaning Times (minutes)			Water Usage, gal (L)		
			Max	Min	Avg	Max	Min	Avg
Jeep	Int, ext, & eng	29	20	4	10.1	54(204)	6(22)	23.7(89.7)
	& Trailer	1	15	-	-	29(109)	-	-
	Engine	2	6	5	5.5	12(45)	10(37)	11.0(41.6)
	Transmission	1	4	-	-	3(11)	-	-
	Misc parts	1	8	-	-	3(11)	-	-
Jeep Trailer	-	1	10	-	-	30(113)	-	-
<hr/>								
AVLB	Engine	1	18	-	-	27(102)	-	-
	Engine & exterior	1	42	-	-	85(321)	-	-

<sup>10</sup>Badger Meter Manufacturing Co., Milwaukee, WI.

Table 9 (Cont'd)

Vehicles/ Equipment	Item(s) Cleaned	No. of Observations	Cleaning Times (minutes)			Water Usage, gal (L)		
			Max	Min	Avg	Max	Min	Avg
M-88 (medium tracked retriever)	Exterior	1	47	-	-	96(363)	-	-
	Engine	1	71	-	-	71(268)	-	-
	compartment Engine pack in compt	2	15	15	15.0	48(181)	35(132)	41.5(157)
Light vehicle retriever	Exterior	1	17	-	-	35(132)	-	-
	Interior eng & exterior	1	45	-	-	95(359)	-	-
	Engine & transmission	1	24	-	-	64(261)	-	-
Goer	Exterior	2	21	11	16.0	57(215)	18(68)	37.5(141.9)
	Engine & exterior	1	15	-	-	37(140)	-	-
APC	Interior, eng & exterior	4	58	26	38.3	108(408)	60(227)	76.5(289.5)
	Eng, Eng, Comp & interior	5	47	23	32.6	96(363)	42(158)	68.0(257.3)
	Eng, Eng, Comp & exterior	2	46	15	30.5	94(355)	28(105)	61.0(230.8)
	Engine	2	25	5	15.0	47(177)	11(41)	29.0(109)
	Interior, eng & track	1	28	-	-	48(181)	-	-
	Interior	1	40	-	-	42(158)	-	-
	Exterior	1	10	-	-	23(87)	-	-
	Interior & exterior	1	25	-	-	81(306)	-	-
Gamma-goat	Exterior	2	13	6	9.5	24(90)	14(52)	19.0(71.9)
	Exterior & engine	1	20	-	-	43(162)	-	-

Table 9 (Cont'd)

Vehicles/ Equipment	Item(s) Cleaned	No. of Observations	Cleaning Times (minutes)			Water Usage, gal (L)		
			Max	Min	Avg	Max	Min	Avg
5-ton truck	Int, Ext & engine	4	53	20	34.5	149(563)	43(162)	80.8(305.8)
	Exterior	3	23	15	20.0	49(185)	35(132)	43.7(165.4)
	Front axle Wheels & axles	2	5	4	4.5	14(52)	10(37)	12.0(45.4)
		1	8	-	-	11(41)	-	-
2-1/2-ton truck	Exterior & engine	3	26	15	21.0	64(242)	40(151)	50.7(191.8)
	Engine	2	13	5	9.0	34(128)	6(22)	20.0(75.7)
	Engine & underside	1	58	-	-	126(476)	-	-
M-60 (tank)	Exterior	16	117	15	44.4	222(84)	15(56)	100.1(378.8)
	Interior & exterior	17	200	16	65.6	361(1366)	42(158)	113.5(429.5)
	Engine rack Engine	20	164	13	44.3	293(1109)	21(79)	85.2(322.4)
	compartment	14	94	21	48.2	189(715)	40(151)	99.9(378.1)
	Interior	5	45	13	27.8	79(299)	21(79)	40.2(152.1)
	Int, Ext, & Eng comp	2	140	52	96.0	229(866)	124(469)	176.5(668.0)
	Road wheels	3	26	13	18.0	61(230)	31(117)	42.0(158.9)
	Engine pack & exterior	2	61	50	55.5	102(386)	84(317)	93.0(352.0)
	Engine comp & interior	1	80	--	--	135(510)	--	--
	Engine pack in tank	1	12	--	--	31(117)	--	--
	Engine pack & comp	1	95	--	--	198(749)	--	--
	Heat shields	3	28	6	15.7	39(147)	13(49)	27.7(104.8)
	Misc fans, heat shields, etc.	2	5	4	4.5	6(22)	5(18)	55(208)



Table 10

Kerosene Consumption in Gallons by Cleaning Machine Type\*

Date 1980	Cleaning Machine		
	<u>Big Rig 1</u>	<u>Hydroblitz</u>	<u>Big Rig 2</u>
Jan 17	--	10.0	5
18	--	5.0	--
21	--	10.0	--
22		2.5	2.5
23	2.5	5.0	10
24	2.5	7.0	
Feb 4	5.0	5.0	5
6	5.0	5.0	5
7	4.0	9.0	6

\*1 gal = 3.785 L

*Oil/Water Separator Performance*

Table 11 summarizes the data obtained on the performance of the oil/water separator under various levels of hydraulic loading. Daily rainfall data are also included because the two existing wash platforms used during the test were susceptible to storm water intrusion from adjacent hardstand areas. Figures for maximum hourly flow rate were computed from superimposed plots of cleaning times for each cleaning machine under the assumption that each machine was delivering wash water at its rated capacity. Data presented for total suspended solids and total grease and oil concentrations for September to October 1979 generally represent the average of two grab samples -- one taken in the late morning and one taken in the late afternoon -- for each day's run. Data for January to February 1980 represent the results of single grab samples of influent and effluent concentrations taken in the late afternoon. Because of the highly variable nature of the cleaning operation and the characteristics of the generated wastewater, a mean residence time for wastewater within the separator was not computed. Therefore, the percent removal figures can only be considered qualitative measures of the unit's performance.

Plots of effluent total suspended solids and total grease and oil concentrations and their variation with maximum potable water flow rate for the combined September to October 1979 and January to February 1980 periods are in Figures 8 and 9, respectively. The maximum allowable concentration limits established for the wastewater characteristics are also plotted. It should be noted that the separator plates were cleaned once during the January to February 1980 test period because it was noted that separator effluent quality was deteriorating. Analysis of the data plotted on Figures 8 and 9 indicate that the separator's corrugated plate pack did not need cleaning at that time and that the falloff of separator effluent quality was caused by hydraulic inputs

Table 11

Data Summary of Pilot Oil/Water Separator Performance\*\*

Date 79-80	Daily Prec. (in.)	Potable Water Use (gal)	Max. Hourly Flow Rate (gph)	Total Influent (mg/L)	Total Suspended Solids Effluent (mg/L)	Solids Percent Removal	Influent (mg/L)	Total Oil & Grease Effluent (mg/L)	Percent Removal
9-20	0.00	669	134	--	--	--	1505	51	97
9-21	0.00	514	131	2124	134	94	428	147	66
9-24	0.00	513	95	445	103	77	286	26	91
9-25	0.00	335	70	2120	121	94	1243	37	97
10-4	0.00	472	122	7144**	54**	99	268	<3	99
10-5	0.00	150	120	4118	548	87	575	19	97
1-15	0.89	232							
1-16	0.87	69							
1-17	0.00	160							
1-18	Trace	645			63				
1-21	0.00	759							
1-22	0.00	935	212	375	217	42	1240	116	91
1-23	0.00	738	279	445	265	40	1346	80	94
1-24	0.02	530	337	468	12	97	114	7	94
1-25	0.00	1280	431	26660	580	98	>1000	234	--
1-29	0.00	882							
2-4	0.00	854	400	1180	361	69	4834	248	95
2-5	0.44	1538	454	6530	1830	72	232	314	--
2-6	0.28	1680	430	1100	890	19	1265	102	92
2-7	0.00	1191	385	1500	530	65	116	177	--

\*Metric conversions = 1 in. = 25.4 mm; 1 gal = 3.785 L

\*\*Composited samples




Figure 8. Total suspended solids in separator effluent vs. synthesized maximum hourly potable water flow.

TOTAL OIL & GREASE IN SEPARATOR EFFLUENT  
vs  
SYNTHESIZED MAXIMUM HOURLY POTABLE WATER FLOW




Figure 9. Total oil and grease in separator effluent vs. synthesized maximum hourly potable water flow.

in excess of the unit's capacity. At hydraulic inputs less than 300 gal/hour (1137 L/hour), the effluent from the separator meets pretreatment standards. At hydraulic inputs in excess of 380 gal/hour (1440 L/hour), the effluent from the pilot separator definitely did not meet standards. Therefore, the hydraulic capacity of the separator, as determined by test results, was established at 5 gpm (19 L/min). It is also interesting to note that the hydraulic overflow rate computed at the design capacity of 5 gpm (19 L/min) is 58 gpd/sq ft (1366 L/day/m<sup>2</sup>), which approximates the results established by the sedimentation column test data.

#### *Cleaning Performance Using Existing Washrack Facilities*

To quantitatively demonstrate the difference between the capabilities of the new maintenance cleaning equipment and that of existing washrack facilities, a test was conducted in June 1980 involving the cleaning of two M-60 tracked vehicles being prepared for maintenance service. Each vehicle was put on an individual wash pad and its engine pack removed before the pack and engine compartment were cleaned. Water use on one of the pads was measured using a 1-1/2 in. (38 mm) Badger cold water meter. Before the test, the users were told they could use any chemical cleaning aid or piece of equipment available in the motorpool, except the hot water wash equipment. Results of the cleaning test are shown in Table 12. A comparison of these results with average cleaning times and water usage established for similar cleaning tasks using hot water wash equipment (Table 9) shows that existing wash equipment requires 2.5 times as much cleaning time and about 15 times as much water as that required when using the hot water wash equipment. A compilation of all maintenance cleaning data obtained during the course of this investigation is in Appendix B.

Table 12

#### Tactical Equipment Cleaning Using Existing Wash Facilities

Equipment Cleaned: M-60 Engine Pack Plus Engine Compartment

Observation Number	Water Use, gal (L)	Time to Wash (minutes)	Solvent Type	Solvent Usage, gal (L)
1	5400 (20 439)	235	Type II dry cleaning	4 (15)
			Diesel fuel	2 (7)
2		235	Type II dry cleaning	15.5 (58.6)
			Diesel fuel	2 (7)

## 7 CONCLUSIONS

1. Commercial hot water wash equipment using potable flow rates of less than 5 gpm (19 L/min) can meet the maintenance cleaning requirements of the military user without cleaning aids.

2. Commercial equipment is efficient in terms of manhours of effort expended and potable water usage.

3. At least one commercial manufacturer can supply equipment with the operational and maintainability characteristics needed by military personnel.

4. Wastewater discharges from improved tracked vehicle maintenance facilities which use high-pressure, low-volume hot water wash equipment can be pretreated to acceptable levels by simple gravitational techniques to remove suspended solids and free oils. For Fort Lewis, acceptable pretreatment levels were defined as an effluent having an average and maximum total suspended solids of 200 and 300 mg/L, respectively, and an average and maximum total free oil content of 50 and 100 mg/L, respectively, under all conditions of service.

5. Heavy metal concentrations, organic loading, pH value, and effluent temperature were not a factor for consideration in the discharge of treated wastewaters to the sanitary sewer system.

6. To meet the established effluent criteria by gravitational methods, the hydraulic overflow rate has to be maintained below 100 gpd/sq ft (4080 L/day/m<sup>2</sup>); the wastewater must be given a detention time in excess of 8 hours.

7. The established effluent criteria are only achieved when the overflow rate does not exceed about 58 gpd/sq ft (2978 L/day/m<sup>2</sup>).

## APPENDIX A:

### EXPERIMENTAL METHOD FOR QUANTITATIVELY DIFFERENTIATING BETWEEN FREE, EMULSIFIED, AND DISSOLVED OIL IN WASTEWATER

#### Discussion

Existing standard procedures for analytically determining the oil content of wastewaters are based on the establishment of total oil concentrations in the wastewater under investigation.<sup>11</sup> Although this determination is significant for purposes of regulating effluent quality, its usefulness as a parameter for oil/water separator design is extremely limited. A method establishing the various states in which oil is found in a given sample would indicate whether gravity separation alone was adequate to achieve a desired effluent quality or whether more sophisticated emulsion-breaking unit processes would have to be used.

The method described in this appendix assumes all oily constituents, regardless of state, can be quantitatively solubilized in freon and that existing oil/water emulsion can be completely broken by acid treatment. The weakness of the test method is that the analysis depends on simultaneously collecting three identical grab samples from the wastestream. For wastewater containing considerable quantities of free oil, three identical samples probably cannot be collected.

#### Experimental Method

1. Simultaneously obtain three grab samples of wastewater (about 1 L each). Designate as samples A, B, and C.
2. On Sample A, perform total oil determination in accordance with standard procedures.
3. For Sample B, acidify the sample to pH 1-2, and filter on a Buckner funnel using Whatman No. 40 filter paper that has been treated with filter aid.<sup>12</sup> Extract filtrate obtained with Freon, separate using standard procedures, evaporate and weigh residue. This value corresponds to the dissolved oil concentration of the wastewater.
4. Pour the contents of Sample C into a straight-walled separatory funnel. Allow to settle for 2 hours. After settling, acidify the sample to pH 1-2, and extract with Freon using standard procedures. The results of this determination represent the sum of the emulsified and dissolved oil concentrations.

<sup>11</sup>Methods for Chemical Analysis of Water and Wastes (U.S. Environmental Protection Agency, 1974).

<sup>12</sup>Hyflo Super-Cel, Johns-Manville Corporation, or equivalent.

5. The emulsified oil concentration is obtained by subtracting the results of Step 3 from Step 4.

6. The free oil concentration is determined by subtracting the results of Step 4 from Step 2.

# APPENDIX B:

## SUMMARY OF ALL OBSERVED WATER USAGE DATA AND CLEANING TIMES OBTAINED DURING STUDY

Vehicle/ Equipment	Item(s) Cleaned	No. of Observations	Cleaning Times (minutes)			Water Usage, gal (L)		
			Max	Min	Avg	Max	Min	Avg
Jeep	Int, ext, & eng	62	23	2	11.5	60(227)	2(7)	25.7(97.2)
	& Trailer	1	15	-	-	29(109)	-	-
	Engine	2	6	5	5.5	12(45)	10(37)	11.0(41.6)
	Transmission	1	4	-	-	3(11)	-	-
	Misc parts	1	8	-	-	3(11)	-	-
Jeep Trailer	-	1	10	-	-	30(113)	-	-
M-88 (Medium Tracked Retriever)	Exterior	2	47	22	34.5	96(363)	71(268)	83.5(316.0)
	engine pack (in compartment)	2	15	15	15	48(181)	35(132)	41.5(157.0)
	Engine compartment	1	71	-	-	71(268)	-	-
M-60 (Tank)	Exterior	17	117	15	45.5	222(840)	15(56)	104.7(396.2)
	Interior & exterior	17	200	16	65.6	361(1366)	42(158)	113.5(429.5)
	Engine pack	23	164	13	44.0	293(1109)	21(79)	82.6(312.6)
	Engine compartment	15	94	21	47.0	189(715)	40(151)	98.1(371.3)
	Interior engine pack (in tank)	5	45	13	27.8	79(299)	21(79)	40.2(152.1)
	Interior, exterior & eng comp	1	12	-	-	31(117)	-	-
	Engine pack & compartment	2	140	52	96.0	229(866)	124(969)	176.5(668.0)
	Heat shields	1	95	-	-	198(749)	-	-
	Road wheels	3	28	6	15.7	39(147)	13(49)	27.7(104.8)
	Engine pack & exterior	3	26	13	18.0	61(230)	31(117)	42.0(158.9)
	Engine com- partment & interior	2	61	50	55.5	102(386)	84(311)	93.0(352.0)
	Misc parts, fans, heat shields, etc.	1	80	-	-	135(510)	-	-
		2	5	4	4.5	6(22)	5(18)	5.5(20.8)
APC	Int, ext, & eng,	15	74	22	41.2	108(408)	35(132)	68.3(258.5)
	Eng, eng comp & interior	5	47	23	32.6	96(363)	42(158)	68.0(257.3)



Appendix B (Cont'd)

Vehicle/ Equipment	Item(s) Cleaned	No. of Observations	Cleaning Times (minutes)			Water Usage, gal (L)		
			Max	Min	Avg	Max	Min	Avg
	Eng, eng comp & exterior	2	46	15	30.5	94(355)	28(105)	61.0(230.8)
	Engine	2	25	5	15.0	47(177)	11(41)	29.0(109.7)
	Interior, engine & track	1	28	-	-	48(181)	-	-
	Interior	1	40	-	-	42(158)	-	-
	Exterior	1	10	-	-	23(83)	-	-
	Interior & exterior	1	25	-	-	81(306)	-	-
2-1/2-ton truck	Exterior & engine	11	27	10	19.5	64(242)	15(56)	37.5(141.9)
	Engine	2	13	5	9.0	34(128)	6(22)	20.0(75.7)
	engine & underside	1	58	-	-	126(476)	-	-
5-ton truck	Int, Ext, & engine	4	53	20	34.5	149(563)	43(162)	80.8(305.8)
	Exterior	4	23	15	20.5	80(302)	35(132)	52.8(199.8)
	Front axle	2	5	4	4.5	14(52)	10(37)	12.0(45.4)
	Wheels & axles	1	8	-	-	11(41)	-	-
MILVAN & Trailer	-	2	31	25	28.0	90(340)	56(211)	73.0(276.3)
Gamma-Goat	Exterior	7	42	6	17.4	59(223)	13(49)	31.1(117.7)
	Engine & exterior	1	20	-	-	43(162)	-	-
Goer	Exterior	7	150	11	48.6	191(722)	18(68)	69.9(264.5)
	Engine & exterior	1	15	-	-	37(140)	-	-
AVLB	Engine	1	18	-	-	27(102)	-	-
	Engine & exterior	1	42	-	-	85(321)	-	-
Light vehicle retriever	Exterior	1	17	-	-	35(132)	-	-
	Int, & Ext, & Engine &	1	45	-	-	95(359)	-	-
	transmission	1	24	-	-	64(242)	-	-

# CERL DISTRIBUTION

Chief of Engineers  
ATTN: Tech Monitor  
ATTN: DAEN-ASI-L (2)  
ATTN: DAEN-CCP  
ATTN: DAEN-CW  
ATTN: DAEN-CWE  
ATTN: DAEN-CWM-R  
ATTN: DAEN-CWO  
ATTN: DAEN-CWP  
ATTN: DAEN-MP  
ATTN: DAEN-MPC  
ATTN: DAEN-MPE  
ATTN: DAEN-MPO  
ATTN: DAEN-MPR-A  
ATTN: DAEN-RD  
ATTN: DAEN-RDC  
ATTN: DAEN-RDM  
ATTN: DAEN-RH  
ATTN: DAEN-ZC  
ATTN: DAEN-ZCE  
ATTN: DAEN-ZCI  
ATTN: DAEN-ZCM

US Army Engineer Districts  
ATTN: Library  
Alaska  
Al Batin  
Albuquerque  
Baltimore  
Buffalo  
Charleston  
Chicago  
Detroit  
Far East  
Fort Worth  
Galveston  
Huntington  
Jacksonville  
Japan  
Kansas City  
Little Rock  
Los Angeles  
Louisville  
Memphis  
Mobile  
Nashville  
New Orleans  
New York  
Norfolk  
Omaha  
Philadelphia  
Pittsburgh  
Portland  
Riyadh  
Rock Island  
Sacramento  
San Francisco  
Savannah  
Seattle  
St. Louis  
St. Paul  
Tulsa  
Vicksburg  
Walla Walla  
Wilmington

US Army Engineer Divisions  
ATTN: Library  
Europe  
Huntsville  
Lower Mississippi Valley  
Middle East  
Middle East (Rear)  
Missouri River  
New England  
North Atlantic  
North Central  
North Pacific  
Ohio River  
Pacific Ocean  
South Atlantic  
South Pacific  
Southwestern

Waterways Experiment Station  
ATTN: Library

Cold Regions Research Engineering Lab  
ATTN: Library

US Government Printing Office  
Receiving Section/Depository Copies (2)

Defense Technical Information Center  
ATTN: DDA (12)

Engineering Societies Library  
New York, NY

FESA, ATTN: Library

ETL, ATTN: Library

Engr. Studies Center, ATTN: Library

Inst. for Water Res., ATTN: Library

SHAPE  
ATTN: Survivability Section, CCB-OPS  
Infrastructure Branch, LANDA

HQ USEUCOM  
ATTN: ECJ 4/7-LOE

Army Instl. and Major Activities (CONUS)  
DARCOM - Dir., Inst., & Svcs.  
ATTN: Facilities Engineer  
ARRADCOM  
Aberdeen Proving Ground  
Army Matls. and Mechanics Res. Ctr.  
Corpus Christi Army Depot  
Harry Diamond Laboratories  
Dugway Proving Ground  
Jefferson Proving Ground  
Fort Monmouth  
Letterkenny Army Depot  
Natick Research and Dev. Ctr.  
New Cumberland Army Depot  
Pueblo Army Depot  
Red River Army Depot  
Redstone Arsenal  
Rock Island Arsenal  
Savanna Army Depot  
Sharpe Army Depot  
Seneca Army Depot  
Tobyhanna Army Depot  
Tooele Army Depot  
Watervliet Arsenal  
Yuma Proving Ground  
White Sands Missile Range

FORSOCOM  
FORSOCOM Engineer, ATTN: AFEN-FE  
ATTN: Facilities Engineers  
Fort Buchanan  
Fort Bragg  
Fort Campbell  
Fort Carson  
Fort Devens  
Fort Drum  
Fort Hood  
Fort Indiantown Gap  
Fort Irwin  
Fort Sam Houston  
Fort Lewis  
Fort McCoy  
Fort McPherson  
Fort George G. Meade  
Fort Ord  
Fort Polk  
Fort Richardson  
Fort Riley  
Presidio of San Francisco  
Fort Sheridan  
Fort Stewart  
Fort Wainwright  
Vancouver Bks.

TRADOC  
HQ, TRADOC, ATTN: ATEN-FE  
ATTN: Facilities Engineer  
Fort Belvoir  
Fort Benning  
Fort Bliss  
Carlisle Barracks  
Fort Chaffee  
Fort Dix  
Fort Eustis  
Fort Gordon  
Fort Hamilton  
Fort Benjamin Harrison  
Fort Jackson  
Fort Knox  
Fort Leavenworth  
Fort Lee  
Fort McClellan  
Fort Monroe  
Fort Rucker  
Fort Sill  
Fort Leonard Wood

INSCOM - Ch, Instl. Div.  
ATTN: Facilities Engineer  
Vint Hill Farms Station  
Arlington Hall Station

WESTCOM  
ATTN: Facilities Engineer  
Fort Shafter

MDW  
ATTN: Facilities Engineer  
Cameron Station  
Fort Lesley J. McNair  
Fort Myer

HSE  
HQ USAHSE, ATTN: HSE-1  
ATTN: Facilities Engineer  
Fitzsimons Army Medical Center  
Walter Reed Army Medical Center

USACE  
ATTN: Facilities Engineer  
Fort Huachuca  
Fort Ritchie

MTMC  
HQ, ATTN: MTMC-SA  
ATTN: Facilities Engineer  
Oakland Army Base  
Bayonne Mgt  
Sunny Point Mgt

US Military Academy  
ATTN: Facilities Engineer  
ATTN: Dept of Geography & Computer Science  
ATTN: DSCPER/MAEN-A

USAES, Fort Belvoir, VA  
ATTN: ATZA-DTE-IM  
ATTN: ATZA-DTE-SW  
ATTN: ATZA-FE  
ATTN: Engr. Library

Chief Inst. Div., IASA, Rock Island, IL

USA ARRLCOM, ATTN: Dir., Instl & Svc  
TARCOM, Fac. Div.  
TECOM, ATTN: DRTI-LG-F  
TSARCOM, ATTN: STSA-F  
NARAD COM, ATTN: DRINA-F  
AMMRC, ATTN: DRXMR WE

HQ, XVIII Airborne Corps and Ft. Bragg  
ATTN: AFZA-FE-EE

HQ, 7th Army Training Command  
ATTN: AETTG-DIH (5)

HQ USAREUR and 7th Army  
ODCS/Engineer  
ATTN: AEAEN-EH (4)

V Corps  
ATTN: AETVDEH (5)

VII Corps  
ATTN: AETSDEH (5)

21st Support Command  
ATTN: AEREH (5)

US Army Berlin  
ATTN: AEBA-EN (2)

US Army Southern European Task Force  
ATTN: AESE-ENG (5)

US Army Installation Support Activity, Europe  
ATTN: AEUES-RP

8th USA, Korea  
ATTN: EAPE  
Cdr, Fac Engr Act (F)  
AFE, Yongsan Area  
AFE, 2D Inf Div  
AFE, Area II Spt Det  
AFE, Cp Humphreys  
AFE, Pusan  
AFE, Taegu

DLA ATTN: DLA-WI

USA Japan (USARJ)  
Ch, FE Div, AJEN-FE  
Fac Engr (Honshu)  
Fac Engr (Okinawa)

ROK/US Combined Forces Command  
ATTN: EUSA-HMC-(FC)/Engr

416th Engineer Command  
ATTN: Facilities Engineering

Norton AFB  
ATTN: AFRCCE-MX/DEE

Port Hueneke, CA 93043  
ATTN: Library (Code LOMA)

AFESC/Engineering & Service Lab  
Tyndall AFB, FL 32403

Chanute AFB, IL 61864  
3345 CES/DE, Stop 27

National Guard Bureau  
Installation Division  
WASH DC 20310

ENE Team Distribution

USA ARRADCOM  
ATTN: DRDAR-LCA-OK

Director of Facilities Engineering  
Miami, FL 34004

West Point, NY 10996  
ATTN: Dept of Mechanics  
ATTN: Library

HQDA (SGRD-EDE)

Chief of Engineers  
ATTN: DAEN-MPO-D  
ATTN: DAEN-MPO-U  
ATTN: DAEN-MPR  
ATTN: DAEN-MPZ-A  
ATTN: DAEN-RDL

National Defense Headquarters  
Director General of Construction  
Ottawa, Ontario  
Canada K1A 0K2

Division of Building Research  
National Research Council  
Ottawa, Ontario  
Canada K1A 0R6

Airports and Construction Services Dir  
Technical Information Reference Centre  
Ottawa, Ontario  
Canada K1A 0N8

Aberdeen Proving Ground, MD 21005  
ATTN: AMXHE  
ATTN: HSE-EW

Ft. Belvoir, VA 22060  
ATTN: Learning Resources Center  
ATTN: ATSE-TD-TL (2)  
ATTN: Kingman Bldg. Library  
ATTN: Canadian Liaison Officer (1)  
ATTN: British Liaison Officer (5)

Ft. Leavenworth, KS 66027  
ATTN: ATZLCA-SA

Ft. McPherson, GA 30330  
ATTN: AFEN-CD

Ft. Monroe, VA 23651  
ATTN: ATEN-AD (3)  
ATTN: ATEN-FE-E  
ATTN: ATEN-FE-U

Ft. Lee, VA 23801  
ATTN: DRXMC-D (2)

Ft. A. P. Hill 24502  
ATTN: FE

US Army Foreign Science & Tech Center  
ATTN: Charlottesville, VA 22901  
ATTN: Far East Office

5th US Army  
ATTN: AFKB-LG-E

6th US Army  
ATTN: AFKC-EN

7th US Army  
ATTN: AETTM-HRD-EHD

US Army Engineer District  
New York  
ATTN: Chief, NANEN-E  
ATTN: Chief, Design Br.  
Pittsburgh  
ATTN: Chief, Engr Div  
Philadelphia  
ATTN: Chief, NAPEN-E

US Army Engineer District  
Norfolk  
ATTN: Chief, NAQEN-D  
Huntington  
ATTN: Chief, ORHED-H  
Wilmington  
ATTN: Chief, SAWEN-PM  
ATTN: Chief, SAWEN-I  
Charleston  
ATTN: Chief, Engr Div  
Savannah  
ATTN: Chief, SASAS-L  
Jacksonville  
ATTN: Env Res Br  
Mobile  
ATTN: Chief, SAMEN-C  
Vicksburg  
ATTN: Chief, Engr Div  
Louisville  
ATTN: Chief, Engr Div  
St. Paul  
ATTN: Chief, ED-H  
Chicago  
ATTN: Chief, NCCCO-R  
ATTN: Chief, NCCED-H  
ATTN: Chief, NCCPD-ER  
ATTN: Chief, NCCPE-PES  
St. Louis  
ATTN: Chief, ED-B  
ATTN: Chief, ED-D  
Kansas City  
ATTN: Chief, Engr Div  
Omaha  
ATTN: Chief, Engr Div  
Little Rock  
ATTN: Chief, Engr Div  
Tulsa  
ATTN: Chief, Engr Div  
Fort Worth  
ATTN: Chief, SWFED-D  
ATTN: Chief, SWFED-MA/MR  
Galveston  
ATTN: Chief, SWGAS-L  
ATTN: Chief, SWGCO-M  
Los Angeles  
ATTN: Chief, SPLED-E  
San Francisco  
ATTN: Chief, Engr Div  
Sacramento  
ATTN: Chief, SPKED-D  
Far East  
ATTN: Chief, Engr Div  
Seattle  
ATTN: Chief, NPSEN-FM  
ATTN: Chief, EN-DB-SE  
ATTN: Chief, NPSEN-PL-WC  
ATTN: Chief, NPSEN-PL-ER  
Walla Walla  
ATTN: Chief, Engr Div  
Alaska  
ATTN: Chief, NPASA-R

US Army Engineer Division  
New England  
ATTN: Chief, NEDED-E  
North Atlantic  
ATTN: Chief, NADEN-T  
Middle East (Rear)  
ATTN: Chief, MEDED-T  
South Atlantic  
ATTN: Chief, SADEN-TE  
Huntsville  
ATTN: Chief, HNDED-CS  
ATTN: Chief, HNDED-ME  
ATTN: Chief, HNDED-SR  
Lower Mississippi Valley  
ATTN: Chief, PD-R  
Ohio River  
ATTN: Chief, Engr Div  
North Central  
ATTN: Chief, Engr Planning Br  
Missouri River  
ATTN: Chief, MRDED-T  
Southwestern  
ATTN: Chief, SWDED-TH

US Army Engineer Division  
South Pacific  
ATTN: Chief, SPDED-TG  
ATTN: Laboratory  
Pacific Ocean  
ATTN: Chief, Engr Div  
ATTN: Chief, PODED-MP  
ATTN: Chief, PODED-P  
North Pacific  
ATTN: Chief, Engr Div

AF/RDXT  
WASH DC 20330

2854 ABG/DEEE  
Tinker AFB, OK 73145

2852 APG/DE  
McClellan AFB, CA 95652

Patrick AFB, FL 32925  
ATTN: XRO

AFESC/PRT  
Tyndall AFB, FL 32403

AF/PREEU  
Bolling AFB, DC 20332

Little Rock AFB  
ATTN: 314/DEEE

US Naval Oceanographic Office  
ATTN: Library  
Bay St. Louis, MS 39522

Naval Training Equipment Center  
ATTN: Technical Library  
Orlando, FL 32813

Naval Facilities Engr Command  
ATTN: Code 04  
Alexandria, VA 22332

Port Hueneme, CA 93043  
ATTN: Library (Code L08A)  
ATTN: Morell Library

Washington, DC  
ATTN: Bldg Research Advisory Board  
ATTN: Transportation Research Board  
ATTN: Library of Congress (2)  
ATTN: Dept of Transportation Library

Dept of Transportation  
Tallahassee, FL 32304

US Army Tank-Automotive  
Materiel Readiness Command  
Warren MI 48090

Deputy Chief of Staff for Logistics  
Directorate of Supply & Maintenance  
HQDA (DALO-SMZ)  
WASH DC 20310

Fileccia, Robert J.

Pretreatment of waste discharges from improved Army tactical equipment maintenance facilities / by R. Fileccia ... (et al.)- Champaign, IL : Construction Engineering Research Lab ; available from NTIS, 1981.

39 p. (Technical report ; N-107)

1. Vehicles, military-cleaning. 2. Petroleum waste.  
I. Kloster, Sharen E. II. Benson, Leslie Jerome III. Kamiya, Mark. IV. Matherly, Joseph E. V. Title. VI. Series : U.S. Army Construction Engineering Research Lab. Technical report ; N-107.