AD-A242 552

S DTIC S ELECTE NOV 1 8 1991 C (à)

APPROVED FOR PUBLIC RELEASE DISTRIBUTION UNLIMITED

REPORT NO. 91-R-03 AFPEA PROJ. NO. 88-P-108

JASON GILREATH

MECHANICAL ENGINEER

AUTOVON 787-3362

COMMERCIAL (513) 257-3362

QUALIFICATION TESTING OF VARIOUS FASTENING DEVICES ON WOOD BOXES

HQ AFLC/DSTZ
AIR FORCE PACKAGING EVALUATION ACTIVITY
WRIGHT-PATTERSON AFB OH 45433-5999

OCT 1991

91-15737

91 1115 057

NOTICE

When government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related government procurement operation, the United States Government thereby incurs no responsibility whatsoever, and the fact that the government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation or conveying any rights or permission to manufacture use or sell any patented invention that may in any way be related thereto. This report is not to be used in whole or part for advertising or sales purposes.

ABSTRACT

In April 1988, the Air Force Packaging Evaluation Activity (AFPEA) initiated this project in order to find a better method of fastening the cover to the base of the MIL-B-26195 wooden box design in order to make the containers more reusable. The present design requires that new holes be drilled for the placement of the lag bolts after the container has been disassembled and reassembled several times.

Three boxes were constructed and tested at the AFPEA, HQ AFLC/LGTPD, Wright Patterson AFB, OH 45433-5999. Box number one utilized the present method of lag bolts into the skids as a control. Box number two consisted of bolts and blind nuts as the cover to base fasteners. Box number three used drywall screws as the fasteners.

The test plan was developed to evaluate how well the cover held to the base. The tests were conducted in accordance with Federal Test Method Standard 101C.

Results of the tests conducted on the prototypes show that bolts and blind nuts provided better fastening and nearly indefinite reusability.

PREPARED BY:

PUBLICATION DATE:

Jason Gilreath Engineer Trainee

AFPEA

REVIEWED BY:

Ted Hinds

Ch, Design Branch

AFPEA

i 6 OCT 1991

APPROVED BY:

Charlie P. Edmonson Chief, AF Packaging Evaluation Activity

	Acums	ion for
	NTIS	GRADI S
:	Dric 1	
Ì	Manico	
Ì	Justif	leation
	By Distr	lbutles/
		lability Code
		Avail and/or
Page	Dist	Special
- 490	1.0	
i	14.	
i	H-/	

TABLE OF CONTENTS

ABSTRACT	i
TABLE OF CONTENTS	ii
INTRODUCTION	1
BACKGROUND	1
PURPOSE	1
DESCRIPTION OF TEST CONTAINER	1
TEST OUTLINE AND TEST EQUIPMENT	1
TEST PROCEDURES AND RESULTS	2
TEST NO. 1, EDGEWISE-DROP (ROTATIONAL) TEST	2
TEST NO. 2, CORNERWISE-DROP (ROTATIONAL) TEST	2
TEST NO. 3, SUPERIMPOSED LOAD TEST	2
TEST NO. 4, REPETITIVE SHOCK TEST	2
CONCLUSION	3
RECOMMENDATIONS	3
TABLE 1, CONTAINER TEST PLAN	4
TABLE 2, CONTAINER TEST PLAN	5
FIGURE 1, CORNER NUMBERING	6
FIGURE 2, LEAD DUMMY LOAD	7
IGURE 3, EDGEWISE DROP (ROTATIONAL) TEST	8
FIGURE 4, CORNERWISE DROP (ROTATIONAL) TEST	9
FIGURE 5, CONTAINER NO. 3 FAILURE	10
FIGURE 6, SUPERIMPOSED LOAD TEST	10
FIGURE 7, REPETITIVE SHOCK TEST	11
DISTRIBUTION LIST	12

INTRODUCTION

BACKGROUND: The Air Force Packaging Evaluation Activity (AFPEA) initiated this project to find a better method of fastening the cover to the base of the PPP-B-601H wooden box design as a result of problems encountered in the field.

<u>PURPOSE</u>: The purpose of this project was to design a method of fastening the cover to the base of the MIL-B-26195 wooden box that was more reusable than the present method of lag bolts.

DESCRIPTION OF TEST CONTAINERS

One container, using the present method of lag bolts, was constructed as a control. Two other containers were made with two different types of cover to base fasteners. The corners of each of the three containers were numbered counterclockwise from the front right-side corner as shown in figure 1.

Design: Box no. 1 (control) used ten of the standard 3" X 3/8"
lag bolts. Box no. 2 used ten sets of 4 1/2" X 3/8" bolts and
3/8" blind nuts. Box no. 3 used eighteen 2" drywall screws. All
hardware was obtained off the shelf from a hardware store.

Construction: All containers were 36" X 26" X 33" built in accordance with PPP-B-601H and MIL-B-26195C style A.

TEST OUTLINE AND TEST EQUIPMENT

Test Plan: Tests were conducted in accordance with AFPEA Test Plan 88-P-108 (see attachment 1). The tests were developed to evaluate the structural integrity of the container with the new fasteners. Test methods, procedures and pass/fail criteria were in accordance with Federal Test Method Standard 101 (FTMS101C).

Test Load: All tests, except the superimposed load test, were conducted using a 1000 pound lead dummy load which was constructed at the AFPEA (see figure 2).

Test Site: All testing was conducted at the AFPEA, HQ AFLC/LGTPD, Building 70, Area C, Wright-Patterson AFB OH 45433-5999. The equipment required for each test is noted in the test plan.

TEST PROCEDURES AND RESULTS

Edgewise-Drop Test

Test No. 1: The edgewise-drop (rotational) test was performed in accordance with Method 5008.1. The drop height was 16" (see figure 3).

Results: Visual inspection revealed no damage to any of the containers.

Cornerwise-Drop Test

Test No. 2: The cornerwise-drop (rotational) test was performed in accordance with Method 5005.1. The drop height was 16" (see figure 4).

Results: Visual inspection revealed no damage to containers 1 and 2. On the second drop, container 3 failed. The skid pulled away from the cover section. After disassembly, it was found that all screws holding the cover to the base, except those on side 2-3, had been sheared off. One screw on side 1-4 was badly bent but not broken. This is because a chunk of wood from the end header had broken off before the screw could break (see figure 5). Due to this failure, no further testing will be done on container 3.

Superimposed Load Test

Test No. 3: The ambient superimposed load test was conducted in accordance with Method 5016.1. A load of 10,500 pounds was placed on top of a fully assembled container using a loaded base of another container, simulating a stack of containers 16 feet high with a safety factor of two (see figure 6).

Results: Visual inspection revealed no damage to containers 1 and 2.

Repetitive Shock

Test No. 4: The repetitive shock test was conducted in accordance with Method 5019.1. The containers were placed separately on the shaker table and blocked in with 1/2" spacing on all sides (see figure 7). A 1/16" vertical bounce was applied at 4.5 Hz with 1" double amplitude for two hours.

Results: Visual inspection revealed no damage to containers 1 and 2. All the fasteners on container 2 were still in place and tight. Four of the ten bolts in container 1 were loose as a result of the testing.

CONCLUSION

Containers no. 1 and no. 2 gave the same results when tested in accordance with the container test plan. As expected, some of the holes in container 1 were so worn out from the assembly and disassembly that new holes would need to be drilled for continued use of that container. Container no. 2 would never need to have the holes re-done. The drywall screws on container 3 were too weak to be acceptable due to the failure during the second drop test and it is also not probable that an increase in the number of screws would sufficiently improve this design.

RECOMMENDATIONS

It is recommended to use blind nut fasteners because of their reusability. An adhesive to hold the blind nuts in place permanently would be beneficial. If too much force is used when pushing the bolts through to the blind nuts, the nuts may be knocked out.

	AIH FORCE	CE PACKAGING EVALUATION ACTIVITY			ROJECT NUMBER				
-					T (198)	7 5005 75		88-P-1	
CC	NTAINER SIZE (L INTERIOR:		TERIOR:	GROSS:	T (LBS) ITEM:	CORE (C	U. F1.)	QUANTITY	DATE
3x2		6x26x		1083	1000	17.7		3	11 Sep 91
EM N	AME				MANU	FACTURER		A	- +
ead ONTA	Dummy Load	<u> </u>	27 TOTAL CO. AMERICAN CO. 10 TO THE]		CO	NTAINER COS	BT
	B-26195C L	ag Bo	lt Test						
	DESCRIPTION en Containe	r							
ONDI:	FIONING								
s n	oted below.					J			ı
NO.	REF STD/SP AND TEST METI PROCEDURE	HOD OR	TEST TITLE AND PARAMETERS				CONTA		INSTRU- MENTATION
L.	EDGEWISE DR	ROP	!						
	FED-STD-101	C	Containe				e edg		Forklift
	METHOD 5008	3.1	dropped bottom e				all r	est block.	or hoist
			height o			011	a 0	DIOCK.	
			total of						
				_					
2.	CORNERWISE	DROP							
	FED-STD-101	LC	Containe			,	e cor		Forklift
	Method 5005	5.1	dropped			1		est on	or hoist
			bottom cheight c				6" bl	acent	
			total of					shall	
				•				n a 12"	
						bl	ock.		
									į
						ļ			
						i			
			:			-			
						!			
			:			ì			
			:						
	1		:						
			1						
			!						
						† !			
			1			1			
						İ			
OMM	ENTS:								
REPA	RED BY:				APPROVI	ED BY:			
T 3. C./	ON GILREATH	. Engi	neer Tra	inee	TED I	HINDS,	Chief	, Design	Br., AFPE

AIR FORCE PACKAGING EVALUATION ACTIVE (Container Test Plan)					Υ	AFPEA PROJE 88-P-10		3
		TERIOR: GROSS:	ITEM:			QUANTITY	DATE	
ITEM N	24x26 36x26	k33 1083	1000	ACTURE	.7	3	11 S	ep 9
	Dummy Load		MANOR	ACIONE	EN			}
CONTAI	NER NAME		i .		COI	NTAINER COST		
MIL-	-B-26195C Lag Bo	olt Test						
	escription den Container							
CONDIT	IONING		•				···	
Ası	noted below							
TEST NO.	REF STD/SPEC AND TEST METHOD OR PROCEDURE NO'S	TEST TITLE AND PARA	METERS			TATION	INSTRI MENTAT	
							,	
3.	SUPERIMPOSED LO	AD						:
	FED-STD-101C METHOD 5016.1	Stack loaded bas container onto a		I		containe ng tested		
	METHOD SOIG.I	fully assmbled	nocher			onducted		es,
		container. Leav	e stac	1	at amb		buckl defor	
		Weight=Px(16-H)/	Hxs		cemper	ature.	tions	
		=1083x(16-						
		2.75x2 where P=weight o	f load	ed				
		containe	r (lbs					
		H=height o containe						
		S=safety f	actor					1
		level A	packin	g				
4.	REPETITIVE SHOCE FED-STD-101C	<u>K</u> Test using verti	cal		Ambien	t l		
	Method 5019.1	motion for two h	ours a	t				
		$1 \pm .1$ G or $1/16$ " between 3 to 5 H		e unt				
		restraining bloc	ks 1/2	i i				
		away from sides container	of					
		Concarner						
		! ! !				Ì		
		<u> </u> :						
COMMENTS:								
DDEDA	PREPARED BY: APPROVED BY:							
	JASON GILREATH, Engineer Trainee TED HINDS, Chief, Design Br., AFPEA							

AFALD FORM, 4

PAGE 2 OF 2




FIGURE 1. Corner Numbering




Figure 2: 1000 Pound Lead Dummy Load



Figure 3: Edgewise Drop - 16 inches FTMS101C - Method 5008.1




Figure 4: Cornerwise Drop - 16 inches FTMS101C - Method 5005.1




Figure 5: Container 3 - Failed Cornerwise Drop



Figure 6: Superimposed Load Test - 10,500 pounds FTMS101C - Method 5016.1




Figure 7: Repetitive Shock Test FTMS101C - Method 5019.1

DISTRIBUTION LIST

DTIC/FDAC Cameron Station Alexandria, VA 22304-6145	12
HQ AFLC/LGT Wright-Patterson AFB OH 45433-5999	2
HQ AFLC/LGTPP Wright-Patterson AFB OH 45433-5999	2
HQ USAF/LGTT Washington DC 20330	1
HQ AFSC/LGT Andrews AFB MD 20334-5000	1
OC-ALC/DST Tinker AFB OK 73145	1
OO-ALC/TID Hill AFB UT 84406	2
SA-ALC/DST Kelly AFB TX 78241	1
SM-ALC/1fD McClellan AFB CA 95652	1
WR-ALC/DST Robins AFB GA 31098	1
ASD/AWL Wright-Patterson AFB OH 45433	1
ASD/ALXP Wright-Patterson AFB OH 45433	2
ASD/YJA Eglin AFB FL 32542	2
GSA, Office of Engineering Mgt Packaging Division Washington DC 20406	1
Commander Naval Supply Systems Command Attn: N. Karl (SUP 0611F) Washington DC 20376-5000	1

Commander Naval Air Systems Command Attn: E. Panigot (AIR 41212A) Washington DC 20361	1
Commander Space and Naval Warfare Systems Command Attn: T. Corbe (Code 8218) Washington DC 20360	1
Commander Naval Facilities Engineering Command Hoffman Bldg. #2, Room 12S21 Attn: C. Manwarring (FAC 0644) Alexandria, VA 22332	1
Commanding Officer Naval Construction Battalion Center Attn: K. Pollock (Code 15611K) Port Hueneme, CA 93043	1
Commander Naval Sea Systems Command Attn: G. Mustin (SEA 66P) Washington DC 20362	1
Commander Naval Sea Systems Command Attn: F. Basford (SEA 05M3) Washington DC 20362	1
Commanding Officer Naval Aviation Supply Office 700 Robbins Avenue Attn: J. Yannello (Code EPP-A) Philadelphia, PA 19111-5098	1
Commanding Officer Navy Ships Parts Control Center P.O. Box 2020 Attn: F. Sechrist (Code 0541) Mechanicsburg, PA 17055-0788	1
Commanding Officer Naval Air Engineering Center Attn: F. Magnifico (SESD Code 9321) Lakehurst, NJ 08733-5100	1
Commanding Officer	2

Naval weapons Station Earle NWHC/Code 8023 Colts Neck,NJ 07722-5000	
ASO/TEP-A 4030 700 Robbins Ave Philadelphia, PA 19111	1
US AMC Packaging, Storage, and Containerization Center/SDSTO-T Tobyhanna, PA 18466-5097	1
DLSIE/AMXMC-D US Army Logistics Mgt Ctr Ft Lee VA 23801-6034	1
US Army ARDEC/SMCAR-AEP Attn: Mike Ivankoe Dover, NJ 07801-5001	1
US Army Natick Labs/STRNC-ES Natick MA 01760	1
HQ DLA/OWP Cameron Station Alexandria, VA 22304-6100	1
HQ AFLC/LGS Wright-Patterson AFB OH 45433	2
ASD/SDM Wright-Patterson AFB OH 45433	2
HQ TAC/LGWL Langley AFB, VA 23665	2
OO-ALC/TIDT Hill AFB, UT 84056	2
OO-ALC/LIW Hill AFB, UT 84056-5609	2
Defense Logistics Agency ATTN: DLA-OWP Cameron Station Alexandria VA 22304-6100	1
Defense Contract Management Command ATTN: DLA-AT Cameron Station	1

Alexandria VA 22304-6190