UNCLASSIFIED

AD NUMBER ADB810773 CLASSIFICATION CHANGES TO: UNCLASSIFIED FROM: CONFIDENTIAL LIMITATION CHANGES

TO:

Approved for public release; distribution is unlimited.


FROM:

Distribution authorized to U.S. Gov't. agencies and their contractors;
Administrative/Operational Use; 31 MAY 1945.
Other requests shall be referred to Office of Scientific Research and Development,
Washington, DC 20301.

AUTHORITY

OSRD list no. 6 dtd 28 Jan-1 Feb 1946; OTS index dtd Jun 1947

Reproduced by AIR DOCUMENTS DIVISION



HEADQUARTERS AIR MATERIEL COMMAND

WRIGHT FIELD, DAYTON, OHIO

U.S. GOVERNMENT

IS ABSOLVED

FROM ANY LITIGATION WHICH MAY

ENSUE FROM THE CONTRACTORS IN-

FRINGING ON THE FOREIGN PATENT

RIGHTS WHICH MAY BE INVOLVED.

WRIGHT FIELD, DAYTON, UNIV

3/645 Division 11

NATIONAL DEFENSE RESEARCH COMMITTEE

of the

OFFICE OF SCIENTIFIC RESEARCH AND DEVELOPMENT

OSRD No. 5154 Copy No. 33 X-1656 85

DIVISION 11 NATIONAL DEFENSE RESEARCH COMMITTEE of the

OFFICE OF SCIENTIFIC RESEARCH AND DEVELOPMENT

OXYGEN PLANT DEVELOPMENT EMPLOYING REGENERATIVE CHEMICALS

> March 16, 1945 by W. E. Lobo and G. Bockius

Report OSRD No. 5154
Gopy No. 33
Date: May 31, 1945

Copy No. and the state of t Dr. Irvin Stewart OSRD Liaison Office Air Corps Diaison Officer with NDRC Attn: Brig. Gen. James F. Phillips Chief, Eureau of Ships, Attn: Capt. R. V. Lleinschmidt Chief, Eureau of Aeronautics, Attn: Capt. J.E. Sullivan Director, Naval Research Laboratory 26-27 hero Mudical Research Laboratory, Wright Field Attn: Dr. F. W. Berner 31 Naval Research Laboratory, Attn: Capt. R. H. Gibbs Board of Engineers, Fort Belvoir Attn: Major H. E. Fitzgerald 33-34 Johnanding General, Wright Field Attn: Major J. P. Aulierter Office of the Chief of Engineers, Attn: Major W. J. New 36 Col. L. E. Griffis 37 Dr. J. H. Rushton 38 Dr. T. A. Gelssman 39 Dean John Goff hó Mr. Daniel Curli 41 Chief, Bureau of Ships, Attn: Capt. T. J. Bay 42-43 Dr. J. H. Wolfenden Mr. W. E. Lobo Dr. G. G. Furnas Dr. T. H. Chilton Dr. W. R. Hainsworth Mr. E. P. Stevenson Division 11 Files

Total Number of Copies - 75

This document contains information affecting the national defense of the United States within the meaning of the Espionage Act, U.S.C. 50; 31 and 32. Its transmission or the revelation of its contents in any manner to an unauthor-ized person is prohibited by law.

NATIONAL DEFENSE RESEARCH COMMITTEE of the OFFICE OF SCIENTIFIC RESEARCH AND DEVELOPMENT

Section 11.1

OXYGEN PLANT DEVELOPMENT EMPLOYING REGENERATIVE CHEMICALS

Service Directive NL-B₁2; NS-117

Endorsement (1) from H. M. Chadwell, Chief Division 11 to Dr. Irvin Stewart, Executive Secretary of the National Befense Research Committee. Forwarding report and noting:

"This report covers oxygen generating plants utilizing the absorbent "Salcomine." The plants were designed by the M. W. Kellogg Co. and such construction as took place was done by the American Machine Defense Corp. The shipboard unit, though completed, was superseded by one designed and constructed by the A. D. Little Co. (Now installed on a Naval Vessel). The truck-mounted units were early abandoned as non-competitive with liquifaction units. Other units were largely experimental. This work was completed about to years ago."

This is a progress report under Contract 11-244, OEM r-365 with M. W. Kellogg Co. and a final report under Contract 11-261, OEMsr-499 with American Machine Defense Corporation.

Final Report

(Employing Regenerative Chemicals)

To Mational Defense Research Committee

By
The M. W. Kellogg Company
Contract No. OFM-sr-365

And American Machine Defense Corporation Contract No. OFM-sr-499

Submitted by:

for The M. W. Kellogg Company

for American Machine Defense Corporation

CONFIDENTIAL

March 16, 1945

X - 1665 87

CONFIDENTIAL

TABLE OF CONTENTS

Title	Paro No.
Surmary	
General Description of Work	
Preliminary Activities	1-5
Shipboard Unit (C-2)	8-7
Shipyard Unit (C-4)	7-8
Mobile Truck Units (C-1A and C-1C)	8-9
Bombing Plane Unit	9
Medical Corps Unit	9
Air Transported Unit (C-5)	9-10
Fluid Powder Study	10
Miscellaneous Process Studies	10-11
Miscellaneous Shop Work	n
Bibliography	12-15
Process Calculations for Shipboard Unit	14-51
Index of Drawings (Shipboard Unit)	52-55
Schematic Flow Sheets and Sketches	54

CONFIDENTIAL

1.1505 38

CONFIDENTIAL

SUMMARY

This report contains a description of the work

performed by The M. W. Kellogg Company and the American Machine

Defense Corporation for the National Defense Research Committee

in the development of oxygen plants employing regenerative

chemicals.

In addition to a chronological description of each plant or study involved in the program, the roport contains a bibliography of correspondence, memoranda, reports and specifications dealing with equipment details and operating experiments.

Detailed process calculations and a list of all drawings are supplied for the Shipboard (C-2) unit, the only complete unit febricated by the contracting companies. Process calculations and detailed designs are not furnished for plants which were studied but not erected.

GENERAL DESCRIPTION OF WORK

Preliminary Activities

In Docember, 1941, exploratory discussions were held between representatives of the National Defense Research Committee and The M. W. Kellogg Company. In the following month, January, 1942, Kellogg formally agreed to become the central engineering agency for the NDRC oxygen program. On January 27, Kellogg representatives attended a general conference on oxygen problems convened at Massachusetts Institute of Technology under the sponsorship of the NDRC oxygen section.

At this meeting it was made clear that high hopes were entertained for mobile oxygen plants based on the use of the regenerative chemical "Salcomine". Preliminary engineering studies by Dr. Gilliland's group at M.I.T. had indicated that attractive yields of oxygen could be absorbed from the atmosphere by beds of Salcomine undergoing what then seemed to be moderate changes of temperature and pressure.

During February negotiations were carried on between the NDRC and the American Machine & Foundry Co., which finally culminated in the granting of a contract to the American Machine Defense Corporation, a newly formed subsidiary of American Machine & Foundry Co. Kellogg meanwhile began process and equipment studies for mobile truck Salcomine units producing 1000 cu. ft./hr of high purity exygen. The difficulties to be overcome in this work were materially and unexpectedly augmented by the realization that mobile units for field service would be required to operate in all climates without dependence on external agents other than the local atmosphere and engine fuel.

This requirement was made only too clear in a discussion between Kellogg representatives and Capt. Beverly (U.S. Army Engineer Corps) on February 6. The nobile unit was thus seen to require not only air and oxygen compressors (driven by gasoline organes) but also heating and cooling devices to move the Salcomine through the necessary temperature range. Atmospheric air became the basic cooling medium while all heat had to be obtained from engine fuel.

To establish designs which would meet the most severe atmospheric conditions that might be encountered in all forseeable combat areas, it was decided to design all ground units for operation in air at 120°F with a dew point of 90°F, a condition which might occur in Pacific Islands lying near the

Equator.

()

The Salcomine program also visualized the development of units for use on shipboard and in long-range bombing planes. A ground unit capable of being separated into relatively small sections for transportation by plane to remote localities (so-called "air transported" unit) was also contemplated, but at the period in question, February, 1942, greatest emphasis was being placed on mobile truck units for use by the Engineer and Air Corps.

A then-recent development by the M.I.T. group further restricted the design of the equipment. Most reaction vessel designs under discussion involved fixed beds of powdered Salcomine surrounding coils or pipes for the heating and cooling fluids. In view of the poor heat-conducting properties of Salcomine, it would have been highly desirable to employ heat transfer tubes fitted with fins, ribbons or other extended surfaces - thereby greatly shortening the time required to heat or cool the powder through a specified temperature change. Unfortunately the powder, as then prepared, packed into a very rigid cake in the course of operation. It was therefore agreed that it would be almost impossible to remove Salcomine from a reactor fitted with extended surface tubing. Reactor designs were to be drastically restricted to those containing plain tubing arranged for easy cleaning.

At the same time, Kellogg undertook discussions with the Clark Brothers Co. on the specifications for the air and oxygen compressors in the proposed Salcomine units.

During March designs were prepared in some detail for two mobile truck units. These designs differed from one another principally in the shape and internal tube arrangements of the heating surfaces. Both proposed to supply heating and cooling by a continuously circulating refrigerant which was to act as a heating medium at high pressure and a cooling medium at low pressure.

However, when preliminary mobile unit designs were completed it was apparent that Salcomine units would be hoavier, larger and more complex than units of the same capacity producing oxygen by the employment of liquid air cycles. Thus, it was estimated that a chemical truck unit producing 1000 cu.ft./hr. would weigh about 8 tons (exclusive of truck or trailer) and would require engines developing about 180 horsepower. Corres-

ponding liquid air units, it was believed, would weigh about 5 tons (exclusive of truck or trailer) and would require about 80 horsepower.

On March 20, at a meeting with the NDRC oxygen staff, Kellogg representatives proposed the abandonment of the Salcomine process for mobile truck units. During this meeting it was pointed out that recent laboratory work at M.I.T. indicated that an adiabatic unit might ultimately be realized. This unit would operate over a narrow temperature range using very high pressure nir (600 psi or greater) in the absorption step. Such an arrangement would dispense with the elaborate heating and cooling apparatus required for lower pressure operation.

Accordingly, it was agreed to suspend all further work on truck units until a laboratory evaluation of the adiabatic cycle had been made. Meanwhile, studies of units for generating oxygen on shipboard were to be inaugurated. These units would depend on ship supplies of steam and cooling water, and would therefore, be much smaller and simpler than the completely self-contained truck units.

Shipboard Unit (C-2)

()

On March 26, Kellogg and NDRC representatives confered in Washington with officers of the Eurem of Ships(USN) to establish the major features of the shipboard unit. It was agreed at that time to construct a unit similar to those previously proposed for the truck units, but relying on supplies of steam and cooling water from external sources. In addition, the unit would be designed to generate oxygen at 20 psig pressure which was then considered adequate for cutting torch use and which would obviate the need for an exygen compressor. It was decided to employ reactors containing flat, removable coils for the heat transfer fluids with the powder bed surrounding the coils.

Drawings and specifications for most of the necessary equipment in the shipboard unit (type C-2) were delivered to American Machine Defense by the end of March. These were promptly forwarded to the Whitlock Manufacturing Company at Hartford, Connecticut, which had undertaken to fabricate the pressure vessels and erect the unit as sub-contractors to American Machine Defense.

The general procedure followed by the participating companies during the ensuing weeks was:

- A) Kellogg made process calculations; prepared detailed flowsheets; designed and prepared assembly drawings for pressure vessels and other items; prepared detailed specifications; prepared detailed piping drawings;
- B) American Machine Defense, upon receipt of the foregoing material from Kollogg, reviewed all designs and suggested improvements on the basis of their nanufacturing experience; issued purchase orders for all materials and parts; arranged for shipment and delivery of all items to their plant or to Whitlock; prepared shop detail drawings; arranged with American Machine & Foundry Co. for fabrication of all parts requiring close machine work; shipped to Whitlock all items delivered to or fabricated in their plant;
- C) Whitlook took delivery and inventoried all items required in the assembly of the unit; fabricated the pressure vessels and other heavy pieces in accordance with instructions from Kellogg and American Machine Defense; constructed supporting structures; assembled piping; erected the entire unit; supplied utilities from their plant system.

As originally designed in March, 1942, the unit was to operate on air at 275-300 psi pressure. At about this time the M.I.T. group undertook a study of the decline in activity experienced by the Salcomine in use. It was soon noted that, when operated at these pressures, the chemical lost most of its activity in much fewer cycles than it did when operated at about 100 psl. By then, construction of the unit was well advanced and it was decided to leave the design unchanged but to operate at air of about the latter pressure. Under these circumstances, with a large air supply available, process calculations indicated that the unit would produce only 600 cfh instead of the 1000 cfh which was predicted for the higher pressure operation.

It was also discovered that generation of oxygen under 20 psi pressure (as contemplated in the meeting of Murch 26)

would be very harmful to the chemical activity of the Salcomine. Accordingly, during the month of June it was decided to desorb the oxygen from the reactors at atmospheric pressure and to employ a 2-stage oxygen compressor to raise the final oxygen pressure to 150 psi(which was felt to be necessary for under-water cutting work). A compressor for this service was ordered at that time from Clark Brothers.

The construction of the unit was greatly delayed by many shortages of critical materials and components, a condition which hampered the entire war production program during most of 1942. As originally designed for shipboard service, the reactors were to be cooled by circulation of sen water through the internal coils. These were to be of cupro-nickel alloy and were to be connected by headers made from cast Monel metal. It soon developed that these materials were almost unobtainable under the priority ratings then assigned to the project. During May the unit was drastically revised to permit the use of more abundant materials, with a consequent loss in operating flexibility. Fresh water was to be used as the coolant; the cupro-nickel tubes were replaced by bracs; and the Monel castings by builtup assemblies of carbon steel. For marine use, the fresh water would be cooled in a cupro-nickel, shell-and-tube exchanger against a stream of sea water. This scheme merely shifted the critical alloys from the reactors to the heat exchanger, but resulted in an overall saving in time required to develop the unit. It was realized that a considerable quantity of test work would be required at a share station before the unit could be installed on a ship, and it was clear that the time required for the shore testing (which would be done with fresh water as the coolant) would be ample for obtaining the cupro-nickel exchanger.

()

During June and July it became evident that operations were moving very slowly at the Hartford plant of the Whitlock Co. This was not surprising because Whitlock was carrying an extremely heavy production schedule of equipment for the Navy and the Rubber program. This condition, combined with the acute shortage of good mechanic and engineer personnel, made it impossible for Whitlock to give the experimental exygen unit the close attention which it required.

In August, therefore, American Machine Defense stationed one of its development engineers at the Hartford plant with instructions to push shead the fabrication of the C-2 unit. This arrangement produced a noteworthy improvement, but to expedite matters further, Kellogg placed a member of

its Operating Department at Whitlock to cooperate with the American Machine Dofense representative in hastening the job. It was then learned that certain key components for the unit had been incorrectly or carelessly fabricated and were unusable. To eliminate further cases of this sort, Kellogg inspectors made regular visits to the job during ensuing weeks and passed "official" judgment on current production.

Of the four reactors employed in the complete unit, one was placed in operation on November 12, to be joined by a second reactor the following day. The third reactor went on stream on November 28, and the last reactor was ready by December 14. Exhaustive studies were made to establish the best operating conditions, but in spite of all efforts, the maximum production was only 300-400 cfh. This low production was attributed to several factors:

- A) Poor heat transfer characteristics of the plain brass tubing used to heat and cool the Salcomine.
- B) Insufficient air supply to the reactors. Because of limitations in the Whitlock compressed air system, the unit usually received 4000-5000 of at 80-85 psi instead of the expected 8500 of at 90-100 psi.

The unit was given a praisininary demonstration in December before representatives of the Eureau of Ships and the NDRC. At that time plans were made for a more formal showing as soon as all mechanical work was complete. It was also agreed that Kellogg would construct a scale model of a proposed shipboard unit, similar in general to the existing C-2 unit but rearranged and revised to occupy minimum space. This model was intended to demonstrate to Navy officials the layout possibilities which might be attained in future units.

During January the oxygen compressor was received from Clark Brothers. It was installed with an electric metor drive and, after a few preliminary adjustments, was found to give satisfactory service.

In order to improve the heat transfer characteristics of the reactors, it was decided to install finned coils in place of the existing smooth coils. It will be recalled that the smooth coils had originally been selected to facilitate

removal of caked Salcomine from the reactors. During the Summer of 1942, however, the Rumford Chemical Works had developed a grade of Salcomine powder which did NOT form solid cakes in use. Since this non-caking material was now available for use in the C-2 unit, it became practical to employ finned coils to improve heat transfer. Such coils were designed by Kellogg and ordered by American Machine Defense from the Rome-Turney Company at Rome, N.Y.

On January 20, 1945, the unit was formally demonstrated to representatives of the Bureau of Ships and the Office of the Coordinator of Scientific Research and Development (USN), in the presence of the NDRC caygen staff and personnel of the participating contractors. Bureau of Ships representatives expressed great interest in the unit and urged that the finned coils (then on order) be fabricated and installed with all possible speed. It was stated that when this work was complete, the unit should be prepared for shipment to an overseas base where it would be placed in regular operation to augment a critical oxygen shortage.

During February, one set of the new finned coils was received and placed in service. Performance in the reactor was greatly improved and it was calculated that, when the ontire unit was so equipped, production would easily reach 500 cfh even with the restricted air supply available. The remaining finned coils were received and installed during March.

By this time it became clear that the Bureau of Ships was not going to place the unit in immediato service. All equipment was therefore dismantled and shipped to the Central Engineering Laboratory of the Oxygen program at the University of Pennsylvania. It was agreed that the unit would be reassembled there if Navy interest revived.

The delivery of the unit, on April 16, 1945, to the Central Engineering Laboratory terminated the work of Kellogg and American Machine Defense on the development and design of shipboard oxygen plants.

Shipward Unit (C-4)

()

In the early part of 1942 a critical shortage of exygen existed in some of the recently established shippards in various parts of the country. During March of that year the NDRC requested Kellogg to prepare preliminary designs for a Salcomine unit to generate exygen in chippards, drawing utilities from local supplies. Kellogg accordingly proposed a slight modifi-

cation of the shipboard unit for this service. Specifications, flowsheets and drawings for this unit were submitted to the War Production Board, the Shore Facilities Section of the Bureau of Ships and the Office of the Coordinator of Scientific Research and Development of the Navy Department.

No further action was taken by Kellogg.

Mobile Truck Units (C-1A and C-1C)

()

As was previously stated, active design work on these units was temporarily suspended in March, 1942, pending further laboratory studies at M.I.T. During the next two months further experiments made it clear that adiabatic processes would not prove advantageous for the mobile truck units. In May, therefore, process studies were resumed on truck units similar to the types outlined in February and March. Kellogg continued to believe that the Salcomine process was not suitable for truck use in any form, but the project was continued at the request of the Army Air Corps and the NDRC. This decision was motivated by the realization that many aspects of the military oxygen program were not then completely clarified and that, as yet, no possible research lead could safely be neglected.

The prime contract for fabrication and assembly of these units was placed with the Independent Engineering Company at O'Fallon, Ill. A sub-contract for pressure vessel fabrication was arranged with the Whitlock Manufacturing Company. Each unit was to be mounted on two trailers, one containing the Salcomine reactors and the other carrying the engines and compressors. It was further agreed that the compressor-engine trailers for each unit would be fabricated and assembled by Clark Brothers as sub-contractors to Independent Engineering.

Detailed design and purchasing work was begun at once. Due to the usual delays in obtaining critical materials and components, many months elapsed before assembling operations could be started. In the meantime, the development of mechanical units in other parts of the Kellogg organization proceeded very favorably while the original disadvantages noted in the Salcomine units persisted despite prolonged research efforts in many quarters.

At length, the Army Air Corps agreed to the cancellation of these units. On November 24, the NDRC ordered its contractors to terminate their activities and ship any non-returnable or partly fabricated components to the Central

Engineering Laboratory at the University of Pennsylvania.

Kellogg's work in connection with cancellation and return of materials was concluded in February, 1945.

Bombing Plane Unit

During May, 1942, mumerous process and equipment studies were made in an affort to develop a small Salcomine unit which would daliver 100 cfh when operated in a bombing plane at high altitude.

With the information them available, all designs appeared unattractive because of weight and size requirements. The project was accordingly tabled, pending the development of more active chemical adsorbents for this very exacting service.

Several months later, work was resumed by the M. I.T. group and, after numerous studies of reactor designs and other variables, was permanently dropped.

Medical Corps Unit

()

During May, 1942, numerous process and equipment studies were made in an effort to develop a small Salcomine unit to meet the requirements of the Army Medical Corps. Due to the difficult host and pressure requirements placed upon self-contained units, it was agreed that the Salcomine process was not attractive for the service contemplated. The project was dropped.

Air Transported Unit (C-5)

Detailed process studies for this unit were undertaken in September, 1942. In addition to the usual requirements confronting self-contained units, this unit was to be capable of rapid field assembly from packages not exceeding 20" x 34" x 50". Pieces of equipment and cases smaller than these dimensions were considered to be suitable for transportation by air to remote localities.

A design was developed, based on a group of packages of the allowable size, in which each package performed only a few of the functions demanded of the overall unit. The main package contained two Salcomine reactors which were to be heated and cooled by recirculation of gas through the powder

beds. The recirculating gases were heated, or cooled, in exchangers which contacted a circulating refrigerant system not unlike that proposed for the mobile truck units.

Preliminary information on this plan was presented to the NDRC on October 8, 1942. Kellogg took no further action on the project.

Fluid Powder Study

During the preliminary process studies made in February, 1942, Kellogg investigated the possibilities of applying the fluid powder technique to the Salcomine process. This new method for handling gases and solids was then finding very wide application in the expanding aviation gasoline program, and it seemed reasonable to consider its utility in the task at hand for the NDRC.

Preliminary designs did not seem attractive because of the very large pressure changes to which the fluidized gaspowder mixture would be subjected. It was felt that no further process studies should be made until some laboratory work was done to determine whether or not the exygen-making process would actually occur under fluid powder conditions.

In July of the same year, Kellogg submitted to the NDRC an estimate covering the cost of creeting and operating a Salcomine fluid powder pilot plant at the Kellogg Laboratories in Jersey City, N.J.

The proposal was not authorized and Kellogg did no further work on the matter.

Miscellaneous Process Studies

Kollegg prepared engineering appraisals of several process and equipment schemes developed by other participants in the NDRC program. Among these were:

A) Salcomine-Oil Suspension

Preliminary studies were made by the DuPont Company of a plant circulating suspension of Salcomine in white oil. A flowsheet for a truck unit prepared by DuPont was appraised by Kellogg. It was concluded that such a unit would not compare favorably with liquid air units of the same capacity.

B) Screw-Conveyor Unit

Brief engineering studies were made by Kellogg of a unit developed at the University of Iowa. This unit employed Methomine (a them-new Sallomine derivative) which was moved through the process cycle by a system of screw conveyors. The unit was not recommended for further consideration.

C) Tessie duMotay Process

Kellogg inspected the pilot plant erected by DuPont for their modification of this process. After a review of energy and equipment requirements it was concluded that the process might be applicable for shippard units. It was not considered suitable for truck or shipboard scrvice. Kellogg submitted a report on these findings to the NDRC on December 16,1942. No further action was taken.

Miscellaneous Shop Work

In addition to activities previously described, the American Machine Defense Corporation ordered and supervised the execution of several miscellaneous fabrication jobs in the shops of the parent company, the American Machine & Foundry Company.

Among these were:

- A) Fabrication of several Collins-type heat exchangers for the mobile mechanical units and for research studies at Yale University.
- B) Automatic timers (according to Kellogg designs) for use on the Salcomine and mechanical truck units.

BIBLIOGRAPHY

Detailed information concerning the work summarised in this report will be found in the following tabulation of correspondence and reports (arranged by type of unit or project):

Shipboard Unit (C-2)

- A) M. W. Kellogg Company equipment specifications dated April 25, 1942(revised June 1, 1942)
- B) M. W. Kellogg Company progress reports to NDRC (July 15, 1942 through April 15, 1943).
- C) M. W. Kellogg Company Report "Small Oxygon Plants (Salcomine Process) for Shipboard Installation", January 19, 1945.

Shipyard Unit (C-4)

M. W. Kellogg Company equipment specifications dated April 20, 1942(revised May 14, 1942).

Mobile Truck Units (C-11 and C-10)

M. W. Kellogg Company progress reports to NDRC (June 15 through December 15,1942)

Bombing Plane Unit

M. W. Kellogg Company letter from Walter E. Lobo to C. C. Furnas at NDRC Washington Office, May 25, 1942.

Air Transported Unit (C-5)

M. W. Kellogg Company letter from Walter E. Lobo to C. C. Furnas at A. D. Little Co. New York City Office, October 8, 1942.

BIBLIOGRAPHY CONTD.

Fluid Powder Study

M. W. Kellogg Company letter from Walter E. Lobo to C. C. Furnas at NDRC Washington Office, August 6, 1942.

Tessie duMotay Process Study

M. W. Kellogg Company letter from Walter E. Lobo to E. P. Stevenson at A. D. Little Co., Cambridge, Mass. Office, December 19, 1942.

PROCESS CALCULATIONS

Basis of Design (As of March 10, 1942)

Output - 1000 CFH Oxygen at STP (60°F, 1 atm)

Number of Reactors - 4

Cycle Time on Each Reactor:

Absorption	31 0"
Evacuation	20"
Heating and Desorption	5140"
Valving	5"
Cooling	2150"
Valving	5"
88	121001

Absorption Pressure
Desorption Pressure
Absorption Temperature
Desorption Temperature
Absorption Temperature
Absorption Temperature
Desorption Temperature
250 lbs gage
Atmospheric
35°C - 95°F
100°C - 212°F

% Oxygen in Compound After Absorption

3.65% based on weight of compound

% Oxygen in Compound Before Absorption Yield

0.30% 3.35%

From data in letter of December 4,1941 from E.R. Gilliland to C.C. Furnas

% Oxygen Desorbed

93% of Oxygen Absorbed

True Density of Salcomine 1.5 Packed Density of Salcomine 0.7

Exit Gas Rate

4 CFH per 40.7 GRS of Salcomine at 25°C and 1 atm

Compound Required

Weight of Oxygen Produced = $\frac{1000 \times 32}{379}$ = 2.64 mols/hr x 32=84.5 lbs/hr

Assuming 3% Loss in Voids, etc. 0_2 Desorbed = $\frac{84.5}{1.03}$ = 87.0 lbs

Process Calculations C-2 Unit Page - 15 -

Compound Required Contd.

Frequency - 5 complete cycles/hr

Weight of compound = $\frac{67.0}{5}$ = $\frac{100}{3.35}$ = 519 lbs of unsaturated compound

= $519 \times 1.045 = 542$ lbs of saturated compound

Compound per reactor = $\frac{542}{h}$ = $\frac{135}{100}$ lbs

Air Required (for absorption at 250 lbs/sq.in. and original cycle)

Exit gas rate = 4 CFH per 40.7 GRS of sat. Salcomine at 25°C

Total exit gas =
$$\frac{135 \times 454}{40.7} \times 1 \times \frac{520}{537} = 5820$$
 CFH

Air input = 5820 + 1000 CFH 0₂ = 6820 CFH @ 60°F, 1 atm

$$0_2$$
 yield = $\frac{1000}{6820 \times 21}$ 100 = 70%

Reactor Design

28 flat spiral coils of 9/16" OD copper tubing, turns 7/8" between centers with the horizontal coils 0.76" apart.

Fraction Void in Salcomine

packed density 0.7 true density 1.5

Fraction void = $1 - \frac{\text{packed density}}{\text{true density}} = 1 - \frac{0.7}{1.5} = 0.53$

Estimated Weight of Reactor

Coils and coil fittings	185 lbs
Flanges and bolts	160 lbs
Top head	60 lbs
Bottom head	50 1bs
Bottom header	75 lbs
Top header	30 1bs
Shell, core, screens	145 1bs
J. J	705 lbs


Process Calculations C-2 Unit Page - 16 -

Effective Compound in Reactor


Reactor Volume

Shell 24.75" ID x 21.375 h core $(24.75^2 - 3^2) \frac{77}{2}$ x 21.375 = 10,140 cubic inches

Lower Head



Vol. 1 head = $\frac{1}{2}$ $\frac{4}{3}$ if a^2 b where $b = \frac{21.5}{4}$ and $a = \frac{21.5}{2}$ $V = \frac{2\pi}{3} \left(\frac{21.5}{16}\right)^3 = \frac{\pi}{24} (9938) = 1300 \text{ cubic inches}$




Vol. of cylindrical part (1) = $\frac{17}{4}$ (24.75)² x 1.75 = 842 cu.inches Vol. of part (3) = $\frac{17}{4}$ 9 x 7.25 = 51.2 cu. inches Total vol. = (1) + (2) - (3) = 1300 + 842 2242 - 51 2191 - say 2190 cubic inches void

Process Calculations C-2 Unit Page -17-

Upper Head

(1) Vol. of ellipsoidal part = $\frac{2}{3}$ TT $\frac{(24.5)^3}{16} = \frac{27}{24}$ (14706)= 1925 cu.in. Neglect effect of glass wool



(2) Cylindrical part -

$$V = \frac{1}{4} (24.5^2 - 49) \frac{7}{8} = 378$$
 cubic inches

(3) $V = \frac{4977}{4} \times 2 = 77$ cubic inches

(4) Vol. of tubes = 4.75 x
$$\left(\frac{9}{16}\right)^{\frac{1}{4}}$$
 x 28 = 33

Total vol.= (1) + (2) -(3) -(4) = 1925 77
$$\frac{378}{2303} - \frac{33}{110}$$
 $\frac{110}{2193}$ say 2200 cubic inches

Volume of Pancake Coils

Vol. of BA = 10.25 x 28 x $(\frac{7}{8})^2 = 172$ cubic inches

Process Calculations C-2 Unit Page - 18 -

Volume of Pancake Coils Contd.

Total tube vol. = 2840 + 172 = 3010 cubic inches

Spacer volume = $\frac{3}{8} \times \frac{3}{8} \times 6 \times \frac{7}{8} \times \frac{3}{4} \times 84 = 60$ cubic inches

Tubes and spacers = 3070 cubic inches

Net compound volume = 10140 - 3070 = 7070 cubic inches = 4.09 cu.ft.

Weight of compound = $4.09 \times 62.5 \times .7 = 179 \text{ lbs/reactor}$

Active Portion of Compound

Edge: Assume Salcomine within 1/2" of tubes will desorb

. . A layer of compound 3/4" deep will be inert all around the walls.

Volume of this annulus = approx. 24 77 x 21.375 = 1610 cubic in.

less vol. of BA

170

1440 cubic in.

inert

Center: Radius of inert core = 3"

Volume of annulus = $(6^2 - 3^2) \stackrel{\frown}{=} x 21.375 = 453$ cubic inches

Volume of ED = $28 \times \frac{9}{16}$ $\frac{7}{4} \times 10^{n} = 70$ cubic inches

Net volume = 453 - 70 = 383 cubic inches inert

Total = 1440

383 1823 = 1.1 cubic feet

1.1 x .7 x 62.5 = 48.3 lbs, inert compound say 49 lbs.

Effective compound = 179
-49
130 lbs.

Process Calculations C-2 Unit Page - 19 -

rested Reactor Performance

O

Reactor as designed contains 179 lbs. of saturated Salcomine of which 130 lbs. are effective.

Maximum Expected Production (for max, consumption of utilities)

Abs. temp. - 63°F at 105 lbs/sq.in.abs. Desorb temp. - 212° F at atm.

Abs. - 6 min. Cycle Des. - 4 min. Cool - 2 min. - 1/2 min.

frequency = $\frac{60}{125}$ = 4.8

Exit gas rate - 4 CFH/40.7 grams Salcomin: C 25°C and 1 atm.

Absorption = 3.47% from completely desorbed Salcomine

Desorption = 93%

Residual $0_2 = 3.46 \times .07 = 0.2$ Not yield = 3.45%

 0_2 production = 130 x 0.0345 x 4 x 4.8 = 86.1 lbs/hr

less void loss which = $4.2 \times 0.065 \times 4 \times 4.8 = 8.1$ lbs/hr

Net production = $(86.1 - 8.1) \times \frac{1000}{84.5} = 925 \text{ CFH}$

Air consumption = 2 $\left(\frac{179 \times 454}{40.7} \times 4 \times \frac{520}{537}\right)$ + 925 = 16385 CFH

 0_2 yield = $\frac{925}{16385 \times .21}$ 100 = 27%

Cycle As Designed (12' total, 3 min. abs.)

Exit gas rate - 4 CFH/40.7 gr. Salcomine at 25°C

Absorption = 2.25% Net yield

 0_2 production = 130 x 0.0223 x 20 = 58.0 lbs/hr

Void loss = $4.2 \times .065 \times 20 = 5.5$ lbs/hr

Process Calculations C-2 Unit Page - 20 -

Cycle As Designed Contd.

Net production = 52.5 x $\frac{1000}{84.5}$ = 622 CFH

Air consumption = $\frac{179 \times 454}{40.7} \times 4 \times \frac{520}{537} + 622 = 8352$ CFH

Oxygen yield = $\frac{622}{8352 \times .21} \times 100 = 352$

Purity of Product

Volume of reactor shells = 2300 cubic inches - upper head - lower head total = 2.6 cubic feet

Most recent data at time of writing, October 5, 1942, indicates that Salcomine is 39% voids and weighs 42 lbs/cu.ft.

Volume of compound per reactor = 4.09 cubic feet $rac{1}{G}$ = density of 0_2 left in powder Volume of gas in Salcomine voids = 4.09 x .39 = 1.6 cubic feet Total volume of residual gas = vol. in voids + vol. in heads = 1.6 + 2.6 = 4.2 cubic ft.

Assume this gas is air because reaction rate is nearly zero at end of absorption.

. Nitrogen in residual gas = (4.2) (.79) (f_G^0) lbs. = $3.3/g_G^0$ where ${}^{\circ}_{G}$ = air density in voids Oxygen evolved = $\frac{84.5}{20}$ lbs/hr = 4.22 lbs/reactor per cycle

Approx. \$ N₂ in O₂ = $\frac{3.3 \, \text{Å}_{\text{G}}}{4.2}$ 100 = $\frac{330 \, \text{Å}_{\text{G}}}{4.2}$ = 79 Å_{G}

~G at 80° and 760 mmHg = 0.076 lbs/cu.ft.

 \mathcal{P}_{G} at 80° and any pressure (Pmm) = 0.076 x $\frac{P}{760}$ =

For pressure after evacuation of Pmm, average % N2 in O2 is

$$% N_2 = (79) \frac{(0.076)}{760} (P) = 0.0079 P$$

0, purity = 100 - 0.0079 P

Process Calculations C-2 Unit Page - 21 -

Ocygen Losses in Voids

Total voids = 4.2 cubic feet

Density of 0, at 100°C and 1 atm. = 0.065 lbs/cu. ft.

Loss per hour = $4.2 \times 0.065 \times 20 = 5.46$ lbs/hr

02 product = 84.5 lbs/hr

 $$10ss = \frac{5.46}{84.5 + 5.46}100 = 6.1$$

Oxygen Coolers

Oxygen Cooler (between reactors and compressor) "C-1"

Duty - cooling 84.5 lbs/hr of 02 from 210°F to 100°F

h of 0_2 at 210° and 1 atm. = 143.2 BTU/lb (G-605.30)*

h of 0_2 at 100° and 1 atm. = $\frac{119.2}{24.0}$ " "

Total duty = (24.0) (84.5) = 2030 BTU/lb

Cooling medium - 85° water Pressure drop in 0₂ <0.5 lbs/sq.in.

Owwen Compressor Coolers "C-2" and "C-5"

Suction to 1st stage - 100°F and 1 atm.

Discharge from 1st stage - 306°F and 49.0 lbs/sq.in.abs.

Suction to 2nd stage -100°F and 49.0 lbs/sq.in.abs.

Discharge from 2nd stage - 506°F and 165.0 lbs/sq.in.abs.

Suction to holder -100°F and 165.0 lbs/sq.in.abs.

Compressor discharge temperatures based on n = 1.55 instead of 1.40 to correct for non-adiabatic compression.

Cooling medium - 85° water C_p for $O_2 = 0.22$ BTU/ lb.°F

Duty to C-2 cooler = (84.5) (306 - 100) (0.22) = 5850 BTU/hr Duty to C-3 cooler = (84.5) (306 - 100) (0.22) = 5850 BTU/hr

Pressure drop in 02 streams < 2.0 lbs/sq.in.

* Note: Number in parenthesis refers to chart in M. W. Kellogg Company Technical Data Book.

Process Calculations C-2 Unit Page - 22 -

Oxygen Compressor Coolers "C-2 and "C-5" Contd.

Total cooler duties - C-1 2050 C-2 5850 C-5 5850 9750 BTU/hr


Oxygen Holder

Description data from E.R. Gilliland on May 13,1942 - 90° C from 35° C 5.37% absorbed

Timo (G)	& Desorbed (<u>e) 42 i</u>	<u> </u>	AP/A	<u>d9</u>	₫ <u>₽</u>
0	0	4.6	2/2		0	16.7
1/2	4.0	4.0	1/2	8.0	14.8	5 0.5
1	15.5	9.5	1/2	19.0	21.9	36.9
1-1/2	26.0	12.5	1/2	25.0		
•		13.4	1/2	26.8	25.2	39.4
2	59.4	8.7	1/2	17.4	22.4	34.8
2-1/2	48.1	8.6	1/2	17.2	18.3	27.4
8	56.7	8.8	1/2	17.6	18.7	21.7
5-1/2	65.5		•		15.7	
4	72.1	8.6	1/2	15.2	15.0	
4-1/2	82.8	10.7	1/2	21.4	14.2	
		4.7	1/2	9.4		
5	87.5	8.7	1	8.7	12.4	
8	96.2				5.0	


Calculation of rate of oxygen evolution as a function of desorption time. $dP/d\theta$ by graphical differentiation.

Col. 6 is table of values of dP/d0 for one reactor alone. Col. 7 is table of values of dP/d0 for two reactors desorbing with three minutes overlap.



MINUTES

Process Calculations C-2 Unit Page - 22B -



Process Calculations C-2 Unit Page - 25 -

Curve on page 2B is plot of rate of 0_2 evolution (expressed as a percent)against time for two reactors desorbing on a three minute overlap. Data from Col.7 page 22.

Average rate is about 32% in one minute as shown by line AA'.

Area above AA' is equal to 9% of area below AA', i.e., peak load to be carried by O_2 holder is 9% of total flow in three minutes.

Total flow in three minutes = $\frac{1000}{60}$ x 5 = 50 cubic feet

9% of 50 cubic feet = 4.5 cubic feet - theoretical holder volume

Use a holder 18" in diameter and 5' long with internal volume of 8.5 cubic feet to allow 90% safety factor.

Heat Duty

Heat Duty to Reactors	(for original cycle with Heated Through	68° water) Heated Through
Item	Entire Tomo.Range	65% of Temp.Range
Coils and fittings Flanges and bolts Top head Bottom head Bottom header Top header Shell, core, screen	75 80	160 60 50 145 415 x.65 270 through entire range

Heat Duty

Heat of reaction 2.64 x 19,000 x 1.8 = 90,400

Sonsible heat to Salcomine (179)(212 - 68)(0.25)(20) = 129,000

Sensible heat to metal (560)(212 - 68)(0.10)(20) = 161.000 / 380,400 BTU/hr

Duty to 02 coolers 9,750 / 590,150 BTU/hr

Process Calculations C-2 Unit Page - 24 -

Cooling Water System

Ave. temp. change in water - 10° F

Water rate = $\frac{590.150}{10 \times 60}$ = 650 lbs/min. = 78 GPM

Fresh water cooler "C-4"

Duty - 400,000

Fresh water rate - 80 GPM

Fresh water temp. change - 10°

Temp. approach - 10° between see water in and fresh water out

See water rate - 160 GPM

Sea water temp. change - 50

Fresh water pump "J - 4" to deliver 80 GPM at room temp. and 80 lb/sq.in. ga. discharge pressure

Steam System

Heat duty to steam = reactor duty only = 580,400 BTU/hr

Assuming latent heat of steam at 1000 BTU/1b, steam consumption =

$$\frac{580.400}{1000} = \underline{580} \text{ lbs/hr}$$

BAY 400

Analysis of Dryer Heat Loads

Dryer Weight

Assume shell is 5/16" thick x 7-5/4" ID x 58" tell

Shell weight = $\frac{5}{16} \times \left(7 \frac{3}{4} + \frac{5}{16}\right) \times 58 \times 0.28$ lbs/cu.ft. x 77 = 50 lbs.

Process Calculations C-2 Unit Page - 25 -

Dryer Weight Contd.

a

Weight of head =(11 5/8)² $\frac{\pi}{4} = \frac{5}{8} = 0.28$ · = 18 1bs.

Wt. of bottom = $(8 1/8)^2 \frac{\pi}{4} \times \frac{5}{8} \times 0.28 = 9 1bs.$

Wt. of flange =(11 $5/6^2$ -8 $1/8^2$) $\frac{77}{4}$ x $\frac{5}{8}$ x 0.28 = 9 lbs.

Bolts • 10 lbs.

Screens 4 1bs. 100 1bs.

Alumina volume without inner insulation:

 $\binom{7}{4} = \frac{1}{4} \times 52^{n} = 1510$ cubic inches = 0.875 cubic feet

Wt. of alumina = 0.875 x 50 = 45.8 = 44 lbs.

Heat Duty No insulation

Final alumina temp. = 500°F after heating Initial alumina temp. = 100°F after cooling Atmosphere temp. = 80°F

Thermal conductivity of steel = $k = 26 \frac{BTU}{(hr)(sq.ft.)(°F)/ft}$.

 $R_{\text{steel}} = \frac{L}{kA} = \frac{\frac{3}{8} \times \frac{1}{12}}{26 \times 1} = 0.0012 \frac{(\text{hr})(^{\circ} \text{ F})}{(\text{BTU})(\text{sq.ft.})}$

For air film $(h_r + h_c) = 4$ $\frac{BTU}{hr.°F sq.ft.}$ Perry, 2nd ed. page 987 table 14

 $R_{film} = \frac{1}{hA} = \frac{1}{4 \times 1} = 0.25 \frac{hr \circ F}{(BTU)(sq.ft.)}$

Total resistance = 0.25 + 0.0012 = 0.2512

Total A T = 500°F - 80°F = 420°F

△T through steel = 420 x 0.0012 = 20F

•• average final steel temp. = $500^{\circ}F - \frac{2}{1} = 499^{\circ}F$. say $500^{\circ}F$

Process Calculations C-2 Unit Page - 26 -

Mater Absorption (1 hr. cycle, 50 minutes drying)

Air dew point = 80°F

O

Vapor pressure of water @ COOF = 0.5067 lbs/sq.in.

Partial pressure of dry air at 1 atm. = 14.7-0.5067 = 14.2 lbs/sq.in.

. Partial pressure of dry air at 105 psia = 105-0.5067 = 104.5

lbs./sq.in.
Water content of saturated air at 1 atm. = 0.02226 lbs water/lb.
dry air (from tables)

Water content of air at 105 psia =

 $0.02226 \times \frac{14.2}{104.5} = 0.00802$ lbs water/lb dry sir

Design air flow rate = 875 lbs/hr.
Design water input = 875 x 0.00502 = 2.64 lbs water/hr.

Water absorbed per cycle = 1.52 lbs.

 $\frac{1.32 \times 100}{44}$ = 5% saturation on alumina

Heat Leak

Initial $(h_c + h_r) = 2$

Final $(h_c + h_r) = 4$

Average = 3 BTU/hr.sq.ft. F

Dryer Surface Area =

 End
 8 1/8" dia.
 = 0.5600 sq.ft.

 Top
 11 5/8" dia.
 = 0.7050 " "

 Top edge
 1 1/4" x 11 5/8" x 77 x 1/144 = 0.5100 " "

 Top flange
 0.7050 - 0.5600 = 0.5450 " "

 Side
 8 1/8 x 77 x 58 x 1/144 = 6.55 " "

 8 1/8 x 77 x 58 x 1/144 = 6.55 " "

say 8.3 sq.ft.

Initial temp. difference = 20° Final temp. difference = 420°

Mean AT

= 220°F

Heat leak = $(h_c + h_r)$ A \triangle T = (5)(8.5)(220) = 5500 BTU/hr

CONFIDENTIAL

Process Calculations C-2 Unit Page - 27 -

Heat Leak Contd.

Add 25% for safety = heat leak = 7000 BTU/hr and for 15 min. = 1700 BTU

Total Heat Duty (one cycle)

Power rate = 11740 x 4 = 14 KW

Insulated Dryer

Use lead slag wool inside shell so that alumina bed dia. = 6"

New alumina volume = $6^2 \frac{11}{4} \times 52^n = 906$ cu.in. = 0.525 cu.ft.

Weight of alumina = 0.523 x 50 = 26 lbs.

Water Absorption

In 30 minutes = 1.32 lbs.

% saturation =
$$\frac{1.32 \times 100}{26}$$
 = 5.1% OK
Wt. of insulation(12 lbs/cu.ft.) = $\left[\left(7\frac{5}{4}\right)^2 - (6)^2\right] \frac{T}{4} \times \frac{52}{1728} \times 12=4.2$ lbs.

Heat capacity = 0.22 $\frac{BTU}{(1b.)(°F)}$

Temperature Differences

Use 0.026 to correct for effect of higher temperature. Depth of insulation = $7/8^{8}$ = 0.075 ft. = L

Process Calculations C-2 Unit Page - 28 -

Temperature Differences Contd.

Inside insulation area = $\frac{677 \times 32}{144}$ = 4.18 sq.ft.

Outside insulation area = $\frac{7-5/4 \prod x \cdot 32}{144} = 5.40 \text{ sq.ft.}$

Log mean area = 4.8 sq.ft.

(E-1.501)

 R_i = resistance of insulation = $\frac{L}{kA}$ = $\frac{0.075}{0.026 \times 4.8}$ = 0.585 $\frac{hr.of}{BTU}$

 R_{g} (through shell) = $R_{film} + R_{m} + R_{i} = 0.25 + 0.0012 + 0.585 = 0.8562$


(Note: Neglecting offect of changes in area on metal and film resistances)

Total AT = 500-80 = 420°

$$\Delta T_{\rm m} = 420 \times \frac{0.0012}{0.8362} = 0.60$$
 Mean $T_{\rm m} = 206$

 \triangle T_{film} = 420 x $\frac{0.25}{0.8362}$ = 125.6°F Kean T_f = 105°

$$\Delta T_i = 420 \times \frac{0.585}{0.8362} = \frac{293.80F}{420.00F}$$
 Mean $T_i = 3530$



Heat Leak Tron Mall

Initial film $\triangle T = (say)$ 5° Final film $\triangle T = 125.6$ °

Process Calculations C-2 Unit Page _ 29 _

Heat Leak From Shell Contd.

Hean
$$\triangle T = \frac{125.6.5}{2} = 66^{\circ}$$

$$(h_c + h_r) = 2$$
 ($\triangle T$ calculated from $(h_c + h_r) = 4$)

Revised T's

Assume
$$(h_c + h_r) = 2.4$$

•••
$$R_f = \frac{1}{2.4 \times 1} = 0.417$$

$$R_{t} = 0.417 + 0.0012 + 0.585 = 1.0052$$

Final Temp.

$$\triangle T_{T} = 420 \times \frac{0.417}{1.0032} = 174.50$$

$$\Delta T_{m} = 420 \times \frac{0.0012}{1.0032} = 0.50^{\circ}$$

$$\Delta T_1 = 420 \times \frac{0.585}{1.0052} = 245.20$$

$$Mean T_{1} = 5770$$

Revised Heat Leak

Mean
$$\triangle T = \frac{174 + 5}{2} = 90^{\circ}$$

Mean
$$(h_c + h_r) = say 2$$

 $(= 5.68 sq.ft.)$

Heat leak = (2) $(8\frac{1}{8}\pi \times \frac{52}{144})$ (90) = 1020 BTU/hr through shell

CONFIDENTIAL

Process Calculations C-2 Unit Page - 50 -

Revised Heat Loak Contd.

Assume that rate of heat leak through remainder is at same rate as in uninsulated case.

Remaining area = 8.27-5.68 = 2.59 sq.ft.

for 15 min. leak = $\frac{2750}{4}$ = 680 BTU

Heat Duty

To $H_2O = 1.52 \times 1000$ To alumina = (26)(500-80)(.20) To metal =	1820 2180
shell - (50)(254.5-80)(0.12) heads, etc.(50)(500-80)(0.12) To insulation (4.2)(352-80)(0.22) To heat leak	1050 2520 252 680 8002 BTU in 15 min.
	<u>680</u> 8002 BTU in 15 min.

Power rate = $\frac{8002 \times 4}{5420}$ = 9.56 KW

Safety factor = $\frac{10-9.36}{10}$ 100 = 6.4%

Utilities & Supplies

Steam

Low pressure - 400 lbs/hr High pressure (150 lb)- 20 lbs/hr @ rate of 100 lbs/hr

Sea Water

160 gals/min @ 80 lb/sq.in. ga. pressure

Air

At 90 lbs/sq.in.gage - 16400 CFH max.

Electricity

230 v 60 cycle AC, 10 KW

Process Calculations C-2 Unit Page - 51 -

Fresh Hater

150 gals. in system

Salcomine

720 lbs.

Alumina

80 lbs.

INDEX OF DRAWINGS

Shipboard Unit

M. W. Kellogg Company Drawings

Drawing #	Date	Title
2-A	8/25/42	Flat Spiral Coil Type Reactor
11-A	5/51/42	Flat Spiral Coil Type Reactor
15-A	8/26/42	Layout of Piping
14-A	4/20/42	Flat Spiral Coil Type Reactor
25-A	5/26/42	Flow Diagram
12-B	4/9/42	Dryers, Filter and Drip Drum
18-B	4/15/42	O _o Cooler
20-B	4/24/42	Electric Heater
22-B	5/6/42	Support Frame for Two Reactors and Piping
23-B	5/23/42	Modified All Steel Construction of Reactor
1-D	5/2/42	Typical Piping Arrangement for Flow Recorders
8-D	9/12/42	Revision to Construction of Reactor
2-G	4/13/42	1' x 5' (30 gul.) Tank
5-G	4/22/42	Adapter for Reactor Coils and Wrenches
4-G	4/30/42	Support Frame for Oil Filter, Dryers and Drip Drum
5-G	5/11/42	Single Tube Keyes-Collins Heat Exchanger
6-G	6/8/42	Instrument Panel
7-G	6/11/42	Electric Wiring Diagram
14-G	8/5/42	Modification of Screens in Reactor
28-G	9/19/42	"Hopcalite" Gas Filter
97-G	5/25/45	Two Stage Oxygen Compressor Piping
American Machine	& Foundry Co	mpeny Drawings
MWK-1	6/22/42	Interval Timer Bed Plate
MWK-A005	6/22/42	Interval Timer
MWK-A006	9/30/42	MWK Preumatic Interval Timer-Compound Gearing
MWK-5A1-10	10/1/42	Interval Timer Drum (56 functions)
MWK-5Al-11	10/1/42	Interval Timer Drum (10 functions)
MWK-5D1-Blank	10/1/42	Interval Timer Segment

INDEX OF DRAWINGS CONTD.

Shipboard Unit

Whitlock Manufacturing Company Drawings

Drawing #	Date	Title	
L-9994-A-1 L-9994-B-1 B-9994 *A-1 *1 *2 *5 *4	5/25/42 5/28/42 5/26/42 2/4/45 2/4/45 2/4/45 2/4/45 2/4/45	50" OD Fabricated Steel Top Head Fabricated Steel Bottom Header Flat Spiral Coil Type Reactor "Lobo Job" Reactor Alteration Top Head Flange (Lobo Job) Top Head Stuffing Box Body (Lobo Job) Bottom Head Stuffing Box Body (Lobo Job) Stuffing Box Gland (Lobo Job) Stuffing Box Parts List	

*Mote: These drawings bear the Whitlock Title Box corrected to read *AMD Co.*. They were prepared at the Whitlock plant by an engineer from the American Machine Defense Corporation.

Clark Brothers Company Drawings


105-48	8/1/42	2 State Vertical Compressor
105-50	8/17/42	Motor Driven 2 Stage Comp. Unit

Schematic Flow Sheets and Sketches

of the basic stages in the operation of the Shipboard unit.


There is also appended a sketch of the automatic timer which actuates the valves controlling the various gas and liquid streams in the unit.

MOORPTION FLOW SHEET I




This portion of the flow sheet shows the source taken by the compressed air in passing through the drip drum, oil filter and reactor during an absorption period. During this time cold water is flowing through the reactor coils.

ABSORPTION FLOW SHEET I




In addition to the items shown on Absorption Flow Shoot I, this flow shoot indicates the path of the reactor exhaust gas through the heater and the dryer which is being represented.

EVACUATION FLOW SHEET




At the end of the absorption period the compressed air is sent to another reactor, and the reactor which has finished absorption is evacuated by means of the exhauster as shown above. Cold water continues to flow through the reactor coils.




exhauster is disconnected from the reactor and hot water is sent through the reactor coils. Oxygen is given off and flows through the filter to the drum and the compressor. Here it is compressed and delivered to storage tanks or cutting torches.

AUTOMATIC TIMER



FRONT VIEW



SIDE VIEW

PIN WALVE SHUT

I

PIN VALVE OPEN

٠.

.. .-

. .

· ·							
AUTHOR(S): L ORIGINATING	obo, Walter AGENCY: K	E. ; Bockius Cellogg Co., I	evelopment (Emp., C. J. W., Jersey Circarch and Develo	oloying (Regenerativ Defense Co and Amer	rp. ican Machine	AVI- 31645 ENERGY (None) CRO. ACTIV ED. (None) PULIFICAD ACTIV ED. OSRO-5154
May '45	confd'l	U.S.	Eng.	PAG28	diagre,	graphs	-
ABSTRACT:					Xe, 0	SRD	.\$
A description is given of oxygen generating plants utilizing the absorbent "Salcomine". The plants were designed by the M. W. Kellogg Co., and such construction as took place was done by the American Machine Defense Corporation. In addition to a chronological description of each plant or study involved in the program, the report contains a bibliography of correspondence, memoranda, reports and specifications dealing with equipment details and operating experiments. Detailed process calculations and a list of all drawings are supplied for the Shipboard (C-2) unit, the only complete unit fabricated by the contracting companies. Process calculations and detailed designs are not furnished for plants which were studied but not erected.							
the					d detailed (designs are not f	
the for DISTRIBUTION	plants which	h were studie this report o	ed but not erected	i. ADO	• .	designs are not f	
the for	plants which Copies of avy Materiel	this report o	ed but not erected btainable from C SUBJ	ADO ECT HE	ADINGS:	s. Shipborne (687	urnished

184: 05RD Front #6 dtd 288am -1 Hel 46 (23) × oxygen generators Sal comine (25)

p23/05