Advanced Gun System (AGS) and Long Range Land Attack Projectile (LRLAP)


Joe McPherson
DD(X) AGS Lead Project Engineer

US Navy: Surface Warfare Vision


- Family of surface combatants required to meet future warfighting requirements, not just a single ship class
- Winning the fight requires the ability to conduct assured access and maneuver warfare
- DD(X) is the multi-mission, precision strike and volume fires provider within the family of surface combatants
- The DD(X) Program will focus on risk mitigation of transformational technologies for the Surface Fleet

DD(X) Centerpiece to Transformational 21st Century Navy

DD(X) Land Dominance Roles



Total Ship Systems Engineering



- Rate of Fire
- Power
- High Reliability
- Shock Load
- Ship Integration
- Base Ring Diameter
- Automated Operation
- Chamber Volume
- Projectile Length
- ROF 12 rds / min
- Proj Weight 260 lbs
- 600 750 rds / mag
- Volume
- Ammo Selectivity
 - Effectiveness
 - Low Manning
 - Weight
 - Volume

ultimately affect total ship design

LRLAP design parameters

Requirements Definition

- Sustained ROF
- 2 Gun Systems
- Maximum ROF

- Magazine
- Battery Equivalents
- Range / Accuracy

Battery Equivalents

Munitions

Munitions Warhead M795 24 lbs HE

M483A1 88 M42 / M46 DPICM

Rate of Fire

Battery ROF

12 rounds / minute

12 rounds / minute

Throw Weight

Quantity / Minute

288 lbs HE

1056 submunitions






AGS LRLAP Program Status

- LRLAP Concept Development (June 99 April 00)
 - Two Contracts awarded 3QFY99 (Raytheon & SAIC-Lockheed Martin)
 - Completed Development Spec and Interface Control Documents
- LRLAP Risk Reduction Demonstration (May 00 December 02)
 - Initiate Risk Reduction Subcontracts
 - Awards to SAIC / LM & Raytheon August 00
 - LRLAP Static Rocket Motor tests conducted
 - Competitive Fly-Off
 - Fly to 60 70% of Objective Range
 - **★** Planned for 1QFY03
- Planned Initiation of Engineering & Manufacturing Development (E&MD) 2QFY03


Demonstration Program Milestones



Demonstration Program Progress

- Both subcontractors have completed Airframe tests
- Propulsion subsystem tests planned
- Completed several GNC design, integration, and test activities
- Established initial test sites:
 - UDLP Elk River Proving Grounds short range tests
 - US Army Dugway Proving Grounds intermediate range tests
 - Test sites being evaluated for long range tests
 - Completed design, fabrication, and test of two AGS barrels (62-caliber)

AGS Gun Barrel Test Assets




155mm 62 caliber Test Barrel for test firings at the UDLP Large Caliber test facility in Elk River, MN.



155mm 39 caliber test barrel for munitions testing mounted on a modified M110 8" Self Propelled Howitzer at Dugway Proving Grounds, UT.

DD(X) Flight I Integrated Schedule



Conclusion

- AGS, teamed with LRLAP, will have the ability to respond to a call for fire 24/7 with ordnance on target up to 100nm
- With the capability to provide on demand, timely, lethal, measured effects in a multi-mission environment, the AGS provides the transformational characteristics needed by both the Navy and Marine Corps